SOLICITATION, OFFER, AND AWARD *(Construction, Alteration, or Repair)*	1. SOLICITATION NUMBER	2. TYPE OF SOLICITATION	3. DATE ISSUED	PAGE OF PAGES
	DACA67-02-R-0208	☐ SEALED BID *(IFB)* ☒ NEGOTIATED *(RFP)*	11 Jan, 2002	1 7

IMPORTANT - The "offer" section on the reverse must be fully completed by the offeror.

4. CONTRACT NUMBER	5. REQUISITION/PURCHASE REQUEST NUMBER	6. PROJECT NUMBER
DACA67-02-C-0207	W68MD9-1337-8503	

7. ISSUED BY CODE W68MD9	8. ADDRESS OFFER TO
Seattle District, Corps of Engineers ATTN: CENWS-CT-MU PO Box 3755 Seattle, WA 98124-3755	Seattle District, Corps of Engineers PO Box 3755 ATTN: CENWS-CT-CB-MU Seattle, WA 98124-3755 HAND CARRY: Seattle District Corps of Engineers Contracting Division 4735 East Marginal Way South Seattle, WA 98134-2385

9. FOR INFORMATION CALL	A. NAME	B. TELEPHONE NUMBER *(Include area code) (NO COLLECT CALLS)*
	See Information Page inside Front Cover	See Information Page inside Front Cover

SOLICITATION

NOTE: In sealed bid solicitations "offer" and "offeror" mean "bid" and "bidder".

10. THE GOVERNMENT REQUIRES PERFORMANCE OF THE WORK DESCRIBED IN THESE DOCUMENTS *(Title, identifying number, date):*

Furnish all labor, materials and equipment and perform all work for project entitled "Repair Aircraft Parking Apron/Repair Runway, Mt. Home AFB, ID" in accordance with the attached Contract Clauses, Special Clauses, Technical Specifications and Drawings.

1. Solicitation No. DACA67-02-R-0208 dated 11 January 2002 with 6 amendments thereto.
2. Wage Determination No. ID020001 with 1 modification thereto.
3. Drawings as listed in Section 00800.

11. The Contractor shall begin performance within 10 calendar days and complete it within * calendar days after receiving ☐ award, ☒ notice to proceed. This performance period is ☒ mandatory, ☐ negotiable. *(See* * Paragraph SC-1, 00800 *.)*

12A. THE CONTRACTOR MUST FURNISH ANY REQUIRED PERFORMANCE PAYMENT BONDS? *(If "YES," indicate within how many calendar days after award in Item 12B.)* ☒ YES ☐ NO	12B. CALENDAR DAYS
	10

13. ADDITIONAL SOLICITATION REQUIREMENTS:

A. Sealed offers in original and 4 copies to perform the work required are due at the place specified in Item 8 by 2:00 p.m. *(hour)* local time 12 Feb, 2002 *(date).* If this is a sealed bid solicitation, offers will be publicly opened at that time. Sealed envelo containing offers shall be marked to show the offeror's name and address, the solicitation number, and the date and time offers are due.

B. An offer guarantee ☒ is, ☐ is not required.

C. All offers are subject to the (1) work requirements, and (2) other provisions and clauses incorporated in the solicitation in full text or by referenc

D. Offers providing less than 120 calendar days for Government acceptance after the date offers are due will not be considered and w be rejected.

OFFER *(Must be fully completed by offeror)*

14. NAME AND ADDRESS OF OFFEROR *(Include ZIP Code)*
WESTERN CONSTRUCTION, INC.
10139 S. FEDERAL WAY
PO BOX 15569
BOISE, ID 83715
Tax ID No: 82-0254196 DUNS No: 007817612
eMail: MRWCI@HOTMAIL.COM CAGE 1MBB3
CODE FACILITY CODE

15. TELEPHONE NUMBER *(Include area code)*
(208) 345-1440 Fax No.: (208) 345-1548

16. REMITTANCE ADDRESS *(Include only if different than Item 14)*

17. The offeror agrees to perform the work required at the prices specified below in strict accordance with the terms of this solicitation, if this accepted by the Government in writing within 120 calendar days after the date offers are due. *(Insert any number equal or greater than minimum requirement stated in 13D. Failure to insert any number means the offeror accepts the minimum in Item 13D.)*

AMOUNTS ▶ See Pages 00010-5 thru 00010-7

18. The offeror agrees to furnish any required performance and payment bonds.

19. ACKNOWLEDGEMENT OF AMENDMENTS
(The offeror acknowledges receipt of amendments to the solicitation - give number and date of each)

AMENDMENT NO.	1	2	3	5	4	6				
DATE	7FEB02	7FEB02	12FEB02	14FEB02	15FEB02	6MAR02				

20A. NAME AND TITLE OF PERSON AUTHORIZED TO SIGN OFFER *(Type or print)*
STEVEN C. HEATON, VICE-PRESIDENT

20B. SIGNATURE

20C. OFFER DATE
12 MAR 02

AWARD *(To be completed by Government)*

21. ITEMS ACCEPTED

Base Items (Apron): 0001, 0002, 0002AA, 0002AB and Option Items(Apron): 0003AA, 0003AB, 0004, 0005, 0005AA and 0005AB.
Base Items (Runway): 0006, 0007, 0007AA,0007AB, 0008, 0008AA, 0008AB, 0009, 0009AA, 0009AB, 0010, 0010AA, 0010AB, 0011, 0012, 0012AA, 0012AB, 0013, 0013AA, 0013AB

22. AMOUNT
$15,209,895

23. ACCOUNTING AND APPROPRIATION DATA
See page 00010-3

24. SUBMIT INVOICES TO ADDRESS SHOWN IN *(4 copies unless otherwise specified)* ▶ ITEM 26

25. OTHER THAN FULL AND OPEN COMPETITION PURSUANT TO
☐ 10 U.S.C. 2304(c) ( ) ☐ 41 U.S.C. 253(c) ( )

26. ADMINISTERED BY CODE
United States Army Corps of Engineers, Seattle District
Northwest Area Office
PO Box 92146
Tillicum, WA 98492-0146

27. PAYMENT WILL BE MADE BY
US Army Corps of Engineers Finance Center
CEFC-AO-P
5722 Integrity Drive
Millington, TN 38054-5005

CONTRACTING OFFICER WILL COMPLETE ITEM 28 OR 29 AS APPLICABLE

☐ 28. NEGOTIATED AGREEMENT *(Contractor is required to sign document and return _____ copies to the issuing office.)* Contractor agrees to furnish and deliver all items or perform all work requirements identified on this form and any continuation sheets for the consideration stated in this contract. The rights and obligations of the parties to this contract shall be governed by (a) this contract award, (b) the solicitation, and (c) the clauses, representations, certifications, and specifications incorporated by reference in or attached to this

☒ 29. AWARD. *(Contractor is not required to sign this document.)* offer on this solicitation is hereby accepted as to the items listed. This award consummates the contract, which consists of (a) the Government solicitation and your offer, and (b) this contract award. No further contractual document is necessary.

30A. NAME AND TITLE OF CONTRACTOR OR PERSON AUTHORIZED TO SIGN *(Type or print)*

30B. SIGNATURE

30C. DATE

31A. NAME OF CONTRACTING OFFICER *(Type or print)*
CHERYL A. ANDERSON

31B. UNITED STATES OF AMERICA
BY Cheryl A. Anderson

31C. AWARD DATE
26 MAR 2002

STANDARD FORM 1442 BACK (REV. 4-85)

00010-2 R0001

Submit Invoices as follows:

Submit 1 Copies of Invoice to:

Mountain Home Resident Office
USACE, Seattle
390 Gunfighter Ave
Mtn. Home AFB, ID 83648-5264

This page was intentionally left blank for duplex printing.

ALTERATIONS IN CONTRACT (FAR 52.252-4) (APRIL 1984)
PORTIONS OF THIS CONTRACT ARE ALTERED AS FOLLOWS:

A. The Contractor's letter dated 22 March 2002, agreeing to incorporation of Modification No. 1, 03/08/2002, to General Wage Decision No. ID020001, with no increase to the proposed prices, is provided immediately following the pricing schedule as page ALT-1.

B. The firm's technical proposal, as listed below, is hereby incorporated by reference in its entirety into the contract:

1. Initial technical proposal dated 20 February 2002
2. Final Revised Proposal dated 12 March 2002

C. Accounting and Appropriations Data:

BASE LINE ITEMS FOR APRON – 0001- 0002AB, OPTIONAL LINE ITEMS FOR APRON – 0003-0005AB:

57233000000 088082 32303L3JLB32100000000 NA 35026
$7,305,025.00

BASE LINE ITEMS FOR RUNWAY – 0006 - 0013AB:

21220500000 088082 3230BB963870000000000 E314 35026
$7,904,870.00

D. The following revised wage determination is incorporated into the contract via alteration to contract: General Decision Number ID020001, Mod 1 dated 03/08/2002

This page intentionally blank

IF THE CONTRACTOR IS A CORPORATION OR PARTNERSHIP, THE **APPLICABLE PORTION** OF THE FORM LISTED BELOW MUST BE COMPLETED. IN THE ALTERNATIVE, OTHER EVIDENCE MUST BE SUBMITTED TO SUBSTANTIATE THE AUTHORITY OF THE PERSON SIGNING THE CONTRACT. IF A CORPORATION, **THE SAME OFFICER SHALL NOT EXECUTE BOTH THE CONTRACT AND THE CERTIFICATE.**

CORPORATE CERTIFICATE

I, Jack R. Snyder, certify that I am the Assistant Secretary of the Corporation named as Contractor herein; that Steven C. Heaton, who signed this contract on behalf of the Contractor was then Vice-President of said corporation; that said contract was duly signed for and on behalf of said corporation by authority of its governing body and is within the scope of its corporate powers.

(Secretary) (CORPORATE SEAL)

AUTHORITY TO BIND PARTNERSHIP

This is to certify that the names, signatures and Social Security Numbers of all partners are listed below and that the person signing the contract has authority actually to bind the partnership pursuant to its partnership agreements. Each of the partners individually has full authority to enter into and execute contractual instruments on behalf of said partnership with the United States of America, except as follows: (state "none" or describe limitations, if any)

This authority shall remain in full force and effect until such time as the revocation of authority by any cause whatsoever has been furnished in writing to, and acknowledged by, the Contracting Officer.

(Names, Signatures and Social Security Numbers of all Partners)

NAME	SIGNATURE	SOCIAL SECURITY NO.

This page was intentionally left blank for duplex printing.

The SCHEDULE is revised in it's entirety by amendment R0001 DACA67-02-C-0207

REVISED SCHEDULE **12 MAR 02**

REPAIR AIRCRAFT PARKING APRON REPAIR RUNWAY

Item No.	Description of Item	Quantity	Unit	Unit Price	Amount
	BASE ITEMS (Repair Aircraft Parking Apron)				
0001	All Work for Repair Aircraft Parking Apron and Taxiway A, except for Items 0002, 0003, 0004, 0005, 0006 and 0007	1	JOB	L.S.	$3,057,000.00
0002	PCC Placement for Aircraft Parking Apron and Taxiway A:				
0002AA	First 30,900 Cubic Meters	30,900	C.M.	$115.00	$3,553,500.00
0002AB	Over 30,900 Cubic Meters	4,700	C.M.	$105.00	$493,500.00
	TOTAL BASE ITEMS (Repair Aircraft Parking Apron)				$7,104,000.00
	OPTIONAL ITEMS (Repair Aircraft Parking Apron)				
0003	Excavation and Disposal of Contaminated Soil:				
0003AA	First 1,200 Cubic Meters	1,200	C.M.	$10.00	$12,000.00
0003AB	Over 1,200 Cubic Meters	120	C.M.	$10.00	$1,200.00
0004	Electrical and Communications Ductbank	1	JOB	L.S.	$132,000.00
0005	Rock Excavation for Ductbank:				
0005AA	First 350 Cubic Meters	350	C.M.	$145.00	$50,750.00
0005AB	Over 350 Cubic Meters	35	C.M.	$145.00	$5,075.00
	TOTAL OPTIONAL ITEMS (Repair Aircraft Parking Apron)				$201,025.00
	TOTAL BASE AND OPTIONAL ITEMS (Repair Aircraft Parking Apron)				$7,305,025.00
	BASE ITEMS (Repair Runway)				
0006	All Work to Repair Runway 12/30, except for Items 0007, 0008, 0009, 0010, 0011, 0012 and 0013	1	JOB	L.S.	$2,566,950.00
0007	Provide, Place and Finish PCC Pavement to Reconstruct Portions of Runway 12/30:				
0007AA	First 27,300 C.Y.	27,300	C.Y.	$100.00	$2,730,000.00
0007AB	Over 27,300 C.Y.	2,700	C.Y.	$90.00	$243,000.00

(See notes on last page of the SCHEDULE)

Item No.	Description of Item	Quantity	Unit	Unit Price	Amount
0008	Provide, Place, and Compact AC Pavement:				
0008AA	First 57,000 TON	57,000	TON	$34.00	$1,938,000.00
0008AB	Over 57,000 TON	5,700	TON	$34.00	$193,800.00
0009	Repair Small Asphalt Cracks:				
0009AA	First 50,000 L.F.	50,000	L.F.	$1.50	$75,000.00
0009AB	Over 50,000 L.F.	5,000	L.F.	$1.50	$7,500.00
0010	Repair Medium Asphalt Cracks:				
0010AA	First 50,000 L.F.	50,000	L.F.	$1.70	$85,000.00
0010AB	Over 50,000 L.F.	5,000	L.F.	$1.70	$8,500.00
0011	Repair Large Asphalt Cracks:				
0011AA	First 6,000 L.F.	6,000	L.F.	$2.50	$15,000.00
0011AB	Over 6,000 L. F.	600	L.F.	$2.50	$1,500.00
0012	Rock Excavation for Waterline, Sewerline, Sewage Effluent, and Ductbanks:				
0012AA	First 900 C.Y.	900	C.Y.	$35.00	$31,500.00
0012AB	Over 900 C.Y.	90	C.Y.	$30.00	$2,700.00
0013	Excavation, Removal and Replacement of Unsatisfactory Material:				
0013AA	First 970 C.Y.	970	C.Y.	$6.00	$5,820.00
0013AB	Over 970 C.Y.	100	C.Y.	$6.00	$600.00
		TOTAL BASE ITEMS (Repair Runway)			$7,904,870.00
	OPTIONAL ITEMS (Repair Runway)				
0014	All Work to Repair Taxiway A, except for Item 0015	1	JOB	L.S.	$155,000.00
0015	Provide, Place, and Finish PCC Pavement to Repair Taxiway A:				
0015AA	First 3,950 C.Y.	3,950	C.Y.	$135.00	$533,250.00
0015AB	Over 3,950 C.Y.	400	C.Y.	$135.00	$54,000.00
0016	All Work to Repair Taxiway E, except for Item 0017	1	JOB	L.S.	$135,000.00

Item No.	Description of Item	Quantity	Unit	Unit Price	Amount
0017	Provide, Place, and Finish PCC Pavement to Repair Taxiway E:				
0017AA	First 3,000 C.Y.	3,000	C.Y.	$140.00	$420,000.00
0017AB	Over 3,000 C.Y.	300	C.Y.	$140.00	$42,000.00

TOTAL OPTIONAL ITEMS (Repair Runway)	$1,339,250.00
TOTAL BASE AND OPTIONAL ITEMS (Repair Runway)	$9,244,120.00
TOTAL OPTIONAL ITEMS (Repair Aircraft Parking Apron/Repair Runway)	$1,540,275.00
TOTAL BASE AND OPTIONAL ITEMS (Repair Aircraft Parking Apron/Repair Runway)	$16,549,145.00

NOTES:

1. Bid prices must be entered for all items of the schedule. Additions and multiplications will be subject to verification by the Government. In case of variation between the lump-sum prices and the total amount, the lump-sum prices will be considered the amount proposed. In case of variation between the unit prices and the extensions, the unit prices will be considered the proposed unit price.
2. Repair Aircraft Parking Apron is in metric units of measurement. Repair Runway is in English units of measurement.
3. Option Item 0005 will not be awarded unless Option Item 0004 is awarded.
4. Option Item 00015 will not be awarded unless Option Item 00014 is awarded.
5. Option Item 00017 will not be awarded unless Option Item 00016 is awarded.
6. Option Items 0014 and 0015 are shown as Optional Item #1 on the contract drawings.
7. Option Items 0016 and 0017 are shown as Optional Item #2 on the contract drawings.

This page intentionally blank

Western CONSTRUCTION, INC.
An Equal Opportunity Employer

TELEPHONE (208) 345-1440
FAX (208) 345-1548
10139 S. FEDERAL WAY
P. O. BOX 15569
BOISE, IDAHO 83715-0569

March 22, 2002

To: Nancy A. Gary U.S. Corps of Engineers Fax 206-764-6817

From: Jack R. Snyder, Chief Engineer

Re: DACA67-02-R-0208

Western Construction Inc. acknowledges that Wage Decision ID 02-0001 Dated March 8, 2002 will have no cost impact on the prices contained in our proposal.

ALT-1

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE	PAGE OF PAGES
	1 | 2

2. AMENDMENT/MODIFICATION NO.	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO.(If applicable)
0006	06-Mar-2002	W68MD9-1337-8503	

6. ISSUED BY CODE DACA67
USA ENGINEER DISTRICT, SEATTLE
ATTN: CENWS-CT
P.O. BOX 3755
SEATTLE WA 98124-3755

7. ADMINISTERED BY (If other than item 6) CODE
See Item 6

8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)

CODE FACILITY CODE

X	9A. AMENDMENT OF SOLICITATION NO. DACA67-02-R-0208
X	9B. DATED (SEE ITEM 11) 11-Jan-2002
	10A. MOD. OF CONTRACT/ORDER NO.
	10B. DATED (SEE ITEM 13)

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

[X] The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer [ ] is extended, [ ] is not extended.

Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS.
IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

[ ] A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.

[ ] B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).

[ ] C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:

[ ] D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor [ ] is not, [ ] is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

PROJECT: Repair Apron, Runway Mt Hme AFB, Idaho

Address technical questions to: techbid@nws02.usace.army.mil

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
15B. CONTRACTOR/OFFEROR _____ (Signature of person authorized to sign)	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA BY _____ (Signature of Contracting Officer)	16C. DATE SIGNED 06-Mar-2002

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

A. The purpose of this Amendment Number SIX (0006) is to incorporate a wage decision, revise Criteria Number Five - Extent of Small and Small Disadvantaged Business Participation in Section 00100 Introduction, and provide a copy of SF 1442 and original bid schedule as follows:

- **DELETE**: Section 00100 Introduction
  INSERT: Revised Section 00100 Introduction

- **DELETE**: General Decision Number ID010001, Mod 15, dated 01/04/2002
  INSERT: General Decision Number ID020001, dated 03/01/2002, Construction Type: Heavy/Highway.

B.. NOTICE TO OFFERORS: Offerors must acknowledge receipt of this amendment by number and date on Standard Form 1442 BACK, in Block 19, or by telegram. Please mark the outside of the envelope in which the proposal is enclosed to show the amendment received

Enclosures:
SF 1442
BID SCHEDULE
Section 00100 Introduction
Idaho Wage Decision (Heavy/Highway)

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE	PAGE OF PAGES
	1

2. AMENDMENT/MODIFICATION NO.	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO.(If applicable)
0005	14-Feb-2002	W68MD9-1337-8503	

6. ISSUED BY CODE DACA67
USA ENGINEER DISTRICT, SEATTLE
ATTN: CENWS-CT
P.O. BOX 3755
SEATTLE WA 98124-3755

7. ADMINISTERED BY (If other than item 6) CODE
See Item 6

8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)

X	9A. AMENDMENT OF SOLICITATION NO. DACA67-02-R-0208
X	9B. DATED (SEE ITEM 11) 11-Jan-2002
	10A. MOD. OF CONTRACT/ORDER NO.
	10B. DATED (SEE ITEM 13)

CODE FACILITY CODE

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

[X] The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer [X] is extended, [ ] is not extended.

Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS.
IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.

B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).

C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:

D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor [ ] is not, [ ] is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

PROJECT: REPAIR AIRCRAFT PARKING APRON/REPAIR RUNWAY, MT HOME AFB, IDAHO

1. THE PURPOSE OF THIS AMENDMENT IS TO CHANGE THE PROPOSAL DUE DATE, AND TO RESERVE AMENDMENT 0004 FOR TECHNICAL CHANGES.

2. THE PROPOSAL DUE DATE IS EXTENDED TO READ: 20 FEB 02, 12 NOON PST.

3. PROPOSERS MUST ACKNOWLEDGE RECEIPT OF THIS AMENDMENT BY NUMBER AND DATE ON THE SF 1442 BACK IN BLOCK 19, OR BY TELEGRAM.

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
15B. CONTRACTOR/OFFEROR _____ (Signature of person authorized to sign)	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA BY _____ (Signature of Contracting Officer)	16C. DATE SIGNED 14-Feb-2002

This page was intentionally left blank for duplex printing.

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE	PAGE OF PAGES
	1 | 2

2. AMENDMENT/MODIFICATION NO.	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO.(If applicable)
0004	15-Feb-2002	W68MD9-1337-8503	

6. ISSUED BY	CODE	7. ADMINISTERED BY (If other than item 6)	CODE
USA ENGINEER DISTRICT, SEATTLE ATTN: CENWS-CT P.O. BOX 3755 SEATTLE WA 98124-3755	DACA67	**See Item 6**	

8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)		
	X	9A. AMENDMENT OF SOLICITATION NO. DACA67-02-R-0208
	X	9B. DATED (SEE ITEM 11) 11-Jan-2002
		10A. MOD. OF CONTRACT/ORDER NO.
		10B. DATED (SEE ITEM 13)
CODE FACILITY CODE		

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

[X] The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer [ ] is extended, [X] is not extended.

Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS.
IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

[ ] A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.

[ ] B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).

[ ] C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:

[ ] D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor [ ] is not, [ ] is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

PROJECT: DACA67-02-R-0208
REPAIR AIRCRAFT PARKING APRON/REPAIR RUNWAY, MT HOME AFB, IDAHO

(SEE ATTACHED CONTINUATION PAGE)

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
15B. CONTRACTOR/OFFEROR _____ (Signature of person authorized to sign)	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA BY _____ (Signature of Contracting Officer)	16C. DATE SIGNED 15-Feb-2002

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

1. The purpose of this Amendment Number FOUR (0004), dated 15 Feb 2002, is to add revised Sections 00100 Intro, 00800, and 02111(A) as follows:

DELETE : Section 00100 Intro,
INSERT: Revised Section 00100 Intro.

DELETE : Section 00800, Special Clauses
INSERT: Revised Section 00800, Special Clauses

DELETE: Section 02111 (A) Excavation and Handling of Contaminated Material
INSERT: Section 02111 (A) Excavation and Handling of Contaminated Material

2. **THE PROPOSAL DUE DATE AND TIME REMAINS AT 20 FEBRUARY 2002, 12 NOON PST.**

3. NOTICE TO BIDDERS: Bidders must acknowledge receipt of this amendment by number and date on Standard Form 1442 BACK, in Block 19, or by telegram. Please mark the outside of the envelope in which the bid is enclosed to show the amendment received

4. All Technical Amendments are available for download this date on the Army Corps of Engineers website at http://www.nws.usace.army.mil/ct/.,

Enclosures:
1. 00800
2. Section 00100 Intro
3. Section Section 02111 (A)

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE	PAGE OF PAGES
	1 | 2

2. AMENDMENT/MODIFICATION NO.	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO.(If applicable)
0003	12-Feb-2002	W68MD9-1337-8503	

6. ISSUED BY CODE DACA67
USA ENGINEER DISTRICT, SEATTLE
ATTN: CENWS-CT
P.O. BOX 3755
SEATTLE WA 98124-3755

7. ADMINISTERED BY (If other than item 6) CODE
See Item 6

8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)

CODE FACILITY CODE

X	9A. AMENDMENT OF SOLICITATION NO. DACA67-02-R-0208
X	9B. DATED (SEE ITEM 11) 11-Jan-2002
	10A. MOD. OF CONTRACT/ORDER NO.
	10B. DATED (SEE ITEM 13)

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

[X] The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer [ ] is extended, [X] is not extended.

Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS.
IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

[ ] A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.

[ ] B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).

[ ] C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:

[ ] D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor [ ] is not, [ ] is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)
Project: Repair Aircraft Parking Apron/Repair Runway, Mt Home AFB, Idaho

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
15B. CONTRACTOR/OFFEROR _____ (Signature of person authorized to sign)	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA BY _____ (Signature of Contracting Officer)	16C. DATE SIGNED 12-Feb-2002

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

DACA67-02 R-0208

PAGE 2 OF 2

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

1. The purpose of this Amendment Number Three (0003), dated 12 February 2002, is to provide for the following changes, clarifications, and/or additions:

a. DELETE: Section 0800 (Special Clauses)
INSERT: Revised Section 0800 (Special Clauses)

b. DELETE: Section 01005(AR) Site Specific Supplementary Requirements
INSERT: Revised Section 01005(AR)

c. DELETE: Section 02316 (R) Excavation, Trenching and Backfilling for Utilities Systems.
INSERT: Revised Section 02316 (R)

d. DELETE: Section 02531(R) Sanitary Sewers
INSERT: Revised Section 02531(R)

e. DELETE: Section 02753(R) Concrete Pavement for Airfield and other Heavy-Duty
INSERT: Revised Section 02753(R)

2. **THE PROPOSAL DUE DATE REMAINS UNCHANGED ON 15 FEB 03:00 P.M, Pacific Standard Time.**

3. NOTICE TO BIDDERS: Bidders must acknowledge receipt of this amendment by number and date on Standard Form 1442 BACK, in Block 19, or by telegram. Please mark the outside of the envelope in which the proposal is enclosed to show the amendment received

4. All Technical Amendments are available for download this date on the Army Corps of Engineers website at http://www.nws.usace.army.mil/ct/.,

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE	PAGE OF PAGES
	1 2

2. AMENDMENT/MODIFICATION NO.	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO.(If applicable)
0002	07-Feb-2002	W68MD9-1337-8503	

6. ISSUED BY CODE DACA67
USA ENGINEER DISTRICT, SEATTLE
ATTN: CENWS-CT
P.O. BOX 3755
SEATTLE WA 98124-3755

7. ADMINISTERED BY (If other than item 6) CODE
See Item 6

8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)

CODE FACILITY CODE

X	9A. AMENDMENT OF SOLICITATION NO. DACA67-02-R-0208
X	9B. DATED (SEE ITEM 11) 11-Jan-2002
	10A. MOD. OF CONTRACT/ORDER NO.
	10B. DATED (SEE ITEM 13)

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

[X] The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer [X] is extended, [ ] is not extended.

Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS.
IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

[ ] A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.

[ ] B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).

[ ] C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:

[ ] D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor [ ] is not, [ ] is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)
Solicitation No. DACA67-02-R-0208
Amendment No. 2

Title: Repair Aircraft Parking Apron/Repair Runway
Mountain Home Air Force Base, Idaho

SEE CONTINUATION SHEET

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
15B. CONTRACTOR/OFFEROR _____ (Signature of person authorized to sign)	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA BY _____ (Signature of Contracting Officer)	16C. DATE SIGNED 07-Feb-2002

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

A. This Amendment, **Amendment No. 2**, is being issued in order to incorporate Revisions to the Plans. These revisions are marked Revision "A1".

1) Revisions to Sheet No. 4 of 40, Safety/ Phasing Plan Phases 1 and 2

2) Revisions to Sheet No. 5 of 40, Safety/ Phasing Plan Phases 3 and 4

3) Revisions to Sheet No. 6 of 40, Safety Details

B. The attached revised sections are to be replaced in their entirety. Specification changes are generally identified, for convenience, either by strikeout for deletions, and underlining of text for additions or a single dark line in the margin. All portions of the revised or new pages shall apply whether or not changes have been indicated.

C. NOTICE TO OFFERORS: Offerors must acknowledge receipt of this Amendment by Number and Date on the Standard Form 1442 BACK in block 19, or by telegram.

D. The Proposal Due Date for this Solicitation is Extended by this Amendment. The Proposal Due Date is changed from ~~2:00 p.m. on 12 February 2002~~ to 2:00 p.m. Pacific Time on 15 February 2002.

Enclosures:

Replacement Sheet No. 4 of 40, Safety/ Phasing Plan Phases 1 and 2
Replacement Sheet No. 5 of 40, Safety/ Phasing Plan Phases 3 and 4
Replacement Sheet No. 6 of 40, Safety Details

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE	PAGE OF PAGES
	1 of 3

2. AMENDMENT/MODIFICATION NO.	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO.(If applicable)
0001	07-Feb-2002	W68MD9-1337-8503	

6. ISSUED BY CODE DACA67
USA ENGINEER DISTRICT, SEATTLE
ATTN: CENWS-CT
P.O. BOX 3755
SEATTLE WA 98124-3755

7. ADMINISTERED BY (If other than item 6) CODE
See Item 6

8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)

CODE FACILITY CODE

X	9A. AMENDMENT OF SOLICITATION NO. DACA67-02-R-0208
X	9B. DATED (SEE ITEM 11) 11-Jan-2002
	10A. MOD. OF CONTRACT/ORDER NO.
	10B. DATED (SEE ITEM 13)

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

[X] The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer [ ] is extended, [X] is not extended.

Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS.
IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

[ ] A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.

[ ] B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).

[ ] C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:

[ ] D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor [ ] is not, [ ] is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

Solicitation #DACA67-02-R-0208
Amendment No. 1

Title: Repair Aircraft Parking Apron/Repair Runway
Mountain Home AFB, Idaho

SEE CONTINUATION SHEET

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
15B. CONTRACTOR/OFFEROR _____ (Signature of person authorized to sign)	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA BY _____ (Signature of Contracting Officer)	16C. DATE SIGNED 07-Feb-2002

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

A. This Amendment is being issued in order to incorporate Technical Changes and to add and incorporate the Attendance List, Meeting Minutes and List of Questions and Answers from the Site Visit/Pre-proposal Conference held on Wednesday January 23, 2002.

1. Revision to Standard Form 1442 (Solicitation, Offer and Award)
Item 13 – D is changed to read as follows:

D. Offers providing less than ~~0~~ 120 calendar days for Government acceptance after the date offers are due will not be considered and be rejected.

2. Technical Changes:

a) Revisions to the SCHEDULE, Sections 00800 (Special Clauses), 01005AR, 01010R, 01025AR, 01356R, 02111A, 02220A, 02220R, 02300R, 02316R, 02510R, 02531R,02722R, 02749R, 02753A, and 02753R

b) Replaced Section 16900 with new Section 16900.

B. The attached revised sections are to be replaced in their entirety. Specification Changes are generally identified, for convenience, either by strikeout for deletions, and underlining of text for additions or a single dark line in the margin. All portions of the revised or new pages shall apply whether or not changes have been indicated.

C. The minutes of the preproposal conference, the sign in sheet from the meeting, and the list of questions and answers from the preproposal conference are provided with this amendment. They are **provided for information purposes only** and do not become part of the contract.

D. NOTICE TO OFFERORS: Offerors must acknowledge receipt of this Amendment By Number and Date on the Standard Form 1442 BACK in block 19, or by telegram.

E. The Proposal Due Time/Date remain unchanged at**: 2:00 p.m. Pacific Time on 12 February 2002 .**

Enclosures:

1) Revised Standard Form 1442

2) Revised SCHEDULE, Sections 00800 (Special Clauses), 01005AR, 01010R, 01025AR, 01356R, 02111A, 02220A, 02220R, 02300R, 02316R, 02510R, 02531R, 02722R, 02749R, 02753A, and 02753R

3) Replaced Section 16900 with new Section 16900

4) Sign-in Sheet/Attendance List for the Site Visit/Pre-proposal Conference

5) Meeting Minutes for the Site Visit/Pre-proposal Conference

6) List of Questions with Answers from Site Visit/Pre-proposal Conference

This page was intentionally left blank for duplex printing.

CLAUSES INCORPORATED BY FULL TEXT

TABLE OF CONTENTS
SECTION 00700 Contract Clauses

52.201-4001	Successor Contracting Officers	DEC 1999
52.202-1 Alt I	Definitions (Dec 2001) --Alternate I	MAY 2001
52.203-3	Gratuities	APR 1984
52.203-5	Covenant Against Contingent Fees	APR 1984
52.203-7	Anti-Kickback Procedures	JUL 1995
52.203-8	Cancellation, Rescission, and Recovery of Funds for Illegal or Improper Activity	JAN 1997
52.203-10	Price Or Fee Adjustment For Illegal Or Improper Activity	JAN 1997
52.203-12	Limitation On Payments To Influence Certain Federal Transactions	JUN 1997
52.204-4	Printed or Copied Double-Sided on Recycled Paper	AUG 2000
52.209-6	Protecting the Government's Interest When Subcontracting With Contractors Debarred, Suspended, or Proposed for Debarment	JUL 1995
52.211-13	Time Extensions	SEP 2000
52.212-4007	Environmental Litigation	NOV 1999
52.215-2	Audit and Records--Negotiation	JUN 1999
52.215-8	Order of Precedence--Uniform Contract Format	OCT 1997
52.215-11	Price Reduction for Defective Cost or Pricing Data--Modifications	OCT 1997
52.215-13	Subcontractor Cost or Pricing Data--Modifications	OCT 1997
52.219-8	Utilization of Small Business Concerns	OCT 2000
52.219-9	Small Business Subcontracting Plan	OCT 2001
52.219-16	Liquidated Damages-Subcontracting Plan	JAN 1999
52.219-25	Small Disadvantaged Business Participation Program--Disadvantaged Status and Reporting	OCT 1999
52.222-1	Notice To The Government Of Labor Disputes	FEB 1997
52.222-3	Convict Labor	AUG 1996
52.222-4	Contract Work Hours and Safety Standards Act - Overtime Compensation	SEP 2000
52.222-6	Davis Bacon Act	FEB 1995
52.222-7	Withholding of Funds	FEB 1988
52.222-8	Payrolls and Basic Records	FEB 1988
52.222-9	Apprentices and Trainees	FEB 1988
52.222-10	Compliance with Copeland Act Requirements	FEB 1988
52.222-11	Subcontracts (Labor Standards)	FEB 1988
52.222-12	Contract Termination-Debarment	FEB 1988
52.222-13	Compliance with Davis-Bacon and Related Act Regulations.	FEB 1988
52.222-14	Disputes Concerning Labor Standards	FEB 1988
52.222-15	Certification of Eligibility	FEB 1988
52.222-21	Prohibition Of Segregated Facilities	FEB 1999
52.222-23	Notice of Requirement for Affirmative Action to Ensure Equal Employment Opportunity for Construction	FEB 1999

52.222-26	Equal Opportunity	FEB 1999
52.222-27	Affirmative Action Compliance Requirements for Construction	FEB 1999
52.222-35	Equal Opportunity For Disabled Veterans, Veterans of the Vietnam Era and Other Eligible Veterans	DEC 2001
52.222-36	Affirmative Action For Workers With Disabilities	JUN 1998
52.222-37	Employment Reports On Special Disabled Veterans, Veterans Of The Vietnam Era and Other Eligible Veterans	DEC 2001
52.223-5	Pollution Prevention and Right-to-Know Information	APR 1998
52.223-6	Drug Free Workplace	MAY 2001
52.223-14	Toxic Chemical Release Reporting	OCT 2000
52.225-5	Trade Agreements	DEC 2001
52.225-11	Buy American Act--Balance of Payments Program--Construction Materials Under Trade Agreements	DEC 2001
52.225-13	Restrictions on Certain Foreign Purchases	JUL 2000
52.226-1	Utilization Of Indian Organizations And Indian-Owned Economic Enterprises	JUN 2000
52.227-1	Authorization and Consent	JUL 1995
52.228-2	Additional Bond Security	OCT 1997
52.228-11	Pledges Of Assets	FEB 1992
52.228-12	Prospective Subcontractor Requests for Bonds	OCT 1995
52.228-14	Irrevocable Letter of Credit	DEC 1999
52.228-15	Performance and Payment Bonds--Construction	JUL 2000
52.229-3	Federal, State And Local Taxes	JAN 1991
52.230-3	Disclosure And Consistency Of Cost Accounting Practices	APR 1998
52.232-5	Payments under Fixed-Price Construction Contracts	MAY 1997
52.232-16	Progress Payments	MAR 2000
52.232-23	Assignment Of Claims	JAN 1986
52.232-27	Prompt Payment for Construction Contracts	MAY 2001
52.232-33	Payment by Electronic Funds Transfer--Central Contractor Registration	MAY 1999
52.233-1	Disputes	DEC 1998
52.233-3	Protest After Award	AUG 1996
52.236-2	Differing Site Conditions	APR 1984
52.236-3	Site Investigation and Conditions Affecting the Work	APR 1984
52.236-5	Material and Workmanship	APR 1984
52.236-6	Superintendence by the Contractor	APR 1984
52.236-7	Permits and Responsibilities	NOV 1991
52.236-8	Other Contracts	APR 1984
52.236-9	Protection of Existing Vegetation, Structures, Equipment, Utilities, and Improvements	APR 1984
52.236-10	Operations and Storage Areas	APR 1984
52.236-11	Use and Possession Prior to Completion	APR 1984
52.236-12	Cleaning Up	APR 1984
52.236-13	Accident Prevention	NOV 1991
52.236-14	Availability and Use of Utility Services	APR 1984
52.236-15	Schedules for Construction Contracts	APR 1984
52.236-21	Specifications and Drawings for Construction	FEB 1997
52.236-26	Preconstruction Conference	FEB 1995
52.242-13	Bankruptcy	JUL 1995
52.242-14	Suspension of Work	APR 1984
52.243-4	Changes	AUG 1987
52.244-2	Subcontracts	AUG 1998
52.246-12	Inspection of Construction	AUG 1996
52.246-21	Warranty of Construction	MAR 1994
52.248-3	Value Engineering-Construction	FEB 2000

52.249-2 Alt I	Termination for Convenience of the Government (Fixed-Price) (Sep 1996) - Alternate I	SEP 1996
52.249-10	Default (Fixed-Price Construction)	APR 1984
52.253-1	Computer Generated Forms	JAN 1991
252.201-7000	Contracting Officer's Representative	DEC 1991
252.203-7002	Display Of DOD Hotline Poster	DEC 1991
252.204-7003	Control Of Government Personnel Work Product	APR 1992
252.209-7004	Subcontracting With Firms That Are Owned or Controlled By The Government of a Terrorist Country	MAR 1998
252.223-7004	Drug Free Work Force	SEP 1988
252.223-7004	Drug Free Work Force	SEP 1988
252.223-7006	Prohibition On Storage And Disposal Of Toxic And Hazardous Materials	APR 1993
252.227-7033	Rights in Shop Drawings	APR 1966
252.231-7000	Supplemental Cost Principles	DEC 1991
252.236-7000	Modification Proposals-Price Breakdown	DEC 1991
252.242-7000	Postaward Conference	DEC 1991
252.243-7001	Pricing Of Contract Modifications	DEC 1991
252.243-7002	Requests for Equitable Adjustment	MAR 1998

Successor Contracting Officers (52.201-4001)

The Contracting Officer who signed this contract is the primary Contracting Officer for the contract. Neverthless, any Contracting Officer assigned to the Seattle District and acting within his/her authority may take formal action on this contract when a contract action needs to be taken and the primary Contracting Officer is unavailable.

52.202-1 DEFINITIONS (DEC 2001) --ALTERNATE I (MAY 2001)

(a) Agency head or head of the agency means the Secretary (Attorney General, Administrator, Governor, Chairperson, or other chief official, as appropriate) of the agency, unless otherwise indicated, including any deputy or assistant chief official of the executive agency.

(b) "Commercial component" means any component that is a commercial item.

(c) Any item, other than real property, that is of a type customarily used by the general public or by non-governmental entities for purposes other than governmental purposes, and that--

(i) Has been sold, leased, or licensed to the general public; or

(ii) Has been offered for sale, lease, or license to the general public;

(2) Any item that evolved from an item described in paragraph (c)(1) of this clause through advances in technology or performance and that is not yet available in the commercial marketplace, but will be available in the commercial marketplace in time to satisfy the delivery requirements under a Government solicitation;

(3) Any item that would satisfy a criterion expressed in paragraphs (c)(1) or (c)(2) of this clause, but for--

(i) Modifications of a type customarily available in the commercial marketplace; or

(ii) Minor modifications of a type not customarily available in the commercial marketplace made to meet Federal Government requirements. "Minor" modifications means modifications that do not significantly alter the nongovernmental function or essential physical characteristics of an item or component, or change the purpose of a process. Factors to be considered in determining whether a modification is minor include the value and size of the modification and the comparative value and size of the final product. Dollar values and percentages may be used as guideposts, but are not conclusive evidence that a modification is minor;

(4) Any combination of items meeting the requirements of paragraphs (c)(1), (2), (3), or (5) of this clause that are of a type customarily combined and sold in combination to the general public;

(5) Installation services, maintenance services, repair services, training services, and other services if--

(i) Such services are procured for support of an item referred to in paragraph (c)(1), (2), (3), or (4) of this definition, regardless of whether such services are provided by the same source or at the same time as the item; and

(ii) The source of such services provides similar services contemporaneously to the general public under terms and conditions similar to those offered to the Federal Government;

(6) Services of a type offered and sold competitively in substantial quantities in the commercial marketplace based on established catalog or market prices for specific tasks performed under standard commercial terms and conditions. This does not include services that are sold based on hourly rates without an established catalog or market price for a specific service performed. For purposes of these services--

(i) Catalog price means a price included in a catalog, price list, schedule, or other form that is regularly maintained by the manufacturer or vendor, is either published or otherwise available for inspection by customers, and states prices at which sales are currently, or were last, made to a significant number of buyers constituting the general public; and

(ii) Market prices means current prices that are established in the course of ordinary trade between buyers and sellers free to bargain and that can be substantiated through competition or from sources independent of the offerors.

(7) Any item, combination of items, or service referred to in subparagraphs (c)(1) through (c)(6), notwithstanding the fact that the item, combination of items, or service is transferred between or among separate divisions, subsidiaries, or affiliates of a Contractor; or

(8) A nondevelopmental item, if the procuring agency determines the item was developed exclusively at private expense and sold in substantial quantities, on a competitive basis, to multiple State and local Governments.

(d) Component means any item supplied to the Government as part of an end item or of another component, except that for use in 52.225-9, and 52.225-11 see the definitions in 52.225-9(a) and 52.225-11(a).

(e) Contracting Officer means a person with the authority to enter into, administer, and/or terminate contracts and make related determinations and findings. The term includes certain authorized representatives of the Contracting Officer acting within the limits of their authority as delegated by the Contracting Officer.

(f) Nondevelopmental item means--

(1) Any previously developed item of supply used exclusively for governmental purposes by a Federal agency, a State or local government, or a foreign government with which the United States has a mutual defense cooperation agreement;

(2) Any item described in paragraph (f)(1) of this definition that requires only minor modification or modifications of a type customarily available in the commercial marketplace in order to meet the requirements of the procuring department or agency; or

(3) Any item of supply being produced that does not meet the requirements of paragraph (f)(1) or (f)(2) solely because the item is not yet in use.

(End of clause)

52.203-3 GRATUITIES (APR 1984)

(a) The right of the Contractor to proceed may be terminated by written notice if, after notice and hearing, the agency head or a designee determines that the Contractor, its agent, or another representative--

(1) Offered or gave a gratuity (e.g., an entertainment or gift) to an officer, official, or employee of the Government; and

(2) Intended, by the gratuity, to obtain a contract or favorable treatment under a contract.

(b) The facts supporting this determination may be reviewed by any court having lawful jurisdiction.

(c) If this contract is terminated under paragraph (a) of this clause, the Government is entitled--

(1) To pursue the same remedies as in a breach of the contract; and

(2) In addition to any other damages provided by law, to exemplary damages of not less than 3 nor more than 10 times the cost incurred by the Contractor in giving gratuities to the person concerned, as determined by the agency head or a designee. (This subparagraph (c)(2) is applicable only if this contract uses money appropriated to the Department of Defense.)

(d) The rights and remedies of the Government provided in this clause shall not be exclusive and are in addition to any other rights and remedies provided by law or under this contract.

(End of clause)

52.203-5 COVENANT AGAINST CONTINGENT FEES (APR 1984)

(a) The Contractor warrants that no person or agency has been employed or retained to solicit or obtain this contract upon an agreement or understanding for a contingent fee, except a bona fide employee or agency. For breach or violation of this warranty, the Government shall have the right to annul this contract without liability or, in its discretion, to deduct from the contract price or consideration, or otherwise recover, the full amount of the contingent fee.

(b) "Bona fide agency," as used in this clause, means an established commercial or selling agency, maintained by a contractor for the purpose of securing business, that neither exerts nor proposes to exert improper influence to solicit or obtain Government contracts nor holds itself out as being able to obtain any Government contract or contracts through improper influence.

"Bona fide employee," as used in this clause, means a person, employed by a contractor and subject to the contractor's supervision and control as to time, place, and manner of performance, who neither exerts nor proposes to exert improper influence to solicit or obtain Government contracts nor holds out as being able to obtain any Government contract or contracts through improper influence.

"Contingent fee," as used in this clause, means any commission, percentage, brokerage, or other fee that is contingent upon the success that a person or concern has in securing a Government contract.

"Improper influence," as used in this clause, means any influence that induces or tends to induce a Government employee or officer to give consideration or to act regarding a Government contract on any basis other than the merits of the matter.

(End of clause)

52.203-7 ANTI-KICKBACK PROCEDURES. (JUL 1995)

(a) Definitions.

"Kickback," as used in this clause, means any money, fee, commission, credit, gift, gratuity, thing of value, or compensation of any kind which is provided, directly or indirectly, to any prime Contractor, prime Contractor employee, subcontractor, or subcontractor employee for the purpose of improperly obtaining or rewarding favorable treatment in connection with a prime contract or in connection with a subcontract relating to a prime contract.

"Person," as used in this clause, means a corporation, partnership, business association of any kind, trust, joint-stock company, or individual.

"Prime contract," as used in this clause, means a contract or contractual action entered into by the United States for the purpose of obtaining supplies, materials, equipment, or services of any kind.

"Prime Contractor," as used in this clause, means a person who has entered into a prime contract with the United States.

"Prime Contractor employee," as used in this clause, means any officer, partner, employee, or agent of a prime Contractor.

"Subcontract," as used in this clause, means a contract or contractual action entered into by a prime Contractor or subcontractor for the purpose of obtaining supplies, materials, equipment, or services of any kind under a prime contract.

"Subcontractor," as used in this clause, (1) means any person, other than the prime Contractor, who offers to furnish or furnishes any supplies, materials, equipment, or services of any kind under a prime contract or a subcontract entered into in connection with such prime contract, and (2) includes any person who offers to furnish or furnishes general supplies to the prime Contractor or a higher tier subcontractor.

"Subcontractor employee," as used in this clause, means any officer, partner, employee, or agent of a subcontractor.

(b) The Anti-Kickback Act of 1986 (41 U.S.C. 51-58) (the Act), prohibits any person from -

(1) Providing or attempting to provide or offering to provide any kickback;

(2) Soliciting, accepting, or attempting to accept any kickback; or

(3) Including, directly or indirectly, the amount of any kickback in the contract price charged by a prime Contractor to the United States or in the contract price charged by a subcontractor to a prime Contractor or higher tier subcontractor.

(c)(1) The Contractor shall have in place and follow reasonable procedures designed to prevent and detect possible violations described in paragraph (b) of this clause in its own operations and direct business relationships.

(2) When the Contractor has reasonable grounds to believe that a violation described in paragraph (b) of this clause may have occurred, the Contractor shall promptly report in writing the possible violation. Such reports shall be made to the inspector general of the contracting agency, the head of the contracting agency if the agency does not have an inspector general, or the Department of Justice.

(3) The Contractor shall cooperate fully with any Federal agency investigating a possible violation described in paragraph (b) of this clause.

(4) The Contracting Officer may (i) offset the amount of the kickback against any monies owed by the United States under the prime contract and/or (ii) direct that the Prime Contractor withhold, from sums owed a subcontractor under the prime contract, the amount of any kickback. The Contracting Officer may order the monies withheld under subdivision (c)(4)(ii) of this clause be paid over to the Government unless the Government has already offset those monies under subdivision (c)(4)(i) of this clause. In either case, the Prime Contractor shall notify the Contracting Officer when the monies are withheld.

(5) The Contractor agrees to incorporate the substance of this clause, including this subparagraph (c)(5) but excepting subparagraph (c)(1), in all subcontracts under this contract which exceed $100,000.

(End of clause)

52.203-8 CANCELLATION, RESCISSION, AND RECOVERY OF FUNDS FOR ILLEGAL OR IMPROPER ACTIVITY (JAN 1997)

(a) If the Government receives information that a contractor or a person has engaged in conduct constituting a violation of subsection (a), (b), (c), or (d) of Section 27 of the Office of Federal Procurement Policy Act (41 U.S.C. 423) (the Act), as amended by section 4304 of the 1996 National Defense Authorization Act for Fiscal Year 1996 (Pub. L. 104-106), the Government may--

(1) Cancel the solicitation, if the contract has not yet been awarded or issued; or

(2) Rescind the contract with respect to which--

(i) The Contractor or someone acting for the Contractor has been convicted for an offense where the conduct constitutes a violation of subsection 27(a) or (b) of the Act for the purpose of either--

(A) Exchanging the information covered by such subsections for anything of value; or

(B) Obtaining or giving anyone a competitive advantage in the award of a Federal agency procurement contract; or

(ii) The head of the contracting activity has determined, based upon a preponderance of the evidence, that the Contractor or someone acting for the Contractor has engaged in conduct constituting an offense punishable under subsections 27(e)(1) of the Act.

(b) If the Government rescinds the contract under paragraph (a) of this clause, the Government is entitled to recover, in addition to any penalty prescribed by law, the amount expended under the contract.

(c) The rights and remedies of the Government specified herein are not exclusive, and are in addition to any other rights and remedies provided by law, regulation, or under this contract.

(End of clause)

52.203-10 PRICE OR FEE ADJUSTMENT FOR ILLEGAL OR IMPROPER ACTIVITY (JAN 1997)

(a) The Government, at its election, may reduce the price of a fixed-price type contract and the total cost and fee under a cost-type contract by the amount of profit or fee determined as set forth in paragraph (b) of this clause if the head of the contracting activity or designee determines that there was a violation of subsection 27 (a), (b), or (c) of the Office of Federal Procurement Policy Act, as amended (41 U.S.C. 423), as implemented in section 3.104 of the Federal Acquisition Regulation.

(b) The price or fee reduction referred to in paragraph (a) of this clause shall be--

(1) For cost-plus-fixed-fee contracts, the amount of the fee specified in the contract at the time of award;

(2) For cost-plus-incentive-fee contracts, the target fee specified in the contract at the time of award, notwithstanding any minimum fee or "fee floor" specified in the contract;

(3) For cost-plus-award-fee contracts--

(i) The base fee established in the contract at the time of contract award;

(ii) If no base fee is specified in the contract, 30 percent of the amount of each award fee otherwise payable to the Contractor for each award fee evaluation period or at each award fee determination point.

(4) For fixed-price-incentive contracts, the Government may--

(i) Reduce the contract target price and contract target profit both by an amount equal to the initial target profit specified in the contract at the time of contract award; or

(ii) If an immediate adjustment to the contract target price and contract target profit would have a significant adverse impact on the incentive price revision relationship under the contract, or adversely affect the contract financing provisions, the Contracting Officer may defer such adjustment until establishment of the total final price of the contract. The total final price established in accordance with the incentive price revision provisions of the contract shall be reduced by an amount equal to the initial target profit specified in the contract at the time of contract award and such reduced price shall be the total final contract price.

(5) For firm-fixed-price contracts, by 10 percent of the initial contract price or a profit amount determined by the Contracting Officer from records or documents in existence prior to the date of the contract award.

(c) The Government may, at its election, reduce a prime contractor's price or fee in accordance with the procedures of paragraph (b) of this clause for violations of the Act by its subcontractors by an amount not to exceed the amount of profit or fee reflected in the subcontract at the time the subcontract was first definitively priced.

(d) In addition to the remedies in paragraphs (a) and (c) of this clause, the Government may terminate this contract for default. The rights and remedies of the Government specified herein are not exclusive, and are in addition to any other rights and remedies provided by law or under this contract.

(End of clause)

52.203-12 LIMITATION ON PAYMENTS TO INFLUENCE CERTAIN FEDERAL TRANSACTIONS (JUN 1997)

(a) Definitions.

"Agency," as used in this clause, means executive agency as defined in 2.101.

"Covered Federal action," as used in this clause, means any of the following Federal actions:

(1) The awarding of any Federal contract.

(2) The making of any Federal grant.

(3) The making of any Federal loan.

(4) The entering into of any cooperative agreement.

(5) The extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.

"Indian tribe" and "tribal organization," as used in this clause, have the meaning provided in section 4 of the Indian Self-Determination and Education Assistance Act (25 U.S.C. 450B) and include Alaskan Natives.

"Influencing or attempting to influence," as used in this clause, means making, with the intent to influence, any communication to or appearance before an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with any covered Federal action.

"Local government," as used in this clause, means a unit of government in a State and, if chartered, established, or otherwise recognized by a State for the performance of a governmental duty, including a local public authority, a special district, an intrastate district, a council of governments, a sponsor group representative organization, and any other instrumentality of a local government.

"Officer or employee of an agency," as used in this clause, includes the following individuals who are employed by an agency:

(1) An individual who is appointed to a position in the Government under Title 5, United States Code, including a position under a temporary appointment.

(2) A member of the uniformed services, as defined in subsection 101(3), Title 37, United States Code.

(3) A special Government employee, as defined in section 202, Title 18, United States Code.

(4) An individual who is a member of a Federal advisory committee, as defined by the Federal Advisory Committee Act, Title 5, United States Code, appendix 2.

"Person," as used in this clause, means an individual, corporation, company, association, authority, firm, partnership, society, State, and local government, regardless of whether such entity is operated for profit, or not for profit. This term excludes an Indian tribe, tribal organization, or any other Indian organization with respect to expenditures specifically permitted by other Federal law.

"Reasonable compensation," as used in this clause, means, with respect to a regularly employed officer or employee of any person, compensation that is consistent with the normal compensation for such officer or employee for work that is not furnished to, not funded by, or not furnished in cooperation with the Federal Government.

"Reasonable payment," as used in this clause, means, with respect to professional and other technical services, a payment in an amount that is consistent with the amount normally paid for such services in the private sector.

"Recipient," as used in this clause, includes the Contractor and all subcontractors. This term excludes an Indian tribe, tribal organization, or any other Indian organization with respect to expenditures specifically permitted by other Federal law.

"Regularly employed," as used in this clause, means, with respect to an officer or employee of a person requesting or receiving a Federal contract, an officer or employee who is employed by such person for at least 130 working days within 1 year immediately preceding the date of the submission that initiates agency consideration of such person for receipt of such contract. An officer or employee who is employed by such person for less than 130 working days within 1 year immediately preceding the date of the submission that initiates agency consideration of such person shall be considered to be regularly employed as soon as he or she is employed by such person for 130 working days.

"State," as used in this clause, means a State of the United States, the District of Columbia, the Commonwealth of Puerto Rico, a territory or possession of the United States, an agency or instrumentality of a State, and multi-State, regional, or interstate entity having governmental duties and powers.

(b) Prohibitions.

(1) Section 1352 of Title 31, United States Code, among other things, prohibits a recipient of a Federal contract, grant, loan, or cooperative agreement from using appropriated funds to pay any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with any of the following covered Federal actions: the awarding of any Federal contract; the making of any Federal grant; the making of any Federal loan; the entering into of any cooperative agreement; or the modification of any Federal contract, grant, loan, or cooperative agreement.

(2) The Act also requires Contractors to furnish a disclosure if any funds other than Federal appropriated funds (including profit or fee received under a covered Federal transaction) have been paid, or will be paid, to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with a Federal contract, grant, loan, or cooperative agreement.

(3) The prohibitions of the Act do not apply under the following conditions:

(i) Agency and legislative liaison by own employees.

(A) The prohibition on the use of appropriated funds, in subparagraph (b)(1) of this clause, does not apply in the case of a payment of reasonable compensation made to an officer or employee of a person requesting or receiving a covered Federal action if the payment is for agency and legislative liaison activities not directly related to a covered Federal action.

(B) For purposes of subdivision (b)(3)(i)(A) of this clause, providing any information specifically requested by an agency or Congress is permitted at any time.

(C) The following agency and legislative liaison activities are permitted at any time where they are not related to a specific solicitation for any covered Federal action:

(1) Discussing with an agency the qualities and characteristics (including individual demonstrations) of the person's products or services, conditions or terms of sale, and service capabilities.

(2) Technical discussions and other activities regarding the application or adaptation of the person's products or services for an agency's use.

(D) The following agency and legislative liaison activities are permitted where they are prior to formal solicitation of any covered Federal action--

(1) Providing any information not specifically requested but necessary for an agency to make an informed decision about initiation of a covered Federal action;

(2) Technical discussions regarding the preparation of an unsolicited proposal prior to its official submission; and

(3) Capability presentations by persons seeking awards from an agency pursuant to the provisions of the Small Business Act, as amended by Pub. L. 95-507, and subsequent amendments.

(E) Only those services expressly authorized by subdivision (b)(3)(i)(A) of this clause are permitted under this clause.

(ii) Professional and technical services.

(A) The prohibition on the use of appropriated funds, in subparagraph (b)(1) of this clause, does not apply in the case of--

(1) A payment of reasonable compensation made to an officer or employee of a person requesting or receiving a covered Federal action or an extension, continuation, renewal, amendment, or modification of a covered Federal action, if payment is for professional or technical services rendered directly in the preparation, submission, or negotiation of any bid, proposal, or application for that Federal action or for meeting requirements imposed by or pursuant to law as a condition for receiving that Federal action.

(2) Any reasonable payment to a person, other than an officer or employee of a person requesting or receiving a covered Federal action or an extension, continuation, renewal, amendment, or modification of a covered Federal action if the payment is for professional or technical services rendered directly in the preparation, submission, or negotiation of any bid, proposal, or application for that Federal action or for meeting requirements imposed by or pursuant to law as a condition for receiving that Federal action. Persons other than officers or employees of a person requesting or receiving a covered Federal action include consultants and trade associations.

(B) For purposes of subdivision (b)(3)(ii)(A) of this clause, "professional and technical services" shall be limited to advice and analysis directly applying any professional or technical discipline. For example, drafting of a legal document accompanying a bid or proposal by a lawyer is allowable. Similarly, technical advice provided by an engineer on the performance or operational capability of a piece of equipment rendered directly in the negotiation of a contract is allowable. However, communications with the intent to influence made by a professional (such as a licensed lawyer) or a technical person (such as a licensed accountant) are not allowable under this section unless they provide advice and analysis directly applying their professional or technical expertise and unless the advice or analysis is rendered directly and solely in the preparation, submission or negotiation of a covered Federal action. Thus, for example, communications with the intent to influence made by a lawyer that do not provide legal advice or analysis directly and solely related to the legal aspects of his or her client's proposal, but generally advocate one proposal over another are not allowable under this section because the lawyer is not providing professional legal services. Similarly, communications with the intent to influence made by an engineer providing an engineering analysis prior to the preparation or submission of a bid or proposal are not allowable under this section since the engineer is providing technical services but not directly in the preparation, submission or negotiation of a covered Federal action.

(C) Requirements imposed by or pursuant to law as a condition for receiving a covered Federal award include those required by law or regulation and any other requirements in the actual award documents.

(D) Only those services expressly authorized by subdivisions (b)(3)(ii)(A)(1) and (2) of this clause are permitted under this clause.

(E) The reporting requirements of FAR 3.803(a) shall not apply with respect to payments of reasonable compensation made to regularly employed officers or employees of a person.

(c) Disclosure.

(1) The Contractor who requests or receives from an agency a Federal contract shall file with that agency a disclosure form, OMB standard form LLL, Disclosure of Lobbying Activities, if such person has made or has agreed to make any payment using nonappropriated funds (to include profits from any covered Federal action), which would be prohibited under subparagraph (b)(1) of this clause, if paid for with appropriated funds.

(2) The Contractor shall file a disclosure form at the end of each calendar quarter in which there occurs any event that materially affects the accuracy of the information contained in any disclosure form previously filed by such person under subparagraph (c)(1) of this clause. An event that materially affects the accuracy of the information reported includes--

(i) A cumulative increase of $25,000 or more in the amount paid or expected to be paid for influencing or attempting to influence a covered Federal action; or

(ii) A change in the person(s) or individual(s) influencing or attempting to influence a covered Federal action; or

(iii) A change in the officer(s), employee(s), or Member(s) contacted to influence or attempt to influence a covered Federal action.

(3) The Contractor shall require the submittal of a certification, and if required, a disclosure form by any person who requests or receives any subcontract exceeding $100,000 under the Federal contract.

(4) All subcontractor disclosure forms (but not certifications) shall be forwarded from tier to tier until received by the prime Contractor. The prime Contractor shall submit all disclosures to the Contracting Officer at the end of the calendar quarter in which the disclosure form is submitted by the subcontractor. Each subcontractor certification shall be retained in the subcontract file of the awarding Contractor.

(d) Agreement. The Contractor agrees not to make any payment prohibited by this clause.

(e) Penalties.

(1) Any person who makes an expenditure prohibited under paragraph (a) of this clause or who fails to file or amend the disclosure form to be filed or amended by paragraph (b) of this clause shall be subject to civil penalties as provided for by 31 U.S.C. 1352. An imposition of a civil penalty does not prevent the Government from seeking any other remedy that may be applicable.

(2) Contractors may rely without liability on the representation made by their subcontractors in the certification and disclosure form.

(f) Cost allowability. Nothing in this clause makes allowable or reasonable any costs which would otherwise be unallowable or unreasonable. Conversely, costs made specifically unallowable by the requirements in this clause will not be made allowable under any other provision.

(End of clause)

52.204-4 PRINTED OR COPIED DOUBLE-SIDED ON RECYCLED PAPER (AUG 2000)

(a) Definitions. As used in this clause--

“Postconsumer material” means a material or finished product that has served its intended use and has been discarded for disposal or recovery, having completed its life as a consumer item. Postconsumer material is a part of the broader category of “recovered material.” For paper and paper products, postconsumer material means “postconsumer fiber” defined by the U.S. Environmental Protection Agency (EPA) as--

(1) Paper, paperboard, and fibrous materials from retail stores, office buildings, homes, and so forth, after they have passed through their end-usage as a consumer item, including: used corrugated boxes; old newspapers; old magazines; mixed waste paper; tabulating cards; and used cordage; or

(2) All paper, paperboard, and fibrous materials that enter and are collected from municipal solid waste; but not

(3) Fiber derived from printers' over-runs, converters' scrap, and over-issue publications.

“Printed or copied double-sided” means printing or reproducing a document so that information is on both sides of a sheet of paper.

“Recovered material,” for paper and paper products, is defined by EPA in its Comprehensive Procurement Guideline as “recovered fiber” and means the following materials:

(1) Postconsumer fiber; and

(2) Manufacturing wastes such as--

(i) Dry paper and paperboard waste generated after completion of the papermaking process (that is, those manufacturing operations up to and including the cutting and trimming of the paper machine reel into smaller rolls or rough sheets) including: envelope cuttings, bindery trimmings, and other paper and paperboard waste resulting from printing, cutting, forming, and other converting operations; bag, box, and carton manufacturing wastes; and butt rolls, mill wrappers, and rejected unused stock; and

(ii) Repulped finished paper and paperboard from obsolete inventories of paper and paperboard manufacturers, merchants, wholesalers, dealers, printers, converters, or others.

(b) In accordance with Section 101 of Executive Order 13101 of September 14, 1998, Greening the Government through Waste Prevention, Recycling, and Federal Acquisition, the Contractor is encouraged to submit paper documents, such as offers, letters, or reports, that are printed or copied double-sided on recycled paper that meet minimum content standards specified in Section 505 of Executive Order 13101, when not using electronic commerce methods to submit information or data to the Government.

(c) If the Contractor cannot purchase high-speed copier paper, offset paper, forms bond, computer printout paper, carbonless paper, file folders, white wove envelopes, writing and office paper, book paper, cotton fiber paper, and cover stock meeting the 30 percent postconsumer material standard for use in submitting paper documents to the Government, it should use paper containing no less than 20 percent postconsumer material. This lesser standard should be used only when paper meeting the 30 percent postconsumer material standard is not obtainable at a reasonable price or does not meet reasonable performance standards.

(End of clause)

52.209-6 PROTECTING THE GOVERNMENT'S INTEREST WHEN SUBCONTRACTING WITH CONTRACTORS DEBARRED, SUSPENDED, OR PROPOSED FOR DEBARMENT (JUL 1995)

(a) The Government suspends or debars Contractors to protect the Government's interests. The Contractor shall not enter into any subcontract in excess of the $25,000 with a Contractor that is debarred, suspended, or proposed for debarment unless there is a compelling reason to do so.

(b) The Contractor shall require each proposed first-tier subcontractor, whose subcontract will exceed $25,000, to disclose to the Contractor, in writing, whether as of the time of award of the subcontract, the subcontractor, or its principles, is or is not debarred, suspended, or proposed for debarment by the Federal Government.

(c) A corporate officer or a designee of the Contractor shall notify the Contracting Officer, in writing, before entering into a subcontract with a party that is debarred, suspended, or proposed for debarment (see FAR 9.404 for information on the List of Parties Excluded from Federal Procurement and Nonprocurement Programs). The notice must include the following:

(1) The name of the subcontractor.

(2) The Contractor's knowledge of the reasons for the subcontractor being on the List of Parties Excluded from Federal Procurement and Nonprocurement Programs.

(3) The compelling reason(s) for doing business with the subcontractor notwithstanding its inclusion on the List of Parties Excluded from Federal Procurement and Nonprocurement Programs.

(4) The systems and procedures the Contractor has established to ensure that it is fully protecting the Government's interests when dealing with such subcontractor in view of the specific basis for the party's debarment, suspension, or proposed debarment.

(End of clause)

52.211-13 TIME EXTENSIONS (SEP 2000)

Time extensions for contract changes will depend upon the extent, if any, by which the changes cause delay in the completion of the various elements of construction. The change order granting the time extension may provide that the contract completion date will be extended only for those specific elements related to the changed work and that the remaining contract completion dates for all other portions of the work will not be altered. The change order also may provide an equitable readjustment of liquidated damages under the new completion schedule.

(End of clause)

52.212-4007 ENVIRONMENTAL LITIGATION

(a) If the performance of all or any part of the work is suspended, delayed, or interrupted due to an order of a court of competent jurisdiction as a result of environmental litigation, as defined below, the Contracting Officer, at the request of the Contractor, shall determine whether the order is due in any part to the acts or omissions of the Contractor or a Subcontractor at any tier not required by the terms of this contract. If it is determined that the order is not due in any part to acts or omissions of the Contractor or a Subcontractor at any tier other than as required by the terms of this contract, such suspension, delay, or interruption shall be considered as if ordered by the Contracting Officer in the administration of this contract under the terms of the "Suspension of Work" clause of this contract. The period of such suspension, delay or interruption shall be considered unreasonable, and an adjustment shall be made for any increase in the cost of performance of this contract (excluding profit) as provided in that clause, subject to all the provisions thereof.

(b) The term "environmental litigation", as used herein, means a lawsuit alleging that the work will have an adverse effect on the environment or that the Government has not duly considered, either substantially or procedurally, the effect of the work on the environment.

52.215-2 AUDIT AND RECORDS--NEGOTIATION (JUN 1999)

(a) As used in this clause, "records" includes books, documents, accounting procedures and practices, and other data, regardless of type and regardless of whether such items are in written form, in the form of computer data, or in any other form.

(b) Examination of costs. If this is a cost-reimbursement, incentive, time-and-materials, labor-hour, or price redeterminable contract, or any combination of these, the Contractor shall maintain and the Contracting Officer, or an authorized representative of the Contracting Officer, shall have the right to examine and audit all records and other evidence sufficient to reflect properly all costs claimed to have been incurred or anticipated to be incurred directly or indirectly in performance of this contract. This right of examination shall include inspection at all reasonable times of the Contractor's plants, or parts of them, engaged in performing the contract.

(c) Cost or pricing data. If the Contractor has been required to submit cost or pricing data in connection with any pricing action relating to this contract, the Contracting Officer, or an authorized representative of the Contracting Officer, in order to evaluate the accuracy, completeness, and currency of the cost or pricing data, shall have the right to examine and audit all of the Contractor's records, including computations and projections, related to--

(1) The proposal for the contract, subcontract, or modification;

(2) The discussions conducted on the proposal(s), including those related to negotiating;

(3) Pricing of the contract, subcontract, or modification; or

(4) Performance of the contract, subcontract or modification.

(d) Comptroller General--(1) The Comptroller General of the United States, or an authorized representative, shall have access to and the right to examine any of the Contractor's directly pertinent records involving transactions related to this contract or a subcontract hereunder.

(2) This paragraph may not be construed to require the Contractor or subcontractor to create or maintain any record that the Contractor or subcontractor does not maintain in the ordinary course of business or pursuant to a provision of law.

(e) Reports. If the Contractor is required to furnish cost, funding, or performance reports, the Contracting Officer or an authorized representative of the Contracting Officer shall have the right to examine and audit the supporting records and materials, for the purpose of evaluating (1) the effectiveness of the Contractor's policies and procedures to produce data compatible with the objectives of these reports and (2) the data reported.

(f) Availability. The Contractor shall make available at its office at all reasonable times the records, materials, and other evidence described in paragraphs (a), (b), (c), (d), and (e) of this clause, for examination, audit, or reproduction, until 3 years after final payment under this contract or for any shorter period specified in Subpart 4.7, Contractor Records Retention, of the Federal Acquisition Regulation (FAR), or for any longer period required by statute or by other clauses of this contract. In addition--

(1) If this contract is completely or partially terminated, the Contractor shall make available the records relating to the work terminated until 3 years after any resulting final termination settlement; and

(2) The Contractor shall make available records relating to appeals under the Disputes clause or to litigation or the settlement of claims arising under or relating to this contract until such appeals, litigation, or claims are finally resolved.

(g) The Contractor shall insert a clause containing all the terms of this clause, including this paragraph (g), in all subcontracts under this contract that exceed the simplified acquisition threshold, and--

(1) That are cost-reimbursement, incentive, time-and-materials, labor-hour, or price-redeterminable type or any combination of these;

(2) For which cost or pricing data are required; or

(3) That require the subcontractor to furnish reports as discussed in paragraph (e) of this clause.

The clause may be altered only as necessary to identify properly the contracting parties and the Contracting Officer under the Government prime contract.

(End of clause)

52.215-8 ORDER OF PRECEDENCE--UNIFORM CONTRACT FORMAT (OCT 1997)

Any inconsistency in this solicitation or contract shall be resolved by giving precedence in the following order:

(a) The Schedule (excluding the specifications).

(b) Representations and other instructions.

(c) Contract clauses.

(d) Other documents, exhibits, and attachments.

(e) The specifications.

52.215-11 PRICE REDUCTION FOR DEFECTIVE COST OR PRICING DATA--MODIFICATIONS (OCT 1997)

(a) This clause shall become operative only for any modification to this contract involving a pricing adjustment expected to exceed the threshold for submission of cost or pricing data at FAR 15.403-4, except that this clause does not apply to any modification if an exception under FAR 15.403-1 applies.

(b) If any price, including profit or fee, negotiated in connection with any modification under this clause, or any cost reimbursable under this contract, was increased by any significant amount because (1) the Contractor or a subcontractor furnished cost or pricing data that were not complete, accurate, and current as certified in its Certificate of Current Cost or Pricing Data, (2) a subcontractor or prospective subcontractor furnished the Contractor cost or pricing data that were not complete, accurate, and current as certified in the Contractor's Certificate of Current Cost or Pricing Data, or (3) any of these parties furnished data of any description that were not accurate, the price or cost shall be reduced accordingly and the contract shall be modified to reflect the reduction. This right to a price reduction is limited to that resulting from defects in data relating to modifications for which this clause becomes operative under paragraph (a) of this clause.

(c) Any reduction in the contract price under paragraph (b) of this clause due to defective data from a prospective subcontractor that was not subsequently awarded the subcontract shall be limited to the amount, plus applicable overhead and profit markup, by which--

(1) The actual subcontract; or

(2) The actual cost to the Contractor, if there was no subcontract, was less than the prospective subcontract cost estimate submitted by the Contractor; provided, that the actual subcontract price was not itself affected by defective cost or pricing data.

(d)(1) If the Contracting Officer determines under paragraph (b) of this clause that a price or cost reduction should be made, the Contractor agrees not to raise the following matters as a defense:

(i) The Contractor or subcontractor was a sole source supplier or otherwise was in a superior bargaining position and thus the price of the contract would not have been modified even if accurate, complete, and current cost or pricing data had been submitted.

(ii) The Contracting Officer should have known that the cost or pricing data in issue were defective even though the Contractor or subcontractor took no affirmative action to bring the character of the data to the attention of the Contracting Officer.

(iii) The contract was based on an agreement about the total cost of the contract and there was no agreement about the cost of each item procured under the contract.

(iv) The Contractor or subcontractor did not submit a Certificate of Current Cost or Pricing Data.

(2)(i) Except as prohibited by subdivision (d)(2)(ii) of this clause, an offset in an amount determined appropriate by the Contracting Officer based upon the facts shall be allowed against the amount of a contract price reduction if--

(A) The Contractor certifies to the Contracting Officer that, to the best of the Contractor's knowledge and belief, the Contractor is entitled to the offset in the amount requested; and

(B) The Contractor proves that the cost or pricing data were available before the “as of” date specified on its Certificate of Current Cost or Pricing Data, and that the data were not submitted before such date.

(ii) An offset shall not be allowed if--

(A) The understated data were known by the Contractor to be understated before the “as of” date specified on its Certificate of Current Cost or Pricing Data; or

(B) The Government proves that the facts demonstrate that the contract price would not have increased in the amount to be offset even if the available data had been submitted before the “as of” date specified on its Certificate of Current Cost or Pricing Data.

(e) If any reduction in the contract price under this clause reduces the price of items for which payment was made prior to the date of the modification reflecting the price reduction, the Contractor shall be liable to and shall pay the United States at the time such overpayment is repaid--

(1) Simple interest on the amount of such overpayment to be computed from the date(s) of overpayment to the Contractor to the date the Government is repaid by the Contractor at the applicable underpayment rate effective for each quarter prescribed by the Secretary of the Treasury under 26 U.S.C. 6621(a)(2); and

A penalty equal to the amount of the overpayment, if the Contractor or subcontractor knowingly submitted cost or pricing data that were incomplete, inaccurate, or noncurrent.

52.215-13 SUBCONTRACTOR COST OR PRICING DATA--MODIFICATIONS (OCT 1997)

(a) The requirements of paragraphs (b) and (c) of this clause shall--

(1) Become operative only for any modification to this contract involving a pricing adjustment expected to exceed the threshold for submission of cost or pricing data at FAR 15.403-4; and

(2) Be limited to such modifications.

(b) Before awarding any subcontract expected to exceed the threshold for submission of cost or pricing data at FAR 15.403-4, on the date of agreement on price or the date of award, whichever is later; or before pricing any subcontract modification involving a pricing adjustment expected to exceed the threshold for submission of cost or pricing data at FAR 15.403-4, the Contractor shall require the subcontractor to submit cost or pricing data (actually or by specific identification in writing), unless an exception under FAR 15.403-1 applies.

(c) The Contractor shall require the subcontractor to certify in substantially the form prescribed in FAR 15.406-2 that, to the best of its knowledge and belief, the data submitted under paragraph (b) of this clause were accurate, complete, and current as of the date of agreement on the negotiated price of the subcontract or subcontract modification.

The Contractor shall insert the substance of this clause, including this paragraph (d), in each subcontract that exceeds the threshold for submission of cost or pricing data at FAR 15.403-4 on the date of agreement on price or the date of award, whichever is later.

52.219-8 UTILIZATION OF SMALL BUSINESS CONCERNS (OCT 2000)

(a) It is the policy of the United States that small business concerns, veteran-owned small business concerns, service-disabled veteran-owned small business concerns, HUBZone small business concerns, small disadvantaged business concerns, and women-owned small business concerns shall have the maximum practicable opportunity to

participate in performing contracts let by any Federal agency, including contracts and subcontracts for subsystems, assemblies, components, and related services for major systems. It is further the policy of the United States that its prime contractors establish procedures to ensure the timely payment of amounts due pursuant to the terms of their subcontracts with small business concerns, veteran-owned small business concerns, service-disabled veteran-owned small business concerns, HUBZone small business concerns, small disadvantaged business concerns, and women-owned small business concerns.

(b) The Contractor hereby agrees to carry out this policy in the awarding of subcontracts to the fullest extent consistent with efficient contract performance. The Contractor further agrees to cooperate in any studies or surveys as may be conducted by the United States Small Business Administration or the awarding agency of the United States as may be necessary to determine the extent of the Contractor's compliance with this clause.

Definitions. As used in this contract--

HUBZone small business concern means a small business concern that appears on the List of Qualified HUBZone Small Business Concerns maintained by the Small Business Administration.

Service-disabled veteran-owned small business concern--

(1) Means a small business concern--

(i) Not less than 51 percent of which is owned by one or more service-disabled veterans or, in the case of any publicly owned business, not less than 51 percent of the stock of which is owned by one or more service-disabled veterans; and

(ii) The management and daily business operations of which are controlled by one or more service-disabled veterans or, in the case of a veteran with permanent and severe disability, the spouse or permanent caregiver of such veteran.

(2) Service-disabled veteran means a veteran, as defined in 38 U.S.C. 101(2), with a disability that is service-connected, as defined in 38 U.S.C. 101(16).

Small business concern means a small business as defined pursuant to Section 3 of the Small Business Act and relevant regulations promulgated pursuant thereto.

Small disadvantaged business concern means a small business concern that represents, as part of its offer that--

(1) It has received certification as a small disadvantaged business concern consistent with 13 CFR part 124, subpart B;

(2) No material change in disadvantaged ownership and control has occurred since its certification;

(3) Where the concern is owned by one or more individuals, the net worth of each individual upon whom the certification is based does not exceed $750,000 after taking into account the applicable exclusions set forth at 13 CFR 124.104(c)(2); and

(4) It is identified, on the date of its representation, as a certified small disadvantaged business in the database maintained by the Small Business Administration (PRO-Net).

Veteran-owned small business concern means a small business concern--

(1) Not less than 51 percent of which is owned by one or more veterans (as defined at 38 U.S.C. 101(2)) or, in the case of any publicly owned business, not less than 51 percent of the stock of which is owned by one or more veterans; and

(2) The management and daily business operations of which are controlled by one or more veterans.

Women-owned small business concern means a small business concern--

(1) That is at least 51 percent owned by one or more women, or, in the case of any publicly owned business, at least 51 percent of the stock of which is owned by one or more women; and

(2) Whose management and daily business operations are controlled by one or more women.

(d) Contractors acting in good faith may rely on written representations by their subcontractors regarding their status as a small business concern, a veteran-owned small business concern, a service-disabled veteran-owned small business concern, a HUBZone small business concern, a small disadvantaged business concern, or a women-owned small business concern.

(End of clause)

52.219-9 SMALL BUSINESS SUBCONTRACTING PLAN (OCT 2001)

(a) This clause does not apply to small business concerns.

(b) Definitions. As used in this clause--

Commercial item means a product or service that satisfies the definition of commercial item in section 2.101 of the Federal Acquisition Regulation.

Commercial plan means a subcontracting plan (including goals) that covers the offeror's fiscal year and that applies to the entire production of commercial items sold by either the entire company or a portion thereof (e.g., division, plant, or product line).

Individual contract plan means a subcontracting plan that covers the entire contract period (including option periods), applies to a specific contract, and has goals that are based on the offeror's planned subcontracting in support of the specific contract, except that indirect costs incurred for common or joint purposes may be allocated on a prorated basis to the contract.

Master plan means a subcontracting plan that contains all the required elements of an individual contract plan, except goals, and may be incorporated into individual contract plans, provided the master plan has been approved.

Subcontract means any agreement (other than one involving an employer-employee relationship) entered into by a Federal Government prime Contractor or subcontractor calling for supplies or services required for performance of the contract or subcontract.

(c) The offeror, upon request by the Contracting Officer, shall submit and negotiate a subcontracting plan, where applicable, that separately addresses subcontracting with small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business concerns, small disadvantaged business, and women-owned small business concerns. If the offeror is submitting an individual contract plan, the plan must separately address subcontracting with small business, veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business concerns, with a separate part for the basic contract and separate parts for each option (if any). The plan shall be included in and made a part of the resultant contract. The subcontracting plan shall be negotiated within the time specified by the Contracting Officer. Failure to submit and negotiate the subcontracting plan shall make the offeror ineligible for award of a contract.

(d) The offeror's subcontracting plan shall include the following:

(1) Goals, expressed in terms of percentages of total planned subcontracting dollars, for the use of small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business concerns as subcontractors. Service-disabled veteran-

owned small business concerns meet the definition of veteran-owned small business concerns, and offerors may include them within the subcontracting plan goal for veteran-owned small business concerns. A separate goal for service-disabled veteran-owned small business concerns is not required. The offeror shall include all subcontracts that contribute to contract performance, and may include a proportionate share of products and services that are normally allocated as indirect costs.

(2) A statement of--

(i) Total dollars planned to be subcontracted for an individual contract plan; or the offeror's total projected sales, expressed in dollars, and the total value of projected subcontracts to support the sales for a commercial plan;

(ii) Total dollars planned to be subcontracted to small business concerns;

(iii) Total dollars planned to be subcontracted to veteran-owned small business concerns;

(iv) Total dollars planned to be subcontracted to HUBZone small business concerns;

(v) Total dollars planned to be subcontracted to small disadvantaged business concerns; and

(vi) Total dollars planned to be subcontracted to women-owned small business concerns.

(3) A description of the principal types of supplies and services to be subcontracted, and an identification of the types planned for subcontracting to--

(i) Small business concerns;

(ii) Veteran-owned small business concerns;

(iii) HUBZone small business concerns;

(iv) Small disadvantaged business concerns; and

(v) Women-owned small business concerns.

(4) A description of the method used to develop the subcontracting goals in paragraph (d)(1) of this clause.

(5) A description of the method used to identify potential sources for solicitation purposes (e.g., existing company source lists, the Procurement Marketing and Access Network (PRO-Net) of the Small Business Administration (SBA), veterans service organizations, the National Minority Purchasing Council Vendor Information Service, the Research and Information Division of the Minority Business Development Agency in the Department of Commerce, or small, HUBZone, small disadvantaged, and women-owned small business trade associations). A firm may rely on the information contained in PRO-Net as an accurate representation of a concern's size and ownership characteristics for the purposes of maintaining a small, veteran-owned small, HUBZone small, small disadvantaged, and women-owned small business source list. Use of PRO-Net as its source list does not relieve a firm of its responsibilities (e.g., outreach, assistance, counseling, or publicizing subcontracting opportunities) in this clause.

(6) A statement as to whether or not the offeror in included indirect costs in establishing subcontracting goals, and a description of the method used to determine the proportionate share of indirect costs to be incurred with—

(i) Small business concerns;

(ii) Veteran-owned small business concerns;

(iii) HUBZone small business concerns;

(iv) Small disadvantaged business concerns; and

(v) Women-owned small business concerns.

(7) The name of the individual employed by the offeror who will administer the offeror's subcontracting program, and a description of the duties of the individual.

(8) A description of the efforts the offeror will make to assure that small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business and women-owned small business concerns have an equitable opportunity to compete for subcontracts.

(9) Assurances that the offeror will include the clause of this contract entitled ``Utilization of Small Business Concerns'' in all subcontracts that offer further subcontracting opportunities, and that the offeror will require all subcontractors (except small business concerns) that receive subcontracts in excess of $500,000 ($1,000,000 for construction of any public facility) to adopt a subcontracting plan that complies with the requirements of this clause.

(10) Assurances that the offeror will--

(i) Cooperate in any studies or surveys as may be required;

(ii) Submit periodic reports so that the Government can determine the extent of compliance by the offeror with the subcontracting plan;

(iii) Submit Standard Form (SF) 294, Subcontracting Report for Individual Contracts, and/or SF 295, Summary Subcontract Report, in accordance with paragraph (j) of this clause. The reports shall provide information on subcontract awards to small business concerns, veteran-owned small business concerns, service-disabled veteran-owned small business concerns, small disadvantaged business concerns, women-owned small business concerns, and Historically Black Colleges and Universities and Minority Institutions. Reporting shall be in accordance with the instructions on the forms or as provided in agency regulations.

(iv) Ensure that its subcontractors agree to submit SF 294 and SF 295.

(11) A description of the types of records that will be maintained concerning procedures that have been adopted to comply with the requirements and goals in the plan, including establishing source lists; and a description of the offeror's efforts to locate small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business concerns and award subcontracts to them. The records shall include at least the following (on a plant-wide or company-wide basis, unless otherwise indicated)

(i) Source lists (e.g., PRO-Net), guides, and other data that identify small business, veteran-owner small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business concerns.

(ii) Organizations contacted in an attempt to locate sources that are small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, or women-owned small business concerns.

(iii) Records on each subcontract solicitation resulting in an award of more than $100,000, indicating--

(A) Whether small business concerns were solicited and, if not, why not;

(B) Whether veteran-owned small business concerns were solicited and, if not, why not;

(C) Whether HUBZone small business concerns were solicited and, if not, why not;

(D) Whether small disadvantaged business concerns were solicited and, if not, why not;

(E) Whether women-owned small business concerns were solicited and, if not, why not; and

(F) If applicable, the reason award was not made to a small business concern.

(iv) Records of any outreach efforts to contact--

(A) Trade associations;

(B) Business development organizations;

(C) Conferences and trade fairs to locate small, HUBZone small, small disadvantaged, and women-owned small business sources; and

(D) Veterans service organizations.

(v) Records of internal guidance and encouragement provided to buyers through--

(A) Workshops, seminars, training, etc.; and

(B) Monitoring performance to evaluate compliance with the program's requirements.

(vi) On a contract-by-contract basis, records to support award data submitted by the offeror to the Government, including the name, address, and business size of each subcontractor. Contractors having commercial plans need not comply with this requirement.

(e) In order to effectively implement this plan to the extent consistent with efficient contract performance, the Contractor shall perform the following functions:

(1) Assist small business, veteran-owner small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business concerns by arranging solicitations, time for the preparation of bids, quantities, specifications, and delivery schedules so as to facilitate the participation by such concerns. Where the Contractor's lists of potential small business, veteran-owner small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business subcontractors are excessively long, reasonable effort shall be made to give all such small business concerns an opportunity to compete over a period of time.

(2) Provide adequate and timely consideration of the potentialities of small business, veteran-owner small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business concerns in all ``make-or-buy'' decisions.

(3) Counsel and discuss subcontracting opportunities with representatives of small business, veteran-owner small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business firms.

(4) Provide notice to subcontractors concerning penalties and remedies for misrepresentations of business status as small, veteran-owner small business, HUBZone small, small disadvantaged, or women-owned small business for the purpose of obtaining a subcontract that is to be included as part or all of a goal contained in the Contractor's subcontracting plan.

(f) A master plan on a plant or division-wide basis that contains all the elements required by paragraph (d) of this clause, except goals, may be incorporated by reference as a part of the subcontracting plan required of the offeror by this clause; provided--

(1) the master plan has been approved, (2) the offeror ensures that the master plan is updated as necessary and provides copies of the approved master plan, including evidence of its approval, to the Contracting Officer, and (3) goals and any deviations from the master plan deemed necessary by the Contracting Officer to satisfy the requirements of this contract are set forth in the individual subcontracting plan.

(g) A commercial plan is the preferred type of subcontracting plan for contractors furnishing commercial items. The commercial plan shall relate to the offeror's planned subcontracting generally, for both commercial and Government business, rather than solely to the Government contract. Commercial plans are also preferred for subcontractors that provide commercial items under a prime contract, whether or not the prime contractor is supplying a commercial item.

(h) Prior compliance of the offeror with other such subcontracting plans under previous contracts will be considered by the Contracting Officer in determining the responsibility of the offeror for award of the contract.

(i) The failure of the Contractor or subcontractor to comply in good faith with (1) the clause of this contract entitled "Utilization Of Small Business Concerns," or (2) an approved plan required by this clause, shall be a material breach of the contract.

(j) The Contractor shall submit the following reports:

(1) Standard Form 294, Subcontracting Report for Individual Contracts. This report shall be submitted to the Contracting Officer semiannually and at contract completion. The report covers subcontract award data related to this contract. This report is not required for commercial plans.

(2) Standard Form 295, Summary Subcontract Report. This report encompasses all of the contracts with the awarding agency. It must be submitted semi-annually for contracts with the Department of Defense and annually for contracts with civilian agencies. If the reporting activity is covered by a commercial plan, the reporting activity must report annually all subcontract awards under that plan. All reports submitted at the close of each fiscal year (both individual and commercial plans) shall include a breakout, in the Contractor's format, of subcontract awards, in whole dollars, to small disadvantaged business concerns by North American Industry Classification System (NAICS) Industry Subsector. For a commercial plan, the Contractor may obtain from each of its subcontractors a predominant NAICS Industry Subsector and report all awards to that subcontractor under its predominant NAICS Industry Subsector.

(End of clause)

52.219-16 LIQUIDATED DAMAGES-SUBCONTRACTING PLAN (JAN 1999)

(a) Failure to make a good faith effort to comply with the subcontracting plan, as used in this clause, means a willful or intentional failure to perform in accordance with the requirements of the subcontracting plan approved under the clause in this contract entitled "Small Business Subcontracting Plan," or willful or intentional action to frustrate the plan.

(b) Performance shall be measured by applying the percentage goals to the total actual subcontracting dollars or, if a commercial plan is involved, to the pro rata share of actual subcontracting dollars attributable to Government contracts covered by the commercial plan. If, at contract completion or, in the case of a commercial plan, at the close of the fiscal year for which the plan is applicable, the Contractor has failed to meet its subcontracting goals and the Contracting Officer decides in accordance with paragraph (c) of this clause that the Contractor failed to make a good faith effort to comply with its subcontracting plan, established in accordance with the clause in this contract entitled “Small Business Subcontracting Plan,” the Contractor shall pay the Government liquidated damages in an amount stated. The amount of probable damages attributable to the Contractor's failure to comply shall be an amount equal to the actual dollar amount by which the Contractor failed to achieve each subcontract goal.

(c) Before the Contracting Officer makes a final decision that the Contractor has failed to make such good faith effort, the Contracting Officer shall give the Contractor written notice specifying the failure and permitting the

Contractor to demonstrate what good faith efforts have been made and to discuss the matter. Failure to respond to the notice may be taken as an admission that no valid explanation exists. If, after consideration of all the pertinent data, the Contracting Officer finds that the Contractor failed to make a good faith effort to comply with the subcontracting plan, the Contracting Officer shall issue a final decision to that effect and require that the Contractor pay the Government liquidated damages as provided in paragraph (b) of this clause.

(d) With respect to commercial plans, the Contracting Officer who approved the plan will perform the functions of the Contracting Officer under this clause on behalf of all agencies with contracts covered by the commercial plan.

(e) The Contractor shall have the right of appeal, under the clause in this contract entitled Disputes, from any final decision of the Contracting Officer.

(f) Liquidated damages shall be in addition to any other remedies that the Government may have.

(End of clause)

52.219-25 SMALL DISADVANTAGED BUSINESS PARTICIPATION PROGRAM—DISADVANTAGED STATUS AND REPORTING (OCT 1999)

(a) Disadvantaged status for joint venture partners, team members, and subcontractors. This clause addresses disadvantaged status for joint venture partners, teaming arrangement members, and subcontractors and is applicable if this contract contains small disadvantaged business (SDB) participation targets. The Contractor shall obtain representations of small disadvantaged status from joint venture partners, teaming arrangement members, and subcontractors through use of a provision substantially the same as paragraph (b)(1)(i) of the provision at FAR 52.219-22, Small Disadvantaged Business Status. The Contractor shall confirm that a joint venture partner, team member, or subcontractor representing itself as a small disadvantaged business concern, is identified as a certified small disadvantaged business in the database maintained by the Small Business Administration (PRO-Net) or by contacting the SBA's Office of Small Disadvantaged Business Certification and Eligibility.

(b) Reporting requirement. If this contract contains SDB participation targets, the Contractor shall report on the participation of SDB concerns at contract completion, or as otherwise provided in this contract. Reporting may be on Optional Form 312, Small Disadvantaged Business Participation Report, or in the Contractor's own format providing the same information. This report is required for each contract containing SDB participation targets. If this contract contains an individual Small, Small Disadvantaged and Women-Owned Small Business Subcontracting Plan, reports may be submitted with the final Subcontracting Report for Individual Contracts (Standard Form 294) at the completion of the contract.

(End of clause)

52.222-1 NOTICE TO THE GOVERNMENT OF LABOR DISPUTES (FEB 1997)

If the Contractor has knowledge that any actual or potential labor dispute is delaying or threatens to delay the timely performance of this contract, the Contractor shall immediately give notice, including all relevant information, to the Contracting Officer.

52.222-3 CONVICT LABOR (AUG 1996)

The Contractor agrees not to employ in the performance of this contract any person undergoing a sentence of imprisonment which has been imposed by any court of a State, the District of Columbia, the Commonwealth of Puerto Rico, the Virgin Islands, Guam, American Samoa, the Commonwealth of the Northern Mariana Islands, or the Trust Territory of the Pacific Islands. This limitation, however, shall not prohibit the employment by the Contractor in the performance of this contract of persons on parole or probation to work at paid employment during the term of their sentence or persons who have been pardoned or who have served their terms. Nor shall it prohibit

the employment by the Contractor in the performance of this contract of persons confined for violation of the laws of any of the States, the District of Columbia, the Commonwealth of Puerto Rico, the Virgin Islands, Guam, American Samoa, the Commonwealth of the Northern Mariana Islands, or the Trust Territory of the Pacific Islands who are authorized to work at paid employment in the community under the laws of such jurisdiction, if--

(a)(1) The worker is paid or is in an approved work training program on a voluntary basis;

(2) Representatives of local union central bodies or similar labor union organizations have been consulted;

(3) Such paid employment will not result in the displacement of employed workers, or be applied in skills, crafts, or trades in which there is a surplus of available gainful labor in the locality, or impair existing contracts for services; and

(4) The rates of pay and other conditions of employment will not be less than those paid or provided for work of a similar nature in the locality in which the work is being performed; and

(b) The Attorney General of the United States has certified that the work-release laws or regulations of the jurisdiction involved are in conformity with the requirements of Executive Order 11755, as amended by Executive Orders 12608 and 12943.

(End of clause)

52.222-4 CONTRACT WORK HOURS AND SAFETY STANDARDS ACT - OVERTIME COMPENSATION. (SEP 2000)

(a) Overtime requirements. No Contractor or subcontractor employing laborers or mechanics (see Federal Acquisition Regulation 22.300) shall require or permit them to work over 40 hours in any workweek unless they are paid at least 1 and 1/2 times the basic rate of pay for each hour worked over 40 hours.

(b) Violation; liability for unpaid wages; liquidated damages. The responsible Contractor and subcontractor are liable for unpaid wages if they violate the terms in paragraph (a) of this clause. In addition, the Contractor and subcontractor are liable for liquidated damages payable to the Government. The Contracting Officer will assess liquidated damages at the rate of $10 per affected employee for each calendar day on which the employer required or permitted the employee to work in excess of the standard workweek of 40 hours without paying overtime wages required by the Contract Work Hours and Safety Standards Act.

(c) Withholding for unpaid wages and liquidated damages. The Contracting Officer will withhold from payments due under the contract sufficient funds required to satisfy any Contractor or subcontractor liabilities for unpaid wages and liquidated damages. If amounts withheld under the contract are insufficient to satisfy Contractor or subcontractor liabilities, the Contracting Officer will withhold payments from other Federal or Federally assisted contracts held by the same Contractor that are subject to the Contract Work Hours and Safety Standards Act.

(d) Payrolls and basic records.

(1) The Contractor and its subcontractors shall maintain payrolls and basic payroll records for all laborers and mechanics working on the contract during the contract and shall make them available to the Government until 3 years after contract completion. The records shall contain the name and address of each employee, social security number, labor classifications, hourly rates of wages paid, daily and weekly number of hours worked, deductions made, and actual wages paid. The records need not duplicate those required for construction work by Department of Labor regulations at 29 CFR 5.5(a)(3) implementing the Davis-Bacon Act.

(2) The Contractor and its subcontractors shall allow authorized representatives of the Contracting Officer or the Department of Labor to inspect, copy, or transcribe records maintained under paragraph (d)(1) of this clause. The Contractor or subcontractor also shall allow authorized representatives of the Contracting Officer or Department of Labor to interview employees in the workplace during working hours.

(e) Subcontracts. The Contractor shall insert the provisions set forth in paragraphs (a) through (d) of this clause in subcontracts exceeding $100,000 and require subcontractors to include these provisions in any lower tier subcontracts. The Contractor shall be responsible for compliance by any subcontractor or lower-tier subcontractor with the provisions set forth in paragraphs (a) through (d) of this clause.

(End of clause)

52.222-6 DAVIS-BACON ACT (FEB 1995)

(a) All laborers and mechanics employed or working upon the site of the work will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR Part 3), the full amount of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the Contractor and such laborers and mechanics. Contributions made or costs reasonably anticipated for bona fide fringe benefits under section 1(b)(2) of the Davis-Bacon Act on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of paragraph (d) of this clause; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such period. Such laborers and mechanics shall be paid not less than the appropriate wage rate and fringe benefits in the wage determination for the classification of work actually performed, without regard to skill, except as provided in the clause entitled Apprentices and Trainees. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein; provided, That the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classifications and wage rates conformed under paragraph (b) of this clause) and the Davis-Bacon poster (WH-1321) shall be posted at all times by the Contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers.

(b)(1) The Contracting Officer shall require that any class of laborers or mechanics which is not listed in the wage determination and which is to be employed under the contract shall be classified in conformance with the wage determination. The Contracting Officer shall approve an additional classification and wage rate and fringe benefits therefor only when all the following criteria have been met:

(i) The work to be performed by the classification requested is not performed by a classification in the wage determination.

(ii) The classification is utilized in the area by the construction industry.

(iii) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.

(2) If the Contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the Contracting Officer agree on the classification and wage rate (including the amount designated for fringe benefits, where appropriate), a report of the action taken shall be sent by the Contracting Officer to the Administrator of the Wage and Hour Division, Employment Standards Administration, U.S. Department of Labor, Washington, DC 20210. The Administrator or an authorized representative will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the Contracting Officer or will notify the Contracting Officer within the 30-day period that additional time is necessary.

(3) In the event the Contractor, the laborers or mechanics to be employed in the classification, or their representatives, and the Contracting Officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the Contracting Officer shall refer the questions,

including the views of all interested parties and the recommendation of the Contracting Officer, to the Administrator of the Wage and Hour Division for determination. The Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the Contracting Officer or will notify the Contracting Officer within the 30-day period that additional time is necessary.

(4) The wage rate (including fringe benefits, where appropriate) determined pursuant to subparagraphs (b)(2) and (b)(3) of this clause shall be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.

(c) Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the Contractor shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly cash equivalent thereof.

(d) If the Contractor does not make payments to a trustee or other third person, the Contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program; provided, That the Secretary of Labor has found, upon the written request of the Contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the Contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

52.222-7 WITHHOLDING OF FUNDS (FEB 1988)

The Contracting Officer shall, upon his or her own action or upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the Contractor under this contract or any other Federal contract with the same Prime Contractor, or any other Federally assisted contract subject to Davis-Bacon prevailing wage requirements, which is held by the same Prime Contractor, so much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the Contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the Contracting Officer may, after written notice to the Contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

52.222-8 PAYROLLS AND BASIC RECORDS (FEB 1988)

(a) Payrolls and basic records relating thereto shall be maintained by the Contractor during the course of the work and preserved for a period of 3 years thereafter for all laborers and mechanics working at the site of the work. Such records shall contain the name, address, and social security number of each such worker, his or her correct classification, hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in section 1(b)(2)(B) of the Davis-Bacon Act), daily and weekly number of hours worked, deductions made, and actual wages paid. Whenever the Secretary of Labor has found, under paragraph (d) of the clause entitled Davis-Bacon Act, that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in section 1(b)(2)(B) of the Davis-Bacon Act, the Contractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits. Contractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprenticeship programs and certification of trainee programs, the registration of the apprentices and trainees, and the ratios and wage rates prescribed in the applicable programs.

(b)(1) The Contractor shall submit weekly for each week in which any contract work is performed a copy of all payrolls to the Contracting Officer. The payrolls submitted shall set out accurately and completely all of the information required to be maintained under paragraph (a) of this clause. This information may be submitted in any

form desired. Optional Form WH-347 (Federal Stock Number 029-005-00014-1) is available for this purpose and may be purchased from the Superintendent of Documents, U.S. Government Printing Office, Washington, DC 20402. The Prime Contractor is responsible for the submission of copies of payrolls by all subcontractors.

(2) Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the Contractor or subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract and shall certify--

(i) That the payroll for the payroll period contains the information required to be maintained under paragraph (a) of this clause and that such information is correct and complete;

(ii) That each laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in the Regulations, 29 CFR Part 3; and

(iii) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.

(3) The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by subparagraph (b)(2) of this clause.

(4) The falsification of any of the certifications in this clause may subject the Contractor or subcontractor to civil or criminal prosecution under Section 1001 of Title 18 and Section 3729 of Title 31 of the United States Code.

(c) The Contractor or subcontractor shall make the records required under paragraph (a) of this clause available for inspection, copying, or transcription by the Contracting Officer or authorized representatives of the Contracting Officer or the Department of Labor. The Contractor or subcontractor shall permit the Contracting Officer or representatives of the Contracting Officer or the Department of Labor to interview employees during working hours on the job. If the Contractor or subcontractor fails to submit required records or to make them available, the Contracting Officer may, after written notice to the Contractor, take such action as may be necessary to cause the suspension of any further payment. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

52.222-9 APPRENTICES AND TRAINEES (FEB 1988)

(a) Apprentices. Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Bureau of Apprenticeship and Training, or with a State Apprenticeship Agency recognized by the Bureau, or if a person is employed in his or her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Bureau of Apprenticeship and Training or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice. The allowable ratio of apprentices to journeymen on the job site in any craft classification shall not be greater than the ratio permitted to the Contractor as to the entire work force under the registered program. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated in this paragraph, shall be paid not less than the applicable wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman's hourly rate) specified in the Contractor's or subcontractor's registered program shall be observed. Every apprentice must be paid at not less than the rate

specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination. In the event the Bureau of Apprenticeship and Training, or a State Apprenticeship Agency recognized by the Bureau, withdraws approval of an apprenticeship program, the Contractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

(b) Trainees. Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the U.S. Department of Labor, Employment and Training Administration. The ratio of trainees to journeymen on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration. Every trainee must be paid at not less than the rate specified in the approved program for the trainee's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed in the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman wage rate in the wage determination which provides for less than full fringe benefits for apprentices. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate in the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate in the wage determination for the work actually performed. In the event the Employment and Training Administration withdraws approval of a training program, the Contractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

(c) Equal employment opportunity. The utilization of apprentices, trainees, and journeymen under this clause shall be in conformity with the equal employment opportunity requirements of Executive Order 11246, as amended, and 29 CFR Part 30.

52.222-10 COMPLIANCE WITH COPELAND ACT REQUIREMENTS (FEB 1988)

The Contractor shall comply with the requirements of 29 CFR Part 3, which are hereby incorporated by reference in this contract.

52.222-11 SUBCONTRACTS (LABOR STANDARDS (FEB 1988)

(a) The Contractor or subcontractor shall insert in any subcontracts the clauses entitled Davis-Bacon Act, Contract Work Hours and Safety Standards Act-Overtime Compensation, Apprentices and Trainees, Payrolls and Basic Records, Compliance with Copeland Act Requirements, Withholding of Funds, Subcontracts (Labor Standards), Contract Termination-Debarment, Disputes Concerning Labor Standards, Compliance with Davis-Bacon and Related Act Regulations, and Certification of Eligibility, and such other clauses as the Contracting Officer may, by appropriate instructions, require, and also a clause requiring subcontractors to include these clauses in any lower tier subcontracts. The Prime Contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with all the contract clauses cited in this paragraph.

(b)(1) Within 14 days after award of the contract, the Contractor shall deliver to the Contracting Officer a completed Statement and Acknowledgment Form (SF 1413) for each subcontract, including the subcontractor's

signed and dated acknowledgment that the clauses set forth in paragraph (a) of this clause have been included in the subcontract.

(2) Within 14 days after the award of any subsequently awarded subcontract the Contractor shall deliver to the Contracting Officer an updated completed SF 1413 for such additional subcontract.

52.222-12 CONTRACT TERMINATION--DEBARMENT (FEB 1988)

A breach of the contract clauses entitled Davis-Bacon Act, Contract Work Hours and Safety Standards Act--Overtime Compensation, Apprentices and Trainees, Payrolls and Basic Records, Compliance with Copeland Act Requirements, Subcontracts (Labor Standards), Compliance with Davis-Bacon and Related Act Regulations, or Certification of Eligibility may be grounds for termination of the contract, and for debarment as a Contractor and subcontractor as provided in 29 CFR 5.12.

52.222-13 COMPLIANCE WITH DAVIS-BACON AND RELATED ACT REGULATIONS (FEB 1988)

All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR Parts 1, 3, and 5 are hereby incorporated by reference in this contract.

52.222-14 DISPUTES CONCERNING LABOR STANDARDS (FEB 1988)

The United States Department of Labor has set forth in 29 CFR Parts 5, 6, and 7 procedures for resolving disputes concerning labor standards requirements. Such disputes shall be resolved in accordance with those procedures and not the Disputes clause of this contract. Disputes within the meaning of this clause include disputes between the Contractor (or any of its subcontractors) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.

52.222-15 CERTIFICATION OF ELIGIBILITY (FEB 1988)

(a) By entering into this contract, the Contractor certifies that neither it (nor he or she) nor any person or firm who has an interest in the Contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).

(b) No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).

(c) The penalty for making false statements is prescribed in the U.S. Criminal Code, 18 U.S.C. 1001.

52.222-21 PROHIBITION OF SEGREGATED FACILITIES (FEB 1999)

(a) Segregated facilities, as used in this clause, means any waiting rooms, work areas, rest rooms and wash rooms, restaurants and other eating areas, time clocks, locker rooms and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees, that are segregated by explicit directive or are in fact segregated on the basis of race, color, religion, sex, or national origin because of written or oral policies or employee custom. The term does not include separate or single-user rest rooms or necessary dressing or sleeping areas provided to assure privacy between the sexes.

(b) The Contractor agrees that it does not and will not maintain or provide for its employees any segregated facilities at any of its establishments, and that it does not and will not permit its employees to perform their services at any

location under its control where segregated facilities are maintained. The Contractor agrees that a breach of this clause is a violation of the Equal Opportunity clause in this contract.

(c) The Contractor shall include this clause in every subcontract and purchase order that is subject to the Equal Opportunity clause of this contract.

(End of clause)

52.222-23 NOTICE OF REQUIREMENT FOR AFFIRMATIVE ACTION TO ENSURE EQUAL EMPLOYMENT OPPORTUNITY FOR CONSTRUCTION (FEB 1999)

(a) The offeror's attention is called to the Equal Opportunity clause and the Affirmative Action Compliance Requirements for Construction clause of this solicitation.

(b) The goals for minority and female participation, expressed in percentage terms for the Contractor's aggregate workforce in each trade on all construction work in the covered area, are as follows:

Goals for minority participation for each trade	Goals for female participation for each trade
ST/COUNTY/% MT/ELMORE/4.4%	6.9%

These goals are applicable to all the Contractor's construction work performed in the covered area. If the Contractor performs construction work in a geographical area located outside of the covered area, the Contractor shall apply the goals established for the geographical area where the work is actually performed. Goals are published periodically in the Federal Register in notice form, and these notices may be obtained from any Office of Federal Contract Compliance Programs office.

(c) The Contractor's compliance with Executive Order 11246, as amended, and the regulations in 41 CFR 60-4 shall be based on (1) its implementation of the Equal Opportunity clause, (2) specific affirmative action obligations required by the clause entitled "Affirmative Action Compliance Requirements for Construction," and (3) its efforts to meet the goals. The hours of minority and female employment and training must be substantially uniform throughout the length of the contract, and in each trade. The Contractor shall make a good faith effort to employ minorities and women evenly on each of its projects. The transfer of minority or female employees or trainees from Contractor to Contractor, or from project to project, for the sole purpose of meeting the Contractor's goals shall be a violation of the contract, Executive Order 11246, as amended, and the regulations in 41 CFR 60-4. Compliance with the goals will be measured against the total work hours performed.

(d) The Contractor shall provide written notification to the Deputy Assistant Secretary for Federal Contract Compliance, U.S. Department of Labor, within 10 working days following award of any construction subcontract in excess of $10,000 at any tier for construction work under the contract resulting from this solicitation. The notification shall list the --

(1) Name, address, and telephone number of the subcontractor;

(2) Employer's identification number of the subcontractor;

(3) Estimated dollar amount of the subcontract;

(4) Estimated starting and completion dates of the subcontract; and

(5) Geographical area in which the subcontract is to be performed.

(e) As used in this Notice, and in any contract resulting from this solicitation, the "covered area" is

[Contracting Officer shall insert description of the geographical areas where the contract is to be performed, giving the State, county, and city].

52.222-26 EQUAL OPPORTUNITY (FEB 1999)

(a) If, during any 12-month period (including the 12 months preceding the award of this contract), the Contractor has been or is awarded nonexempt Federal contracts and/or subcontracts that have an aggregate value in excess of $10,000, the Contractor shall comply with subparagraphs (b)(1) through (11) of this clause. Upon request, the Contractor shall provide information necessary to determine the applicability of this clause.

(b) During performing this contract, the Contractor agrees as follows:

(1) The Contractor shall not discriminate against any employee or applicant for employment because of race, color, religion, sex, or national origin. However, it shall not be a violation of this clause for the Contractor to extend a publicly announced preference in employment to Indians living on or near an Indian reservation, in connection with employment opportunities on or near an Indian reservation, as permitted by 41 CFR 60-1.5.

(2) The Contractor shall take affirmative action to ensure that applicants are employed, and that employees are treated during employment, without regard to their race, color, religion, sex, or national origin. This shall include, but not be limited to, (i) employment, (ii) upgrading, (iii) demotion, (iv) transfer, (v) recruitment or recruitment advertising, (vi) layoff or termination, (vii) rates of pay or other forms of compensation, and (viii) selection for training, including apprenticeship.

(3) The Contractor shall post in conspicuous places available to employees and applicants for employment the notices to be provided by the Contracting Officer that explain this clause.

(4) The Contractor shall, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, state that all qualified applicants will receive consideration for employment without regard to race, color, religion, sex, or national origin.

(5) The Contractor shall send, to each labor union or representative of workers with which it has a collective bargaining agreement or other contract or understanding, the notice to be provided by the Contracting Officer advising the labor union or workers' representative of the Contractor's commitments under this clause, and post copies of the notice in conspicuous places available to employees and applicants for employment.

(6) The Contractor shall comply with Executive Order 11246, as amended, and the rules, regulations, and orders of the Secretary of Labor.

(7) The Contractor shall furnish to the contracting agency all information required by Executive Order 11246, as amended, and by the rules, regulations, and orders of the Secretary of Labor. The Contractor shall also file Standard Form 100 (EEO-1), or any successor form, as prescribed in 41 CFR part 60-1. Unless the Contractor has filed within the 12 months preceding the date of contract award, the Contractor shall, within 30 days after contract award, apply to either the regional Office of Federal Contract Compliance Programs (OFCCP) or the local office of the Equal Employment Opportunity Commission for the necessary forms.

(8) The Contractor shall permit access to its premises, during normal business hours, by the contracting agency or the OFCCP for the purpose of conducting on-site compliance evaluations and complaint investigations. The Contractor shall permit the Government to inspect and copy any books, accounts, records (including computerized records), and other material that may be relevant to the matter under investigation and pertinent to compliance with Executive Order 11246, as amended, and rules and regulations that implement the Executive Order.

(9) If the OFCCP determines that the Contractor is not in compliance with this clause or any rule, regulation, or order of the Secretary of Labor, this contract may be canceled, terminated, or suspended in whole or in part and the Contractor may be declared ineligible for further Government contracts, under the procedures authorized in

Executive Order 11246, as amended. In addition, sanctions may be imposed and remedies invoked against the Contractor as provided in Executive Order 11246, as amended; in the rules, regulations, and orders of the Secretary of Labor; or as otherwise provided by law.

(10) The Contractor shall include the terms and conditions of subparagraphs (b)(1) through (11) of this clause in every subcontract or purchase order that is not exempted by the rules, regulations, or orders of the Secretary of Labor issued under Executive Order 11246, as amended, so that these terms and conditions will be binding upon each subcontractor or vendor.

(11) The Contractor shall take such action with respect to any subcontract or purchase order as the contracting officer may direct as a means of enforcing these terms and conditions, including sanctions for noncompliance; provided, that if the Contractor becomes involved in, or is threatened with, litigation with a subcontractor or vendor as a result of any direction, the Contractor may request the United States to enter into the litigation to protect the interests of the United States.

(c) Notwithstanding any other clause in this contract, disputes relative to this clause will be governed by the procedures in 41 CFR 60-1.1.

(End of clause)

52.222-27 AFFIRMATIVE ACTION COMPLIANCE REQUIREMENTS FOR CONSTRUCTION (FEB 1999)

(a) Definitions. "Covered area," as used in this clause, means the geographical area described in the solicitation for this contract.

"Deputy Assistant Secretary," as used in this clause, means Deputy Assistant Secretary for Federal Contract Compliance, U.S. Department of Labor, or a designee.

"Employer's identification number," as used in this clause, means the Federal Social Security number used on the employer's quarterly federal tax return, U.S. Treasury Department Form 941.

"Minority," as used in this clause, means--

(1) American Indian or Alaskan Native (all persons having origins in any of the original peoples of North America and maintaining identifiable tribal affiliations through membership and participation or community identification).

(2) Asian and Pacific Islander (all persons having origins in any of the original peoples of the Far East, Southeast Asia, the Indian Subcontinent, or the Pacific Islands);

(3) Black (all persons having origins in any of the black African racial groups not of Hispanic origin); and

(4) Hispanic (all persons of Mexican, Puerto Rican, Cuban, Central or South American, or other Spanish culture or origin, regardless of race).

(b) If the Contractor, or a subcontractor at any tier, subcontracts a portion of the work involving any construction trade, each such subcontract in excess of $10,000 shall include this clause and the Notice containing the goals for minority and female participation stated in the solicitation for this contract.

(c) If the Contractor is participating in a Hometown Plan (41 CFR 60-4) approved by the U.S. Department of Labor in a covered area, either individually or through an association, its affirmative action obligations on all work in the plan area (including goals) shall comply with the plan for those trades that have unions participating in the plan. Contractors must be able to demonstrate participation in, and compliance with, the provisions of the plan. Each Contractor or subcontractor participating in an approved plan is also required to comply with its obligations under the Equal Opportunity clause, and to make a good faith effort to achieve each goal under the plan in each trade in which it has employees. The overall good-faith performance by other Contractors or subcontractors toward a goal in an approved plan does not excuse any Contractor's or subcontractor's failure to make good-faith efforts to achieve

the plan's goals.

(d) The Contractor shall implement the affirmative action procedures in subparagraphs (g)(1) through (16) of this clause. The goals stated in the solicitation for this contract are expressed as percentages of the total hours of employment and training of minority and female utilization that the Contractor should reasonably be able to achieve in each construction trade in which it has employees in the covered area. If the Contractor performs construction work in a geographical area located outside of the covered area, it shall apply the goals established for the geographical area where that work is actually performed. The Contractor is expected to make substantially uniform progress toward its goals in each craft.

(e) Neither the terms and conditions of any collective bargaining agreement, nor the failure by a union with which the Contractor has a collective bargaining agreement, to refer minorities or women shall excuse the Contractor's obligations under this clause, Executive Order 11246, as amended, or the regulations thereunder.

(f) In order for the nonworking training hours of apprentices and trainees to be counted in meeting the goals, apprentices and trainees must be employed by the Contractor during the training period, and the Contractor must have made a commitment to employ the apprentices and trainees at the completion of their training, subject to the availability of employment opportunities. Trainees must be trained pursuant to training programs approved by the U.S. Department of Labor.

(g) The Contractor shall take affirmative action to ensure equal employment opportunity. The evaluation of the Contractor's compliance with this clause shall be based upon its effort to achieve maximum results from its actions. The Contractor shall document these efforts fully and implement affirmative action steps at least as extensive as the following:

(1) Ensure a working environment free of harassment, intimidation, and coercion at all sites and in all facilities where the Contractor's employees are assigned to work. The Contractor, if possible, will assign two or more women to each construction project. The Contractor shall ensure that foremen, superintendents, and other onsite supervisory personnel are aware of and carry out the Contractor's obligation to maintain such a working environment, with specific attention to minority or female individuals working at these sites or facilities.

(2) Establish and maintain a current list of sources for minority and female recruitment. Provide written notification to minority and female recruitment sources and community organizations when the Contractor or its unions have employment opportunities available, and maintain a record of the organizations' responses.

(3) Establish and maintain a current file of the names, addresses, and telephone numbers of each minority and female off-the-street applicant, referrals of minorities or females from unions, recruitment sources, or community organizations, and the action taken with respect to each individual. If an individual was sent to the union hiring hall for referral and not referred back to the Contractor by the union or, if referred back, not employed by the Contractor, this shall be documented in the file, along with whatever additional actions the Contractor may have taken.

(4) Immediately notify the Deputy Assistant Secretary when the union or unions with which the Contractor has a collective bargaining agreement has not referred back to the Contractor a minority or woman sent by the Contractor, or when the Contractor has other information that the union referral process has impeded the Contractor's efforts to meet its obligations.

(5) Develop on-the-job training opportunities and/or participate in training programs for the area that expressly include minorities and women, including upgrading programs and apprenticeship and trainee programs relevant to the Contractor's employment needs, especially those programs funded or approved by the Department of Labor. The Contractor shall provide notice of these programs to the sources compiled under subparagraph (g)(2) of this clause.

(6) Disseminate the Contractor's equal employment policy by--

(i) Providing notice of the policy to unions and to training, recruitment, and outreach programs, and requesting their

cooperation in assisting the Contractor in meeting its contract obligations;

(ii) Including the policy in any policy manual and in collective bargaining agreements;

(iii) Publicizing the policy in the company newspaper, annual report, etc.;

(iv) Reviewing the policy with all management personnel and with all minority and female employees at least once a year; and

(v) Posting the policy on bulletin boards accessible to employees at each location where construction work is performed.

(7) Review, at least annually, the Contractor's equal employment policy and affirmative action obligations with all employees having responsibility for hiring, assignment, layoff, termination, or other employment decisions. Conduct review of this policy with all on-site supervisory personnel before initiating construction work at a job site. A written record shall be made and maintained identifying the time and place of these meetings, persons attending, subject matter discussed, and disposition of the subject matter.

(8) Disseminate the Contractor's equal employment policy externally by including it in any advertising in the news media, specifically including minority and female news media. Provide written notification to, and discuss this policy with, other Contractors and subcontractors with which the Contractor does or anticipates doing business.

(9) Direct recruitment efforts, both oral and written, to minority, female, and community organizations, to schools with minority and female students, and to minority and female recruitment and training organizations serving the Contractor's recruitment area and employment needs. Not later than 1 month before the date for acceptance of applications for apprenticeship or training by any recruitment source, send written notification to organizations such as the above, describing the openings, screening procedures, and tests to be used in the selection process.

(10) Encourage present minority and female employees to recruit minority persons and women. Where reasonable, provide after-school, summer, and vacation employment to minority and female youth both on the site and in other areas of the Contractor's workforce.

(11) Validate all tests and other selection requirements where required under 41 CFR 60-3.

(12) Conduct, at least annually, an inventory and evaluation at least of all minority and female personnel for promotional opportunities. Encourage these employees to seek or to prepare for, through appropriate training, etc., opportunities for promotion.

(13) Ensure that seniority practices, job classifications, work assignments, and other personnel practices do not have a discriminatory effect by continually monitoring all personnel and employment-related activities to ensure that the Contractor's obligations under this contract are being carried out.

(14) Ensure that all facilities and company activities are nonsegregated except that separate or single-user rest rooms and necessary dressing or sleeping areas shall be provided to assure privacy between the sexes.

(15) Maintain a record of solicitations for subcontracts for minority and female construction contractors and suppliers, including circulation of solicitations to minority and female contractor associations and other business associations.

(16) Conduct a review, at least annually, of all supervisors' adherence to and performance under the Contractor's equal employment policy and affirmative action obligations.

(h) The Contractor is encouraged to participate in voluntary associations that may assist in fulfilling one or more of the affirmative action obligations contained in subparagraphs (g)(1) through (16) of this clause. The efforts of a contractor association, joint contractor-union, contractor-community, or similar group of which the contractor is a

member and participant may be asserted as fulfilling one or more of its obligations under subparagraphs (g)(1) through (16) of this clause, provided the Contractor--

(1) Actively participates in the group;

(2) Makes every effort to ensure that the group has a positive impact on the employment of minorities and women in the industry;

(3) Ensures that concrete benefits of the program are reflected in the Contractor's minority and female workforce participation;

(4) Makes a good-faith effort to meet its individual goals and timetables; and

(5) Can provide access to documentation that demonstrates the effectiveness of actions taken on behalf of the Contractor. The obligation to comply is the Contractor's, and failure of such a group to fulfill an obligation shall not be a defense for the Contractor's noncompliance.

(i) A single goal for minorities and a separate single goal for women shall be established. The Contractor is required to provide equal employment opportunity and to take affirmative action for all minority groups, both male and female, and all women, both minority and nonminority. Consequently, the Contractor may be in violation of Executive Order 11246, as amended, if a particular group is employed in a substantially disparate manner.

(j) The Contractor shall not use goals or affirmative action standards to discriminate against any person because of race, color, religion, sex, or national origin.

(k) The Contractor shall not enter into any subcontract with any person or firm debarred from Government contracts under Executive Order 11246, as amended.

(l) The Contractor shall carry out such sanctions and penalties for violation of this clause and of the Equal Opportunity clause, including suspension, termination, and cancellation of existing subcontracts, as may be imposed or ordered under Executive Order 11246, as amended, and its implementing regulations, by the OFCCP. Any failure to carry out these sanctions and penalties as ordered shall be a violation of this clause and Executive Order 11246, as amended.

(m) The Contractor in fulfilling its obligations under this clause shall implement affirmative action procedures at least as extensive as those prescribed in paragraph (g) of this clause, so as to achieve maximum results from its efforts to ensure equal employment opportunity. If the Contractor fails to comply with the requirements of Executive Order 11246, as amended, the implementing regulations, or this clause, the Deputy Assistant Secretary shall take action as prescribed in 41 CFR 60-4.8.

(n) The Contractor shall designate a responsible official to--

(1) Monitor all employment-related activity to ensure that the Contractor's equal employment policy is being carried out;

(2) Submit reports as may be required by the Government; and

(3) Keep records that shall at least include for each employee the name, address, telephone number, construction trade, union affiliation (if any), employee identification number, social security number, race, sex, status (e.g., mechanic, apprentice, trainee, helper, or laborer), dates of changes in status, hours worked per week in the indicated trade, rate of pay, and locations at which the work was performed. Records shall be maintained in an easily understandable and retrievable form; however, to the degree that existing records satisfy this requirement, separate records are not required to be maintained.

Nothing contained herein shall be construed as a limitation upon the application of other laws that establish different

standards of compliance or upon the requirements for the hiring of local or other area residents (e.g., those under the Public Works Employment Act of 1977 and the Community Development Block Grant Program).

52.222-35 EQUAL OPPORTUNITY FOR SPECIAL DISABLED VETERANS, VETERANS OF THE VIETNAM ERA AND OTHER ELIGIBLE VETERANS (DEC 2001)

(a) Definitions. As used in this clause--

All employment openings means all positions except executive and top management, those positions that will be filled from within the Contractor's organization, and positions lasting 3 days or less. This term includes full-time employment, temporary employment of more than 3 days duration, and part-time employment.

Executive and top management means any employee--

(1) Whose primary duty consists of the management of the enterprise in which the individual is employed or of a customarily recognized department or subdivision thereof;

(2) Who customarily and regularly directs the work of two or more other employees;

(3) Who has the authority to hire or fire other employees or whose suggestions and recommendations as to the hiring or firing and as to the advancement and promotion or any other change of status of other employees will be given particular weight;

(4) Who customarily and regularly exercises discretionary powers; and

(5) Who does not devote more than 20 percent or, in the case of an employee of a retail or service establishment, who does not devote more than 40 percent of total hours of work in the work week to activities that are not directly and closely related to the performance of the work described in paragraphs (1) through (4) of this definition. This paragraph (5) does not apply in the case of an employee who is in sole charge of an establishment or a physically separated branch establishment, or who owns at least a 20 percent interest in the enterprise in which the individual is employed.

Other eligible veteran means any other veteran who served on active duty during a war or in a campaign or expedition for which a campaign badge has been authorized.

Positions that will be filled from within the Contractor's organization means employment openings for which the Contractor will give no consideration to persons outside the Contractor's organization (including any affiliates, subsidiaries, and parent companies) and includes any openings the Contractor proposes to fill from regularly established “recall” lists. The exception does not apply to a particular opening once an employer decides to consider applicants outside of its organization.

Qualified special disabled veteran means a special disabled veteran who satisfies the requisite skill, experience, education, and other job-related requirements of the employment position such veteran holds or desires, and who, with or without reasonable accommodation, can perform the essential functions of such position.

Special disabled veteran means--

(1) A veteran who is entitled to compensation (or who but for the receipt of military retired pay would be entitled to compensation) under laws administered by the Department of Veterans Affairs for a disability--

(i) Rated at 30 percent or more; or

(ii) Rated at 10 or 20 percent in the case of a veteran who has been determined under 38 U.S.C. 3106 to have a serious employment handicap (i.e., a significant impairment of the veteran's ability to prepare for, obtain, or retain employment consistent with the veteran's abilities, aptitudes, and interests); or

(2) A person who was discharged or released from active duty because of a service-connected disability.

Veteran of the Vietnam era means a person who--

(1) Served on active duty for a period of more than 180 days and was discharged or released from active duty with other than a dishonorable discharge, if any part of such active duty occurred--

(i) In the Republic of Vietnam between February 28, 1961, and May 7, 1975; or

(ii) Between August 5, 1964, and May 7, 1975, in all other cases; or

(2) Was discharged or released from active duty for a service-connected disability if any part of the active duty was performed--

(i) In the Republic of Vietnam between February 28, 1961, and May 7, 1975; or

(ii) Between August 5, 1964, and May 7, 1975, in all other cases.
(b) General. (1) The Contractor shall not discriminate against the individual because the individual is a special disabled veteran, a veteran of the Vietnam era, or other eligible veteran, regarding any position for which the employee or applicant for employment is qualified. The Contractor shall take affirmative action to employ, advance in employment, and otherwise treat qualified special disabled veterans, veterans of the Vietnam era, and other eligible veterans without discrimination based upon their disability or veterans' status in all employment practices such as--

(i) Recruitment, advertising, and job application procedures;

(ii) Hiring, upgrading, promotion, award of tenure, demotion, transfer, layoff, termination, right of return from layoff and rehiring;

(iii) Rate of pay or any other form of compensation and changes in compensation;

(iv) Job assignments, job classifications, organizational structures, position descriptions, lines of progression, and seniority lists;

(v) Leaves of absence, sick leave, or any other leave;

(vi) Fringe benefits available by virtue of employment, whether or not administered by the Contractor;

(vii) Selection and financial support for training, including apprenticeship, and on-the-job training under 38 U.S.C. 3687, professional meetings, conferences, and other related activities, and selection for leaves of absence to pursue training;

(viii) Activities sponsored by the Contractor including social or recreational programs; and

(ix) Any other term, condition, or privilege of employment.

(2) The Contractor shall comply with the rules, regulations, and relevant orders of the Secretary of Labor issued under the Vietnam Era Veterans' Readjustment Assistance Act of 1972 (the Act), as amended (38 U.S.C. 4211 and 4212).

(c) Listing openings. (1) The Contractor shall immediately list all employment openings that exist at the time of the execution of this contract and those which occur during the performance of this contract, including those not generated by this contract, and including those occurring at an establishment of the Contractor other than the one where the contract is being performed, but excluding those of independently operated corporate affiliates, at an

appropriate local public employment service office of the State wherein the opening occurs. Listing employment openings with the U.S. Department of Labor's America's Job Bank shall satisfy the requirement to list jobs with the local employment service office.

(2) The Contractor shall make the listing of employment openings with the local employment service office at least concurrently with using any other recruitment source or effort and shall involve the normal obligations of placing a bona fide job order, including accepting referrals of veterans and nonveterans. This listing of employment openings does not require hiring any particular job applicant or hiring from any particular group of job applicants and is not intended to relieve the Contractor from any requirements of Executive orders or regulations concerning nondiscrimination in employment.

(3) Whenever the Contractor becomes contractually bound to the listing terms of this clause, it shall advise the State public employment agency in each State where it has establishments of the name and location of each hiring location in the State. As long as the Contractor is contractually bound to these terms and has so advised the State agency, it need not advise the State agency of subsequent contracts. The Contractor may advise the State agency when it is no longer bound by this contract clause.

(d) Applicability. This clause does not apply to the listing of employment openings that occur and are filled outside the 50 States, the District of Columbia, the Commonwealth of Puerto Rico, the Commonwealth of the Northern Mariana Islands, American Samoa, Guam, the Virgin Islands of the United States, and Wake Island.

(e) Postings. (1) The Contractor shall post employment notices in conspicuous places that are available to employees and applicants for employment.

(2) The employment notices shall--

(i) State the rights of applicants and employees as well as the Contractor's obligation under the law to take affirmative action to employ and advance in employment qualified employees and applicants who are special disabled veterans, veterans of the Vietnam era, and other eligible veterans; and

(ii) Be in a form prescribed by the Deputy Assistant Secretary for Federal Contract Compliance Programs, Department of Labor (Deputy Assistant Secretary of Labor), and provided by or through the Contracting Officer.

(3) The Contractor shall ensure that applicants or employees who are special disabled veterans are informed of the contents of the notice (e.g., the Contractor may have the notice read to a visually disabled veteran, or may lower the posted notice so that it can be read by a person in a wheelchair).

(4) The Contractor shall notify each labor union or representative of workers with which it has a collective bargaining agreement, or other contract understanding, that the Contractor is bound by the terms of the Act and is committed to take affirmative action to employ, and advance in employment, qualified special disabled veterans, veterans of the Vietnam era, and other eligible veterans.

(f) Noncompliance. If the Contractor does not comply with the requirements of this clause, the Government may take appropriate actions under the rules, regulations, and relevant orders of the Secretary of Labor issued pursuant to the Act.

(g) Subcontracts. The Contractor shall insert the terms of this clause in all subcontracts or purchase orders of $25,000 or more unless exempted by rules, regulations, or orders of the Secretary of Labor. The Contractor shall act as specified by the Deputy Assistant Secretary of Labor to enforce the terms, including action for noncompliance.

(End of clause)

52.222-36 AFFIRMATIVE ACTION FOR WORKERS WITH DISABILITIES (JUN 1998)

(a) General. (1) Regarding any position for which the employee or applicant for employment is qualified, the Contractor shall not discriminate against any employee or applicant because of physical or mental disability. The Contractor agrees to take affirmative action to employ, advance in employment, and otherwise treat qualified individuals with disabilities without discrimination based upon their physical or mental disability in all employment practices such as--

(i) Recruitment, advertising, and job application procedures;

(ii) Hiring, upgrading, promotion, award of tenure, demotion, transfer, layoff, termination, right of return from layoff, and rehiring;

(iii) Rates of pay or any other form of compensation and changes in compensation;

(iv) Job assignments, job classifications, organizational structures, position descriptions, lines of progression, and seniority lists;

(v) Leaves of absence, sick leave, or any other leave;

(vi) Fringe benefits available by virtue of employment, whether or not administered by the Contractor;

(vii) Selection and financial support for training, including apprenticeships, professional meetings, conferences, and other related activities, and selection for leaves of absence to pursue training;

(viii) Activities sponsored by the Contractor, including social or recreational programs; and

(ix) Any other term, condition, or privilege of employment.

(2) The Contractor agrees to comply with the rules, regulations, and relevant orders of the Secretary of Labor (Secretary) issued under the Rehabilitation Act of 1973 (29 U.S.C. 793) (the Act), as amended.

(b) Postings. (1) The Contractor agrees to post employment notices stating--

(i) The Contractor's obligation under the law to take affirmative action to employ and advance in employment qualified individuals with disabilities; and

(ii) The rights of applicants and employees.

(2) These notices shall be posted in conspicuous places that are available to employees and applicants for employment. The Contractor shall ensure that applicants and employees with disabilities are informed of the contents of the notice (e.g., the Contractor may have the notice read to a visually disabled individual, or may lower the posted notice so that it might be read by a person in a wheelchair). The notices shall be in a form prescribed by the Deputy Assistant Secretary for Federal Contract Compliance of the U.S. Department of Labor (Deputy Assistant Secretary) and shall be provided by or through the Contracting Officer.

(3) The Contractor shall notify each labor union or representative of workers with which it has a collective bargaining agreement or other contract understanding, that the Contractor is bound by the terms of Section 503 of the Act and is committed to take affirmative action to employ, and advance in employment, qualified individuals with physical or mental disabilities.

(c) Noncompliance. If the Contractor does not comply with the requirements of this clause, appropriate actions may be taken under the rules, regulations, and relevant orders of the Secretary issued pursuant to the Act.

(d) Subcontracts. The Contractor shall include the terms of this clause in every subcontract or purchase order in excess of $10,000 unless exempted by rules, regulations, or orders of the Secretary. The Contractor shall act as specified by the Deputy Assistant Secretary to enforce the terms, including action for noncompliance.

(End of clause)

52.222-37 EMPLOYMENT REPORTS ON SPECIAL DISABLED VETERANS, VETERANS OF THE VIETNAM ERA, AND OTHER ELIGIBLE VETERANS (DEC 2001)

(a) Unless the Contractor is a State or local government agency, the Contractor shall report at least annually, as required by the Secretary of Labor, on--

(1) The number of special disabled veterans, the number of veterans of the Vietnam era, and other eligible veterans in the workforce of the Contractor by job category and hiring location; and

(2) The total number of new employees hired during the period covered by the report, and of the total, the number of special disabled veterans, the number of veterans of the Vietnam era, and the number of other eligible veterans; and

(3) The maximum number and the minimum number of employees of the Contractor during the period covered by the report.

(b) The Contractor shall report the above items by completing the Form VETS-100, entitled “Federal Contractor Veterans” Employment Report (VETS-100 Report)”.

(c) The Contractor shall submit VETS-100 Reports no later than September 30 of each year beginning September 30, 1988.

(d) The employment activity report required by paragraph (a)(2) of this clause shall reflect total hires during the most recent 12-month period as of the ending date selected for the employment profile report required by paragraph (a)(1) of this clause. Contractors may select an ending date--

(1) As of the end of any pay period between July 1 and August 31 of the year the report is due; or

(2) As of December 31, if the Contractor has prior written approval from the Equal Employment Opportunity Commission to do so for purposes of submitting the Employer Information Report EEO-1 (Standard Form 100).

(e) The Contractor shall base the count of veterans reported according to paragraph (a) of this clause on voluntary disclosure. Each Contractor subject to the reporting requirements at 38 U.S.C. 4212 shall invite all special disabled veterans, veterans of the Vietnam era, and other eligible veterans who wish to benefit under the affirmative action program at 38 U.S.C. 4212 to identify themselves to the Contractor. The invitation shall state that--

(1) The information is voluntarily provided;

(2) The information will be kept confidential;

(3) Disclosure or refusal to provide the information will not subject the applicant or employee to any adverse treatment; and

(4) The information will be used only in accordance with the regulations promulgated under 38 U.S.C. 4212.

(f) The Contractor shall insert the terms of this clause in all subcontracts or purchase orders of $25,000 or more unless exempted by rules, regulations, or orders of the Secretary of Labor.

(End of clause)

52.223-5 POLLUTION PREVENTION AND RIGHT-TO-KNOW INFORMATION (APR 1998)

(a) Executive Order 12856 of August 3, 1993, requires Federal facilities to comply with the provisions of the

Emergency Planning and Community Right-to-Know Act of 1986 (EPCRA)(42 U.S.C. 11001-11050) and the Pollution Prevention Act of 1990 (PPA)(42 U.S.C. 13101-13109).

(b) The Contractor shall provide all information needed by the Federal facility to comply with the emergency planning reporting requirements of Section 302 of EPCRA; the emergency notice requirements of Section 304 of EPCRA; the list of Material Safety Data Sheets required by Section 311 of EPCRA; the emergency and hazardous chemical inventory forms of Section 312 of EPCRA; the toxic chemical release inventory of Section 313 of EPCRA, which includes the reduction and recycling information required by Section 6607 of PPA; and the toxic chemical reduction goals requirements of Section 3-302 of Executive Order 12856.

52.223-6 DRUG-FREE WORKPLACE (MAY 2001)

(a) Definitions. As used in this clause --

"Controlled substance" means a controlled substance in schedules I through V of section 202 of the Controlled Substances Act (21 U.S.C. 812) and as further defined in regulation at 21 CFR 1308.11 - 1308.15.

"Conviction" means a finding of guilt (including a plea of nolo contendere) or imposition of sentence, or both, by any judicial body charged with the responsibility to deter- mine violations of the Federal or State criminal drug statutes.

"Criminal drug statute" means a Federal or non-Federal criminal statute involving the manufacture, distribution, dispensing, possession, or use of any controlled substance.

"Drug-free workplace" means the site(s) for the performance of work done by the Contractor in connection with a specific contract where employees of the Contractor are prohibited from engaging in the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance.

"Employee" means an employee of a Contractor directly engaged in the performance of work under a Government contract. "Directly engaged" is defined to include all direct cost employees and any other Contractor employee who has other than a minimal impact or involvement in contract performance.

"Individual" means an offeror/contractor that has no more than one employee including the offeror/contractor.

(b) The Contractor, if other than an individual, shall-- within 30 days after award (unless a longer period is agreed to in writing for contracts of 30 days or more performance duration), or as soon as possible for contracts of less than 30 days performance duration--

(1) Publish a statement notifying its employees that the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance is prohibited in the Contractor's workplace and specifying the actions that will be taken against employees for violations of such prohibition;

(2) Establish an ongoing drug-free awareness program to inform such employees about--

(i) The dangers of drug abuse in the workplace;

(ii) The Contractor's policy of maintaining a drug-free workplace;

(iii) Any available drug counseling, rehabilitation, and employee assistance programs; and

(iv) The penalties that may be imposed upon employees for drug abuse violations occurring in the workplace;

(3) Provide all employees engaged in performance of the contract with a copy of the statement required by subparagraph (b)(1) of this clause;

(4) Notify such employees in writing in the statement required by subparagraph (b)(1) of this clause that, as a condition of continued employment on this contract, the employee will--

(i) Abide by the terms of the statement; and

(ii) Notify the employer in writing of the employee's conviction under a criminal drug statute for a violation occurring in the workplace no later than 5 days after such conviction.

(5) Notify the Contracting Officer in writing within 10 days after receiving notice under subdivision (b)(4)(ii) of this clause, from an employee or otherwise receiving actual notice of such conviction. The notice shall include the position title of the employee;

(6) Within 30 days after receiving notice under subdivision (b)(4)(ii) of this clause of a conviction, take one of the following actions with respect to any employee who is convicted of a drug abuse violation occurring in the workplace:

(i) Taking appropriate personnel action against such employee, up to and including termination; or

(ii) Require such employee to satisfactorily participate in a drug abuse assistance or rehabilitation program approved for such purposes by a Federal, State, or local health, law enforcement, or other appropriate agency; and

(7) Make a good faith effort to maintain a drug-free workplace through implementation of subparagraphs (b)(1) though (b)(6) of this clause.

(c) The Contractor, if an individual, agrees by award of the contract or acceptance of a purchase order, not to engage in the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance while performing this contract.

(d) In addition to other remedies available to the Government, the Contractor's failure to comply with the requirements of paragraph (b) or (c) of this clause may, pursuant to FAR 23.506, render the Contractor subject to suspension of contract payments, termination of the contract for default, and suspension or debarment.

(End of clause)

52.223-14 TOXIC CHEMICAL RELEASE REPORTING (OCT 2000)

(a) Unless otherwise exempt, the Contractor, as owner or operator of a facility used in the performance of this contract, shall file by July 1 for the prior calendar year an annual Toxic Chemical Release Inventory Form (Form R) as described in sections 313(a) and (g) of the Emergency Planning and Community Right-to-Know Act of 1986 (EPCRA) (42 U.S.C. 11023(a) and (g)), and section 6607 of the Pollution Prevention Act of 1990 (PPA) (42 U.S.C. 13106). The Contractor shall file, for each facility subject to the Form R filing and reporting requirements, the annual Form R throughout the life of the contract.

(b) A Contractor owned or operated facility used in the performance of this contract is exempt from the requirement to file an annual Form R if--

(1) The facility does not manufacture, process, or otherwise use any toxic chemicals listed under section 313(c) of EPCRA, 42 U.S.C. 11023(c);

(2) The facility does not have 10 or more full-time employees as specified in section 313(b)(1)(A) of EPCRA, 42 U.S.C. 11023(b)(1)(A);

(3) The facility does not meet the reporting thresholds of toxic chemicals established under of EPCRA, 42 U.S.C. 11023(f) (including the alternate thresholds at 40 CFR 372.27, provided an appropriate certification form has been filed with EPA);

(4) The facility does not fall within Standard Industrial Classification Code (SIC) major groups 20 through 39 or their corresponding North American Industry Classification System (NAICS) sectors 31 through 33; or

(5) The facility is not located within any State of the United States, the District of Columbia, the Commonwealth of Puerto Rico, Guam, American Samoa, the United States Virgin Islands, the Northern Mariana Islands, or any other territory or possession over which the United States has jurisdiction.

(c) If the Contractor has certified to an exemption in accordance with one or more of the criteria in paragraph (b) of this clause, and after award of the contract circumstances change so that any of its owned or operated facilities used in the performance of this contract is no longer exempt--

(1) The Contractor shall notify the Contracting Officer; and

(2) The Contractor, as owner or operator of a facility used in the performance of this contract that is no longer exempt, shall (i) submit a Toxic Chemical Release Inventory Form (Form R) on or before July 1 for the prior calendar year during which the facility becomes eligible; and (ii) continue to file the annual Form R for the life of the contract for such facility.

(d) The Contracting Officer may terminate this contract or take other action as appropriate, if the Contractor fails to comply accurately and fully with the EPCRA and PPA toxic chemical release filing and reporting requirements.

(e) Except for acquisitions of commercial items, as defined in FAR Part 2, the Contractor shall--

(1) For competitive subcontracts expected to exceed $100,000 (including all options), include a solicitation provision substantially the same as the provision at FAR 52.223-13, Certification of Toxic Chemical Release Reporting; and

(2) Include in any resultant subcontract exceeding $100,000 (including all options), the substance of this clause, except this paragraph (e).

52.225-5 TRADE AGREEMENTS (DEC 2001)

(a) Definitions. As used in this clause.

Caribbean Basin country means any of the following countries: Antigua and Barbuda, Aruba, Bahamas, Barbados, Belize, British Virgin Islands, Costa Rica, Dominica, El Salvador, Grenada, Guatemala, Guyana, Haiti, Iceland, Jamaica, Montserrat, Netherlands Antilles, Nicaragua, Panama, St. Kitts and Nevis, St. Lucia, St. Vincent and the Grenadines, Trinidad and Tobago.

Caribbean Basin country end product means an article that--

(1) Is wholly the growth, product, or manufacture of a Caribbean Basin country; or

(2) In the case of an article that consists in whole or in part of materials from another country, has been substantially transformed in a Caribbean Basin country into a new and different article of commerce with a name, character, or use distinct from that of the article or articles from which it was transformed. The term refers to a product offered for purchase under a supply contract, but for purposes of calculating the value of the end product includes services (except transportation services) incidental to the article, provided that the value of those incidental services does not exceed that of the article itself. The term excludes products that are excluded from duty-free treatment for Caribbean countries under 19 U.S.C. 2703(b), which presently are--

(i) Textiles and apparel articles that are subject to textile agreements;

(ii) Footwear, handbags, luggage, flat goods, work gloves, and leather wearing apparel not designated as eligible articles for the purpose of the Generalized System of Preferences under Title V of the Trade Act of 1974;

(iii) Tuna, prepared or preserved in any manner in airtight containers;

(iv) Petroleum, or any product derived from petroleum; and

(v) Watches and watch parts (including cases, bracelets, and straps) of whatever type including, but not limited to, mechanical, quartz digital, or quartz analog, if such watches or watch parts contain any material that is the product of any country to which the Harmonized Tariff Schedule of the United States (HTSUS) column 2 rates of duty apply.

Designated country means any of the following countries: Aruba, Austria, Bangladesh Belgium, Benin, Bhutan, Botswana, Burkina Faso, Burundi, Canada, Cape Verde, Central African Republic, Chad, Comoros, Denmark, Djibouti, Equatorial Guinea.

Finland, France, Gambia, Germany, Greece, Guinea, Guinea-Bissau, Haiti, Hong Kong, Ireland, Israel, Italy, Japan.

Kiribati, Korea, Republic of Lesotho, Liechtenstein, Luxembourg, Malawi, Maldives, Mali, Mozambique, Nepal, Netherlands, Niger, Norway, Portugal, Rwanda.

Sao Tome and Principe, Sierra Leone, Singapore, Somalia, Spain, Sweden, Switzerland, Tanzania U.R., Togo, Tuvalu, Uganda, United Kingdom, Vanuatu, Western Samoa, Yemen.

Designated country end product means an article that--

(1) Is wholly the growth, product, or manufacture of a designated country; or

(2) In the case of an article that consists in whole or in part of materials from another country, has been substantially transformed in a designated country into a new and different article of commerce with a name, character, or use distinct from that of the article or articles from which it was transformed. The term refers to a product offered for purchase under a supply contract, but for purposes of calculating the value of the end product includes services, (except transportation services) incidental to the article, provided that the value of those incidental services does not exceed that of the article itself.

End product means supplies delivered under a line item of a Government contract.

North American Free Trade Agreement country means Canada or Mexico.

North American Free Trade Agreement country end product means an article that--

(1) Is wholly the growth, product, or manufacture of a North American Free Trade Agreement (NAFTA) country; or

(2) In the case of an article that consists in whole or in part of materials from another country, has been substantially transformed in a NAFTA country into a new and different article of commerce with a name, character, or use distinct from that of the article or articles from which it was transformed. The term refers to a product offered for purchase under a supply contract, but for purposes of calculating the value of the end product includes services, (except transportation services) incidental to the article, provided that the value of those incidental services does not exceed that of the article itself.

United States means the 50 States and the District of Columbia, U.S. territories and possessions, Puerto Rico, the Northern Mariana Islands, and any other place subject to U.S. jurisdiction, but does not include leased bases.

U.S.-made end product means an article that is mined, produced, or manufactured in the United States or that is substantially transformed in the United States into a new and different article of commerce with a name, character, or use distinct from that of the article or articles from which it was transformed.,

(b) Implementation. This clause implements the Trade, Agreements Act (19 U.S.C. 2501, et seq.) and the North American Free Trade Agreement Implementation Act of 1993, (NAFTA) (19 U.S.C. 3301 note), by restricting the acquisition of end products that are not U.S.-made, designated country, Caribbean Basin country, or NAFTA country end products.,

(c) Delivery of end products. The Contracting Officer has determined that the Trade Agreements Act and NAFTA apply to this acquisition. Unless otherwise specified, these trade agreements apply to all items in the Schedule. The Contractor shall deliver under this contract only U.S.-made, designated country, Caribbean Basin country, or NAFTA country end products except to the extent that, in its offer, it specified delivery of other end products in the provision entitled “Trade Agreements Certificate.”

(End of clause)

52.225-11 BUY AMERICAN ACT--BALANCE OF PAYMENTS PROGRAM--CONSTRUCTION MATERIALS UNDER TRADE AGREEMENTS (DEC 2001)

(a) Definitions. As used in this clause--

Component means an article, material, or supply incorporated directly into a construction material.

Construction material means an article, material, or supply brought to the construction site by the Contractor or subcontractor for incorporation into the building or work. The term also includes an item brought to the site preassembled from articles, materials, or supplies. However, emergency life safety systems, such as emergency lighting, fire alarm, and audio evacuation systems, that are discrete systems incorporated into a public building or work and that are produced as complete systems, are evaluated as a single and distinct construction material regardless of when or how the individual parts or components of those systems are delivered to the construction site. Materials purchased directly by the Government are supplies, not construction material.

Cost of components means--

(1) For components purchased by the Contractor, the acquisition cost, including transportation costs to the place of incorporation into the end product (whether or not such costs are paid to a domestic firm), and any applicable duty (whether or not a duty-free entry certificate is issued); or

(2) For components manufactured by the Contractor, all costs associated with the manufacture of the component, including transportation costs as described in paragraph (1) of this definition, plus allocable overhead costs, but excluding profit. Cost of components does not include any costs associated with the manufacture of the end product.

Designated country means any of the following countries: Aruba, Austria, Bangladesh, Belgium, Benin, Bhutan, Botswana, Burkina Faso, Burundi, Canada, Cape Verde, Central African Republic, Chad, Comoros, Denmark, Djibouti, Equatorial Guinea, Finland, France, Gambia, Germany, Greece, Guinea, Guinea-Bissau, Haiti, Hong Kong, Iceland, Ireland, Israel, Italy, Japan.

Kiribati, Korea, Republic of, Lesotho, Liechtenstein, Luxembourg, Malawi, Maldives, Mali, Mozambique, Nepal, Netherlands, Niger, Norway, Portugal, Rwanda.

Sao Tome and Principe, Sierra Leone, Singapore, Somalia, Spain, Sweden, Switzerland, Tanzania U.R., Togo, Tuvalu, Uganda, United Kingdom, Vanuatu, Western Samoa, Yemen.

Designated country construction material means a construction material that--

(1) Is wholly the growth, product, or manufacture of a designated country; or

(2) In the case of a construction material that consists in whole or in part of materials from another country, has been substantially transformed in a designated country into a new and different construction material distinct from the materials from which it was transformed.

Domestic construction material means--

(1) An unmanufactured construction material mined or produced in the United States; or

(2) A construction material manufactured in the United States, if the cost of its components mined, produced, or manufactured in the United States exceeds 50 percent of the cost of all its components. Components of foreign origin of the same class or kind for which nonavailability determinations have been made are treated as domestic.

Foreign construction material means a construction material other than a domestic construction material.

North American Free Trade Agreement country means Canada or Mexico.

North American Free Trade Agreement country construction material means a construction material that--

(1) Is wholly the growth, product, or manufacture of a North American Free Trade Agreement (NAFTA) country; or

(2) In the case of a construction material that consists in whole or in part of materials from another country, has been substantially transformed in a NAFTA country into a new and different construction material distinct from the materials from which it was transformed.

United States means the 50 States and the District of Columbia, U.S. territories and possessions, Puerto Rico, the Northern Mariana Islands, and any other place subject to U.S. jurisdiction, but does not include leased bases.

(b) Construction materials. (1) This clause implements the Buy American Act (41 U.S.C. 10a-10d) and the Balance of Payments Program by providing a preference for domestic construction material. In addition, the Contracting Officer has determined that the Trade Agreements Act and the North American Free Trade Agreement (NAFTA) apply to this acquisition. Therefore, the Buy American Act and Balance of Payments Program restrictions are waived for designated country and NAFTA country construction materials.

(2) The Contractor shall use only domestic, designated country, or NAFTA country construction material in performing this contract, except as provided in paragraphs (b)(3) and (b)(4) of this clause.

(3) The requirement in paragraph (b)(2) of this clause does not apply to the construction materials or components listed by the Government as follows: NONE

(4) The Contracting Officer may add other foreign construction material to the list in paragraph (b)(3) of this clause if the Government determines that--

(i) The cost of domestic construction material would be unreasonable. The cost of a particular domestic construction material subject to the restrictions of the Buy American Act is unreasonable when the cost of such material exceeds the cost of foreign material by more than 6 percent. For determination of unreasonable cost under the Balance of Payments Program, the Contracting Officer will use a factor of 50 percent;

(ii) The application of the restriction of the Buy American Act or Balance of Payments Program to a particular construction material would be impracticable or inconsistent with the public interest; or

(iii) The construction material is not mined, produced, or manufactured in the United States in sufficient and reasonably available commercial quantities of a satisfactory quality.

(c) Request for determination of inapplicability of the Buy American Act or Balance of Payments Program. (1)(i) Any Contractor request to use foreign construction material in accordance with paragraph (b)(4) of this clause shall include adequate information for Government evaluation of the request, including--

(A) A description of the foreign and domestic construction materials;

(B) Unit of measure;

(C) Quantity;

(D) Price;

(E) Time of delivery or availability;

(F) Location of the construction project;

(G) Name and address of the proposed supplier; and

(H) A detailed justification of the reason for use of foreign construction materials cited in accordance with paragraph (b)(3) of this clause.

(ii) A request based on unreasonable cost shall include a reasonable survey of the market and a completed price comparison table in the format in paragraph (d) of this clause.

(iii) The price of construction material shall include all delivery costs to the construction site and any applicable duty (whether or not a duty-free certificate may be issued).

(iv) Any Contractor request for a determination submitted after contract award shall explain why the Contractor could not reasonably foresee the need for such determination and could not have requested the determination before contract award. If the Contractor does not submit a satisfactory explanation, the Contracting Officer need not make a determination.

(2) If the Government determines after contract award that an exception to the Buy American Act or Balance of Payments Program applies and the Contracting Officer and the Contractor negotiate adequate consideration, the Contracting Officer will modify the contract to allow use of the foreign construction material. However, when the basis for the exception is the unreasonable price of a domestic construction material, adequate consideration is not less than the differential established in paragraph (b)(4)(i) of this
clause.

(3) Unless the Government determines that an exception to the Buy American Act or Balance of Payments Program applies, use of foreign construction material is noncompliant with the Buy American Act or Balance of Payments Program.

(d) Data. To permit evaluation of requests under paragraph (c) of this clause based on unreasonable cost, the Contractor shall include the following information and any applicable supporting data based on the survey of suppliers:

Foreign and Domestic Construction Materials Price Comparison

Construction material description	Unit of measure	Quantity	Price (dollars) \1\
Item 1:			

Foreign construction material.... ....
Domestic construction material... ....
Item 2:
Foreign construction material.... ....
Domestic construction material... ....

\1\ Include all delivery costs to the construction site and any applicable duty (whether or not a duty-free entry certificate is issued).
List name, address, telephone number, and contact for suppliers surveyed. Attach copy of response; if oral, attach summary.
Include other applicable supporting information.

(End of clause)

52.225-13 RESTRICTIONS ON CERTAIN FOREIGN PURCHASES (JUL 2000)

(a) The Contractor shall not acquire, for use in the performance of this contract, any supplies or services originating from sources within, or that were located in or transported from or through, countries whose products are banned from importation into the United States under regulations of the Office of Foreign Assets Control, Department of the Treasury. Those countries are Cuba, Iran, Iraq, Libya, North Korea, Sudan, the territory of Afghanistan controlled by the Taliban, and Serbia (excluding the territory of Kosovo).

(b) The Contractor shall not acquire for use in the performance of this contract any supplies or services from entities controlled by the government of Iraq.

(c) The Contractor shall insert this clause, including this paragraph (c), in all subcontracts.

(End of clause)

52.226-1 UTILIZATION OF INDIAN ORGANIZATIONS AND INDIAN-OWNED ECONOMIC ENTERPRISES (JUN 2000)

(a) Definitions. As used in this clause:

"Indian" means any person who is a member of any Indian tribe, band, group, pueblo or community that is recognized by the Federal Government as eligible for services from the Bureau of Indian Affairs (BIA) in accordance with 25 U.S.C. 1452(c) and any ``Native" as defined in the Alaska Native Claims Settlement Act (43 U.S.C. 1601).

"Indian organization" means the governing body of any Indian tribe or entity established or recognized by the governing body of an Indian tribe for the purposes of 25 U.S.C., chapter 17.

"Indian-owned economic enterprise" means any Indian-owned (as determined by the Secretary of the Interior) commercial, industrial, or business activity established or organized for the purpose of profit, provided that Indian ownership constitutea not less than 51 percent of the enterprise.

"Indian tribe" means any Indian tribe, band, group, pueblo or community, including native villages and native groups (including corporations organized by Kenai, Juneau, Sitka, and Kodiak) as defined in the Alaska Native Claims Settlement Act, that is recognized by the Federal Government as eligible for services from BIA in accordance with 25 U.S.C. 1542(c).

"Interested party" means a prime contractor or an actual or prospective offeror whose direct economic interest would be affected by the award of a subcontract or by the failure to award a subcontract.

(b) The Contractor shall use its best efforts to give Indian organizations and Indian-owned economic enterprises (25 U.S.C. 1544) the maximum practicable opportunity to participate in the subcontracts it awards to the fullest extent consistent with efficient performance of its contract.

(1) The Contracting Officer and the Contractor, acting in good faith, may rely on the representation of an Indian organization or Indian-owned economic enterprise as to its eligibility, unless an interested party challenges its status or the Contracting Officer has independent reason to question that status. In the event of a challenge to the representation of a subcontractor, the Contracting Officer will refer the matter to the U.S. Department of the Interior, Bureau of Indian Affairs (BIA), Attn: Chief, Division of Contracting and Grants Administration, 1849 C Street, NW., MS 2626-MIB, Washington, DC 20240-4000.

The BIA will determine the eligibility and notify the Contracting Officer. No incentive payment will be made within 50 working days of subcontract award or while a challenge is pending. If a subcontractor is determined to be an ineligible participant, no incentive payment will be made under the Indian Incentive Program.

(2) The Contractor may request an adjustment under the Indian Incentive Program to the following:

(i) The estimated cost of a cost-type contract.

(ii) The target cost of a cost-plus-incentive-fee prime contract.

(iii) The target cost and ceiling price of a fixed-price incentive prime contract.

(iv) The price of a firm-fixed-price prime contract.

(3) The amount of the adjustment to the prime contract is 5 percent of the estimated cost, target cost, or firm-fixed-price included in the subcontract initially awarded to the Indian organization or Indian-owned economic enterprise.

(4) The Contractor has the burden of proving the amount claimed and must assert its request for an adjustment prior to completion of contract performance.

(c) The Contracting Officer, subject to the terms and conditions of the contract and the availability of funds, will authorize an incentive payment of 5 percent of the amount paid to the subcontractor. The Contracting Officer will seek funding in accordance with agency procedures.

(End of clause)

52.227-1 AUTHORIZATION AND CONSENT (JUL 1995)

(a) The Government authorizes and consents to all use and manufacture, in performing this contract or any subcontract at any tier, of any invention described in and covered by a United States patent (1) embodied in the structure or composition of any article the delivery of which is accepted by the Government under this contract or (2) used in machinery, tools, or methods whose use necessarily results from compliance by the Contractor or a subcontractor with (i) specifications or written provisions forming a part of this contract or (ii) specific written instructions given by the Contracting Officer directing the manner of performance. The entire liability to the Government for infringement of a patent of the United States shall be determined solely by the provisions of the indemnity clause, if any, included in this contract or any subcontract hereunder (including any lower-tier subcontract), and the Government assumes liability for all other infringement to the extent of the authorization and consent hereinabove granted.

(b) The Contractor agrees to include, and require inclusion of, this clause, suitably modified to identify the parties, in all subcontracts at any tier for supplies or services (including construction, architect-engineer services, and

materials, supplies, models, samples, and design or testing services expected to exceed the simplified acquisition threshold (however, omission of this clause from any subcontract, including those at or below the simplified acquisition threshold, does not affect this authorization and consent.)

52.228-2 ADDITIONAL BOND SECURITY (OCT 1997)

The Contractor shall promptly furnish additional security required to protect the Government and persons supplying labor or materials under this contract if--

(a) Any surety upon any bond, or issuing financial institution for other security, furnished with this contract becomes unacceptable to the Government.

(b) Any surety fails to furnish reports on its financial condition as required by the Government;

(c) The contract price is increased so that the penal sum of any bond becomes inadequate in the opinion of the Contracting Officer; or

(d) An irrevocable letter of credit (ILC) used as security will expire before the end of the period of required security. If the Contractor does not furnish an acceptable extension or replacement ILC, or other acceptable substitute, at least 30 days before an ILC's scheduled expiration, the Contracting officer has the right to immediately draw on the ILC.

52.228-11 PLEDGES OF ASSETS (FEB 1992)

(a) Offerors shall obtain from each person acting as an individual surety on a bid guarantee, a performance bond, or a payment bond--

(1) Pledge of assets; and

(2) Standard Form 28, Affidavit of Individual Surety.

(b) Pledges of assets from each person acting as an individual surety shall be in the form of--

(1) Evidence of an escrow account containing cash, certificates of deposit, commercial or Government securities, or other assets described in FAR 28.203-2 (except see 28.203-2(b)(2) with respect to Government securities held in book entry form) and/or;

(2) A recorded lien on real estate. The offeror will be required to provide--

(i) Evidence of title in the form of a certificate of title prepared by a title insurance company approved by the United States Department of Justice. This title evidence must show fee simple title vested in the surety along with any concurrent owners; whether any real estate taxes are due and payable; and any recorded encumbrances against the property, including the lien filed in favor of the Government as required by FAR 28.203-3(d);

(ii) Evidence of the amount due under any encumbrance shown in the evidence of title;

(iii) A copy of the current real estate tax assessment of the property or a current appraisal dated no earlier than 6 months prior to the date of the bond, prepared by a professional appraiser who certifies that the appraisal has been conducted in accordance with the generally accepted appraisal standards as reflected in the Uniform Standards of Professional Appraisal Practice, as promulgated by the Appraisal Foundation.

(End of clause)

52.228-12 PROSPECTIVE SUBCONTRACTOR REQUESTS FOR BONDS. (OCT 1995)

In accordance with Section 806(a)(3) of Pub. L. 102-190, as amended by Sections 2091 and 8105 of Pub. L. 103-355, upon the request of a prospective subcontractor or supplier offering to furnish labor or material for the performance of this contract for which a payment bond has been furnished to the Government pursuant to the Miller Act, the Contractor shall promptly provide a copy of such payment bond to the requester.

52.228-14 IRREVOCABLE LETTER OF CREDIT (DEC 1999)

(a) “Irrevocable letter of credit” (ILC), as used in this clause, means a written commitment by a federally insured financial institution to pay all or part of a stated amount of money, until the expiration date of the letter, upon presentation by the Government (the beneficiary) of a written demand therefor. Neither the financial institution nor the offeror/Contractor can revoke or condition the letter of credit.

(b) If the offeror intends to use an ILC in lieu of a bid bond, or to secure other types of bonds such as performance and payment bonds, the letter of credit and letter of confirmation formats in paragraphs (e) and (f) of this clause shall be used.

(c) The letter of credit shall be irrevocable, shall require presentation of no document other than a written demand and the ILC (including confirming letter, if any), shall be issued/confirmed by an acceptable federally insured financial institution as provided in paragraph (d) of this clause, and--

(1) If used as a bid guarantee, the ILC shall expire no earlier than 60 days after the close of the bid acceptance period;

(2) If used as an alternative to corporate or individual sureties as security for a performance or payment bond, the offeror/Contractor may submit an ILC with an initial expiration date estimated to cover the entire period for which financial security is required or may submit an ILC with an initial expiration date that is a minimum period of one year from the date of issuance. The ILC shall provide that, unless the issuer provides the beneficiary written notice of non-renewal at least 60 days in advance of the current expiration date, the ILC is automatically extended without amendment for one year from the expiration date, or any future expiration date, until the period of required coverage is completed and the Contracting Officer provides the financial institution with a written statement waiving the right to payment. The period of required coverage shall be:

(i) For contracts subject to the Miller Act, the later of--

(A) One year following the expected date of final payment;

(B) For performance bonds only, until completion of any warranty period; or

(C) For payment bonds only, until resolution of all claims filed against the payment bond during the one-year period following final payment.

(ii) For contracts not subject to the Miller Act, the later of--

(A) 90 days following final payment; or

(B) For performance bonds only, until completion of any warranty period.

(d) Only federally insured financial institutions rated investment grade or higher shall issue or confirm the ILC. The offeror/Contractor shall provide the Contracting Officer a credit rating that indicates the financial institution has the required rating(s) as of the date of issuance of the ILC. Unless the financial institution issuing the ILC had letter of credit business of less than $25 million in the past year, ILCs over $5 million must be confirmed by another

acceptable financial institution that had letter of credit business of less than $25 million in the past year.

(e) The following format shall be used by the issuing financial institution to create an ILC:

_____

[Issuing Financial Institution's Letterhead or Name and Address]

Issue Date _____

IRREVOCABLE LETTER OF CREDIT NO. _____

Account party's name _____

Account party's address _____

For Solicitation No. _____(for reference only)

TO: [U.S. Government agency]

[U.S. Government agency's address]

1. We hereby establish this irrevocable and transferable Letter of Credit in your favor for one or more drawings up to United States $_____. This Letter of Credit is payable at [issuing financial institution's and, if any, confirming financial institution's] office at [issuing financial institution's address and, if any, confirming financial institution's address] and expires with our close of business on _____, or any automatically extended expiration date.

2. We hereby undertake to honor your or the transferee's sight draft(s) drawn on the issuing or, if any, the confirming financial institution, for all or any part of this credit if presented with this Letter of Credit and confirmation, if any, at the office specified in paragraph 1 of this Letter of Credit on or before the expiration date or any automatically extended expiration date.

3. [This paragraph is omitted if used as a bid guarantee, and subsequent paragraphs are renumbered.] It is a condition of this Letter of Credit that it is deemed to be automatically extended without amendment for one year from the expiration date hereof, or any future expiration date, unless at least 60 days prior to any expiration date, we notify you or the transferee by registered mail, or other receipted means of delivery, that we elect not to consider this Letter of Credit renewed for any such additional period. At the time we notify you, we also agree to notify the account party (and confirming financial institution, if any) by the same means of delivery.

4. This Letter of Credit is transferable. Transfers and assignments of proceeds are to be effected without charge to either the beneficiary or the transferee/assignee of proceeds. Such transfer or assignment shall be only at the written direction of the Government (the beneficiary) in a form satisfactory to the issuing financial institution and the confirming financial institution, if any.

5. This Letter of Credit is subject to the Uniform Customs and Practice (UCP) for Documentary Credits, 1993 Revision, International Chamber of Commerce Publication No. 500, and to the extent not inconsistent therewith, to the laws of _____ [state of confirming financial institution, if any, otherwise state of issuing financial institution].

6. If this credit expires during an interruption of business of this financial institution as described in Article 17 of the UCP, the financial institution specifically agrees to effect payment if this credit is drawn against within 30 days after the resumption of our business.

Sincerely,

_____

[Issuing financial institution]

(f) The following format shall be used by the financial institution to confirm an ILC:

_____
[Confirming Financial Institution's Letterhead or Name and Address]

(Date) _____

Our Letter of Credit Advice Number _____

Beneficiary: _____ [U.S. Government agency]

Issuing Financial Institution: _____

Issuing Financial Institution's LC No.: _____

Gentlemen:

1. We hereby confirm the above indicated Letter of Credit, the original of which is attached, issued by _____ [name of issuing financial institution] for drawings of up to United States dollars _____/U.S. $_____ and expiring with our close of business on _____ [the expiration date], or any automatically extended expiration date.

2. Draft(s) drawn under the Letter of Credit and this Confirmation are payable at our office located at _____.

3. We hereby undertake to honor sight draft(s) drawn under and presented with the Letter of Credit and this Confirmation at our offices as specified herein.

4. [This paragraph is omitted if used as a bid guarantee, and subsequent paragraphs are renumbered.] It is a condition of this confirmation that it be deemed automatically extended without amendment for one year from the expiration date hereof, or any automatically extended expiration date, unless:

(a) At least 60 days prior to any such expiration date, we shall notify the Contracting Officer, or the transferee and the issuing financial institution, by registered mail or other receipted means of delivery, that we elect not to consider this confirmation extended for any such additional period; or

(b) The issuing financial institution shall have exercised its right to notify you or the transferee, the account party, and ourselves, of its election not to extend the expiration date of the Letter of Credit.

5. This confirmation is subject to the Uniform Customs and Practice (UCP) for Documentary Credits, 1993 Revision, International Chamber of Commerce Publication No. 500, and to the extent not inconsistent therewith, to the laws of _____ [state of confirming financial institution].

6. If this confirmation expires during an interruption of business of this financial institution as described in Article 17 of the UCP, we specifically agree to effect payment if this credit is drawn against within 30 days after the resumption of our business.

Sincerely,

_____

[Confirming financial institution]

(g) The following format shall be used by the Contracting Officer for a sight draft to draw on the Letter of Credit:

SIGHT DRAFT

_____

[City, State]

(Date) _____

[Name and address of financial institution]

Pay to the order of _____ [Beneficiary Agency] _____ the sum of United States $_____. This draft is drawn under Irrevocable Letter of Credit No. _____.

_____

[Beneficiary Agency]

By: _____

(End of clause)

52.228-15 PERFORMANCE AND PAYMENT BONDS--CONSTRUCTION (JUL 2000)-

(a) Definitions. As used in this clause--

Original contract price means the award price of the contract; or, for requirements contracts, the price payable for the estimated total quantity; or, for indefinite-quantity contracts, the price payable for the specified minimum quantity. Original contract price does not include the price of any options, except those options exercised at the time of contract award.

(b) Amount of required bonds. Unless the resulting contract price is $100,000 or less, the successful offeror shall furnish performance and payment bonds to the Contracting Officer as follows:

(1) Performance bonds (Standard Form 25). The penal amount of performance bonds at the time of contract award shall be 100 percent of the original contract price.

(2) Payment Bonds (Standard Form 25-A). The penal amount of payment bonds at the time of contract award shall be 100 percent of the original contract price.

(3) Additional bond protection. (i) The Government may require additional performance and payment bond protection if the contract price is increased. The increase in protection generally will equal 100 percent of the increase in contract price.

(ii) The Government may secure the additional protection by directing the Contractor to increase the penal amount of the existing bond or to obtain an additional bond.

(c) Furnishing executed bonds. The Contractor shall furnish all executed bonds, including any necessary reinsurance agreements, to the Contracting Officer, within the time period specified in the Bid Guarantee provision of the solicitation, or otherwise specified by the Contracting Officer, but in any event, before starting work.

(d) Surety or other security for bonds. The bonds shall be in the form of firm commitment, supported by corporate sureties whose names appear on the list contained in Treasury Department Circular 570, individual sureties, or by other acceptable security such as postal money order, certified check, cashier's check, irrevocable letter of credit, or, in accordance with Treasury Department regulations, certain bonds or notes of the United States. Treasury Circular 570 is published in the Federal Register or may be obtained from the U.S. Department of Treasury, Financial Management Service, Surety Bond Branch, 401 14th Street, NW, 2nd Floor, West Wing, Washington, DC 20227.

(e) Notice of subcontractor waiver of protection (40 U.S.C. 270b(c). Any waiver of the right to sue on the payment bond is void unless it is in writing, signed by the person whose right is waived, and executed after such person has first furnished labor or material for use in the performance of the contract.

(End of clause)

52.229-3 FEDERAL, STATE, AND LOCAL TAXES (JAN 1991)

(a) "Contract date," as used in this clause, means the date set for bid opening or, if this is a negotiated contract or a modification, the effective date of this contract or modification.

"All applicable Federal, State, and local taxes and duties," as used in this clause, means all taxes and duties, in effect on the contract date, that the taxing authority is imposing and collecting on the transactions or property covered by this contract.

"After-imposed Federal tax," as used in this clause, means any new or increased Federal excise tax or duty, or tax that was exempted or excluded on the contract date but whose exemption was later revoked or reduced during the contract period, on the transactions or property covered by this contract that the Contractor is required to pay or bear as the result of legislative, judicial, or administrative action taking effect after the contract date. It does not include social security tax or other employment taxes.

"After-relieved Federal tax," as used in this clause, means any amount of Federal excise tax or duty, except social security or other employment taxes, that would otherwise have been payable on the transactions or property covered by this contract, but which the Contractor is not required to pay or bear, or for which the Contractor obtains a refund or drawback, as the result of legislative, judicial, or administrative action taking effect after the contract date.

(b) The contract price includes all applicable Federal, State, and local taxes and duties.

(c) The contract price shall be increased by the amount of any after-imposed Federal tax, provided the Contractor warrants in writing that no amount for such newly imposed Federal excise tax or duty or rate increase was included in the contract price, as a contingency reserve or otherwise.

(d) The contract price shall be decreased by the amount of any after-relieved Federal tax.

(e) The contract price shall be decreased by the amount of any Federal excise tax or duty, except social security or other employment taxes, that the Contractor is required to pay or bear, or does not obtain a refund of, through the Contractor's fault, negligence, or failure to follow instructions of the Contracting Officer.

(f) No adjustment shall be made in the contract price under this clause unless the amount of the adjustment exceeds $250.

(g) The Contractor shall promptly notify the Contracting Officer of all matters relating to any Federal excise tax or duty that reasonably may be expected to result in either an increase or decrease in the contract price and shall take appropriate action as the Contracting Officer directs.

(h) The Government shall, without liability, furnish evidence appropriate to establish exemption from any Federal, State, or local tax when the Contractor requests such evidence and a reasonable basis exists to sustain the exemption.

(End of clause)

52.230-3 DISCLOSURE AND CONSISTENCY OF COST ACCOUNTING PRACTICES (APR 1998)

(a) The Contractor, in connection with this contract, shall--

(1) Comply with the requirements of 48 CFR 9904.401, Consistency in Estimating, Accumulating, and Reporting Costs; 48 CFR 9904.402, Consistency in Allocating Costs Incurred for the Same Purpose; 48 CFR 9904.405, Accounting for Unallowable Costs; and 48 CFR 9904.406, Cost Accounting Standard--Cost Accounting Period, in effect on the date of award of this contract as indicated in 48 CFR Part 9904.

(2) (CAS-covered Contracts Only) If it is a business unit of a company required to submit a Disclosure Statement, disclose in writing its cost accounting practices as required by 48 CFR 9903.202-1 through 9903.202-5. If the Contractor has notified the Contracting Officer that the Disclosure Statement contains trade secrets and commercial or financial information which is privileged and confidential, the Disclosure Statement shall be protected and shall not be released outside of the Government.

(3)(i) Follow consistently the Contractor's cost accounting practices. A change to such practices may be proposed, however, by either the Government or the Contractor, and the Contractor agrees to negotiate with the Contracting Officer the terms and conditions under which a change may be made. After the terms and conditions under which the change is to be made have been agreed to, the change must be applied prospectively to this contract, and the Disclosure Statement, if affected, must be amended accordingly.

(ii) The Contractor shall, when the parties agree to a change to a cost accounting practice and the Contracting Officer has made the finding required in 48 CFR 9903.201-6(b), that the change is desirable and not detrimental to the interests of the Government, negotiate an equitable adjustment as provided in the Changes clause of this contract. In the absence of the required finding, no agreement may be made under this contract clause that will increase costs paid by the United States.

(4) Agree to an adjustment of the contract price or cost allowance, as appropriate, if the Contractor or a subcontractor fails to comply with the applicable CAS or to follow any cost accounting practice, and such failure results in any increased costs paid by the United States. Such adjustment shall provide for recovery of the increased costs to the United States together with interest thereon computed at the annual rate of interest established under the Internal Revenue Code of 1986 (26 U.S.C. 6621), from the time the payment by the United States was made to the time the adjustment is effected.

(b) If the parties fail to agree whether the Contractor has complied with an applicable CAS, rule, or regulation as specified in 48 CFR 9903 and 9904 and as to any cost adjustment demanded by the United States, such failure to agree will constitute a dispute under the Contract Disputes Act (41 U.S.C. 601).

(c) The Contractor shall permit any authorized representatives of the Government to examine and make copies of any documents, papers, and records relating to compliance with the requirements of this clause.

(d) The Contractor shall include in all negotiated subcontracts, which the Contractor enters into, the substance of this clause, except paragraph (b), and shall require such inclusion in all other subcontracts of any tier, except that--

(1) If the subcontract is awarded to a business unit which pursuant to 48 CFR 9903.201-2 is subject to other types of CAS coverage, the substance of the applicable clause set forth in subsection 30.201-4 of the Federal Acquisition Regulation shall be inserted.

(2) This requirement shall apply only to negotiated subcontracts in excess of $500,000.

(3) The requirement shall not apply to negotiated subcontracts otherwise exempt from the requirement to include a CAS clause as specified in 48 CFR 9903.201-1.

52.232-5 PAYMENTS UNDER FIXED-PRICE CONSTRUCTION CONTRACTS (MAY 1997)

(a) Payment of price. The Government shall pay the Contractor the contract price as provided in this contract.

(b) Progress payments. The Government shall make progress payments monthly as the work proceeds, or at more frequent intervals as determined by the Contracting Officer, on estimates of work accomplished which meets the standards of quality established under the contract, as approved by the Contracting Officer.

(1) The Contractor's request for progress payments shall include the following substantiation:

(i) An itemization of the amounts requested, related to the various elements of work required by the contract covered by the payment requested.

(ii) A listing of the amount included for work performed by each subcontractor under the contract.

(iii) A listing of the total amount of each subcontract under the contract.

(iv) A listing of the amounts previously paid to each such subcontractor under the contract.

(v) Additional supporting data in a form and detail required by the Contracting Officer.

(2) In the preparation of estimates, the Contracting Officer may authorize material delivered on the site and preparatory work done to be taken into consideration. Material delivered to the Contractor at locations other than the site also may be taken into consideration if--

(i) Consideration is specifically authorized by this contract; and

(ii) The Contractor furnishes satisfactory evidence that it has acquired title to such material and that the material will be used to perform this contract.

(c) Contractor certification. Along with each request for progress payments, the Contractor shall furnish the following certification, or payment shall not be made: (However, if the Contractor elects to delete paragraph (c)(4) from the certification, the certification is still acceptable.)

I hereby certify, to the best of my knowledge and belief, that--

(1) The amounts requested are only for performance in accordance with the specifications, terms, and conditions of the contract;

(2) Payments to subcontractors and suppliers have been made from previous payments received under the contract, and timely payments will be made from the proceeds of the payment covered by this certification, in accordance with subcontract agreements and the requirements of chapter 39 of Title 31, United States Code;

(3) This request for progress payments does not include any amounts which the prime contractor intends to withhold or retain from a subcontractor or supplier in accordance with the terms and conditions of the subcontract; and

(4) This certification is not to be construed as final acceptance of a subcontractor's performance.

_____

(Name)

_____

(Title)

_____

(Date)

(d) Refund of unearned amounts. If the Contractor, after making a certified request for progress payments, discovers that a portion or all of such request constitutes a payment for performance by the Contractor that fails to conform to the specifications, terms, and conditions of this contract (hereinafter referred to as the "unearned amount"), the Contractor shall--

(1) Notify the Contracting Officer of such performance deficiency; and

(2) Be obligated to pay the Government an amount (computed by the Contracting Officer in the manner provided in paragraph (j) of this clause) equal to interest on the unearned amount from the 8th day after the date of receipt of the unearned amount until--

(i) The date the Contractor notifies the Contracting Officer that the performance deficiency has been corrected; or

(ii) The date the Contractor reduces the amount of any subsequent certified request for progress payments by an amount equal to the unearned amount.

(e) Retainage. If the Contracting Officer finds that satisfactory progress was achieved during any period for which a progress payment is to be made, the Contracting Officer shall authorize payment to be made in full. However, if satisfactory progress has not been made, the Contracting Officer may retain a maximum of 10 percent of the amount of the payment until satisfactory progress is achieved. When the work is substantially complete, the Contracting Officer may retain from previously withheld funds and future progress payments that amount the Contracting Officer considers adequate for protection of the Government and shall release to the Contractor all the remaining withheld funds. Also, on completion and acceptance of each separate building, public work, or other division of the contract, for which the price is stated separately in the contract, payment shall be made for the completed work without retention of a percentage.

(f) Title, liability, and reservation of rights. All material and work covered by progress payments made shall, at the time of payment, become the sole property of the Government, but this shall not be construed as--

(1) Relieving the Contractor from the sole responsibility for all material and work upon which payments have been made or the restoration of any damaged work; or

(2) Waiving the right of the Government to require the fulfillment of all of the terms of the contract.

(g) Reimbursement for bond premiums. In making these progress payments, the Government shall, upon request, reimburse the Contractor for the amount of premiums paid for performance and payment bonds (including coinsurance and reinsurance agreements, when applicable) after the Contractor has furnished evidence of full payment to the surety. The retainage provisions in paragraph (e) of this clause shall not apply to that portion of progress payments attributable to bond premiums.

(h) Final payment. The Government shall pay the amount due the Contractor under this contract after--

(1) Completion and acceptance of all work;

(2) Presentation of a properly executed voucher; and

(3) Presentation of release of all claims against
the Government arising by virtue of this contract, other than claims, in stated amounts, that the Contractor has specifically excepted from the operation of the release. A release may also be required of the assignee if the Contractor's claim to amounts payable under this contract has been assigned under the Assignment of Claims Act of

1940 (31 U.S.C. 3727 and 41 U.S.C. 15).

(i) Limitation because of undefinitized work. Notwithstanding any provision of this contract, progress payments shall not exceed 80 percent on work accomplished on undefinitized contract actions. A "contract action" is any action resulting in a contract, as defined in FAR Subpart 2.1, including contract modifications for additional supplies or services, but not including contract modifications that are within the scope and under the terms of the contract, such as contract modifications issued pursuant to the Changes clause, or funding and other administrative changes.

(j) Interest computation on unearned amounts. In accordance with 31 U.S.C. 3903(c)(1), the amount payable under subparagraph (d)(2) of this clause shall be--

(1) Computed at the rate of average bond equivalent rates of 91-day Treasury bills auctioned at the most recent auction of such bills prior to the date the Contractor receives the unearned amount; and

(2) Deducted from the next available payment to the Contractor.

52.232-16 PROGRESS PAYMENTS (MAR 2000)

The Government will make progress payments to the Contractor when requested as work progresses, but not more frequently than monthly, in amounts of $2,500 or more approved by the Contracting Officer, under the following conditions:

(a) Computation of amounts. (1) Unless the Contractor requests a smaller amount, the Government will compute each progress payment as 80 percent of the Contractor's total costs incurred under this contract whether or not actually paid, plus financing payments to subcontractors (see paragraph (j) of this clause), less the sum of all previous progress payments made by the Government under this contract. The Contracting Officer will consider cost of money that would be allowable under FAR 31.205-10 as an incurred cost for progress payment purposes.

(2) The amount of financing and other payments for supplies and services purchased directly for the contract are limited to the amounts that have been paid by cash, check, or other forms of payment, or that will be paid to subcontractors--

(i) In accordance with the terms and conditions of a subcontract or invoice; and

(ii) Ordinarily prior to the submission of the Contractor's next payment request to the Government.

(3) The Government will exclude accrued costs of Contractor contributions under employee pension plans until actually paid unless--

(i) The Contractor's practice is to make contributions to the retirement fund quarterly or more frequently; and

(ii) The contribution does not remain unpaid 30 days after the end of the applicable quarter or shorter payment period (any contribution remaining unpaid shall be excluded from the Contractor's total costs for progress payments until paid).

(4) The Contractor shall not include the following in total costs for progress payment purposes in subparagraph (a)(1)(i) above:

(i) Costs that are not reasonable, allocable to this contract, and consistent with sound and generally accepted accounting principles and practices.

(ii) Costs incurred by subcontractors or suppliers.

(iii) Costs ordinarily capitalized and subject to depreciation or amortization except for the properly depreciated or amortized portion of such costs.

(iv) Payments made or amounts payable to subcontractors or suppliers, except for --

(A) Completed work, including partial deliveries, to which the Contractor has acquired title; and

(B) Work under cost-reimbursement or time-and-material subcontracts to which the Contractor has acquired title.

(5) The Contractor shall not include the following in total costs for progress payment purposes in paragraph (a)(1) of this clause:

(i) the progress payments made against incomplete work (including allowable unliquidated progress payments to subcontractors) nor

(ii) the value, for progress payment purposes, of the incomplete work. Incomplete work shall be considered to be the supplies and services required by this contract, for which delivery and invoicing by the Contractor and acceptance by the Government are incomplete.

(6) The total amount of progress payments shall not exceed 80 percent of the total contract price.

(7) If a progress payment or the unliquidated progress payments exceed the amounts permitted by subparagraphs (a)(4) or (a)(5) above, the Contractor shall repay the amount of such excess to the Government on demand.

(8) Notwithstanding any other terms of the contract, the Contractor agrees not to request progress payments in dollar amounts of less than $2,500. The Contracting Officer may make exceptions.

(b) Liquidation. Except as provided in the Termination for Convenience of the Government clause, all progress payments shall be liquidated by deducting from any payment under this contract, other than advance or progress payments, the unliquidated progress payments, or 80 percent of the amount invoiced, whichever is less. The Contractor shall repay to the Government any amounts required by a retroactive price reduction, after computing liquidations and payments on past invoices at the reduced prices and adjusting the unliquidated progress payments accordingly. The Government reserves the right to unilaterally change from the ordinary liquidation rate to an alternate rate when deemed appropriate for proper contract financing.

(c) Reduction or suspension. The Contracting Officer may reduce or suspend progress payments, increase the rate of liquidation, or take a combination of these actions, after finding on substantial evidence any of the following conditions:

(1) The Contractor failed to comply with any material requirement of this contract (which includes paragraphs (f) and (g) below).

(2) Performance of this contract is endangered by the Contractor's (i) failure to make progress or (ii) unsatisfactory financial condition.

(3) Inventory allocated to this contract substantially exceeds reasonable requirements.

(4) The Contractor is delinquent in payment of the costs of performing this contract in the ordinary course of business.

(5) The unliquidated progress payments exceed the fair value of the work accomplished on the undelivered portion of this contract.

(6) The Contractor is realizing less profit than that reflected in the establishment of any alternate liquidation rate in paragraph (b) above, and that rate is less than the progress payment rate stated in subparagraph (a)(1) above.

(d) Title. (1) Title to the property described in this paragraph (d) shall vest in the Government. Vestiture shall be immediately upon the date of this contract, for property acquired or produced before that date. Otherwise, vestiture shall occur when the property is or should have been allocable or properly chargeable to this contract.

(2) "Property," as used in this clause, includes all of the below-described items acquired or produced by the Contractor that are or should be allocable or properly chargeable to this contract under sound and generally accepted accounting principles and practices.

(i) Parts, materials, inventories, and work in process;

(ii) Special tooling and special test equipment to which the Government is to acquire title under any other clause of this contract;

(iii) Nondurable (i.e., noncapital) tools, jigs, dies, fixtures, molds, patterns, taps, gauges, test equipment, and other similar manufacturing aids, title to which would not be obtained as special tooling under subparagraph (ii) above; and

(iv) Drawings and technical data, to the extent the Contractor or subcontractors are required to deliver them to the Government by other clauses of this contract.

(3) Although title to property is in the Government under this clause, other applicable clauses of this contract; e.g., the termination or special tooling clauses, shall determine the handling and disposition of the property.

(4) The Contractor may sell any scrap resulting from production under this contract without requesting the Contracting Officer's approval, but the proceeds shall be credited against the costs of performance.

(5) To acquire for its own use or dispose of property to which title is vested in the Government under this clause, the Contractor must obtain the Contracting Officer's advance approval of the action and the terms. The Contractor shall (i) exclude the allocable costs of the property from the costs of contract performance, and (ii) repay to the Government any amount of unliquidated progress payments allocable to the property. Repayment may be by cash or credit memorandum.

(6) When the Contractor completes all of the obligations under this contract, including liquidation of all progress payments, title shall vest in the Contractor for all property (or the proceeds thereof) not--

(i) Delivered to, and accepted by, the Government under this contract; or

(ii) Incorporated in supplies delivered to, and accepted by, the Government under this contract and to which title is vested in the Government under this clause.

(7) The terms of this contract concerning liability for Government-furnished property shall not apply to property to which the Government acquired title solely under this clause.

(e) Risk of loss. Before delivery to and acceptance by the Government, the Contractor shall bear the risk of loss for property, the title to which vests in the Government under this clause, except to the extent the Government expressly assumes the risk. The Contractor shall repay the Government an amount equal to the unliquidated progress payments that are based on costs allocable to property that is damaged, lost, stolen, or destroyed.

(f) Control of costs and property. The Contractor shall maintain an accounting system and controls adequate for the proper administration of this clause.

(g) Reports and access to records. The Contractor shall promptly furnish reports, certificates, financial statements, and other pertinent information reasonably requested by the Contracting Officer for the administration of this clause. Also, the Contractor shall give the Government reasonable opportunity to examine and verify the Contractor's

books, records, and accounts.

(h) Special terms regarding default. If this contract is terminated under the Default clause, (i) the Contractor shall, on demand, repay to the Government the amount of unliquidated progress payments and (ii) title shall vest in the Contractor, on full liquidation of progress payments, for all property for which the Government elects not to require delivery under the Default clause. The Government shall be liable for no payment except as provided by the Default clause.

(i) Reservations of rights. (1) No payment or vesting of title under this clause shall (i) excuse the Contractor from performance of obligations under this contract or (ii) constitute a waiver of any of the rights or remedies of the parties under the contract.

(2) The Government's rights and remedies under this clause (i) shall not be exclusive but rather shall be in addition to any other rights and remedies provided by law or this contract and (ii) shall not be affected by delayed, partial, or omitted exercise of any right, remedy, power, or privilege, nor shall such exercise or any single exercise preclude or impair any further exercise under this clause or the exercise of any other right, power, or privilege of the Government.

(j) Financing payments to subcontractors. The financing payments to subcontractors mentioned in paragraphs (a)(1) and (a)(2) of this clause shall be all financing payments to subcontractors or divisions, if the following conditions are met:

(1) The amounts included are limited to--

(i) The unliquidated remainder of financing payments made; plus

(ii) Any unpaid subcontractor requests for financing payments.

(2) The subcontract or interdivisional order is expected to involve a minimum of approximately 6 months between the beginning of work and the first delivery; or, if the subcontractor is a small business concern, 4 months.

(3) If the financing payments are in the form of progress payments, the terms of the subcontract or interdivisional order concerning progress payments--

(i) Are substantially similar to the terms of this clause for any subcontractor that is a large business concern, or this clause with its Alternate I for any subcontractor that is a small business concern;

(ii) Are at least as favorable to the Government as the terms of this clause;

(iii) Are not more favorable to the subcontractor or division than the terms of this clause are to the Contractor;

(iv) Are in conformance with the requirements of FAR 32.504(e); and

(v) Subordinate all subcontractor rights concerning property to which the Government has title under the subcontract to the Government's right to require delivery of the property to the Government if--

(A) The Contractor defaults; or

(B) The subcontractor becomes bankrupt or insolvent.

(4) If the financing payments are in the form of performance-based payments, the terms of the subcontract or interdivisional order concerning payments--

(i) Are substantially similar to the Performance-Based Payments clause at FAR 52.232-32 and meet the criteria for, and definition of, performance-based payments in FAR Part 32;

(ii) Are in conformance with the requirements of FAR 32.504(f); and

(iii) Subordinate all subcontractor rights concerning property to which the Government has title under the subcontract to the Government's right to require delivery of the property to the Government if--

(A) The Contractor defaults; or

(B) The subcontractor becomes bankrupt or insolvent.

(5) If the financing payments are in the form of commercial item financing payments, the terms of the subcontract or interdivisional order concerning payments--

(i) Are constructed in accordance with FAR 32.206(c) and included in a subcontract for a commercial item purchase that meets the definition and standards for acquisition of commercial items in FAR Parts 2 and 12;

(ii) Are in conformance with the requirements of FAR 32.504(g); and

(iii) Subordinate all subcontractor rights concerning property to which the Government has title under the subcontract to the Government's right to require delivery of the property to the Government if--

(A) The Contractor defaults; or

(B) The subcontractor becomes bankrupt or insolvent.

(6) If financing is in the form of progress payments, the progress payment rate in the subcontract is the customary rate used by the contracting agency, depending on whether the subcontractor is or is not a small business concern.

(7) Concerning any proceeds received by the Government for property to which title has vested in the Government under the subcontract terms, the parties agree that the proceeds shall be applied to reducing any unliquidated financing payments by the Government to the Contractor under this contract.

(8) If no unliquidated financing payments to the Contractor remain, but there are unliquidated financing payments that the Contractor has made to any subcontractor, the Contractor shall be subrogated to all the rights the Government obtained through the terms required by this clause to be in any subcontract, as if all such rights had been assigned and transferred to the Contractor.

(9) To facilitate small business participation in subcontracting under this contract, the Contractor shall provide financing payments to small business concerns, in conformity with the standards for customary contract financing payments stated in FAR 32.113. The Contractor shall not consider the need for such financing payments as a handicap or adverse factor in the award of subcontracts.

(k) Limitations on Undefinitized Contract Actions. Notwithstanding any other progress payment provisions in this contract, progress payments may not exceed 80 percent of costs incurred on work accomplished under undefinitized contract actions. A "contract action" is any action resulting in a contract, as defined in Subpart 2.1, including contract modifications for additional supplies or services, but not including contract modifications that are within the scope and under the terms of the contract, such as contract modifications issued pursuant to the Changes clause, or funding and other administrative changes. This limitation shall apply to the costs incurred, as computed in accordance with paragraph (a) of this clause, and shall remain in effect until the contract action is definitized. Costs incurred which are subject to this limitation shall be segregated on Contractor progress payment requests and invoices from those costs eligible for higher progress payment rates. For purposes of progress payment liquidation, as described in paragraph (b) of this clause, progress payments for undefinitized contract actions shall be liquidated at 80 percent of the amount invoiced for work performed under the undefinitized contract action as long as the contract action remains undefinitized. The amount of unliquidated progress payments for undefinitized contract actions shall not exceed 80 percent of the maximum liability of the Government under the undefinitized contract

action or such lower limit specified elsewhere in the contract. Separate limits may be specified for separate actions.

52.232-23 ASSIGNMENT OF CLAIMS (JAN 1986)

(a) The Contractor, under the Assignment of Claims Act, as amended, 31 U.S.C. 3727, 41 U.S.C. 15 (hereafter referred to as "the Act"), may assign its rights to be paid amounts due or to become due as a result of the performance of this contract to a bank, trust company, or other financing institution, including any Federal lending agency. The assignee under such an assignment may thereafter further assign or reassign its right under the original assignment to any type of financing institution described in the preceding sentence.

(b) Any assignment or reassignment authorized under the Act and this clause shall cover all unpaid amounts payable under this contract, and shall not be made to more than one party, except that an assignment or reassignment may be made to one party as agent or trustee for two or more parties participating in the financing of this contract.

(c) The Contractor shall not furnish or disclose to any assignee under this contract any classified document (including this contract) or information related to work under this contract until the Contracting Officer authorizes such action in writing.

52.232-27 PROMPT PAYMENT FOR CONSTRUCTION CONTRACTS (MAY 2001)

Notwithstanding any other payment terms in this contract, the Government will make invoice payments and contract financing payments under the terms and conditions specified in this clause. Payment shall be considered as being made on the day a check is dated or the date of an electronic funds transfer. Definitions of pertinent terms are set forth in sections 2.101 and 32.902 of the Federal Acquisition Regulation. All days referred to in this clause are calendar days, unless otherwise specified. (However, see subparagraph (a)(3) concerning payments due on Saturdays, Sundays, and legal holidays.)

(a) Invoice payments. (1) Types of invoice payments. For purposes of this clause, there are several types of invoice payments that may occur under this contract, as follows:

(i) Progress payments, if provided for elsewhere in this contract, based on Contracting Officer approval of the estimated amount and value of work or services performed, including payments for reaching milestones in any project:

(A) The due date for making such payments shall be 14 days after receipt of the payment request by the designated billing office. If the designated billing office fails to annotate the payment request with the actual date of receipt at the time of receipt, the payment due date shall be the 14th day after the date of the Contractor's payment request, provided a proper payment request is received and there is no disagreement over quantity, quality, or Contractor compliance with contract requirements.

(B) The due date for payment of any amounts retained by the Contracting Officer in accordance with the clause at 52.232-5, Payments Under Fixed-Price Construction Contracts, shall be as specified in the contract or, if not specified, 30 days after approval for release to the Contractor by the Contracting Officer.

(ii) Final payments based on completion and acceptance of all work and presentation of release of all claims against the Government arising by virtue of the contract, and payments for partial deliveries that have been accepted by the Government (e.g., each separate building, public work, or other division of the contract for which the price is stated separately in the contract):

(A) The due date for making such payments shall be either the 30th day after receipt by the designated billing office of a proper invoice from the Contractor, or the 30th day after Government acceptance of the work or services completed by the Contractor, whichever is later. If the designated billing office fails to annotate the invoice with the date of actual receipt at the time of receipt, the invoice payment due date shall be the 30th day after the date of the

Contractor's invoice, provided a proper invoice is received and there is no disagreement over quantity, quality, or Contractor compliance with contract requirements.

(B) On a final invoice where the payment amount is subject to contract settlement actions (e.g., release of claims), acceptance shall be deemed to have occurred on the effective date of the contract settlement.

(2) Contractor's invoice. The Contractor shall prepare and submit invoices to the designated billing office specified in the contract. A proper invoice must include the items listed in subdivisions (a)(2)(i) through (a)(2)(ix) of this clause. If the invoice does not comply with these requirements, it shall be returned within 7 days after the date the designated billing office received the invoice, with a statement of the reasons why it is not a proper invoice. Untimely notification will be taken into account in computing any interest penalty owed the Contractor in the manner described in subparagraph (a)(4) of this clause.

(i) Name and address of the Contractor.

(ii) Invoice date. (The Contractor is encouraged to date invoices as close as possible to the date of mailing or transmission.)

(iii) Contract number or other authorization for work or services performed (including order number and contract line item number).

(iv) Description of work or services performed.

(v) Delivery and payment terms (e.g., prompt payment discount terms).

(vi) Name and address of Contractor official to whom payment is to be sent (must be the same as that in the contract or in a proper notice of assignment).

(vii) Name (where practicable), title, phone number, and mailing address of person to be notified in the event of a defective invoice.

(viii) For payments described in subdivision (a)(1)(i) of this clause, substantiation of the amounts requested and certification in accordance with the requirements of the clause at 52.232-5, Payments Under Fixed-Price Construction Contracts.

(ix) Any other information or documentation required by the contract.

(x) While not required, the Contractor is strongly encouraged to assign an identification number to each invoice.

(3) Interest penalty. An interest penalty shall be paid automatically by the designated payment office, without request from the Contractor, if payment is not made by the due date and the conditions listed in subdivisions (a)(3)(i) through (a)(3)(iii) of this clause are met, if applicable. However, when the due date falls on a Saturday, Sunday, or legal holiday when Federal Government offices are closed and Government business is not expected to be conducted, payment may be made on the following business day without incurring a late payment interest penalty.

(i) A proper invoice was received by the designated billing office.

(ii) A receiving report or other Government documentation authorizing payment was processed and there was no disagreement over quantity, quality, Contractor compliance with any contract term or condition, or requested progress payment amount.

(iii) In the case of a final invoice for any balance of funds due the Contractor for work or services performed, the amount was not subject to further contract settlement actions between the Government and the Contractor.

(4) Computing penalty amount. The interest penalty shall be at the rate established by the Secretary of the Treasury under section 12 of the Contract Disputes Act of 1978 (41 U.S.C. 611) that is in effect on the day after the due date, except where the interest penalty is prescribed by other governmental authority (e.g., tariffs). This rate is referred to as the "Renegotiation Board Interest Rate," and it is published in the Federal Register semiannually on or about January 1 and July 1. The interest penalty shall accrue daily on the invoice principal payment amount approved by the Government until the payment date of such approved principal amount; and will be compounded in 30-day increments inclusive from the first day after the due date through the payment date. That is, interest accrued at the end of any 30-day period will be added to the approved invoice principal payment amount and will be subject to interest penalties if not paid in the succeeding 30-day period. If the designated billing office failed to notify the Contractor of a defective invoice within the periods prescribed in subparagraph (a)(2) of this clause, the due date on the corrected invoice will be adjusted by subtracting from such date the number of days taken beyond the prescribed notification of defects period. Any interest penalty owed the Contractor will be based on this adjusted due date. Adjustments will be made by the designated payment office for errors in calculating interest penalties.

(i) For the sole purpose of computing an interest penalty that might be due the Contractor for payments described in subdivision (a)(1)(ii) of this clause, Government acceptance or approval shall be deemed to have occurred constructively on the 7th day after the Contractor has completed the work or services in accordance with the terms and conditions of the contract. In the event that actual acceptance or approval occurs within the constructive acceptance or approval period, the determination of an interest penalty shall be based on the actual date of acceptance or approval. Constructive acceptance or constructive approval requirements do not apply if there is a disagreement over quantity, quality, or Contractor compliance with a contract provision. These requirements also do not compel Government officials to accept work or services, approve Contractor estimates, perform contract administration functions, or make payment prior to fulfilling their responsibilities.

(ii) The following periods of time will not be included in the determination of an interest penalty:

(A) The period taken to notify the Contractor of defects in invoices submitted to the Government, but this may not exceed 7 days.

(B) The period between the defects notice and resubmission of the corrected invoice by the Contractor.

(C) For incorrect electronic funds transfer (EFT) information, in accordance with the EFT clause of this contract.

(iii) Interest penalties will not continue to accrue after the filing of a claim for such penalties under the clause at 52.233-1, Disputes, or for more than 1 year. Interest penalties of less than $1 need not be paid.

(iv) Interest penalties are not required on payment delays due to disagreement between the Government and the Contractor over the payment amount or other issues involving contract compliance, or on amounts temporarily withheld or retained in accordance with the terms of the contract. Claims involving disputes, and any interest that may be payable, will be resolved in accordance with the clause at 52.233-1, Disputes.

(5) Prompt payment discounts. An interest penalty also shall be paid automatically by the designated payment office, without request from the Contractor, if a discount for prompt payment is taken improperly. The interest penalty will be calculated on the amount of discount taken for the period beginning with the first day after the end of the discount period through the date when the Contractor is paid.

(6) Additional interest penalty. (i) If this contract was awarded on or after October 1, 1989, a penalty amount, calculated in accordance with subdivision (a)(6)(iii) of this clause, shall be paid in addition to the interest penalty amount if the Contractor--

(A) Is owed an interest penalty of $1 or more;

(B) Is not paid the interest penalty within 10 days after the date the invoice amount is paid; and

(C) Makes a written demand to the designated payment office for additional penalty payment, in accordance with

subdivision (a)(6)(ii) of this clause, postmarked not later than 40 days after the date the invoice amount is paid.

(ii)(A) Contractors shall support written demands for additional penalty payments with the following data. No additional data shall be required. Contractors shall--

(1) Specifically assert that late payment interest is due under a specific invoice, and request payment of all overdue late payment interest penalty and such additional penalty as may be required;

(2) Attach a copy of the invoice on which the unpaid late payment interest was due; and

(3) State that payment of the principal has been received, including the date of receipt.

(B) Demands must be postmarked on or before the 40th day after payment was made, except that--

(1) If the postmark is illegible or nonexistent, the demand must have been received and annotated with the date of receipt by the designated payment office on or before the 40th day after payment was made; or

(2) If the postmark is illegible or nonexistent and the designated payment office fails to make the required annotation, the demand's validity will be determined by the date the Contractor has placed on the demand; provided such date is no later than the 40th day after payment was made.

(iii)(A) The additional penalty shall be equal to 100 percent of any original late payment interest penalty, except--

(1) The additional penalty shall not exceed $5,000;

(2) The additional penalty shall never be less than $25; and

(3) No additional penalty is owed if the amount of the underlying interest penalty is less than $1.

(B) If the interest penalty ceases to accrue in accordance with the limits stated in subdivision (a)(4)(iii) of this clause, the amount of the additional penalty shall be calculated on the amount of interest penalty that would have accrued in the absence of these limits, subject to the overall limits on the additional penalty specified in subdivision (a)(6)(iii)(A) of this clause.

(C) For determining the maximum and minimum additional penalties, the test shall be the interest penalty due on each separate payment made for each separate contract. The maximum and minimum additional penalty shall not be based upon individual invoices unless the invoices are paid separately. Where payments are consolidated for disbursing purposes, the maximum and minimum additional penalty determination shall be made separately for each contract therein.

(D) The additional penalty does not apply to payments regulated by other Government regulations (e.g., payments under utility contracts subject to tariffs and regulation).

(b) Contract financing payments. (1) Due dates for recurring financing payments. If this contract provides for contract financing, requests for payment shall be submitted to the designated billing office as specified in this contract or as directed by the Contracting Officer. Contract financing payments shall be made on the 30th day after receipt of a proper contract financing request by the designated billing office. In the event that an audit or other review of a specific financing request is required to ensure compliance with the terms and conditions of the contract, the designated payment office is not compelled to make payment by the due date specified.

(2) Due dates for other contract financing. For advance payments, loans, or other arrangements that do not involve recurring submissions of contract financing requests, payment shall be made in accordance with the corresponding contract terms or as directed by the Contracting Officer.

(3) Interest penalty not applicable. Contract financing payments shall not be assessed an interest penalty for payment

delays.

(c) Subcontract clause requirements. The Contractor shall include in each subcontract for property or services (including a material supplier) for the purpose of performing this contract the following:

(1) Prompt payment for subcontractors. A payment clause that obligates the Contractor to pay the subcontractor for satisfactory performance under its subcontract not later than 7 days from receipt of payment out of such amounts as are paid to the Contractor under this contract.

(2) Interest for subcontractors. An interest penalty clause that obligates the Contractor to pay to the subcontractor an interest penalty for each payment not made in accordance with the payment clause--

(i) For the period beginning on the day after the required payment date and ending on the date on which payment of the amount due is made; and

(ii) Computed at the rate of interest established by the Secretary of the Treasury, and published in the Federal Register, for interest payments under section 12 of the Contract Disputes Act of 1978 (41 U.S.C. 611) in effect at the time the Contractor accrues the obligation to pay an interest penalty.

(3) Subcontractor clause flowdown. A clause requiring each subcontractor to include a payment clause and an interest penalty clause conforming to the standards set forth in subparagraphs (c)(1) and (c)(2) of this clause in each of its subcontracts, and to require each of its subcontractors to include such clauses in their subcontracts with each lower-tier subcontractor or supplier.

(d) Subcontract clause interpretation. The clauses required by paragraph (c) of this clause shall not be construed to impair the right of the Contractor or a subcontractor at any tier to negotiate, and to include in their subcontract, provisions that--

(1) Retainage permitted. Permit the Contractor or a subcontractor to retain (without cause) a specified percentage of each progress payment otherwise due to a subcontractor for satisfactory performance under the subcontract without incurring any obligation to pay a late payment interest penalty, in accordance with terms and conditions agreed to by the parties to the subcontract, giving such recognition as the parties deem appropriate to the ability of a subcontractor to furnish a performance bond and a payment bond;

(2) Withholding permitted. Permit the Contractor or subcontractor to make a determination that part or all of the subcontractor's request for payment may be withheld in accordance with the subcontract agreement; and

(3) Withholding requirements. Permit such withholding without incurring any obligation to pay a late payment penalty if--

(i) A notice conforming to the standards of paragraph (g) of this clause previously has been furnished to the subcontractor; and

(ii) A copy of any notice issued by a Contractor pursuant to subdivision (d)(3)(i) of this clause has been furnished to the Contracting Officer.

(e) Subcontractor withholding procedures. If a Contractor, after making a request for payment to the Government but before making a payment to a subcontractor for the subcontractor's performance covered by the payment request, discovers that all or a portion of the payment otherwise due such subcontractor is subject to withholding from the subcontractor in accordance with the subcontract agreement, then the Contractor shall--

(1) Subcontractor notice. Furnish to the subcontractor a notice conforming to the standards of paragraph (g) of this clause as soon as practicable upon ascertaining the cause giving rise to a withholding, but prior to the due date for subcontractor payment;

(2) Contracting Officer notice. Furnish to the Contracting Officer, as soon as practicable, a copy of the notice furnished to the subcontractor pursuant to subparagraph (e)(1) of this clause;

(3) Subcontractor progress payment reduction. Reduce the subcontractor's progress payment by an amount not to exceed the amount specified in the notice of withholding furnished under subparagraph (e)(1) of this clause;

(4) Subsequent subcontractor payment. Pay the subcontractor as soon as practicable after the correction of the identified subcontract performance deficiency, and--

(i) Make such payment within--

(A) Seven days after correction of the identified subcontract performance deficiency (unless the funds therefor must be recovered from the Government because of a reduction under subdivision (e)(5)(i)) of this clause; or

(B) Seven days after the Contractor recovers such funds from the Government; or

(ii) Incur an obligation to pay a late payment interest penalty computed at the rate of interest established by the Secretary of the Treasury, and published in the Federal Register, for interest payments under section 12 of the Contracts Disputes Act of 1978 (41 U.S.C. 611) in effect at the time the Contractor accrues the obligation to pay an interest penalty;

(5) Notice to Contracting Officer. Notify the Contracting Officer upon--

(i) Reduction of the amount of any subsequent certified application for payment; or

(ii) Payment to the subcontractor of any withheld amounts of a progress payment, specifying--

(A) The amounts withheld under subparagraph (e)(1) of this clause; and

(B) The dates that such withholding began and ended; and

(6) Interest to Government. Be obligated to pay to the Government an amount equal to interest on the withheld payments (computed in the manner provided in 31 U.S.C. 3903(c)(1)), from the 8th day after receipt of the withheld amounts from the Government until--

(i) The day the identified subcontractor performance deficiency is corrected; or

(ii) The date that any subsequent payment is reduced under subdivision (e)(5)(i) of this clause.

(f) Third-party deficiency reports. (1) Withholding from subcontractor. If a Contractor, after making payment to a first-tier subcontractor, receives from a supplier or subcontractor of the first-tier subcontractor (hereafter referred to as a "second-tier subcontractor") a written notice in accordance with section 2 of the Act of August 24, 1935 (40 U.S.C. 270b, Miller Act), asserting a deficiency in such first-tier subcontractor's performance under the contract for which the Contractor may be ultimately liable, and the Contractor determines that all or a portion of future payments otherwise due such first-tier subcontractor is subject to withholding in accordance with the subcontract agreement, the Contractor may, without incurring an obligation to pay an interest penalty under subparagraph (e)(6) of this clause--

(i) Furnish to the first-tier subcontractor a notice conforming to the standards of paragraph (g) of this clause as soon as practicable upon making such determination; and

(ii) Withhold from the first-tier subcontractor's next available progress payment or payments an amount not to exceed the amount specified in the notice of withholding furnished under subdivision (f)(1)(i) of this clause.

(2) Subsequent payment or interest charge. As soon as practicable, but not later than 7 days after receipt of

satisfactory written notification that the identified subcontract performance deficiency has been corrected, the Contractor shall--

(i) Pay the amount withheld under subdivision (f)(1)(ii) of this clause to such first-tier subcontractor; or

(ii) Incur an obligation to pay a late payment interest penalty to such first-tier subcontractor computed at the rate of interest established by the Secretary of the Treasury, and published in the Federal Register, for interest payments under section 12 of the Contracts Disputes Act of 1978 (41 U.S.C. 611) in effect at the time the Contractor accrues the obligation to pay an interest penalty.

(g) Written notice of subcontractor withholding. A written notice of any withholding shall be issued to a subcontractor (with a copy to the Contracting Officer of any such notice issued by the Contractor), specifying--

(1) The amount to be withheld;

(2) The specific causes for the withholding under the terms of the subcontract; and

(3) The remedial actions to be taken by the subcontractor in order to receive payment of the amounts withheld.

(h) Subcontractor payment entitlement. The Contractor may not request payment from the Government of any amount withheld or retained in accordance with paragraph (d) of this clause until such time as the Contractor has determined and certified to the Contracting Officer that the subcontractor is entitled to the payment of such amount.

(i) Prime-subcontractor disputes. A dispute between the Contractor and subcontractor relating to the amount or entitlement of a subcontractor to a payment or a late payment interest penalty under a clause included in the subcontract pursuant to paragraph (c) of this clause does not constitute a dispute to which the United States is a party. The United States may not be interpleaded in any judicial or administrative proceeding involving such a dispute.

(j) Preservation of prime-subcontractor rights. Except as provided in paragraph (i) of this clause, this clause shall not limit or impair any contractual, administrative, or judicial remedies otherwise available to the Contractor or a subcontractor in the event of a dispute involving late payment or nonpayment by the Contractor or deficient subcontract performance or nonperformance by a subcontractor.

(k) Non-recourse for prime contractor interest penalty. The Contractor's obligation to pay an interest penalty to a subcontractor pursuant to the clauses included in a subcontract under paragraph (c) of this clause shall not be construed to be an obligation of the United States for such interest penalty. A cost-reimbursement claim may not include any amount for reimbursement of such interest penalty.

52.232-33 PAYMENT BY ELECTRONIC FUNDS TRANSFER—CENTRAL CONTRACTOR REGISTRATION (MAY 1999)

(a) Method of payment. (1) All payments by the Government under this contract shall be made by electronic funds transfer (EFT), except as provided in paragraph (a)(2) of this clause. As used in this clause, the term “EFT” refers to the funds transfer and may also include the payment information transfer.

(2) In the event the Government is unable to release one or more payments by EFT, the Contractor agrees to either--

(i) Accept payment by check or some other mutually agreeable method of payment; or

(ii) Request the Government to extend the payment due date until such time as the Government can make payment by EFT (but see paragraph (d) of this clause).

(b) Contractor's EFT information. The Government shall make payment to the Contractor using the EFT information contained in the Central Contractor Registration (CCR) database. In the event that the EFT information changes, the Contractor shall be responsible for providing the updated information to the CCR database.

(c) Mechanisms for EFT payment. The Government may make payment by EFT through either the Automated Clearing House (ACH) network, subject to the rules of the National Automated Clearing House Association, or the Fedwire Transfer System. The rules governing Federal payments through the ACH are contained in 31 CFR part 210.

(d) Suspension of payment. If the Contractor's EFT information in the CCR database is incorrect, then the Government need not make payment to the Contractor under this contract until correct EFT information is entered into the CCR database; and any invoice or contract financing request shall be deemed not to be a proper invoice for the purpose of prompt payment under this contract. The prompt payment terms of the contract regarding notice of an improper invoice and delays in accrual of interest penalties apply.

(e) Contractor EFT arrangements. If the Contractor has identified multiple payment receiving points (i.e., more than one remittance address and/or EFT information set) in the CCR database, and the Contractor has not notified the Government of the payment receiving point applicable to this contract, the Government shall make payment to the first payment receiving point (EFT information set or remittance address as applicable) listed in the CCR database.

(f) Liability for uncompleted or erroneous transfers. (1) If an uncompleted or erroneous transfer occurs because the Government used the Contractor's EFT information incorrectly, the Government remains responsible for--

(i) Making a correct payment;

(ii) Paying any prompt payment penalty due; and

(iii) Recovering any erroneously directed funds.

(2) If an uncompleted or erroneous transfer occurs because the Contractor's EFT information was incorrect, or was revised within 30 days of Government release of the EFT payment transaction instruction to the Federal Reserve System, and--

(i) If the funds are no longer under the control of the payment office, the Government is deemed to have made payment and the Contractor is responsible for recovery of any erroneously directed funds; or

(ii) If the funds remain under the control of the payment office, the Government shall not make payment, and the provisions of paragraph (d) of this clause shall apply.

(g) EFT and prompt payment. A payment shall be deemed to have been made in a timely manner in accordance with the prompt payment terms of this contract if, in the EFT payment transaction instruction released to the Federal Reserve System, the date specified for settlement of the payment is on or before the prompt payment due date, provided the specified payment date is a valid date under the rules of the Federal Reserve System.

(h) EFT and assignment of claims. If the Contractor assigns the proceeds of this contract as provided for in the assignment of claims terms of this contract, the Contractor shall require as a condition of any such assignment, that the assignee shall register in the CCR database and shall be paid by EFT in accordance with the terms of this clause. In all respects, the requirements of this clause shall apply to the assignee as if it were the Contractor. EFT information that shows the ultimate recipient of the transfer to be other than the Contractor, in the absence of a proper assignment of claims acceptable to the Government, is incorrect EFT information within the meaning of paragraph (d) of this clause.

(i) Liability for change of EFT information by financial agent. The Government is not liable for errors resulting from changes to EFT information made by the Contractor's financial agent.

(j) Payment information. The payment or disbursing office shall forward to the Contractor available payment information that is suitable for transmission as of the date of release of the EFT instruction to the Federal Reserve System. The Government may request the Contractor to designate a desired format and method(s) for delivery of payment information from a list of formats and methods the payment office is capable of executing. However, the Government does not guarantee that any particular format or method of delivery is available at any particular payment office and retains the latitude to use the format and delivery method most convenient to the Government. If the Government makes payment by check in accordance with paragraph (a) of this clause, the Government shall mail the payment information to the remittance address contained in the CCR database.

(End of Clause)

52.233-1 DISPUTES. (DEC 1998)

(a) This contract is subject to the Contract Disputes Act of 1978, as amended (41 U.S.C. 601-613).

(b) Except as provided in the Act, all disputes arising under or relating to this contract shall be resolved under this clause.

(c) "Claim," as used in this clause, means a written demand or written assertion by one of the contracting parties seeking, as a matter of right, the payment of money in a sum certain, the adjustment or interpretation of contract terms, or other relief arising under or relating to this contract. A claim arising under a contract, unlike a claim relating to that contract, is a claim that can be resolved under a contract clause that provides for the relief sought by the claimant. However, a written demand or written assertion by the Contractor seeking the payment of money exceeding $100,000 is not a claim under the Act until certified as required by subparagraph (d)(2) of this clause. A voucher, invoice, or other routine request for payment that is not in dispute when submitted is not a claim under the Act. The submission may be converted to a claim under the Act, by complying with the submission and certification requirements of this clause, if it is disputed either as to liability or amount or is not acted upon in a reasonable time.

(d)(1) A claim by the Contractor shall be made in writing and, unless otherwise stated in this contract, submitted within 6 years after accrual of the claim to the Contracting Officer for a written decision. A claim by the Government against the Contractor shall be subject to a written decision by the Contracting Officer.

(2)(i) The contractors shall provide the certification specified in subparagraph (d)(2)(iii) of this clause when submitting any claim -

(A) Exceeding $100,000; or

(B) Regardless of the amount claimed, when using -

(1) Arbitration conducted pursuant to 5 U.S.C. 575-580; or

(2) Any other alternative means of dispute resolution (ADR) technique that the agency elects to handle in accordance with the Administrative Dispute Resolution Act (ADRA).

(ii) The certification requirement does not apply to issues in controversy that have not been submitted as all or part of a claim.

(iii) The certification shall state as follows: "I certify that the claim is made in good faith; that the supporting data are accurate and complete to the best of my knowledge and belief; that the amount requested accurately reflects the contract adjustment for which the Contractor believes the Government is liable; and that I am duly authorized to certify the claim on behalf of the Contractor.

(3) The certification may be executed by any person duly authorized to bind the Contractor with respect to the claim.

(e) For Contractor claims of $100,000 or less, the Contracting Officer must, if requested in writing by the

Contractor, render a decision within 60 days of the request. For Contractor-certified claims over $100,000, the Contracting Officer must, within 60 days, decide the claim or notify the Contractor of the date by which the decision will be made.

(f) The Contracting Officer's decision shall be final unless the Contractor appeals or files a suit as provided in the Act.

(g) If the claim by the Contractor is submitted to the Contracting Officer or a claim by the Government is presented to the Contractor, the parties, by mutual consent, may agree to use alternative disput resolution (ADR). If the Contractor refuses an offer for ADR, the Contractor shall inform the Contracting Officer, in writing, of the Contractor's specific reasons for rejecting the request.

(h) The Government shall pay interest on the amount found due and unpaid from (1) the date the Contracting Officer receives the claim (certified, if required); or (2) the date that payment otherwise would be due, if that date is later, until the date of payment. With regard to claims having defective certifications, as defined in (FAR) 48 CFR 33.201, interest shall be paid from the date that the Contracting Officer initially receives the claim. Simple interest on claims shall be paid at the rate, fixed by the Secretary of the Treasury as provided in the Act, which is applicable to the period during which the Contracting Officer receives the claim and then at the rate applicable for each 6-month period as fixed by the Treasury Secretary during the pendency of the claim.

(i) The Contractor shall proceed diligently with performance of this contract, pending final resolution of any request for relief, claim, appeal, or action arising under the contract, and comply with any decision of the Contracting Officer.

(End of clause)

52.233-3 PROTEST AFTER AWARD (AUG. 1996)

(a) Upon receipt of a notice of protest (as defined in FAR 33.101) or a determination that a protest is likely (see FAR 33.102(d)), the Contracting Officer may, by written order to the Contractor, direct the Contractor to stop performance of the work called for by this contract. The order shall be specifically identified as a stop-work order issued under this clause. Upon receipt of the order, the Contractor shall immediately comply with its terms and take all reasonable steps to minimize the incurrence of costs allocable to the work covered by the order during the period of work stoppage. Upon receipt of the final decision in the protest, the Contracting Officer shall either--

(1) Cancel the stop-work order; or

(2) Terminate the work covered by the order as provided in the Default, or the Termination for Convenience of the Government, clause of this contract.

(b) If a stop-work order issued under this clause is canceled either before or after a final decision in the protest, the Contractor shall resume work. The Contracting Officer shall make an equitable adjustment in the delivery schedule or contract price, or both, and the contract shall be modified, in writing, accordingly, if--

(1) The stop-work order results in an increase in the time required for, or in the Contractor's cost properly allocable to, the performance of any part of this contract; and

(2) The Contractor asserts its right to an adjustment within 30 days after the end of the period of work stoppage; provided, that if the Contracting Officer decides the facts justify the action, the Contracting Officer may receive and act upon a proposal at any time before final payment under this contract.

(c) If a stop-work order is not canceled and the work covered by the order is terminated for the convenience of the Government, the Contracting Officer shall allow reasonable costs resulting from the stop-work order in arriving at the termination settlement.

(d) If a stop-work order is not canceled and the work covered by the order is terminated for default, the Contracting Officer shall allow, by equitable adjustment or otherwise, reasonable costs resulting from the stop-work order.

(e) The Government's rights to terminate this contract at any time are not affected by action taken under this clause.

(f) If, as the result of the Contractor's intentional or negligent misstatement, misrepresentation, or miscertification, a protest related to this contract is sustained, and the Government pays costs, as provided in FAR 33.102(b)(2) or 33.104(h)(1), the Government may require the Contractor to reimburse the Government the amount of such costs. In addition to any other remedy available, and pursuant to the requirements of Subpart 32.6, the Government may collect this debt by offsetting the amount against any payment due the Contractor under any contract between the Contractor and the Government.

52.236-2 DIFFERING SITE CONDITIONS (APR 1984)

(a) The Contractor shall promptly, and before the conditions are disturbed, give a written notice to the Contracting Officer of

(1) subsurface or latent physical conditions at the site which differ materially from those indicated in this contract, or

(2) unknown physical conditions at the site, of an unusual nature, which differ materially from those ordinarily encountered and generally recognized as inhering in work of the character provided for in the contract.

(b) The Contracting Officer shall investigate the site conditions promptly after receiving the notice. If the conditions do materially so differ and cause an increase or decrease in the Contractor's cost of, or the time required for, performing any part of the work under this contract, whether or not changed as a result of the conditions, an equitable adjustment shall be made under this clause and the contract modified in writing accordingly.

(c) No request by the Contractor for an equitable adjustment to the contract under this clause shall be allowed, unless the Contractor has given the written notice required; provided, that the time prescribed in (a) above for giving written notice may be extended by the Contracting Officer.

(d) No request by the Contractor for an equitable adjustment to the contract for differing site conditions shall be allowed if made after final payment under this contract.

52.236-3 SITE INVESTIGATION AND CONDITIONS AFFECTING THE WORK (APR 1984)

(a) The Contractor acknowledges that it has taken steps reasonably necessary to ascertain the nature and location of the work, and that it has investigated and satisfied itself as to the general and local conditions which can affect the work or its cost, including but not limited to

(1) conditions bearing upon transportation, disposal, handling, and storage of materials;

(2) the availability of labor, water, electric power, and roads;

(3) uncertainties of weather, river stages, tides, or similar physical conditions at the site;

(4) the conformation and conditions of the ground; and (5) the character of equipment and facilities needed preliminary to and during work performance. The Contractor also acknowledges that it has satisfied itself as to the character, quality, and quantity of surface and subsurface materials or obstacles to be encountered insofar as this information is reasonably ascertainable from an inspection of the site, including all exploratory work done by the Government, as well as from the drawings and specifications made a part of this contract. Any failure of the Contractor to take the actions described and acknowledged in this paragraph will not relieve the Contractor from

responsibility for estimating properly the difficulty and cost of successfully performing the work, or for proceeding to successfully perform the work without additional expense to the Government.

(b) The Government assumes no responsibility for any conclusions or interpretations made by the Contractor based on the information made available by the Government. Nor does the Government assume responsibility for any understanding reached or representation made concerning conditions which can affect the work by any of its officers or agents before the execution of this contract, unless that understanding or representation is expressly stated in this contract.

52.236-5 MATERIAL AND WORKMANSHIP (APR 1984)

(a) All equipment, material, and articles incorporated into the work covered by this contract shall be new and of the most suitable grade for the purpose intended, unless otherwise specifically provided in this contract. References in the specifications to equipment, material, articles, or patented processes by trade name, make, or catalog number, shall be regarded as establishing a standard of quality and shall not be construed as limiting competition. The Contractor may, at its option, use any equipment, material, article, or process that, in the judgment of the Contracting Officer, is equal to that named in the specifications, unless otherwise specifically provided in this contract.

(b) The Contractor shall obtain the Contracting Officer's approval of the machinery and mechanical and other equipment to be incorporated into the work. When requesting approval, the Contractor shall furnish to the Contracting Officer the name of the manufacturer, the model number, and other information concerning the performance, capacity, nature, and rating of the machinery and mechanical and other equipment. When required by this contract or by the Contracting Officer, the Contractor shall also obtain the Contracting Officer's approval of the material or articles which the Contractor contemplates incorporating into the work. When requesting approval, the Contractor shall provide full information concerning the material or articles. When directed to do so, the Contractor shall submit samples for approval at the Contractor's expense, with all shipping charges prepaid. Machinery, equipment, material, and articles that do not have the required approval shall be installed or used at the risk of subsequent rejection.

(c) All work under this contract shall be performed in a skillful and workmanlike manner. The Contracting Officer may require, in writing, that the Contractor remove from the work any employee the Contracting Officer deems incompetent, careless, or otherwise objectionable.

52.236-6 SUPERINTENDENCE BY THE CONTRACTOR (APR 1984)

At all times during performance of this contract and until the work is completed and accepted, the Contractor shall directly superintend the work or assign and have on the worksite a competent superintendent who is satisfactory to the Contracting Officer and has authority to act for the Contractor.

52.236-7 PERMITS AND RESPONSIBILITIES (NOV 1991)

The Contractor shall, without additional expense to the Government, be responsible for obtaining any necessary licenses and permits, and for complying with any Federal, State, and municipal laws, codes, and regulations applicable to the performance of the work. The Contractor shall also be responsible for all damages to persons or property that occur as a result of the Contractor's fault or negligence. The Contractor shall also be responsible for all materials delivered and work performed until completion and acceptance of the entire work, except for any completed unit of work which may have been accepted under the contract.

52.236-8 OTHER CONTRACTS (APR 1984)

The Government may undertake or award other contracts for additional work at or near the site of the work under this contract. The Contractor shall fully cooperate with the other contractors and with Government employees and shall carefully adapt scheduling and performing the work under this contract to accommodate the additional work, heeding any direction that may be provided by the Contracting Officer. The Contractor shall not commit or permit any act that will interfere with the performance of work by any other contractor or by Government employees.

52.236-9 PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS (APR 1984)

(a) The Contractor shall preserve and protect all structures, equipment, and vegetation (such as trees, shrubs, and grass) on or adjacent to the work site, which are not to be removed and which do not unreasonably interfere with the work required under this contract. The Contractor shall only remove trees when specifically authorized to do so, and shall avoid damaging vegetation that will remain in place. If any limbs or branches of trees are broken during contract performance, or by the careless operation of equipment, or by workmen, the Contractor shall trim those limbs or branches with a clean cut and paint the cut with a tree-pruning compound as directed by the Contracting Officer.

(b) The Contractor shall protect from damage all existing improvements and utilities

(1) at or near the work site, and

(2) on adjacent property of a third party, the locations of which are made known to or should be known by the Contractor. The Contractor shall repair any damage to those facilities, including those that are the property of a third party, resulting from failure to comply with the requirements of this contract or failure to exercise reasonable care in performing the work. If the Contractor fails or refuses to repair the damage promptly, the Contracting Officer may have the necessary work performed and charge the cost to the Contractor.

52.236-10 OPERATIONS AND STORAGE AREAS (APR 1984)

(a) The Contractor shall confine all operations (including storage of materials) on Government premises to areas authorized or approved by the Contracting Officer. The Contractor shall hold and save the Government, its officers and agents, free and harmless from liability of any nature occasioned by the Contractor's performance.

(b) Temporary buildings (e.g., storage sheds, shops, offices) and utilities may be erected by the Contractor only with the approval of the Contracting Officer and shall be built with labor and materials furnished by the Contractor without expense to the Government. The temporary buildings and utilities shall remain the property of the Contractor and shall be removed by the Contractor at its expense upon completion of the work. With the written consent of the Contracting Officer, the buildings and utilities may be abandoned and need not be removed.

(c) The Contractor shall, under regulations prescribed by the Contracting Officer, use only established roadways, or use temporary roadways constructed by the Contractor when and as authorized by the Contracting Officer. When materials are transported in prosecuting the work, vehicles shall not be loaded beyond the loading capacity recommended by the manufacturer of the vehicle or prescribed by any Federal, State, or local law or regulation. When it is necessary to cross curbs or sidewalks, the Contractor shall protect them from damage. The Contractor shall repair or pay for the repair of any damaged curbs, sidewalks, or roads.

52.236-11 USE AND POSSESSION PRIOR TO COMPLETION (APR 1984)

(a) The Government shall have the right to take possession of or use any completed or partially completed part of the work. Before taking possession of or using any work, the Contracting Officer shall furnish the Contractor a list of items of work remaining to be performed or corrected on those portions of the work that the Government intends to take possession of or use. However, failure of the Contracting Officer to list any item of work shall not relieve

the Contractor of responsibility for complying with the terms of the contract. The Government's possession or use shall not be deemed an acceptance of any work under the contract.

(b) While the Government has such possession or use, the Contractor shall be relieved of the responsibility for the loss of or damage to the work resulting from the Government's possession or use, notwithstanding the terms of the clause in this contract entitled "Permits and Responsibilities." If prior possession or use by the Government delays the progress of the work or causes additional expense to the Contractor, an equitable adjustment shall be made in the contract price or the time of completion, and the contract shall be modified in writing accordingly.

52.236-12 CLEANING UP (APR 1984)

The Contractor shall at all times keep the work area, including storage areas, free from accumulations of waste materials. Before completing the work, the Contractor shall remove from the work and premises any rubbish, tools, scaffolding, equipment, and materials that are not the property of the Government. Upon completing the work, the Contractor shall leave the work area in a clean, neat, and orderly condition satisfactory to the Contracting Officer.

52.236-13 ACCIDENT PREVENTION (NOV 1991)

(a) The Contractor shall provide and maintain work environments and procedures which will

(1) safeguard the public and Government personnel, property, materials, supplies, and equipment exposed to Contractor operations and activities;

(2) avoid interruptions of Government operations and delays in project completion dates; and

(3) control costs in the performance of this contract.

(b) For these purposes on contracts for construction or dismantling, demolition, or removal of improvements, the Contractor shall-

(1) Provide appropriate safety barricades, signs, and signal lights;

(2) Comply with the standards issued by the Secretary of Labor at 29 CFR Part 1926 and 29 CFR Part 1910; and

(3) Ensure that any additional measures the Contracting Officer determines to be reasonably necessary for the purposes are taken.

(c) If this contract is for construction or dismantling, demolition or removal of improvements with any Department of Defense agency or component, the Contractor shall comply with all pertinent provisions of the latest version of U.S. Army Corps of Engineers Safety and Health Requirements Manual, EM 385-1-1, in effect on the date of the solicitation.

(d) Whenever the Contracting Officer becomes aware of any noncompliance with these requirements or any condition which poses a serious or imminent danger to the health or safety of the public or Government personnel, the Contracting Officer shall notify the Contractor orally, with written confirmation, and request immediate initiation of corrective action. This notice, when delivered to the Contractor or the Contractor's representative at the work site, shall be deemed sufficient notice of the noncompliance and that corrective action is required. After receiving the notice, the Contractor shall immediately take corrective action. If the Contractor fails or refuses to promptly take corrective action, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. The Contractor shall not be entitled to any equitable adjustment of the contract price or extension of the performance schedule on any stop work order issued under this clause.

(e) The Contractor shall insert this clause, including this paragraph (e), with appropriate changes in the designation

of the parties, in subcontracts.

52.236-14 AVAILABILITY AND USE OF UTILITY SERVICES (APR 1984)

(a) The Government shall make all reasonably required amounts of utilities available to the Contractor from existing outlets and supplies, as specified in the contract. Unless otherwise provided in the contract, the amount of each utility service consumed shall be charged to or paid for by the Contractor at prevailing rates charged to the Government or, where the utility is produced by the Government, at reasonable rates determined by the Contracting Officer. The Contractor shall carefully conserve any utilities furnished without charge.

(b) The Contractor, at its expense and in a workmanlike manner satisfactory to the Contracting Officer, shall install and maintain all necessary temporary connections and distribution lines, and all meters required to measure the amount of each utility used for the purpose of determining charges. Before final acceptance of the work by the Government, the Contractor shall remove all the temporary connections, distribution lines, meters, and associated paraphernalia.

52.236-15 SCHEDULES FOR CONSTRUCTION CONTRACTS (APR 1984)

(a) The Contractor shall, within five days after the work commences on the contract or another period of time determined by the Contracting Officer, prepare and submit to the Contracting Officer for approval three copies of a practicable schedule showing the order in which the Contractor proposes to perform the work, and the dates on which the Contractor contemplates starting and completing the several salient features of the work (including acquiring materials, plant, and equipment). The schedule shall be in the form of a progress chart of suitable scale to indicate appropriately the percentage of work scheduled for completion by any given date during the period. If the Contractor fails to submit a schedule within the time prescribed, the Contracting Officer may withhold approval of progress payments until the Contractor submits the required schedule.

(b) The Contractor shall enter the actual progress on the chart as directed by the Contracting Officer, and upon doing so shall immediately deliver three copies of the annotated schedule to the Contracting Officer. If, in the opinion of the Contracting Officer, the Contractor falls behind the approved schedule, the Contractor shall take steps necessary to improve its progress, including those that may be required by the Contracting Officer, without additional cost to the Government. In this circumstance, the Contracting Officer may require the Contractor to increase the number of shifts, overtime operations, days of work, and/or the amount of construction plant, and to submit for approval any supplementary schedule or schedules in chart form as the Contracting Officer deems necessary to demonstrate how the approved rate of progress will be regained.

(c) Failure of the Contractor to comply with the requirements of the Contracting Officer under this clause shall be grounds for a determination by the Contracting Officer that the Contractor is not prosecuting the work with sufficient diligence to ensure completion within the time specified in the contract. Upon making this determination, the Contracting Officer may terminate the Contractor's right to proceed with the work, or any separable part of it, in accordance with the default terms of this contract.

52.236-21 SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION (FEB 1997)

(a) The Contractor shall keep on the work site a copy of the drawings and specifications and shall at all times give the Contracting Officer access thereto. Anything mentioned in the specifications and not shown on the drawings, or shown on the drawings and not mentioned in the specifications, shall be of like effect as if shown or mentioned in both. In case of difference between drawings and specifications, the specifications shall govern. In case of discrepancy in the figures, in the drawings, or in the specifications, the matter shall be promptly submitted to the Contracting Officer, who shall promptly make a determination in writing. Any adjustment by the Contractor without such a determination shall be at its own risk and expense. The Contracting Officer shall furnish from time to time such detailed drawings and other information as considered necessary, unless otherwise provided.

(b) Wherever in the specifications or upon the drawings the words "directed", "required", "ordered", "designated", "prescribed", or words of like import are used, it shall be understood that the "direction", "requirement", "order", "designation", or "prescription", of the Contracting Officer is intended and similarly the words "approved", "acceptable", "satisfactory", or words of like import shall mean "approved by," or "acceptable to", or "satisfactory to" the Contracting Officer, unless otherwise expressly stated.

(c) Where "as shown," as indicated", "as detailed", or words of similar import are used, it shall be understood that the reference is made to the drawings accompanying this contract unless stated otherwise. The word "provided" as used herein shall be understood to mean "provide complete in place," that is "furnished and installed".

(d) Shop drawings means drawings, submitted to the Government by the Contractor, subcontractor, or any lower tier subcontractor pursuant to a construction contract, showing in detail (1) the proposed fabrication and assembly of structural elements, and (2) the installation (i.e., fit, and attachment details) of materials or equipment. It includes drawings, diagrams, layouts, schematics, descriptive literature, illustrations, schedules, performance and test data, and similar materials furnished by the contractor to explain in detail specific portions of the work required by the contract. The Government may duplicate, use, and disclose in any manner and for any purpose shop drawings delivered under this contract.

(e) If this contract requires shop drawings, the Contractor shall coordinate all such drawings, and review them for accuracy, completeness, and compliance with contract requirements and shall indicate its approval thereon as evidence of such coordination and review. Shop drawings submitted to the Contracting Officer without evidence of the Contractor's approval may be returned for resubmission. The Contracting Officer will indicate an approval or disapproval of the shop drawings and if not approved as submitted shall indicate the Government's reasons therefor. Any work done before such approval shall be at the Contractor's risk. Approval by the Contracting Officer shall not relieve the Contractor from responsibility for any errors or omissions in such drawings, nor from responsibility for complying with the requirements of this contract, except with respect to variations described and approved in accordance with (f) below.

(f) If shop drawings show variations from the contract requirements, the Contractor shall describe such variations in writing, separate from the drawings, at the time of submission. If the Contracting Officer approves any such variation, the Contracting Officer shall issue an appropriate contract modification, except that, if the variation is minor or does not involve a change in price or in time of performance, a modification need not be issued.

(g) The Contractor shall submit to the Contracting Officer for approval four copies (unless otherwise indicated) of all shop drawings as called for under the various headings of these specifications. Three sets (unless otherwise indicated) of all shop drawings, will be retained by the Contracting Officer and one set will be returned to the Contractor.

52.236-26 PRECONSTRUCTION CONFERENCE (FEB 1995)

If the Contracting Officer decides to conduct a preconstruction conference, the successful offeror will be notified and will be required to attend. The Contracting Officer's notification will include specific details regarding the date, time, and location of the conference, any need for attendance by subcontractors, and information regarding the items to be discussed.

52.242-13 BANKRUPTCY (JUL 1995)

In the event the Contractor enters into proceedings relating to bankruptcy, whether voluntary or involuntary, the Contractor agrees to furnish, by certified mail or electronic commerce method authorized by the contract, written notification of the bankruptcy to the Contracting Officer responsible for administering the contract. This notification shall be furnished within five days of the initiation of the proceedings relating to bankruptcy filing. This

notification shall include the date on which the bankruptcy petition was filed, the identity of the court in which the bankruptcy petition was filed, and a listing of Government contract numbers and contracting offices for all Government contracts against which final payment has not been made. This obligation remains in effect until final payment under this contract.

(End of clause)

52.242-14 SUSPENSION OF WORK (APR 1984)

(a) The Contracting Officer may order the Contractor, in writing, to suspend, delay, or interrupt all or any part of the work of this contract for the period of time that the Contracting Officer determines appropriate for the convenience of the Government.

(b) If the performance of all or any part of the work is, for an unreasonable period of time, suspended, delayed, or interrupted (1) by an act of the Contracting Officer in the administration of this contract, or (2) by the Contracting Officer's failure to act within the time specified in this contract (or within a reasonable time if not specified), an adjustment shall be made for any increase in the cost of performance of this contract (excluding profit) necessarily caused by the unreasonable suspension, delay, or interruption, and the contract modified in writing accordingly. However, no adjustment shall be made under this clause for any suspension, delay, or interruption to the extent that performance would have been so suspended, delayed, or interrupted by any other cause, including the fault or negligence of the Contractor, or for which an equitable adjustment is provided for or excluded under any other term or condition of this contract. (c) A claim under this clause shall not be allowed (1) for any costs incurred more than 20 days before the Contractor shall have notified the Contracting Officer in writing of the act or failure to act involved (but this requirement shall not apply as to a claim resulting from a suspension order), and (2) unless the claim, in an amount stated, is asserted in writing as soon as practicable after the termination of the suspension, delay, or interruption, but not later than the date of final payment under the contract.

52.243-4 CHANGES (AUG 1987)

(a) The Contracting Officer may, at any time, without notice to the sureties, if any, by written order designated or indicated to be a change order, make changes in the work within the general scope of the contract, including changes--

(1) In the specifications (including drawings and designs);

(2) In the method or manner of performance of the work;

(3) In the Government-furnished facilities, equipment, materials, services, or site; or

(4) Directing acceleration in the performance of the work.

(b) Any other written or oral order (which, as used in this paragraph (b), includes direction, instruction, interpretation, or determination) from the Contracting Officer that causes a change shall be treated as a change order under this clause; provided, that the Contractor gives the Contracting Officer written notice stating

(1) the date, circumstances, and source of the order and

(2) that the Contractor regards the order as a change order.

(c) Except as provided in this clause, no order, statement, or conduct of the Contracting Officer shall be treated as a change under this clause or entitle the Contractor to an equitable adjustment.

(d) If any change under this clause causes an increase or decrease in the Contractor's cost of, or the time required for,

the performance of any part of the work under this contract, whether or not changed by any such order, the Contracting Officer shall make an equitable adjustment and modify the contract in writing. However, except for an adjustment based on defective specifications, no adjustment for any change under paragraph (b) of this clause shall be made for any costs incurred more than 20 days before the Contractor gives written notice as required. In the case of defective specifications for which the Government is responsible, the equitable adjustment shall include any increased cost reasonably incurred by the Contractor in attempting to comply with the defective specifications.

(e) The Contractor must assert its right to an adjustment under this clause within 30 days after

(1) receipt of a written change order under paragraph (a) of this clause or (2) the furnishing of a written notice under paragraph (b) of this clause, by submitting to the Contracting Officer a written statement describing the general nature and amount of the proposal, unless this period is extended by the Government. The statement of proposal for adjustment may be included in the notice under paragraph (b) above.

(f) No proposal by the Contractor for an equitable adjustment shall be allowed if asserted after final payment under this contract.

52.244-2 SUBCONTRACTS (AUG 1998)

(a) Definitions. As used in this clause--

Approved purchasing system means a Contractor's purchasing system that has been reviewed and approved in accordance with Part 44 of the Federal Acquisition Regulation (FAR).

Consent to subcontract means the Contracting Officer's written consent for the Contractor to enter into a particular subcontract.

Subcontract means any contract, as defined in FAR Subpart 2.1, entered into by a subcontractor to furnish supplies or services for performance of the prime contract or a subcontract. It includes, but is not limited to, purchase orders, and changes and modifications to purchase orders.

(b) This clause does not apply to subcontracts for special test equipment when the contract contains the clause at FAR 52.245-18, Special Test Equipment.

(c) When this clause is included in a fixed-price type contract, consent to subcontract is required only on unpriced contract actions (including unpriced modifications or unpriced delivery orders), and only if required in accordance with paragraph (d) or (e) of this clause.

(d) If the Contractor does not have an approved purchasing system, consent to subcontract is required for any subcontract that--

(1) Is of the cost-reimbursement, time-and-materials, or labor-hour type; or

(2) Is fixed-price and exceeds--

(i) For a contract awarded by the Department of Defense, the Coast Guard, or the National Aeronautics and Space Administration, the greater of the simplified acquisition threshold or 5 percent of the total estimated cost of the contract; or

(ii) For a contract awarded by a civilian agency other than the Coast Guard and the National Aeronautics and Space Administration, either the simplified acquisition threshold or 5 percent of the total estimated cost of the contract.

(e) If the Contractor has an approved purchasing system, the Contractor nevertheless shall obtain the Contracting Officer's written consent before placing the following subcontracts: NONE

(f)(1) The Contractor shall notify the Contracting Officer reasonably in advance of placing any subcontract or modification thereof for which consent is required under paragraph (c), (d), or (e) of this clause, including the following information:

(i) A description of the supplies or services to be subcontracted.

(ii) Identification of the type of subcontract to be used.

(iii) Identification of the proposed subcontractor.

(iv) The proposed subcontract price.

(v) The subcontractor's current, complete, and accurate cost or pricing data and Certificate of Current Cost or Pricing Data, if required by other contract provisions.

(vi) The subcontractor's Disclosure Statement or Certificate relating to Cost Accounting Standards when such data are required by other provisions of this contract.

(vii) A negotiation memorandum reflecting--

(A) The principal elements of the subcontract price negotiations;

(B) The most significant considerations controlling establishment of initial or revised prices;

(C) The reason cost or pricing data were or were not required;

(D) The extent, if any, to which the Contractor did not rely on the subcontractor's cost or pricing data in determining the price objective and in negotiating the final price;

(E) The extent to which it was recognized in the negotiation that the subcontractor's cost or pricing data were not accurate, complete, or current; the action taken by the Contractor and the subcontractor; and the effect of any such defective data on the total price negotiated;

(F) The reasons for any significant difference between the Contractor's price objective and the price negotiated; and

(G) A complete explanation of the incentive fee or profit plan when incentives are used. The explanation shall identify each critical performance element, management decisions used to quantify each incentive element, reasons for the incentives, and a summary of all trade-off possibilities considered.

(2) The Contractor is not required to notify the Contracting Officer in advance of entering into any subcontract for which consent is not required under paragraph (c), (d), or (e) of this clause.

(g) Unless the consent or approval specifically provides otherwise, neither consent by the Contracting Officer to any subcontract nor approval of the Contractor's purchasing system shall constitute a determination--

(1) Of the acceptability of any subcontract terms or conditions;

(2) Of the allowability of any cost under this contract; or

(3) To relieve the Contractor of any responsibility for performing this contract.

(h) No subcontract or modification thereof placed under this contract shall provide for payment on a cost-plus-a-percentage-of-cost basis, and any fee payable under cost-reimbursement type subcontracts shall not exceed the fee limitations in FAR 15.404-4(c)(4)(i).

(i) The Contractor shall give the Contracting Officer immediate written notice of any action or suit filed and prompt notice of any claim made against the Contractor by any subcontractor or vendor that, in the opinion of the Contractor, may result in litigation related in any way to this contract, with respect to which the Contractor may be entitled to reimbursement from the Government.

(j) The Government reserves the right to review the Contractor's purchasing system as set forth in FAR Subpart 44.3.

(k) Paragraphs (d) and (f) of this clause do not apply to the following subcontracts, which were evaluated during negotiations:

(End of clause)

52.246-12 INSPECTION OF CONSTRUCTION (AUG 1996)

(a) Definition. "Work" includes, but is not limited to, materials, workmanship, and manufacture and fabrication of components.

(b) The Contractor shall maintain an adequate inspection system and perform such inspections as will ensure that the work performed under the contract conforms to contract requirements. The Contractor shall maintain complete inspection records and make them available to the Government. All work shall be conducted under the general direction of the Contracting Officer and is subject to Government inspection and test at all places and at all reasonable times before acceptance to ensure strict compliance with the terms of the contract.

(c) Government inspections and tests are for the sole benefit of the Government and do not--

(1) Relieve the Contractor of responsibility for providing adequate quality control measures;

(2) Relieve the Contractor of responsibility for damage to or loss of the material before acceptance;

(3) Constitute or imply acceptance; or

(4) Affect the continuing rights of the Government after acceptance of the completed work under paragraph (i) of this section.

(d) The presence or absence of a Government inspector does not relieve the Contractor from any contract requirement, nor is the inspector authorized to change any term or condition of the specification without the Contracting Officer's written authorization.

(e) The Contractor shall promptly furnish, at no increase in contract price, all facilities, labor, and material reasonably needed for performing such safe and convenient inspections and tests as may be required by the Contracting Officer. The Government may charge to the Contractor any additional cost of inspection or test when work is not ready at the time specified by the Contractor for inspection or test, or when prior rejection makes reinspection or retest necessary. The Government shall perform all inspections and tests in a manner that will not unnecessarily delay the work. Special, full size, and performance tests shall be performed as described in the contract.

(f) The Contractor shall, without charge, replace or correct work found by the Government not to conform to contract requirements, unless in the public interest the Government consents to accept the work with an appropriate adjustment in contract price. The Contractor shall promptly segregate and remove rejected material from the premises.

(g) If the Contractor does not promptly replace or correct rejected work, the Government may (1) by contract or otherwise, replace or correct the work and charge the cost to the Contractor or (2) terminate for default the Contractor's right to proceed.

(h) If, before acceptance of the entire work, the Government decides to examine already completed work by removing it or tearing it out, the Contractor, on request, shall promptly furnish all necessary facilities, labor, and material. If the work is found to be defective or nonconforming in any material respect due to the fault of the Contractor or its subcontractors, the Contractor shall defray the expenses of the examination and of satisfactory reconstruction. However, if the work is found to meet contract requirements, the Contracting Officer shall make an equitable adjustment for the additional services involved in the examination and reconstruction, including, if completion of the work was thereby delayed, an extension of time.

(i) Unless otherwise specified in the contract, the Government shall accept, as promptly as practicable after completion and inspection, all work required by the contract or that portion of the work the Contracting Officer determines can be accepted separately. Acceptance shall be final and conclusive except for latent defects, fraud, gross mistakes amounting to fraud, or the Government's rights under any warranty or guarantee.

52.246-21 WARRANTY OF CONSTRUCTION (MAR 1994)

(a) In addition to any other warranties in this contract, the Contractor warrants, except as provided in paragraph (i) of this clause, that work performed under this contract conforms to the contract requirements and is free of any defect in equipment, material, or design furnished, or workmanship performed by the Contractor or any subcontractor or supplier at any tier.

(b) This warranty shall continue for a period of 1 year from the date of final acceptance of the work. If the Government takes possession of any part of the work before final acceptance, this warranty shall continue for a period of 1 year from the date the Government takes possession.

(c) The Contractor shall remedy at the Contractor's expense any failure to conform, or any defect. In addition, the Contractor shall remedy at the Contractor's expense any damage to Government-owned or controlled real or personal property, when that damage is the result of--

(1) The Contractor's failure to conform to contract requirements; or

(2) Any defect of equipment, material, workmanship, or design furnished.

(d) The Contractor shall restore any work damaged in fulfilling the terms and conditions of this clause. The Contractor's warranty with respect to work repaired or replaced will run for 1 year from the date of repair or replacement.

(e) The Contracting Officer shall notify the Contractor, in writing, within a reasonable time after the discovery of any failure, defect, or damage.

(f) If the Contractor fails to remedy any failure, defect, or damage within a reasonable time after receipt of notice, the Government shall have the right to replace, repair, or otherwise remedy the failure, defect, or damage at the Contractor's expense.
(g) With respect to all warranties, express or implied, from subcontractors, manufacturers, or suppliers for work performed and materials furnished under this contract, the Contractor shall--

(1) Obtain all warranties that would be given in normal commercial practice;

(2) Require all warranties to be executed, in writing, for the benefit of the Government, if directed by the Contracting Officer; and

(3) Enforce all warranties for the benefit of the Government, if directed by the Contracting Officer.

(h) In the event the Contractor's warranty under paragraph (b) of this clause has expired, the Government may bring suit at its expense to enforce a subcontractor's, manufacturer's, or supplier's warranty.

(i) Unless a defect is caused by the negligence of the Contractor or subcontractor or supplier at any tier, the Contractor shall not be liable for the repair of any defects of material or design furnished by the Government nor for the repair of any damage that results from any defect in Government-furnished material or design.

(j) This warranty shall not limit the Government's rights under the Inspection and Acceptance clause of this contract with respect to latent defects, gross mistakes, or fraud.

(End of clause)

52.248-3 VALUE ENGINEERING--CONSTRUCTION (FEB 2000)

(a) General. The Contractor is encouraged to develop, prepare, and submit value engineering change proposals (VECP's) voluntarily. The Contractor shall share in any instant contract savings realized from accepted VECP's, in accordance with paragraph (f) below.

(b) Definitions. "Collateral costs," as used in this clause, means agency costs of operation, maintenance, logistic support, or Government-furnished property.

"Collateral savings," as used in this clause, means those measurable net reductions resulting from a VECP in the agency's overall projected collateral costs, exclusive of acquisition savings, whether or not the acquisition cost changes.

"Contractor's development and implementation costs," as used in this clause, means those costs the Contractor incurs on a VECP specifically in developing, testing, preparing, and submitting the VECP, as well as those costs the Contractor incurs to make the contractual changes required by Government acceptance of a VECP.

"Government costs," as used in this clause, means those agency costs that result directly from developing and implementing the VECP, such as any net increases in the cost of testing, operations, maintenance, and logistic support. The term does not include the normal administrative costs of processing the VECP.

"Instant contract savings," as used in this clause, means the estimated reduction in Contractor cost of performance resulting from acceptance of the VECP, minus allowable Contractor's development and implementation costs, including subcontractors' development and implementation costs (see paragraph (h) below).

"Value engineering change proposal (VECP)" means a proposal that--

(1) Requires a change to this, the instant contract, to implement; and

(2) Results in reducing the contract price or estimated cost without impairing essential functions or characteristics; provided, that it does not involve a change--

(i) In deliverable end item quantities only; or

(ii) To the contract type only.

(c) VECP preparation. As a minimum, the Contractor shall include in each VECP the information described in subparagraphs (1) through (7) below. If the proposed change is affected by contractually required configuration management or similar procedures, the instructions in those procedures relating to format, identification, and priority assignment shall govern VECP preparation. The VECP shall include the following:

(1) A description of the difference between the existing contract requirement and that proposed, the comparative advantages and disadvantages of each, a justification when an item's function or characteristics are being altered, and the effect of the change on the end item's performance.

(2) A list and analysis of the contract requirements that must be changed if the VECP is accepted, including any suggested specification revisions.

(3) A separate, detailed cost estimate for

(i) the affected portions of the existing contract requirement and

(ii) the VECP. The cost reduction associated with the VECP shall take into account the Contractor's allowable development and implementation costs, including any amount attributable to subcontracts under paragraph (h) below.

(4) A description and estimate of costs the Government may incur in implementing the VECP, such as test and evaluation and operating and support costs.

(5) A prediction of any effects the proposed change would have on collateral costs to the agency.

(6) A statement of the time by which a contract modification accepting the VECP must be issued in order to achieve the maximum cost reduction, noting any effect on the contract completion time or delivery schedule.

(7) Identification of any previous submissions of the VECP, including the dates submitted, the agencies and contract numbers involved, and previous Government actions, if known.

(d) Submission. The Contractor shall submit VECP's to the Resident Engineer at the worksite, with a copy to the Contracting Officer.

(e) Government action.

(1) The Contracting Officer will notify the Contractor of the status of the VECP within 45 calendar days after the contracting office receives it. If additional time is required, the Contracting Officer will notify the Contractor within the 45-day period and provide the reason for the delay and the expected date of the decision. The Government will process VECP's expeditiously; however, it shall not be liable for any delay in acting upon a VECP.

If the VECP is not accepted, the Contracting Officer will notify the Contractor in writing, explaining the reasons for rejection. The Contractor may withdraw any VECP, in whole or in part, at any time before it is accepted by the Government. The Contracting Officer may require that the Contractor provide written notification before undertaking significant expenditures for VECP effort.

Any VECP may be accepted, in whole or in part, by the Contracting Officer's award of a modification to this contract citing this clause. The Contracting Officer may accept the VECP, even though an agreement on price reduction has not been reached, by issuing the Contractor a notice to proceed with the change. Until a notice to proceed is issued or a contract modification applies a VECP to this contract, the Contractor shall perform in accordance with the existing contract. The decision to accept or reject all or part of any VECP is a unilateral decision made solely at the discretion of the Contracting Officer.

(f) Sharing.

(1) Rates. The Government's share of savings is determined by subtracting Government costs from instant contract savings and multiplying the result by

(i) 45 percent for fixed-price contracts or

(ii) 75 percent for cost-reimbursement contracts.

(2) Payment. Payment of any share due the Contractor for use of a VECP on this contract shall be authorized by a modification to this contract to--

(i) Accept the VECP;

(ii) Reduce the contract price or estimated cost by the amount of instant contract savings; and

(iii) Provide the Contractor's share of savings by adding the amount calculated to the contract price or fee.

(g) Collateral savings. If a VECP is accepted, the Contracting Officer will increase the instant contract amount by 20 percent of any projected collateral savings determined to be realized in a typical year of use after subtracting any Government costs not previously offset. However, the Contractor's share of collateral savings will not exceed the contract's firm-fixed-price or estimated cost, at the time the VECP is accepted, or $100,000, whichever is greater. The Contracting Officer is the sole determiner of the amount of collateral savings.

(h) Subcontracts. The Contractor shall include an appropriate value engineering clause in any subcontract of $50,000 or more and may include one in subcontracts of lesser value. In computing any adjustment in this contract's price under paragraph (f) above, the Contractor's allowable development and implementation costs shall include any subcontractor's allowable development and implementation costs clearly resulting from a VECP accepted by the Government under this contract, but shall exclude any value engineering incentive payments to a subcontractor. The Contractor may choose any arrangement for subcontractor value engineering incentive payments; provided, that these payments shall not reduce the Government's share of the savings resulting from the VECP.

(i) Data. The Contractor may restrict the Government's right to use any part of a VECP or the supporting data by marking the following legend on the affected parts:

"These data, furnished under the Value Engineering-- Construction clause of contract . . . . . , shall not be disclosed outside the Government or duplicated, used, or disclosed, in whole or in part, for any purpose other than to evaluate a value engineering change proposal submitted under the clause. This restriction does not limit the Government's right to use information contained in these data if it has been obtained or is otherwise available from the Contractor or from another source without limitations." If a VECP is accepted, the Contractor hereby grants the Government unlimited rights in the VECP and supporting data, except that, with respect to data qualifying and submitted as limited rights technical data, the Government shall have the rights specified in the contract modification implementing the VECP and shall appropriately mark the data. (The terms "unlimited rights" and "limited rights" are defined in Part 27 of the Federal Acquisition Regulation.)

(End of clause)

52.249-2 TERMINATION FOR CONVENIENCE OF THE GOVERNMENT (FIXED-PRICE) (SEP 1996) - ALTERNATE I (SEP 1996)

(a) The Government may terminate performance of work under this contract in whole or, from time to time, in part if the Contracting Officer determines that a termination is in the Government's interest. The Contracting Officer shall terminate by delivering to the Contractor a Notice of Termination specifying the extent of termination and the effective date.

(b) After receipt of a Notice of Termination, and except as directed by the Contracting Officer, the Contractor shall immediately proceed with the following obligations, regardless of any delay in determining or adjusting any amounts due under this clause:

(1) Stop work as specified in the notice.

(2) Place no further subcontracts or orders (referred to as subcontracts in this clause) for materials, services, or facilities, except as necessary to complete the continued portion of the contract.

(3) Terminate all subcontracts to the extent they relate to the work terminated.

(4) Assign to the Government, as directed by the Contracting Officer, all right, title, and interest of the Contractor under the subcontracts terminated, in which case the Government shall have the right to settle or to pay any termination settlement proposal arising out of those terminations.

(5) With approval or ratification to the extent required by the Contracting Officer, settle all outstanding liabilities and termination settlement proposals arising from the termination of subcontracts; the approval or ratification will be final for purposes of this clause.

(6) As directed by the Contracting Officer, transfer title and deliver to the Government (i) the fabricated or unfabricated parts, work in process, completed work, supplies, and other material produced or acquired for the work terminated, and (ii) the completed or partially completed plans, drawings, information, and other property that, if the contract had been completed, would be required to be furnished to the Government.

(7) Complete performance of the work not terminated.

(8) Take any action that may be necessary, or that the Contracting Officer may direct, for the protection and preservation of the property related to this contract that is in the possession of the Contractor and in which the Government has or may acquire an interest.

(9) Use its best efforts to sell, as directed or authorized by the Contracting Officer, any property of the types referred to in subparagraph (b)(6) of this clause; provided, however, that the Contractor (i) is not required to extend credit to any purchaser and (ii) may acquire the property under the conditions prescribed by, and at prices approved by, the Contracting Officer. The proceeds of any transfer or disposition will be applied to reduce any payments to be made by the Government under this contract, credited to the price or cost of the work, or paid in any other manner directed by the Contracting Officer.

(c) The Contractor shall submit complete termination inventory schedules no later than 120 days from the effective date of termination, unless extended in writing by the Contracting Officer upon written request of the Contractor within this 120-day period.

(d) After expiration of the plant clearance period as defined in Subpart 45.6 of the Federal Acquisition Regulation, the Contractor may submit to the Contracting Officer a list, certified as to quantity and quality, of termination inventory not previously disposed of, excluding items authorized for disposition by the Contracting Officer. The Contractor may request the Government to remove those items or enter into an agreement for their storage. Within 15 days, the Government will accept title to those items and remove them or enter into a storage agreement. The Contracting Officer may verify the list upon removal of the items, or if stored, within 45 days from submission of the list, and shall correct the list, as necessary, before final settlement.

(e) After termination, the Contractor shall submit a final termination settlement proposal to the Contracting Officer in the form and with the certification prescribed by the Contracting Officer. The Contractor shall submit the proposal promptly, but no later than 1 year from the effective date of termination, unless extended in writing by the Contracting Officer upon written request of the Contractor within this 1-year period. However, if the Contracting Officer determines that the facts justify it, a termination settlement proposal may be received and acted on after 1 year or any extension. If the Contractor fails to submit the proposal within the time allowed, the Contracting Officer may determine, on the basis of information available, the amount, if any, due the Contractor because of the termination and shall pay the amount determined.

(f) Subject to paragraph (e) of this clause, the Contractor and the Contracting Officer may agree upon the whole or any part of the amount to be paid or remaining to be paid because of the termination. The amount may include a reasonable allowance for profit on work done. However, the agreed amount, whether under this paragraph (g) or

paragraph (g) of this clause, exclusive of costs shown in subparagraph (g)(3) of this clause, may not exceed the total contract price as reduced by (1) the amount of payments previously made and (2) the contract price of work not terminated. The contract shall be modified, and the Contractor paid the agreed amount. Paragraph (g) of this clause shall not limit, restrict, or affect the amount that may be agreed upon to be paid under this paragraph.

(g) If the Contractor and Contracting Officer fail to agree on the whole amount to be paid the Contractor because of the termination of work, the Contracting Officer shall pay the Contractor the amounts determined as follows, but without duplication of any amounts agreed upon under paragraph (f) of this clause:

(1) For contract work performed before the effective date of termination, the total (without duplication of any items) of--

(i) The cost of this work;

(ii) The cost of settling and paying termination settlement proposals under terminated subcontracts that are properly chargeable to the terminated portion of the contract if not included in subdivision (g)(1)(i) of this clause; and

(iii) A sum, as profit on subdivision (g)(1)(i) of this clause, determined by the Contracting Officer under 49.202 of the Federal Acquisition Regulation, in effect on the date of this contract, to be fair and reasonable; however, if it appears that the Contractor would have sustained a loss on the entire contract had it been completed, the Contracting Officer shall allow no profit under this subdivision (iii) and shall reduce the settlement to reflect the indicated rate of loss.

(2) The reasonable costs of settlement of the work terminated, including--

(i) Accounting, legal, clerical, and other expenses reasonably necessary for the preparation of termination settlement proposals and supporting data;

(ii) The termination and settlement of subcontracts (excluding the amounts of such settlements); and

(iii) Storage, transportation, and other costs incurred, reasonably necessary for the preservation, protection, or disposition of the termination inventory.

(h) Except for normal spoilage, and except to the extent that the Government expressly assumed the risk of loss, the Contracting Officer shall exclude from the amounts payable to the Contractor under paragraph (g) of this clause, the fair value, as determined by the Contracting Officer, of property that is destroyed, lost, stolen, or damaged so as to become undeliverable to the Government or to a buyer.

(i) The cost principles and procedures of Part 31 of the Federal Acquisition Regulation, in effect on the date of this contract, shall govern all costs claimed, agreed to, or determined under this clause.

(j) The Contractor shall have the right of appeal, under the Disputes clause, from any determination made by the Contracting Officer under paragraph (e), (g), or (l) of this clause, except that if the Contractor failed to submit the termination settlement proposal or request for equitable adjustment within the time provided in paragraph (e) or (l), respectively, and failed to request a time extension, there is no right of appeal.

(k) In arriving at the amount due the Contractor under this clause, there shall be deducted--

(1) All unliquidated advance or other payments to the Contractor under the terminated portion of this contract;

(2) Any claim which the Government has against the Contractor under this contract; and

(3) The agreed price for, or the proceeds of sale of, materials, supplies, or other things acquired by the Contractor or sold under the provisions of this clause and not recovered by or credited to the Government.

(l) If the termination is partial, the Contractor may file a proposal with the Contracting Officer for an equitable adjustment of the price(s) of the continued portion of the contract. The Contracting Officer shall make any equitable adjustment agreed upon. Any proposal by the Contractor for an equitable adjustment under this clause shall be requested within 90 days from the effective date of termination unless extended in writing by the Contracting Officer.

(m)(1) The Government may, under the terms and conditions it prescribes, make partial payments and payments against costs incurred by the Contractor for the terminated portion of the contract, if the Contracting Officer believes the total of these payments will not exceed the amount to which the Contractor will be entitled.

(2) If the total payments exceed the amount finally determined to be due, the Contractor shall repay the excess to the Government upon demand, together with interest computed at the rate established by the Secretary of the Treasury under 50 U.S.C. App. 1215(b)(2). Interest shall be computed for the period from the date the excess payment is received by the Contractor to the date the excess is repaid. Interest shall not be charged on any excess payment due to a reduction in the Contractor's termination settlement proposal because of retention or other disposition of termination inventory until 10 days after the date of the retention or disposition, or a later date determined by the Contracting Officer because of the circumstances.

(n) Unless otherwise provided in this contract or by statute, the Contractor shall maintain all records and documents relating to the terminated portion of this contract for 3 years after final settlement. This includes all books and other evidence bearing on the Contractor's costs and expenses under this contract. The Contractor shall make these records and documents available to the Government, at the Contractor's office, at all reasonable times, without any direct charge. If approved by the Contracting Officer, photographs, microphotographs, or other authentic reproductions may be maintained instead of original records and documents.

52.249-10 DEFAULT (FIXED-PRICE CONSTRUCTION) (APR 1984)

(a) If the Contractor refuses or fails to prosecute the work or any separable part, with the diligence that will insure its completion within the time specified in this contract including any extension, or fails to complete the work within this time, the Government may, by written notice to the Contractor, terminate the right to proceed with the work (or the separable part of the work) that has been delayed. In this event, the Government may take over the work and complete it by contract or otherwise, and may take possession of and use any materials, appliances, and plant on the work site necessary for completing the work. The Contractor and its sureties shall be liable for any damage to the Government resulting from the Contractor's refusal or failure to complete the work within the specified time, whether or not the Contractor's right to proceed with the work is terminated. This liability includes any increased costs incurred by the Government in completing the work.

(b) The Contractor's right to proceed shall not be terminated nor the Contractor charged with damages under this clause, if--

(1) The delay in completing the work arises from unforeseeable causes beyond the control and without the fault or negligence of the Contractor. Examples of such causes include

(i) acts of God or of the public enemy,

(ii) acts of the Government in either its sovereign or contractual capacity,

(iii) acts of another Contractor in the performance of a contract with the Government,

(iv) fires,

(v) floods,

(vi) epidemics,

(vii) quarantine restrictions,

(viii) strikes,

(ix) freight embargoes,

(x) unusually severe weather, or delays of subcontractors or suppliers at any tier arising from unforeseeable causes beyond the control and without the fault or negligence of both the Contractor and the subcontractors or suppliers; and

(2) The Contractor, within 10 days from the beginning of any delay (unless extended by the Contracting Officer), notifies the Contracting Officer in writing of the causes of delay. The Contracting Officer shall ascertain the facts and the extent of delay. If, in the judgment of the Contracting Officer, the findings of fact warrant such action, the time for completing the work shall be extended. The findings of the Contracting Officer shall be final and conclusive on the parties, but subject to appeal under the Disputes clause.

(c) If, after termination of the Contractor's right to proceed, it is determined that the Contractor was not in default, or that the delay was excusable, the rights and obligations of the parties will be the same as if the termination had been issued for the convenience of the Government.

The rights and remedies of the Government in this clause are in addition to any other rights and remedies provided by law or under this contract.

52.253-1 COMPUTER GENERATED FORMS (JAN 1991)

(a) Any data required to be submitted on a Standard or Optional Form prescribed by the Federal Acquisition Regulation (FAR) may be submitted on a computer generated version of the form, provided there is no change to the name, content, or sequence of the data elements on the form, and provided the form carries the Standard or Optional Form number and edition date.

(b) Unless prohibited by agency regulations, any data required to be submitted on an agency unique form prescribed by an agency supplement to the FAR may be submitted on a computer generated version of the form provided there is no change to the name, content, or sequence of the data elements on the form and provided the form carries the agency form number and edition date.

(c) If the Contractor submits a computer generated version of a form that is different than the required form, then the rights and obligations of the parties will be determined based on the content of the required form.

252.201-7000 CONTRACTING OFFICER'S REPRESENTATIVE (DEC 1991)

(a) "Definition. Contracting officer's representative" means an individual designated in accordance with subsection 201.602-2 of the Defense Federal Acquisition Regulation Supplement and authorized in writing by the contracting officer to perform specific technical or administrative functions.

(b) If the Contracting Officer designates a contracting officer's representative (COR), the Contractor will receive a copy of the written designation. It will specify the extent of the COR's authority to act on behalf of the contracting officer. The COR is not authorized to make any commitments or changes that will affect price, quality, quantity, delivery, or any other term or condition of the contract.

(End of clause)

252.203-7002 DISPLAY OF DOD HOTLINE POSTER (DEC 1991)

(a) The Contractor shall display prominently in common work areas within business segments performing work under Department of Defense (DoD) contracts, DoD Hotline Posters prepared by the DoD Office of the Inspector General.

(b) DoD Hotline Posters may be obtained from the DoD Inspector General, ATTN: Defense Hotline, 400 Army Navy Drive, Washington, DC 22202-2884.

(c) The Contractor need not comply with paragraph (a) of this clause if it has established a mechanism, such as a hotline, by which employees may report suspected instances of improper conduct, and instructions that encourage employees to make such reports.

(End of clause)

252.204-7003 CONTROL OF GOVERNMENT PERSONNEL WORK PRODUCT (APR 1992)

The Contractor's procedures for protecting against unauthorized disclosure of information shall not require Department of Defense employees or members of the Armed Forces to relinquish control of their work products, whether classified or not, to the contractor.

(End of clause)

252.209-7004 SUBCONTRACTING WITH FIRMS THAT ARE OWNED OR CONTROLLED BY THE GOVERNMENT OF A TERRORIST COUNTRY (MAR 1998)

(a) Unless the Government determines that there is a compelling reason to do so, the Contractor shall not enter into any subcontract in excess of $25,000 with a firm, or subsidiary of a firm, that is identified, on the List of Parties Excluded from Federal Procurement and Nonprocurement Programs, as being ineligible for the award of Defense contracts or subcontracts because it is owned or controlled by the government of a terrorist country.

(b) A corporate officer or a designee of the Contractor shall notify the Contracting Officer, in writing, before entering into a subcontract with a party that is identified, on the List of Parties Excluded from Federal Procurement and Nonprocurement Programs, as being ineligible for the award of Defense contracts or subcontracts because it is owned or controlled by the government of a terrorist country. The notice must include the name of the proposed subcontractor notwithstanding its inclusion on the List of Parties Excluded From Federal Procurement and Nonprocurement Programs.

252.223-7004 DRUG-FREE WORK FORCE (SEP 1988)

(a) Definitions.

(1) "Employee in a sensitive position," as used in this clause, means an employee who has been granted access to classified information; or employees in other positions that the Contractor determines involve national security; health or safety, or functions other than the foregoing requiring a high degree of trust and confidence.

(2) "Illegal drugs," as used in this clause, means controlled substances included in Schedules I and II, as defined by section 802(6) of title 21 of the United States Code, the possession of which is unlawful under chapter 13 of that Title. The term "illegal drugs" does not mean the use of a controlled substance pursuant to a valid prescription or other uses authorized by law.

(b) The Contractor agrees to institute and maintain a program for achieving the objective of a drug-free work force. While this clause defines criteria for such a program, contractors are encouraged to implement alternative approaches comparable to the criteria in paragraph (c) that are designed to achieve the objectives of this clause.

(c) Contractor programs shall include the following, or appropriate alternatives:

(1) Employee assistance programs emphasizing high level direction, education, counseling, rehabilitation, and coordination with available community resources;

(2) Supervisory training to assist in identifying and addressing illegal drug use by Contractor employees;

(3) Provision for self-referrals as well as supervisory referrals to treatment with maximum respect for individual confidentiality consistent with safety and security issues;

(4) Provision for identifying illegal drug users, including testing on a controlled and carefully monitored basis. Employee drug testing programs shall be established taking account of the following:

(i) The Contractor shall establish a program that provides for testing for the use of illegal drugs by employees in sensitive positions. The extent of and criteria for such testing shall be determined by the Contractor based on considerations that include the nature of the work being performed under the contract, the employee's duties, and efficient use of Contractor resources, and the risks to health, safety, or national security that could result from the failure of an employee adequately to discharge his or her position.

(ii) In addition, the Contractor may establish a program for employee drug testing--

(A) When there is a reasonable suspicion that an employee uses illegal drugs; or

(B) When an employees has been involved in an accident or unsafe practice;

(C) As part of or as a follow-up to counseling or rehabilitation for illegal drug use;

(D) As part of a voluntary employee drug testing program.

(iii) The Contractor may establish a program to test applicants for employment for illegal drug use.

(iv) For the purpose of administering this clause, testing for illegal drugs may be limited to those substances for which testing is prescribed by section 2..1 of subpart B of the "Mandatory Guidelines for Federal Workplace Drug Testing Programs" (53 FR 11980 (April 11, 1988), issued by the Department of Health and Human Services.

(d) Contractors shall adopt appropriate personnel procedures to deal with employees who are found to be using drugs illegally. Contractors shall not allow any employee to remain on duty or perform in a sensitive position who is found to use illegal drugs until such times as the Contractor, in accordance with procedures established by the Contractor, determines that the employee may perform in such a position.

(e) The provisions of this clause pertaining to drug testing program shall not apply to the extent that are inconsistent with state or local law, or with an existing collective bargaining agreement; provided that with respect to the latter, the Contractor agrees those issues that are in conflict will be a subject of negotiation at the next collective bargaining session.

(End of clause)

252.223-7004 DRUG-FREE WORK FORCE (SEP 1988)

(a) Definitions.

(1) "Employee in a sensitive position," as used in this clause, means an employee who has been granted access to classified information; or employees in other positions that the Contractor determines involve national security; health or safety, or functions other than the foregoing requiring a high degree of trust and confidence.

(2) "Illegal drugs," as used in this clause, means controlled substances included in Schedules I and II, as defined by section 802(6) of title 21 of the United States Code, the possession of which is unlawful under chapter 13 of that Title. The term "illegal drugs" does not mean the use of a controlled substance pursuant to a valid prescription or other uses authorized by law.

(b) The Contractor agrees to institute and maintain a program for achieving the objective of a drug-free work force. While this clause defines criteria for such a program, contractors are encouraged to implement alternative approaches comparable to the criteria in paragraph (c) that are designed to achieve the objectives of this clause.

(c) Contractor programs shall include the following, or appropriate alternatives:

(1) Employee assistance programs emphasizing high level direction, education, counseling, rehabilitation, and coordination with available community resources;

(2) Supervisory training to assist in identifying and addressing illegal drug use by Contractor employees;

(3) Provision for self-referrals as well as supervisory referrals to treatment with maximum respect for individual confidentiality consistent with safety and security issues;

(4) Provision for identifying illegal drug users, including testing on a controlled and carefully monitored basis. Employee drug testing programs shall be established taking account of the following:

(i) The Contractor shall establish a program that provides for testing for the use of illegal drugs by employees in sensitive positions. The extent of and criteria for such testing shall be determined by the Contractor based on considerations that include the nature of the work being performed under the contract, the employee's duties, and efficient use of Contractor resources, and the risks to health, safety, or national security that could result from the failure of an employee adequately to discharge his or her position.

(ii) In addition, the Contractor may establish a program for employee drug testing--

(A) When there is a reasonable suspicion that an employee uses illegal drugs; or

(B) When an employees has been involved in an accident or unsafe practice;

(C) As part of or as a follow-up to counseling or rehabilitation for illegal drug use;

(D) As part of a voluntary employee drug testing program.

(iii) The Contractor may establish a program to test applicants for employment for illegal drug use.

(iv) For the purpose of administering this clause, testing for illegal drugs may be limited to those substances for which testing is prescribed by section 2..1 of subpart B of the "Mandatory Guidelines for Federal Workplace Drug Testing Programs" (53 FR 11980 (April 11, 1988), issued by the Department of Health and Human Services.

(d) Contractors shall adopt appropriate personnel procedures to deal with employees who are found to be using drugs illegally. Contractors shall not allow any employee to remain on duty or perform in a sensitive position who is found to use illegal drugs until such times as the Contractor, in accordance with procedures established by the Contractor, determines that the employee may perform in such a position.

(e) The provisions of this clause pertaining to drug testing program shall not apply to the extent that are inconsistent with state or local law, or with an existing collective bargaining agreement; provided that with respect to the latter, the Contractor agrees those issues that are in conflict will be a subject of negotiation at the next collective bargaining session.

(End of clause)

252.223-7006 PROHIBITION ON STORAGE AND DISPOSAL OF TOXIC AND HAZARDOUS MATERIALS (APR 1993)

(a) "Definitions".

As used in this clause --

(1) "Storage" means a non-transitory, semi-permanent or permanent holding, placement, or leaving of material. It does not include a temporary accumulation of a limited quantity of a material used in or a waste generated or resulting from authorized activities, such as servicing, maintenance, or repair of Department of Defense (DoD) items, equipment, or facilities.

(2) "Toxic or hazardous materials" means:

(i) Materials referred to in section 101(14) of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) of 1980 (42 U.S.C. 9601(14)) and materials designated under section 102 of CERCLA (42 U.S.C. 9602) (40 CFR part 302);

(ii) Materials that are of an explosive, flammable, or pyrotechnic nature; or

(iii) Materials otherwise identified by the Secretary of Defense as specified in DoD regulations.

(b) In accordance with 10 U.S.C. 2692, the Contractor is prohibited from storing or disposing of non-DoD-owned toxic or hazardous materials on a DoD installation, except to the extent authorized by a statutory exception to 10 U.S.C. 2692 or as authorized by the Secretary of Defense or his designee.

(End of clause)

252.227-7033 RIGHTS IN SHOP DRAWINGS (APR 1966)

(a) Shop drawings for construction means drawings, submitted to the Government by the Construction Contractor, subcontractor or any lower-tier subcontractor pursuant to a construction contract, showing in detail (i) the proposed fabrication and assembly of structural elements and (ii) the installation (i.e., form, fit, and attachment details) of materials or equipment. The Government may duplicate, use, and disclose in any manner and for any purpose shop drawings delivered under this contract.

(b) This clause, including this paragraph (b), shall be included in all subcontracts hereunder at any tier.

252.231-7000 SUPPLEMENTAL COST PRINCIPLES (DEC 1991)

When the allowability of costs under this contract is determined in accordance with part 31 of the Federal Acquisition Regulation (FAR), allowability shall also be determined in accordance with part 231 of the Defense FAR Supplement, in effect on the date of this contract.

252.236-7000 MODIFICATION PROPOSALS - PRICE BREAKDOWN. (DEC 1991)

(a) The Contractor shall furnish a price breakdown, itemized as required and within the time specified by the Contracting Officer, with any proposal for a contract modification.

(b) The price breakdown --

(1) Must include sufficient detail to permit an analysis of profit, and of all costs for --

(i) Material;

(ii) Labor;

(iii) Equipment;

(iv) Subcontracts; and

(v) Overhead; and

(2) Must cover all work involved in the modification, whether the work was deleted, added, or changed.

(c) The Contractor shall provide similar price breakdowns to support any amounts claimed for subcontracts.

(d) The Contractor's proposal shall include a justification for any time extension proposed.

252.242-7000 POSTAWARD CONFERENCE (DEC 1991)

The Contractor agrees to attend any postaward conference convened by the contracting activity or contract administration office in accordance with Federal Acquisition Regulation subpart 42.5.

(End of clause)

252.243-7001 PRICING OF CONTRACT MODIFICATIONS (DEC 1991)

When costs are a factor in any price adjustment under this contract, the contract cost principles and procedures in FAR part 31 and DFARS part 231, in effect on the date of this contract, apply.

252.243-7002 REQUESTS FOR EQUITABLE ADJUSTMENT (MAR 1998)

(a) The amount of any request for equitable adjustment to contract terms shall accurately reflect the contract adjustment for which the Contractor believes the Government is liable. The request shall include only costs for performing the change, and shall not include any costs that already have been reimbursed or that have been separately claimed. All indirect costs included in the request shall be properly allocable to the change in accordance with applicable acquisition regulations.

(b) In accordance with 10 U.S.C. 2410(a), any request for equitable adjustment to contract terms that exceeds the simplified acquisition threshold shall bear, at the time of submission, the following certificate executed by an individual authorized to certify the request on behalf of the Contractor:

I certify that the request is made in good faith, and that the supporting data are accurate and complete to the best of my knowledge and belief.

(Official's Name)

(Title)

(c) The certification in paragraph (b) of this clause requires full disclosure of all relevant facts, including--

(1) Cost or pricing data if required in accordance with subsection 15.403-4 of the Federal Acquisition Regulation (FAR); and

(2) Information other than cost or pricing data, in accordance with subsection 15.403-3 of the FAR, including actual cost data and data to support any estimated costs, even if cost or pricing data are not required.

(d) The certification requirement in paragraph (b) of this clause does not apply to----

(1) Requests for routine contract payments; for example, requests for payment for accepted supplies and services, routine vouchers under a cost-reimbursement type contract, or progress payment invoices; or

(2) Final adjustment under an incentive provision of the contract.

TABLE OF CONTENTS

SPECIAL CLAUSES

PARAGRAPH NO.	PARAGRAPH TITLE
SC-1	COMMENCEMENT, PROSECUTION, AND COMPLETION OF WORK
SC-1.1	OPTION FOR INCREASED QUANTITY
SC-2	LIQUIDATED DAMAGES - CONSTRUCTION
SC-3	DELETED - TIME EXTENSIONS
SC-4	VARIATIONS IN ESTIMATED QUANTITIES - SUBDIVIDED ITEMS
SC-5	INSURANCE - WORK ON A GOVERNMENT INSTALLATION
SC-6	DELETED - CONTINUING CONTRACTS
SC-7	PERFORMANCE OF WORK BY THE CONTRACTOR
SC-8	PHYSICAL DATA
SC-9	DELETED - QUANTITY SURVEYS
SC-10	LAYOUT OF WORK
SC-11	DELETED - PAYMENT FOR MOBILIZATION AND DEMOBILIZATION
SC-12	AIRFIELD SAFETY PRECAUTIONS
SC-13	DELETED - IDENTIFICATION OF GOVERNMENT-FURNISHED PROPERTY
SC-14	EQUIPMENT OWNERSHIP AND OPERATING EXPENSE SCHEDULE
SC-15	PAYMENT FOR MATERIALS DELIVERED OFF-SITE
SC-16	DELETED - ORDER OF PRECEDENCE
SC-17	DELETED - LIMITATION OF PAYMENT FOR DESIGN
SC-18	CONTRACT DRAWINGS, MAPS AND SPECIFICATIONS
SC-19	DELETED - TECHNICAL PROPOSAL - COPIES TO BE FURNISHED UPON AWARD
SC-20	DELETED - COMPLIANCE CERTIFICATION
SC-21	DELETED - VALUE ENGINEERING
SC-22	EPA ENERGY STAR
SC-23	RECOVERED MATERIALS

This page intentionally blank

SECTION 00800

SPECIAL CLAUSES

SC-1. COMMENCEMENT, PROSECUTION, AND COMPLETION OF WORK (APR 1984) (FAR 52.211-10).

The Contractor shall be required to (a) commence work under this Contract within 10 calendar days after the date the Contractor receives the notice to proceed, (b) prosecute the work diligently, and (c) complete the entire work ready for use not later than 1 November 2002. The time stated for completion shall include final cleanup of the premises. See Section 01005(AR), paragraph 1.5, and Section 01010(R), paragraph 1.13 for Construction Phasing.

The successful offeror will receive the notice to proceed not later than 15 April 2002.

SC-1.1 OPTION FOR INCREASED QUANTITY

a. The Government may increase the quantity of work awarded by exercising one or more of the Optional Bid Items 0003, 0004, 0005, 0014, 0015, 0016 and 0017 at any time, or not at all, but no later than 30 calendar days after receipt by the Contractor of the notice to proceed. Notice to proceed on work Item(s) added by exercise of the option(s) will be given upon execution of consent of surety.

b. The parties hereto further agree that any option herein shall be considered to have been exercised at the time the Government deposits written notification to the Contractor in the mails.

c. The time allowed for completion of any optional items awarded under this contract will be the same as that for the base items, and will be measured from the date of receipt of the notice to proceed for the base items.

SC-2. LIQUIDATED DAMAGES - CONSTRUCTION (SEP 2000) (FAR 52.211-12)

(a) If the Contractor fails to complete the work within the time specified in the Contract, or any extension, the Contractor shall pay to the Government as liquidated damages as follows:

(1) The sums shown below for delays after 19 August 2002 for completing the runway and concrete ends:

Days of delay	Cost per day
• For days 1-2 after 19 August 2002	$45,100
• For days 3-11 after 19 August 2002	$47,820
• For days 12-15 after 19 August 2002	$53,430
• For day 16 after 19 August 2002	$57,680
• For days 17-25 after 19 August 2002	$62,440
• For days 26-29 after 19 August 2002	$73,150
• For day 30 and beyond after 19 August 2002	$79,100

Plus the following one time charges for delays after 19 August 2002:

• Day 3 after 19 August 2002	$16,700
• Day 12 after 19 August 2002	$37,500
• Day 15 after 19 August 2002	$20,800

(2) The sum of $1,396.00 for each day of delay after 1 September 2002 for completion of Phase 2 of the Aircraft Parking Apron.

(3) The sum of $1272.00 for each day of delay after 1 November 2002 for final completion of construction.

(4) Liquidated damages are cumulative and will be combined if more than one are applicable at the same time.

(b) If the Government terminates the Contractor's right to proceed, the resulting damage will consist of liquidated damages until such reasonable time as may be required for final completion of the work together with any increased costs occasioned the Government in completing the work.

(c) If the Government does not terminate the Contractor's right to proceed, the resulting damage will consist of liquidated damages until the work is completed or accepted.

SC-3 DELETED

SC-4. VARIATIONS IN ESTIMATED QUANTITIES - SUBDIVIDED ITEMS (MAR 1995) (EFARS 52.212-5001): This variation in estimated quantities clause is applicable only to Item Nos. 0002, 0003, 0005, 0007, 0008, 0009, 0010, 0011, 0012, 0013, 0015, 0016, and 0017.

(a) Variation from the estimated quantity in the actual work performed under any second or subsequent sub-item or elimination of all work under such a second or subsequent sub-item will not be the basis for an adjustment in contract unit price.

(b) Where the actual quantity of work performed for Items Nos. 0002, 0003, 0005, 0007, 0008, 0009, 0010, 0011, 0012, 0013, 0015, and 0017 exceeds 115 percent or is less than 85 percent of the quantity of the he first sub-item listed under such item, the Contractor will be paid at the contract unit price for that sub-item for the actual quantity of work performed and, in addition, an equitable adjustment shall be made in accordance with the clause FAR 52.211-18, Variation in Estimated Quantities.

(c) If the actual quantity of work performed under Items Nos. 0002, 0003, 0005, 0007, 0008, 0009, 0010, 0011, 0012, 0013, 0015, and 0017 exceeds 115 percent or is less than 85 percent of the total estimated quantity of the sub-item under that item and/or if the quantity of the work performed under the second sub-item or any subsequent sub-item under Items Nos. 0002, 0003, 0005, 0007, 0008, 0009, 0010, 0011, 0012, 0013, 0015, and 0017 exceeds 115 % or is less than 85 % of the estimated quantity of any such sub-item, and if such variation causes an increase or a decrease in the time required for performance of this contract the contract completion time will be adjusted in accordance with the clause FAR 52.211-18, Variation in Estimated Quantities.

SC-5. INSURANCE - WORK ON A GOVERNMENT INSTALLATION (JAN 1997) (FAR 52.228-5)

(a) The Contractor shall, at its own expense, provide and maintain during the entire performance period of this Contract at least the kinds and minimum amounts of insurance required in the Insurance Liability Schedule or elsewhere in the Contract.

(b) Before commencing work under this Contract, the Contractor shall certify to the Contracting Officer in writing that the required insurance has been obtained. The policies evidencing required insurance shall contain an endorsement to the effect that any cancellation or any material change adversely affecting the Government's interest shall not be effective:

(1) for such period as the laws of the State in which this Contract is to be performed prescribe; or

(2) until 30 days after the insurer or the Contractor gives written notice to the Contracting Officer, whichever period is longer.

(c) The Contractor shall insert the substance of this clause, including this paragraph (c), in subcontracts under this Contract that require work on a Government installation and shall require subcontractors to provide and maintain the insurance required in the Schedule or elsewhere in the Contract. The Contractor shall maintain a copy of all subcontractors' proofs of required insurance, and shall make copies available to the Contracting Officer upon request.

(d) Insurance Liability Schedule (FAR 28.307-2)

(1) Workers' compensation and employer's liability. Contractors are required to comply with applicable Federal and State workers' compensation and occupational disease statutes. If occupational diseases are not compensable under those statutes, they shall be covered under the employer's liability section of the insurance policy, except when Contract operations are so commingled with a Contractor's commercial operation that it would not be practical to require this coverage. Employer's liability coverage of at least $100,000 shall be required, except in states with exclusive or monopolistic funds that do not permit workers' compensation to be written by private carriers.

(2) General Liability.

(a) The Contracting Officer shall require bodily injury liability insurance coverage written on the comprehensive form of policy of at least $500,000 per occurrence.

(b) Property damage liability insurance shall be required only in special circumstances as determined by the agency.

(3) Automobile liability. The Contracting Officer shall require automobile liability insurance written on the comprehensive form of policy. The policy shall provide for bodily injury and property damage liability covering the operation of all automobiles used in connection with performing the Contract. Policies covering automobiles operated in the United States shall provide coverage of at least $200,000 per person and $500,000 per occurrence for bodily injury and $20,000 per occurrence for property damage. The amount of liability coverage on other policies shall be commensurate with any legal requirements of the locality and sufficient to meet normal and customary claims.

(4) Aircraft public and passenger liability. When aircraft are used in connection with performing the Contract, the Contracting Officer shall require aircraft public and passenger liability insurance. Coverage shall be at least $200,000 per person and $500,000 per occurrence for bodily injury, other than passenger liability, and $200,000 per occurrence for property

damage. Coverage for passenger liability bodily injury shall be at least $200,000 multiplied by the number of seats or passengers, whichever is greater.

(5) Environmental Liability If this contract includes the transport, treatment, storage, or disposal of hazardous material waste the following coverage is required.

The Contractor shall ensure the transporter and disposal facility have liability insurance if effect for claims arising out of the death or bodily injury and property damage from hazardous material/waste transport, treatment, storage and disposal, including vehicle liability and legal defense costs in the amount of $1,000,000.00 as evidenced by a certificate of insurance for General, Automobile, and Environmental Liability Coverage. Proof of this insurance shall be provided to the Contracting Officer.

SC-6. DELETED

SC-7. PERFORMANCE OF WORK BY THE CONTRACTOR (APR 1984) (FAR 52.236-1): The Contractor shall perform on the site, and with its own organization, work equivalent to at least fifteen percent (15 %) of the total amount of work to be performed under the Contract. The percentage may be reduced by a supplemental agreement to this Contract if, during performing the work, the Contractor requests a reduction and the Contracting Officer determines that the reduction would be to the advantage of the Government.

SC-8. PHYSICAL DATA (APR 1984) (FAR 52.236-4): Data and information furnished or referred to below is for the Contractor's information. The Government will not be responsible for any interpretation of or conclusion drawn from the data or information by the Contractor.

(a) Physical Conditions: The indications of physical conditions on the drawings and in the specifications are the result of site investigations by test holes shown on the drawings.

(b) Weather Conditions: Each bidder shall be satisfied before submitting his bid as to the hazards likely to arise from weather conditions. Complete weather records and reports may be obtained from any National Weather Service Office.

(c) Transportation Facilities: Each bidder, before submitting his bid, shall make an investigation of the conditions of existing public and private roads and of clearances, restrictions, bridge load limits, and other limitations affecting transportation and ingress and egress at the jobsite. The unavailability of transportation facilities or limitations thereon shall not become a basis for claims for damages or extension of time for completion of the work.

SC-9. DELETED

SC-10. LAYOUT OF WORK (APR 1984) (FAR 52.236-17): The Contractor shall lay out its work from Government-established base lines and bench marks indicated on the drawings, and shall be responsible for all measurements in connection with the layout. The Contractor shall furnish, at its own expense, all stakes, templates, platforms, equipment, tools, materials, and labor required to lay out any part of the work. The Contractor shall be responsible for executing the work to the lines and grades that may be established or indicated by the Contracting Officer. The Contractor shall also be responsible for maintaining and preserving all stakes and other marks established by the Contracting Officer until authorized to remove them. If such marks are destroyed by the Contractor or through its negligence before their removal is authorized, the

Contracting Officer may replace them and deduct the expense of the replacement from any amounts due, or to become due, to the Contractor.

SC-11. DELETED

SC-12. AIRFIELD SAFETY PRECAUTIONS (DEC 1991) (DOD FAR SUPP 252.236-7005)

(a) Definitions: As used in this clause --

(1) "Landing Areas" means:

(i) the primary surfaces which are comprised of the surface of the runways, the runway shoulders, and the lateral safety zones (the length of each primary surface is the same as the runway length; the width of each primary surface is 610 meters (2,000 feet), 305 meters (1,000 feet) on each side of the runway centerline; (see footnote at end of clause).

(ii) the "clear zone" beyond the ends of each runway, i.e., the extension of the "primary surface" for a distance of 305 meters (1,000 feet) beyond each end of each runway;

(iii) all taxiways plus the lateral clearance zones along each side for the length of the taxiways (the outer edge of each lateral clearance zone is laterally 76 meters (250 feet) from the far or opposite edge of the taxiway, i.e., a 23 meters (75-foot)-wide taxiway would have a combined width of taxiway and lateral clearance zones of 130 meters (425 feet); and

(iv) all aircraft parking aprons plus the area 38 meters (125 feet) in width extending beyond each edge all around the aprons.

(2) "Safety precaution areas" means those portions of approach-departure clearance zones and transitional zones where placement of objects incident to Contract performance might result in vertical projections at or above the approach-departure clearance surface or the transitional surface.

(i) The "approach-departure clearance surface" is an extension of the primary surface and the clear zone at each end of each runway, for a distance of 15,240 meters (50,000 feet), first along an inclined (glide angle) and then along a horizontal plane, both flaring symmetrically about the runway centerline extended.

(a) The inclined plane (glide angle) begins in the clear zone 61 meters (200 feet) past the end of the runway (and primary surface) at the same elevation as the end of the runway, and continues upward at a slope of 50:1 (.3048 meter (one foot) vertically for each 15.24 meters (50 feet) horizontally) to an elevation of 152 meters (500 feet) above the established airfield elevation; at that point the plane becomes horizontal, continuing at that same uniform elevation to a point 15,240 meters (50,000 feet) longitudinally from the beginning of the inclined plane (glide angle) and ending there.

(b) The width of the surface at the beginning of the inclined plane (glide angle) is the same as the width of the clear zone; thence it flares uniformly, reaching the maximum width of 4,877 meters (16,000 feet) at the end.

(ii) The "approach-departure clearance zone" is the ground area under the approach-departure clearance surface.

(iii) The "transitional surface" is a sideways extension of all primary surfaces, clear zones, and approach-departure clearance surfaces along inclined planes.

(a) The inclined plane in each case begins at the edge of the surface.

(b) The slope of the inclined plane is 7:1 (.3048 meter (one foot) vertically for each 2.13 meters (7 feet) horizontally), and it continues to the point of intersection with

(1) Inner horizontal surface (which is the horizontal plane 46 meters (150 feet) above the established airfield elevation) or

(2) Outer horizontal surface (which is the horizontal plane 152 meters (500 feet) above the established airfield elevation), whichever is applicable.

(iv) The "transitional zone" is the ground area under the transitional surface. (It adjoins the primary surface, clear zone and approach-departure clearance zone.)

(b) General

(1) The Contractor shall comply with the requirements of this clause while

(i) Operating all ground equipment (mobile or stationary);

(ii) Placing all materials; and

(iii) Performing all work, upon and around all airfields.

(a) The requirements of this clause are in addition to any other safety requirements of this contract.

(c) The Contractor shall--

(1) Report to the Contracting Officer before initiating any work;

(2) Notify the Contracting Officer of proposed changes to locations and operations;

(3) Not permit either its equipment or personnel to use any runway for purposes other than aircraft operation without permission of the Contracting Officer, unless the runway is--

(i) Closed by order of the Contracting Officer, and

(ii) Marked as provided in paragraph (d)(2) of this clause;

(4) Keep all paved surfaces such as runways, taxiways, and hardstands, clean at all times and, specifically, free from small stones which might damage aircraft propellers or jet aircraft;

(5) Operate mobile equipment according to the safety provisions of this clause, while actually performing work on the airfield. At all other times, the Contractor shall remove all mobile equipment to locations--

(i) Approved by the Contracting Officer,

(ii) At a distance of at least 229 meters (750 feet) from the runway centerline, plus any additional distance; and

(iii) Necessary to ensure compliance with the other provisions of this clause; and

(6) Not open a trench unless material is on hand and ready for placing in the trench. As soon as practicable after material has been placed and work approved, the Contractor shall backfill and compact trenches as required by the contract. Meanwhile, all hazardous conditions shall be marked and lighted in accordance with the other provisions of this clause.

(d) Landing Areas

The Contractor shall--

(1) Place nothing upon the landing areas without the authorization of the Contracting Officer.

(2) Outline those landing areas hazardous to aircraft, using (unless otherwise authorized by the Contracting Officer) red flags by day, and electric, battery-operated low-intensity red flasher lights by night;

(3) Obtain, at an airfield where flying is controlled, additional permission from the control tower operator every time before entering any landing area, unless the landing area is marked as hazardous in accordance with paragraph (d)(2) of this clause;

(4) Identify all vehicles it operates in landing areas by means of a flag on a staff attached to, and flying above, the vehicle. The flag shall be .9144 meters (3 feet) square, and consist of a checkered pattern of international orange and white squares of .3048 meter (1 foot) on each side (except that the flag may vary up to 10 percent from each of these dimensions);

(5) Mark all other equipment and materials in the landing areas, using the same marking devices as in paragraph (d)(2) of this clause; and

(6) Perform work so as to leave that portion of the landing area which is available to aircraft free from hazards, holes, piles of material, and projecting shoulders that might damage an airplane tire.

(e) Safety Precaution Areas

The Contractor shall--

(1) Place nothing upon the safety precaution areas without authorization of the Contracting Officer;

(2) Mark all equipment and materials in safety precaution areas, using (unless otherwise authorized by the Contracting Officer) red flags by day, and electric, battery-operated, low-intensity red flasher lights by night; and

(3) Provide all objects placed in safety precaution areas with a red light or red lantern at night, if the objects project above the approach-departure clearance surface or above the transitional surface. Any objects protruding above these surfaces require prior approval by the Contracting Officer.

SC-13. DELETED

SC-14. EQUIPMENT OWNERSHIP AND OPERATING EXPENSE SCHEDULE (MAY 1999)-(EFARS 52.231-5000)

(a) This clause does not apply to terminations. See 52.249-5000, Basis for Settlement of Proposals and FAR Part 49.

(b) Allowable cost for construction and marine plant and equipment in sound workable condition owned or controlled and furnished by a contractor or subcontractor at any tier shall be based on actual cost data for each piece of equipment or groups of similar serial and series for which the Government can determine both ownership and operating costs from the contractor's accounting records. When both ownership and operating costs cannot be determined for any piece of equipment or groups of similar serial or series equipment from the contractor's accounting records, costs for that equipment shall be based upon the applicable provisions of EP 1110-1-8, Construction Equipment Ownership and Operating Expense Schedule, Region VIII. Working conditions shall be considered to be average for determining equipment rates using the schedule unless specified otherwise by the contracting officer. For equipment not included in the schedule, rates for comparable pieces of equipment may be used or a rate may be developed using the formula provided in the schedule. For forward pricing, the schedule in effect at the time of negotiations shall apply. For retroactive pricing, the schedule in effect at the time the work was performed shall apply.

(c) Equipment rental costs are allowable, subject to the provisions of FAR 31.105(d)(ii) and FAR 31.205-36. Rates for equipment rented from an organization under common control, lease-purchase arrangements, and sale-leaseback arrangements, will be determined using the schedule, except that actual rates will be used for equipment leased from an organization under common control that has an established practice of leasing the same or similar equipment to unaffiliated lessees.

(d) When actual equipment costs are proposed and the total amount of the pricing action exceeds the small purchase threshold, the contracting officer shall request the contractor to submit either certified cost or pricing data, or partial/limited data, as appropriate. The data shall be submitted on Standard Form 1411, Contract Pricing Proposal Cover Sheet.

(e) Copies of EP1110-1-8 “Construction Equipment Ownership and Operating Expense Schedule” Volumes 1 through 12 are available in Portable Document Format (PDF) and can be viewed or downloaded at http://www.usace.army.mil/inet/usace-docs/eng-pamplets/cecw.htm. A CD-ROM containing (Volumes 1-12) is available through either the Superintendent of Documents or Government bookstores. For additional information telephone 202-512-2250, or access on the Internet at http://www.access.gpo.gov/su_docs.

SC-15. PAYMENT FOR MATERIALS DELIVERED OFF-SITE (MAY 1999)-(EFARS 52.232-5000)

(a) Pursuant to FAR clause 52.232-5, Payments Under Fixed Priced Construction Contracts, materials delivered to the contractor at locations other than the site of the work may be taken into consideration in making payments if included in payment estimates and if all the conditions of the General Provisions are fulfilled. Payment for items delivered to locations other than the work site will be limited to: (1) materials required by the technical provisions; or (2) materials that have been fabricated to the point where they are identifiable to an item of work required under this contract.

(b) Such payment will be made only after receipt of paid or receipted invoices or invoices with canceled check showing title to the items in the prime contractor and including the value of material and labor incorporated into the item. In addition to petroleum products, payment for materials delivered off-site is limited to the following items: Any other construction material stored offsite may be considered in determining the amount of a progress payment.

SC-16 AND SC-17. DELETED

SC-18. CONTRACT DRAWINGS, MAPS, AND SPECIFICATIONS (OCT 1996) (52.0236-4001 EBS)

(a) The Government--

(1) Will provide the Contractor, without charge, one set of contract drawings and one set of specifications in electronic format on a compact disk. The Government will not give the Contractor any hard copy paper drawings or specifications for any contract resulting from this solicitation.

(b) The Contractor shall--

(1) check all drawings furnished immediately upon receipt;

(2) Compare all drawings and verify the figures before laying out the work;

(3) Promptly notify the Contracting Officer of any discrepancies; and

(4) Be responsible for any errors which might have been avoided by complying with this paragraph (b).

(c) Large scale drawings shall, in general, govern small scale drawings. Figures marked on drawings shall, in general, be followed in preference to scale measurements.

(d) Omissions from the drawings or specifications or the misdescription of details of work which are manifestly necessary to carry out the intent of the drawings and specifications, or which are customarily performed, shall not relieve the Contractor from performing such omitted or misdescribed details of the work, but shall be performed as if fully and correctly set forth and described in the drawings and specifications.

(e) The work shall conform to the specifications and the contract drawings identified in the index of drawings attached at the end of the Special Clauses.

SC-19 THROUGH SC-21. DELETED

SC-22. EPA ENERGY STAR: The Government requires that certain equipment be Energy Star compliant. Initially, the sole Energy Star requirement shall be the self certification by the bidder that the specified equipment is Energy Star compliant. Within 3 months of the availability of an EPA sanctioned test for Energy Star compliance, the Contractor shall submit all equipment upgrades and additions for testing and provide proof of compliance to the Government upon completion of testing. Testing shall be at the Contractor's expense.

SC-23. RECOVERED MATERIALS: Mt. Home AFB recycling requirements are shown in Section 01061 ENVIRNONMENTAL PROTECTION, Appendix A.

INDEX OF DRAWINGS

REPAIR AIRCRAFT PARKING APRON/ REPAIR RUNWAY, MT. HOME AFB, IDAHO

REPAIR AIRCRAFT PARKING APRON (PN: QYZH003009)

REPAIR RUNWAY (PN: QYZH 60-1570)

File No. 227s/113-90-01

SHEET NUMBER	PLATE NUMBER	TITLE	REVISION NUMBER	DATE
		REPAIR AIRCRAFT PARKING APRON		
		GENERAL		
1	G-1	Title, Area Maps and Drawing Index		01DEC17
		GEOTECHNICAL		
2	GT-1	Exploration Logs		01DEC17
3	GT-2	Locations of Explorations		01DEC17
		CIVIL		
4	C-1	Legend and Abbreviations	A	02JAN23
5	C-2	Haul Routes/Staging Areas	A	02JAN23
6	C-3	Temporary Pavement Markings	A	02JAN23
7	C-4	Existing Utility Plan 1		01DEC17
8	C-5	Existing Utility Plan 2		01DEC17
9	C-6	Demolition Plan		01DEC17
10	C-7	Demolition Details		01DEC17
11	C-8	Site Plan		01DEC17
12	C-9	Pavement Sections 1		01DEC17
13	C-10	Grading Plan 1		01DEC17
14	C-11	Grading Plan 2		01DEC17
15	C-12	Joint Layout Plan 1		01DEC17

SHEET NUMBER	PLATE NUMBER	TITLE	REVISION NUMBER	DATE
16	C-13	Joint Layout Plan 2		01DEC17
17	C-14	Joint Details		01DEC17
18	C-15	Pavement Markings		01DEC17
		ELECTRICAL		
19	E-1	Electrical Site Plan and Legend		01DEC17
20	E-2	Grounding Plan I		01DEC17
21	E-3	Grounding Plan II		01DEC17
22	E-4	Details		01DEC17
		REPAIR RUNWAY		
1		Cover		01DEC
2		Construction Layout Plan		01DEC
3		Overall Safety/Phasing Plan		01DEC
4		Safety Phasing Plan, Phases 1 and 2		01DEC
5		Safety Phasing Plan, Phases 3 and 4		01DEC
6		Safety Details		01DEC
7		12 End Pavement Removal Plan		01DEC
8		30 End Pavement Removal Plan		01DEC
9		Taxiway A Reconstruction Plan (Optional Item #1) 1/		01DEC
10		Taxiway E Reconstruction Plan (Optional Item #2) 2/		01DEC
11		Plan & Profile, Station 15+00 to 26+00		01DEC
12		Plan & Profile, Station 26+00 to 37+00		01DEC
13		Plan & Profile, Station 37+00 to 48+00		01DEC
14		Plan & Profile, Station 48+00 to 59+00		01DEC

SHEET NUMBER	PLATE NUMBER	TITLE	REVISION NUMBER	DATE
15		Plan & Profile, Station 59+00 to 70+00		01DEC
16		Plan & Profile, Station 70+00 to 81+00		01DEC
17		Plan & Profile, Station 81+00 to 92+00		01DEC
18		Plan & Profile, Station 92+00 to 103+00		01DEC
19		Plan & Profile, Station 103+00 to 114+00		01DEC
20		Plan & Profile, Station 114+00 to 125+00		01DEC
21		Plan & Profile, Station 125+00 to 136+00		01DEC
22		Plan & Profile, Station 136+00 to 147+00		01DEC
23		Plan & Profile, Station 147+00 to 158+00		01DEC
24		12 End Pavement Jointing Plan		01DEC
25		30 End Pavement Jointing Plan		01DEC
26		Runway Cross Sections, Station 20+00 to 38+43		01DEC
27		Runway Cross Sections, Station 40+00 to 58+04		01DEC
28		Runway Cross Sections, Station 60+00 to 77+51		01DEC
29		Runway Cross Sections, Station 79+24 to 95+93		01DEC
30		Runway Cross Sections, Station 97+86 to 114+33		01DEC
31		Runway Cross Sections, Station 116+32 to 134+75		01DEC
32		Runway Cross Sections, Station 136+74 to 155+12		01DEC
33		Paving Details		01DEC
34		Polyethylene Panel and Runway Light		01DEC

SHEET NUMBER	PLATE NUMBER	TITLE	REVISION NUMBER	DATE
35		Sewer/Utility Crossing		01DEC
36		Pavement Marking Plan		01DEC
37		Pavement Marking Plan		01DEC
38		Pavement Marking and Grooving Details		01DEC
39		Runway Ice Detection System Plan		01DEC
40		Arrestor Details		01DEC

NOTES:

1/ Optional Item #1 shall be read as Optional Items 0014 and 0015.

2/ Optional Item #2 shall be read as Optional Items 0016 and 0017.

DRAWING REVISIONS BY NOTATION

Parking Apron Drawing Sheet 10, Plate C-7: Add "Note 3. Scrap Metal (tiedowns) may be turned in at the base recycle center without charge, however the scrap metal must be Clean (no concrete stuck to it), no wood, paper, etc."

Parking Apron Drawing Sheet 17, Plate C-14:

(a) Add to the general notes, "7. New PCC thickened edge shall be 1.25 x pavement thickness."

(b) Detail C /Thickened-Edge Slip Joint Between New Mobility Ramp and New Taxiway A: Add "New" to the callout, "Taxiway A". Change "Existing Thickened Edge" to "Thickened Edge".

Parking Apron Drawing Sheet 22, Plate E-4, C TIEDOWN DETAIL: Remove 80 mm Radius note and leader from Elevation View. Add the following note under Top View: "Concrete recess pocket shall have 80 mm radius along the longitudinal axis."

Runway Drawing Sheet 4. Phase 1 Work Tasks: Revise Note 4 to read "See note 5."//Phase 1 Notes: Add "Note 5. There are no utility repairs in Phase 1 or on either taxiway under options."

Runway Drawing Sheet 5, Phase 3 Work Tasks: Add "8. Repair water line and sewer line as shown."

Runway Drawing Sheet 8, 30 END PAVEMENT REMOVAL PLAN:

(a) Make the following correction to stations:
152+24.42/198 LT. Change to 173 LT.

152+24.42/223 LT. Change to 198 LT.
152+99.42/198 LT. Change to 173 LT.
152+99.42/223 LT. Change to 198 LT.

(b) Add "Note 7. The only runway edge lights more than 12 inches from the runway or taxiway structural PCC pavement are the infield lights on the 30 end of the runway. All 12 end runway edge and taxiway edge lights are flush against the PCC structural pavement. All outfield (WSW) runway edge lights on the 30 end are flush against the PCC structural pavement."

Runway Drawing Sheets 9 and 10: Add the following to Note 9, each sheet: **"**The contractor shall submit a joint plan for Taxiway Alpha and Taxiway Echo Optional work to the Contracting Officer for approval before construction of new slabs, including joint types and locations based on matching existing. The anticipated joint plan will include some doweled joints, some sawed contraction joints, and a limited number of thickened edge joints as identified during demolition."

Runway Drawing Sheet 32: Cross-Section 142+74 shall be PCC.

Runway Drawing Sheet 33, CRACK REPAIR DETAILS: Add "NOTE: All crack repair shall occur in areas to be milled and overlaid."

Runway Drawing Sheet 40.

(a) Revise Note 6 to read, "6. Contractor shall provide new Hilti HAS Super Rods, 28" in length. They will be cut to a shorter length, if necessary, during installation. There will be a total of 20 (twenty) each 1 1/8" x 28" HAS Super Rods and 4 (four) each 1 ¼" x 28" HAS Super Rods for this installation. Hilti HAS Super Rods are a requirement and no equal will be accepted. No anchor bolt adaptors will be used or allowed in this installation. Set bolts with Hilti Epoxy capsules per manufacturer's recommendations."

(b) Add to notes, "9. Roughen the inner wall surface of the 4" diameter, 8" deep core drilled holes prior to placing the 10,000 psi grout."

STANDARD DETAILS BOUND IN THE SPECIFICATIONS

DRAWING NUMBER	SHEET NUMBER	TITLE	DATE
SECTION 01501 - CONSTRUCTION FACILITIES AND TEMPORARY CONTROLS			
49s/40-05-15	1 & 2	U.S. Air Force Project Sign	84JUN20
	1	Hard Hat Sign	10SEP90

END OF SECTION

This page intentionally blank

02002/II

DESIGN AUTHENTICATION

Repair Aircraft Parking Apron/Repair Runway
Mt. Home AFB, Id.

Signatures affixed below indicate the drawings and specifications included in this solicitation were prepared, reviewed and certified in accordance with Department of Army Engineer Regulation ER 1110 345-100, DESIGN POLICY FOR MILITARY CONSTRUCTION.

David A. Mitchell, P.E.
Toothman-Orton Engineering Company
(Repair Runway)

Amy Brandt, P.E. COE
Project Manager

for Dean M. Schmidt
Chief, Tech. Eng. & Review Section, COE
Construction Branch

for Mark A. Ohlstrom, P.E., COE
Chief, Design Branch

for Rick L. Moshier, P.E., COE
Chief, Engineering & Construction Division

The Repair Aircraft Parking Apron portion was designed by the U.S. Army Corps of Engineers, Seattle District. The Repair Runway portion was designed by Toothman-Orton Engineering Co., Boise, Id, in association with CSHQA, a professional association, Boise, Id. The initials and/or signatures and registration designations of individuals appearing on these project documents are within the scope of their employment as required by ER 1110-1-8152, ENGINEERING AND DESIGN PROFESSIONAL REGISTRATION.

This page intentionally blank

GENERAL DECISION **ID020001** 03/08/2002 ID1

Date: March 8, 2002
General Decision Number **ID020001**

Superseded General Decision No. ID010001

State: Idaho

Construction Type:
HEAVY
HIGHWAY

County(ies):
STATEWIDE

HEAVY AND HIGHWAY CONSTRUCTION PROJECTS

Modification Number	Publication Date
0	03/01/2002
1	03/08/2002

COUNTY(ies):
STATEWIDE

CARP0001D 06/01/2001

	Rates	Fringes
AREA 1:		
CARPENTERS	22.81	5.70
PILEDRIVERS	23.91	5.70
MILLWRIGHTS	23.07	5.70
DIVERS	56.52	5.70
DIVERS TENDERS	26.90	5.70

CARP0808A 01/01/2002

	Rates	Fringes
AREA 2:		
ZONE 1:		
CARPENTERS	20.76	6.86
PILEDRIVERS	20.93	6.86
MILLWRIGHTS AND MACHINE ERECTORS	21.05	6.86
DIVERS	50.72	6.86
DIVERS TENDERS	20.66	6.86

Zone Differential (Add to Zone 1 rates):
Zone 2 - $1.00

---

* ELEC0073D 01/01/2002

	Rates	Fringes

KOOTENAI COUNTY

ELECTRICIANS	23.82	3%+9.58
CABLE SPLICERS	24.22	3%+9.58

ELEC0077A 02/01/2002

	Rates	Fringes
AREA 1:		
LINE CONSTRUCTION:		
CABLE SPLICERS	35.44	3.875%+7.20
LINEMEN, POLE SPRAYERS, HEAVY LINE EQUIPMENT MAN	31.96	3.875%+7.20
LINE EQUIPMENT MEN	27.91	3.875%+5.45
POWDERMEN, JACKHAMMERMEN	24.72	3.875%+5.45
GROUNDMEN	23.27	3.875%+5.45
TREE TRIMMER	22.46	3.875%+5.45

ELEC0291B 06/01/1999

	Rates	Fringes
ADAMS, ADA, BOISE, CANYON, ELMORE, GEM, OWYHEE, PAYETTE, VALLEY AND WASHINGTON COUNTIES		
ELECTRICIANS (including traffic signalization)	21.63	5.67+4.4%

ELEC0291C 03/01/1999

	Rates	Fringes
AREA 2:		
CABLE SPLICER	27.59	4.25%+5.20
LINEMAN	25.00	4.25%+5.20
LINE EQUIPMENT MECHANIC (RIGHT-OF-WAY)	21.17	4.25%+5.20
LINE EQUIPMENT OPERATOR	21.17	4.25%+5.20
GROUNDMAN	15.45	4.25%+4.87

---

* ENGI0370B 01/01/2002

	Rates	Fringes
AREA 2:(Anyone working on HAZMAT jobs working with supplied air shall receive $1.00 per hour above classification)		
THERE IS A HAZMAT CLASSIFICATION INCLUDED IN EACH GROUP		
POWER EQUIPMENT OPERATORS:		
ZONE 1:		
GROUP 1	20.99	5.97
GROUP 2	21.15	5.97
GROUP 3	21.52	5.97
GROUP 4	21.83	5.97

GROUP 5	22.00	5.97
GROUP 6	22.18	5.97
GROUP 7	22.54	5.97
GROUP 8	22.77	5.97
GROUP 9	23.00	5.97
GROUP 10	23.25	5.97

Zone Differential (Add to Zone 1 rate): Zone 2 - $1.50

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Brakeman; Crusher Plant Feeder (Mechanical); Deckhand; Grade Checker; Heater Tender; Land Plane; Pumpman

GROUP 2: Air Compressor; Assistant Refrigeration Plant Operator; Bell Boy; Bit Grinder Operator; Blower Operator (cement); Bolt Threader Machine Operator; Broom; Cement Hog; Concrete Mixer; Concrete Saw multiple cut; Discing - Harrowing or Mulching (regardless of motive power); Distributor Leverman;

Drill Steel Thereader Machine Operator; Fireman-all; Hoist-single drum; Hydraulic Monitor Operator-skid mounted; Oiler (single piece of equipment); Crusher Oiler; Pugmixer-Box Operator; Spray Curing Machine; Tractor-rubber tired farm type using attachments

GROUP 3: A-Frame Truck (hydra lift, Swedish Cranes, Ross Carrier, Hyster on construction jobs); Battery Tunnel Locomotive; Belt Finishing Machine; Cable Tenders (underground); Chip Spreader Machine (self-propelled); Hoist-2 or more durms or Tower Hoist; Hydralift-Fork lift & similar (when hoisting); Oilers (underground); Power Loader (bucket elevator conveyors); Rodman; Road Roller (regardless of motive power)

GROUP 4: Boring Machines (earth or rock); Quarrymaster-Joy-tractor mounted, Drills: Churn-Core-Calyx or Diamond; Front End & Overhead Loaders and similar machines-(up to and including 4 yds)(rubber-tired); Grout Pump; Hydra-Hammer; Locomotive Engineer; Longitudinal Float Machine; Mobilemixer; Spreader Machine; Tractor-rubber tired-using Backhoe, Transverse Finishing Machine; Trenching Machines; Waggoner Compactor and similar; Asphalt Spreaders

GROUP 5: Concrete Plant Operator; Concrete Road Paver (dual); Elevating Grader Operator; Euclid Elevating Loader; Generator Plant Operator-Mechanic (diesel electric); Post Hole Auger or Punch Operator; Power Shovels, Backhoes and Draglines (under 3/4 yd); Pumpcrete; Refrigeration Plant Operator(1000 tons and under; Road Roller(finishing high type pavement); Service Equipment Oiler; Skidder-rubber tired; Sub Grader; Multiple Station Beltline Operator; Screed Operator

GROUP 6: Asphalt Pavers-self propelled; Asphalt Plant Operator; Blade Operator (motor patrol); Concrete Slip Form Paver; Cranes - up to and including 50 ton; Crusher Plant Operator; Derrick Operator; Drilling Equipment (bit under 8 inches) - Robbins Reverse Circulation and similar; Front End and

Overhead Loaders and similar machines-over 4 yds to and including 7 yds; Koehring Scooper; Heavy Duty Mechanic or Welder; Mucking Machine (underground); Multi-batch Concrete Plant Operator; Piledriver Engineer; Power Shovels, Backhoes and Draglines (3/4 yd to and including 3 1/2 yds), Tractor-crawler type-including all attachments; Refrigeration Plant Operator (over 1,000 tons); Trimmer Machine Operator; Concrete Pump Boom Truck; All Scrapers up to and including 40 yards

GROUP 7: Cableway Operator; Continuous Excavator (Barber Greene WL-50); Cranes-over 50 tons; Dredges; Drilling Equipment (bit 8 inches and over)-Robbins Reverse Circulation & similar; Fine Grader-CMI or equivalent; Front End & Overhead Loaders & similar machines-(over 7 yards); Power Shovels & Draglines over 3 1/2 yards; Quad type Tractors with all attachements; all Scrapers, pulling wagons, belly dumps and attachments (over 40 yards to and including 60 yards); Multiple Scraper Units; Tower Crane Operator

GROUP 8: Scrapers - Euclid & similar, pulling wagons, belly

dumps and attachments, over 60 yards to and including 80 yards

GROUP 9: Scrapers - Euclid and similar, pulling wagons, belly dumps and attachements, over 80 yards to and including 100 yards

GROUP 10: Scrapers - Euclids and similar, pulling wagons, belly dumps and attachements, over 100 yards

BOOM PAY: All Cranes and Concrete Pump Boom Trucks

100 ft to 150 ft	$.15 over scale
150 ft to 200 ft	$.30 over scale
Over 200 ft	$.45 over scale

NOTE: In computing the length of the boom on Tower Cranes, they shall be measured from the base of the tower to the point of the boom.

ENGI0370D 06/01/2001

	Rates	Fringes
AREA 1: (Anyone working on HAZMAT jobs working with supplied air shall receive $1.00 per hour above classification)		
POWER EQUIPMENT OPERATORS:		
ZONE 1:		
GROUP 1A	20.94	6.02
GROUP 1	21.49	6.02
GROUP 2	21.81	6.02
GROUP 3	22.42	6.02
GROUP 4	22.58	6.02
GROUP 5	22.74	6.02
GROUP 6	23.02	6.02
GROUP 7	23.29	6.02
GROUP 8	24.39	6.02

Zone Differential (Add to Zone 1 rate): Zone 2- $2.00

BASE POINTS: Spokane, Moses Lake, Pasco, Washington; Lewiston, Idaho

Zone 1: Within 45 radius miles from the main post office
Zone 2: Outside 45 radius miles from the main post office

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1A: Boat Operator; Crush Feeder; Oiler; Steam Cleaner

GROUP 1: Bit Grinders; Bolt Threading Machine; Compressors (under 2000 CFM, gas, diesel, or electric power); Deck Hand; Drillers Helper (assist driller in making drill rod connections, service drill engine and air compressor, repair drill rig and drill tools, drive drill support truck to and one the job site, remove drill cuttings from around bore hole and inspect drill rig

while in operator); Fireman & Heat Tender; Grade Checker; Hydro-seeder, Mulcher, Nozzleman; Oiler Driver, & Cable Tender, Mucking Machine; Pumpman; Rollers, all types on subgrade, including seal and chip coatings (farm type, Case, John Deere & similar, or Compacting Vibrator), except when pulled by Dozer with operable blade; Welding Machine

GROUP 2: A-frame Truck (single drum); Assistant Refrigeration Plant (under 1000 ton); Assistant Plant Operator, Fireman or Pugmixer (asphalt); Bagley or Stationary Scraper; Belt Finishing Machine; Blower Operator (cement); Cement Hog; Compressor (2000 CFM or over, 2 or more, gas, diesel or electric power); Concrete Saw (multiple cut); Distributor Leverman; Ditch Witch or similar; Elevator Hoisting Materials; Dope Pots (power agitated); Fork Lift or Lumber Stacker, hydra-lift & similar; Gin Trucks (pipeline); Hoist, single drum; Loaders (bucket elevators and conveyors); Longitudinal Float; Mixer (portable-concrete); Pavement Breaker, Hydra-Hammer & similar; Power Broom; Railroad Ballast Regulation Operator (self-propelled); Railroad Power Tamper Operator (self-propelled); Railroad Tamper Jack Operator (self-propelled); Spray Curing Machine (concrete); Spreader Box (self-propelled); Straddle Buggy (Ross & similar on construction job only); Tractor (Farm type R/T with attachment, except Backhoe); Tugger Operator

GROUP 3: A-frame Truck (2 or more drums), Assistant Refrigeration Plant & Chiller Operator (over 1000 ton); Backfillers (Cleveland & similar); Batch Plant & Wet Mix Operator, single unit (concrete); Belt-Crete Conveyors with power pack or similar; Belt Loader (Kocal or similar); Bending Machine; Bob Cat; Boring Machine (earth); Boring Machine (rock under 8" bit)(Quarry Master, Joy or similar); Bump Cutter (Wayne, Saginau or similar); Canal Lining Machine (concrete); Chipper (without crane); Cleaning & Doping Machine (pipeline); Deck Engineer; Elevating Belt-type Loader (Euclid, Barber Green & similar); Elevating Grader-type Loader (Dumor, Adams or similar); Generator Plant Engineers (diesel or electric); Gunnite

Combination Mixer & Compressor; Locomotive Engineer; Mixermobile; Mucking Machine; Posthole Auger or Punch; Pump (grout or jet); Soil Stabilizer (P & H or similar); Spreader Machine; Tractor (to D-6 or equivalent) and Traxcavator; Traverse Finish Machine; Turnhead Operator

GROUP 4: Concrete Pumps (squeeze-crete, flow-crete, pump-crete, Whitman & similar); Curb Extruder (asphalt or concrete); Drills (churn, core, calyx or diamond)(operates drilling machine, drive or transport drill rig to and on job site and weld well casing); Equipment Serviceman, Greaser & Oiler; Hoist (2 or more drums or Tower Hoist); Loaders (overhead & front-end, under 4 yds. R/T); Refrigeration Plant Engineer (under 1000 ton); Rubber-tired Skidders (R/T with or without attachments); Surface Heater & Planer Machine; Trenching Machines (under 7 ft. depth capacity); Turnhead (with re-screening); Vacuum Drill (reverse circulation drill under 8" bit)

GROUP 5: Backhoe (under 45,000 gw); Backhoe & Hoe Ram (under 3/4 yd.); Carrydeck & Boom Truck (under 25 tons); Cranes (25 tons

& under), all attachments including clamshell, dragline; Derricks & Stifflegs (under 65 tons); Drilling Equipment (8" bit & over)(Robbins, reverse circulation & similar)(operates drilling machine, drive or transport drill rig to and on job site and weld well casing); Hoe Ram; Piledriving Engineers; Paving (dual drum); Railroad Track Liner Operator (self-propelled); Refrigeration Plant Engineer (1000 tons & over); Signalman (Whirleys, Highline Hammerheads or similar)

GROUP 6: Asphalt Plant Operator; Automatic Subgrader (Ditches & Trimmers) (Autograde, ABC, R.A. Hansen & similar on grade wire); Backhoes (45,000 gw and over to 110,000 gw); Backhoes & Hoe Ram (3/4 yd. to 3 yd.); Batch Plant (over 4 units); Batch & Wet Mix Operator (multiple units, 2 & incl. 4); Blade Operator (motor Patrol & Attachments, Athey & Huber); Boom Cats (side); Cableway Controller (dispatcher); Clamshell Operator (under 3 yds.); Compactor (self-propelled with blade); Concrete Pump Boom Truck; Concrete Slip Form Paver; Cranes (over 25 tons, including 45 tons), all attachments including clamshell, dragline; Crusher, Grizzle and Screening Plant Operator; Dozer, 834 R/T & similar; Draglines (under 3 yds.); Drill Doctor; H.D. Mechanic; H.D. Welder; Loader Operator (front-end & overhead, 4 yds. incl. 8 yds.); Multiple Dozer Units with single blade; Paving Machine (asphalt and concrete); Quad-Track or similar equipment; Rollerman (finishing asphalt pavement); Roto Mill (pavement grinder); Scrapers, all, Rubbert-tired; Screed Operator; Shovel (under 3 yds.); Tractors (D-6 & equilvalent & over); Trenching Machines (7 ft. depth & over); Tug Boat Operator; Vactor Guzzler, Super Sucker

GROUP 7: Backhoe (over 110,000 gw); Backhoes & Hoe Ram (3 yds. & over); Blade (finish & bluetop) Automatic, CMI, ABC, Finish Athey & Huber & similar when used as automatic; Cableway Operators; Conrete Cleaning/Decontamination Machine Operator; Cranes (over 45 tons to but not including 85 tons), all attachments including clamshell, dragline; Derricks & Stifflegs (65 tons & over);

Elevating Belt (Holland type); Heavy Equipment Robotics Operator; Loader (360 degrees revolving Koehring Scooper or similar); Loaders (overhead & front-end, over 8 yds. to 10 yds.); Rubber-tired Scrapers (multiple engine with three or more scrapers); Shovels (3 yds. & over); Ultra High Pressure Wateiet Cutting Tool System Operator (30,000 psi); Vacuum Blasting Machine Operator; Whirleys & Hammerheads, ALL

GROUP 8: Cranes (85 tons and over, and all climbing, overhead, rail and tower); Loaders (overhead and front-end, 10 yards and over); Helicopter Pilot

BOOM PAY: (All Cranes, including Tower)
180' to 250' $.30 over scale
Over 250' $.60 over scale

NOTE: In computing the length of the boom on Tower Cranes, they shall be measured from the base of the Tower to the point of the boom.

IRON0014A 07/01/2001

	Rates	Fringes
ADAMS (REMAINDER), BENEWAH, BONNER, CLEARWATER, IDAHO, KOOTENAI, LATAH, LEMHI (NW CORNER), NEZ PERCE, SHOSHONE, VALLEY (NW 1/3) AND WASHINGTON (NW 1/2) COUNTIES		
IRONWORKERS	24.52	11.35

IRON0732A 06/01/2001

	Rates	Fringes
ADA, ADAMS (E. CORNER), BANNOCK, BEAR LAKE, BINGHAM, BLAINE, BOISE, BUTTE, BONNEVILLE, CAMAS, CANYON, CARIBOU, CASSIA, CLARK, CUSTER, ELMORE, FRANKLIN, FREMONT, GEM GOODING, JEFFERSON, JEROME, LEMHI (REMAINDER), LINCOLN, MADISON, MINIDOKA, ONEIDA, OWYHEE, PAYETTE, POWER, TETON, TWIN FALLS, VALLEY (SE 2/3) AND WASHINGTON (SE 1/2) COUNTIES		
IRONWORKERS	20.13	9.21

LABO0155A 01/01/2002

	Rates	Fringes
AREA 2: (Anyone working on HAZMAT jobs working with supplied air shall receive $1.00 per hour above classification)		
THERE IS A HAZMAT CLASSIFICATION IN EACH GROUP		
LABORERS:		
ZONE 1:		
GROUP 1	18.38	6.90
GROUP 2	18.48	6.90
GROUP 3	18.58	6.90

GROUP 4	18.68	6.90
GROUP 5	18.73	6.90
GROUP 6	18.98	6.90
GROUP 7	19.23	6.90
GROUP 8	18.63	6.90
GROUP 9	18.78	6.90
GROUP 10	18.88	6.90

Zone Differential (Add to Zone 1 rate): Zone 2 - $1.00

LABORERS CLASSIFICATIONS

GROUP 1: General laborers; Sloper, cleaning and grading; Form stripper; Concrete crew; Concrete curing crew; Carpenter tender; Asphalt laborer; Hopper tender; Flagman (including Pilot car); Watchman; Heater Tender; Stake jumper; Choker setters; Spreader and weighman; Scouring concrete; Rip Rap Man (hand placed); Crusher tender; Cribing and shoring (in open ditches); Machinery and parts cleaner; Leverman, manual or mechanical; Demolition,

salvage; Landscaper; Tool roomman; Traffic Stripping Crew; Asbestos Abatement Laborers; Janitor (detail clean-up, such as but not limited to cleaning floors, ceilings, walls, windows, etc., prior to final acceptance by the owner)

GROUP 2: Chuck tender; Driller tender; Air tampers; Gunnite nozzleman tender; Pipewrapper; Tar pot tender; Concrete sawyer; Concrete Grinder; Signalman, handling cement; Dumpman; Steam nozzleman; Air and water nozzleman (Green Cutter, Concrete); Vibrator (less than 4"); Pumpcrete and grout pump crew; hydraulic Monitor; Hydro Blaster

GROUP 3: Pipelayer, including sewer, drainage, sprinkler systems and water lines; Free Air Caisson; Jackhammer; Paving Breaker; Chipping Gun Concrete; Powderman Tender; Asphalt Raker; Gasoline powered Tamper; Electric Ballast Tamper; Sand Blasting; Form Setter, airport paving; Gunman (Gunite); Manhole Setter; Hand guided machines, such as Roto Tillers, Trenchers, Post-Hole Diggers, Walking Garden Tractors, etc.; Cutting Torch

GROUP 4: Hod Carrier; Mason Tender; Plaster Tender; Mason Tender (concrete); Terrazzo-Tile Tender

GROUP 5: Highscaler; Wagon Drill; Grade Checker; Gunnite Nozzleman; Timber faller and bucker

GROUP 6: Diamond Drills; Drillers on Drills with Manufacturers rating 3" or over

GROUP 7: Powderman

UNDERGROUND WORK

GROUP 8: Reboundman; Chucktender; Nipper; Dumpman; Vibrator (less than 4"); Brakeman; Mucker; Bullgang

GROUP 9: Form Setter and Mover

GROUP 10: Miners; Machineman; Timbermen; Steelmen; Drill Doctors; Spaders and Tuggers; Spilling and/or Caisson Workers; Vibrator (over 4")

LABO0238B 06/01/2001

	Rates	Fringes
AREA 1:		
LABORERS:		
ZONE 1:		
GROUP 1	17.66	5.00
GROUP 2	19.76	5.00
GROUP 3	20.03	5.00
GROUP 4	20.30	5.00
GROUP 5	20.58	5.00
GROUP 6	21.95	5.00

Zone Differential (Add to Zone 1 rates): Zone 2 - $2.00

BASE POINTS: Spokane, Moses Lake, Pasco, Lewiston

Zone 1: 0-45 radius miles from the main post office.
Zone 2: 45 radius miles and over from the main post office

LABORERS CLASSIFICATIONS

GROUP 1: Flagman; Landscape Laborer, Scaleman; Traffic Control Maintenance Laborer (to include erection and maintenance of barricades, signs, and relief of flagperson); Window Washer; Washer/Cleaner(Detail cleanup, such as but notlimited to cleaning floors, ceilings, walls, windows, etc. prior to final acceptance by the owner)

GROUP 2: Asbestos Abatement Worker; Brush Hog Feeder; Carpenter Tender; Cement Handler; Cleanup laborer; Concrete Crewman (to include stripping of forms, hand operating jacks on slip form construction, application of concrete curing compounds, pumpcrete machine, signaling, handling the nozzle of squeezcrete or similar machine, 6 inches and smaller); Concrete Signalman; Crusher Feeder; Demolition (to include clean-up, burning, loading, wrecking and salvage of all material); Dumpman; Fence Erector; Form Cleaning Machine Feeder, Stacker; General Laborer; Grout Machine Header Tender; Guard Rail (to include guard rails, guide and reference posts, sign posts, and right-of-way markers); Hazardous Waste Worker; Miner, Class "A" (to include bull gang, concrete crewman, dumpman and pumpcrete crewman, including distributing pipe, assembly and dismantle, and nipper); Nipper; Riprap Man; Sandblast Tailhoseman; Scaffold Erector (wood or steel); Stake Jumper; Structural Mover (to include separating foundation, preparation, cribbing, shoring, jacking and unloading of structures); Tailhoseman (water nozzle); Timber Bucker and Faller (by hand); Track Laborer (RR); Truck Loader; Well-Point Man

GROUP 3: Asphalt Roller, walking; Cement Finisher Tender; Concrete Saw, walking; Demolition Torch; Dope Pot Firemen, non-mechanical; Form Setter, paving; Grader Checker Using Level; Jackhammer Operator Miner, Class B (to include brakeman, finisher, vibrator, form setter); Nozzleman (to include squeeze and flo-crete nozzle); Nozzleman, water, air or steam; Pavement Breaker (under 90 lbs.); Pipelayer, corrugated metal culvert; Pipelayer, multi-plate; Pot Tender; Power Buggy Operator; Power Tool Operator, gas, electric, pneumatic; Railroad Equipment, power driven, except dual mobile power spiker or puller; Railroad Power Spiker or Puller, dual mobile; Rodder and Spreader; Tamper (to include operation of Barco, Essex and similar tampers); Trencher, Shawnee; Tugger Operator; Wagon Drills; Water Pipe Liner; Wheelbarrow, power driven

GROUP 4: Air and Hydraulic Track Drill; Asphalt Raker; Brush Machine (to include, horizontal construction joint clean-up brush machine, power propelled); Caisson Worker, free air; Chain Saw Operator and Faller; Concrete Stack (to include laborers when working on free standing concrete stacks for smoke or fume

control above 40 feet high); Gunnite (to include operation of machine and nozzle); High Scaler; Miner, Class C (to include miner, nozzleman for concrete, laser beamoperator and operator and rigger on tunnels); Monitor Operator, air track or similar mounting; Mortar Mixer; Nozzleman (to include jet blasting nozzleman, over 1,200 lbs., jet blast machine power-propelled, sandblast nozzle); Pavement Breaker, 90 lbs. and over Pipelayer (to include working topman, caulker, collerman, jointer, mortarman, rigger, jacker, shorer, valve or meter installer, tamper); Pipewrapper; Plasterer Tenders; Vibrators, all

GROUP 5 - Drills with dual masts; Hazardous Waste Worker, Level A; Miner Class "D" (to include raise and shaft miner, laser beam operator on raises and shafts)

GROUP 6 - Powderman

LABO0238F 06/01/2001

	Rates	Fringes
AREA 1		
HOD CARRIERS	21.35	5.00

PAIN0005E 07/01/2001

	Rates	Fringes
KOOTEANI COUNTY		
PAINTERS*:		
Brush, Roller, Paperhanger, striping, Steam Cleaningand Spray	19.17	4.24

*$.70 shall be paid over and above the basic wage rates listed for work on swing stages and high work over 30 feet.

PLAS0072A 06/01/1999

	Rates	Fringes
AREA 1:		
ZONE 1:		
CEMENT MASONS	21.57	5.24

Zone Differential (Add to Zone 1 rate): Zone 2 - $2.00

BASE POINTS: Spokane, Moses Lake, Pasco, and Lewiston

Zone 1: 0-45 radius miles from the main post office
Zone 2: Over 45 radius miles from the main post office

PLAS0219B 01/01/2002

	Rates	Fringes
AREA 2:		
CEMENT MASONS:		
ZONE 1		
GROUP 1	15.36	11.70
GROUP 2	15.56	11.70

CEMENT MASONS CLASSIFICATIONS

GROUP 1: - JOURNEYMAN CEMENT MASON (including but not limited to hand chipping and patching, all types grouting and pointing of all concrete constructions, screed setting including screed pins, dry packing of all concrete including Embeco, plugging and filling all voids, etc., concrete construction, waterproofing of concrete with Thoroseal or similar materials.

GROUP 2: - CEMENT MASON (magnesite terazzo and mastic composition, two component epoxies, Clary and similar type screed operator, sandblasting of concrete for architectural finished only, Power chipping and bushhammer, all color concrete work, Power Trowel Operator, Power Grinder Operator, Gunnite and Composition Floor Layer).

Zone Differential (Add to Zone 1 rates): - $1.00

PLUM0044D 06/01/2001

	Rates	Fringes
NEZ PERCE COUNTY		
PLUMBERS & PIPEFITTERS	29.61	9.14
BONNER, BOUNDARY, CLEARWATER, IDAHO(NORTHERN PART), KOOTENAI, LATH, LEWIS AND SHOSHONE COUNTIES		
PLUMBERS AND PIPEFITTERS	29.61	8.54

PLUM0296A 07/01/2001

	Rates	Fringes
AREA 2:		
PLUMBERS AND PIPEFITTERS	23.54	7.77

---

* TEAM0483A 01/01/2002

	Rates	Fringes
AREA 2: (Anyone working on HAZMAT jobs working with supplied air shall receive $1.00 per hour above classification)		
THERE IS A HAZMAT CLASSIFICATION INCLUDED IN EACH GROUP		
TRUCK DRIVERS:		
ZONE 1		
GROUP 1	18.72	8.03
GROUP 2	19.09	8.03
GROUP 3	19.32	8.03
GROUP 4	19.50	8.03
GROUP 5		
CLASS A	19.32	8.03
B	19.50	8.03
C	19.73	8.03
D	20.24	8.03
E	20.47	8.03
F	20.91	8.03

Zone Differential (Add to Zone 1 Rate):
Zone 2 - $1.00

TRUCK DRIVERS CLASSIFICATIONS

GROUP 1: Leverman Loading at Bunkers; Pilot Car or Escort Driver Flat Bed-2 Axle and Pickup Hauling material; Water Truck (1,000 gallons and under); Ambulance Driver; Flat Bed-3 Axle; Fuel Truck (1,000 gallons and under); Greaser; Tireman; Serviceman; Buggymobile; Manhaul (Shuttle Truck or Bus)

GROUP 2: Slurry or Concrete Pumping Truck; Flat Bed using Power Takeoff; Semi Trailer-Low Boy (up to 96,000 lbs. GVW); Bulk Cement Tanker (up to 96,000 lbs. GVW); Fork Lift (Bull Lift, Hydro Lift), Ross Hyster and similar Straddle equipment; "A" Frame Truck (Swedish Crane, Iowa 3,000 Hydro Lift); Transit Mix Truck (0-10 yds); Warehouseman Loading and Unloading

GROUP 3: Water Tank Truck; Fuel Truck (over 1,000 gallons); Transit Mix Trucks (10 yards & over), Dumptors; Distributor or Spreader Truck; Field Tireman-Serviceman; Snow Plow (Truck Mounted); Warehouseman; Counterman, Shipping Receiving, Cardex.

GROUP 4: Low Boy (96,000 lbs. GVW & over); Bulk Cement Tanker

(96,000 lbs. GVW & over); Transit Mix Trucks (over 10 yards); Turnarocker & similar equipment; Warehouseman General

GROUP 5:

CLASS: A - Truck - Side, end and bottom dump, 0-16 yards, inclusive.
B - Truck - Side, end and bottom dump, 16-30 yards, inclusive.
C - Truck - Side, end and bottom dump, 30-50 yards, inclusive, and Truck Mechanic.
D - Truck - Side, end and bottom dump, 50-75 yards, inclusive.
E - Truck - Side, end and bottom dump, 75-100 yards inclusive.
F - Truck - Side, end and bottom dump, over 100 yards.

TEAM0690A 06/01/2000

	Rates	Fringes
AREA 1: (ANYONE WORKING ON HAZMAT JOBS SEE FOOTNOTE A BELOW)		
TRUCK DRIVERS:		
ZONE 1:		
GROUP 1	17.73	7.50
GROUP 2	20.00	7.50
GROUP 3	20.50	7.50
GROUP 4	20.83	7.50
GROUP 5	20.94	7.50
GROUP 6	21.11	7.50
GROUP 7	21.64	7.50
GROUP 8	21.97	7.50

Zone Differential (Add to Zone 1 rate): Zone 2 - $2.00)

BASE POINTS: Spokane, Moses Lake, Pasco, Lewiston

Zone 1: 0-45 radius miles from the main post office
Zone 2: 45 radius miles and over from the main post office

TRUCK DRIVERS CLASSIFICATIONS

GROUP 1: Escort Driver or Pilot Car; Employee Haul; Power Boat Hauling Employees or Material

GROUP 2: Fish Truck; Flat Bed Truck; Fork Lift (3000 lbs. and under); Leverperson (loading trucks at bunkers); Trailer Mounted Hydro Seeder and Mulcher; Seeder & Mulcher; Stationary Fuel Operator; Tractor (small, rubber-tired, pulling trailer or similar equipment)

GROUP 3: Auto Crane (2000 lbs. capacity); Buggy Mobile &

Similar; Bulk Cement Tanks & Spreader; Dumptor (6 yds. & under); Flat Bed Truck with Hydraullic System; Fork Lift (3001-16,000 lbs.); Fuel Truck Driver; Steamcleaner & Washer; Power Operated Sweeper; Rubber-tired Tunnel Jumbo; Scissors Truck; Slurry Truck Driver; Straddle Carrier (Ross, Hyster, & similar); Tireperson; Transit Mixers & Truck Hauling Concrete (3 yd. to & including 6 yds.); Trucks, side, end, bottom & articulated end dump (3 yards to and including 6 yards); Warehouseperson (to include shipping & receiving); Wrecker & Tow Truck

GROUP 4: A-Frame; Burner, Cutter, & Welder; Service Greaser; Trucks, side, end, bottom & articulated end dump (over 6 yds. to & including 12 yds.); Truck Mounted Hydro Seeder; Warehouseperson; Water Tank Truck (0-8000 gallons)

GROUP 5: Dumptor (over 6 yds.); Lowboy (50 tons & under); Self-loading Roll Off; Semi-Truck & Trailer; Tractor with Steer Trailer; Transit Mixers and Trucks Hauling Concrete (over 6 yds. to and including 10 yds.); Trucks, side, end, bottom & articulated end dump (over 12 yds. to & including 20 yds.);

Truck-Mounted Crane (with load bearing surface either mounted or pulled), up to 14 ton; Vacuum truck (super sucker, guzzler, etc.); Water Tank Truck (8,001-14,000 gallons)

GROUP 6: Flaherty Spreader Box Driver; Flowboys; Fork Lift (over 16,000 lbs.); Dumps (Semi-end); Lowboy (over 50 tons); Mechanic (Field); Transfer Truck & Trailer; Transit Mixers & Trucks Hauling Concrete (over 10 yds. to & including 20 yds.); Trucks, side, end, bottom & articulated end dump (over 20 yds. to & including 40 yds.); Truck and Pup; Tournarocker, DW's & similar, with 2 or more 4 wheel-power tractor with trailer, gallonage or yardage scale, whichever is greater; Water Tank Truck (8001-14,000 gallons)

GROUP 7: Oil Distributor Driver; Stringer Truck (cable operated trailer); Transit Mixers & Trucks Hauling Concrete (over 20 yds.); Truck, side, end, bottom & articulated end dump(over 40 yds. to & including 100 yds.); Truck mounted Crane (with load bearing surface either mounted or pulled (16 through 25 tons)

GROUP 8: Prime Movers & Stinger Truck; Trucks, side, end, bottom and articulated end dump (over 100 yds.); Helicopter Pilot Hauling Employees or Materials

FOOTNOTE A - Anyone working on a HAZMAT job, where HAZMAT certification is required, shall be compensated as a premium, in additon to the classification working in as follows:

LEVEL C-D: - $.50 PER HOUR - This is the lowest level of protection. This level may use an air purifying respirator or additional protective clothing.
LEVEL A-B: - $1.00 PER HOUR - Uses supplied air in conjunction with a chemical spash suit or fully encapsulated suit with self-contained breathing apparatus.

NOTE: Trucks Pulling Equipment Trailers: shall receive

$.15/hour over applicable truck rate

ZONE DEFINITIONS
AREA 2

(If a project is located in more than one zone the lower zone rate shall apply)

Zone 1: That area within the State of Idaho located within 30 miles on either side of I-84 from the Oregon-Idaho State Line on the West to the Intersection of I-84 and I-86 in Cassia County, then following I-86 to Pocatello, then following I-15 to Idaho Falls, then following State Highway #20 - 10 miles north to the intersection with Moody Road then following I-15 south from the city of Pocatello to a point 10 miles South of the Southern Boundary of Bannock County extended to the West.

Zone 2: The remaining area of that portion of the State of Idaho south of Parallel 46 (the Washington-Oregon State Line extended eastward to Montana) that is not included in Zone 1 as described

above.

AREA DEFINITIONS
(APPLIES TO ALL CRAFTS)

AREA 1:
Benewah, Bonner, Boundary, Clearwater, Idaho (North of the 46th Parallel), Kootenai, Latah, Lewis, Nez Perce, and Shoshone Counties.

AREA 2:
Ada, Adams, Bannock, Bear Lake, Bingham, Blaine, Boise, Butte, Bonneville, Camas, Canyon, Caribou, Cassia, Clark, Custer, Elmore, Franklin, Fremont, Gem, Gooding, Idaho (South of the 46th Parallel), Jefferson, Jerome, Lemhi, Lincoln, Madison, Minidoka, Oneida, Owyhee, Payette, Power, Teton, Twin Falls, Valley, and Washington Counties.

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.
==========

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29 CFR 5.5(a)(1)(v)).

In the listing above, the "SU" designation means that rates listed under that identifier do not reflect collectively bargained wage and fringe benefit rates. Other designations indicate unions whose rates have been determined to be prevailing.

WAGE DETERMINATION APPEALS PROCESS

1.) Has there been an initial decision in the matter? This can be:

* an existing published wage determination
* a survey underlying a wage determination
* a Wage and Hour Division letter setting forth a position on a wage determination matter
* a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.)

and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations
Wage and Hour Division
U. S. Department of Labor
200 Constitution Avenue, N. W.
Washington, D. C. 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator
U.S. Department of Labor
200 Constitution Avenue, N. W.
Washington, D. C. 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board
U. S. Department of Labor
200 Constitution Avenue, N. W.
Washington, D. C. 20210

4.) All decisions by the Administrative Review Board are final.

END OF GENERAL DECISION

TABLE OF CONTENTS

TECHNICAL SPECIFICATIONS

Section No. Section Title

DIVISION 1 - GENERAL REQUIREMENTS

Repair Aircraft Parking Apron/Repair Runway (AR)

01001 AR Supplementary Requirements
01005 AR Site Specific Supplementary Requirements
01025 AR Measurement and Payment
01035 AR Modification Procedures
01061 AR Environmental Protection
01320 AR Project Schedule
01330 AR Submittal Procedures
01451 AR Contractor Quality Control
01501 AR Construction Facilities and Temporary Controls
01702 AR As Built Records and Drawings
01703 AR Warranty of Construction
01704 AR FORM 1354 CHECKLIST

Repair Aircraft Parking Apron (A)

01415 A Metric Measurements
01450 A Chemical Data Quality Control

Repair Runway (R)

01010 R General Requirements
01051 R Contractor Furnished Construction Surveying and Staking
01110 R Airfield Project Safety Procedures
01356 R Storm Water Pollution Prevention Measures

DIVISION 2 - SITEWORK

Repair Aircraft Parking Apron (A)

02111 A Excavation and Handling of Contaminated Material
02220 A Demolition
02300 A Earthwork
02316 A Excavation, Trenching, and Backfilling for Utilities Systems
02390 A Tiedown Points for Aircraft
02721 A Rigid Base Course
02722 A Aggregate Base Course for Flexible Pavement
02741 A Hot-Mix Asphalt (HMA) For Roads
02748 A Bituminous Tack and Prime Coats
02753 A Concrete Pavement for Airfields
02760 A Field Molded Sealants for Sealing Joints in Rigid Pavements
02762 A Compression Joint Seals for Concrete Pavements
02763 A Pavement Markings
02964 A Cold Milling of Bituminous Pavements

Section
No. Section Title

Repair Runway (R)

02220 R Demolition
02300 R Earthwork
02316 R Excavation, Trenching, and Backfilling for Utilities Systems
02510 R Water Distribution
02531 R Sanitary Sewers
02722 R Graded-Crushed Aggregate Base Course
02748 R Bituminous Tack and Prime Coats
02749 R Hot Mix Asphalt (HMA) for Airfields
02753 R Concrete Pavement for Airfields and Other Heavy-Duty Pavements
02760 R Field Molded Sealants for Sealing Joints in Rigid Pavement
02762 R Compression Joint Seals for Concrete Pavements
02763 R Pavement Markings
02900 R Landscape Work
02964 R Cold Milling of Bituminous Pavement
02975 R Sealing of Cracks in Bituminous Pavements
02981 R Grooving for Airfield Pavements
02999 R Installation of Ultra-High-Molecular Weight Polyethylene (UHMW) Panels Under Aircraft Arresting System Cables

DIVISION 16 - ELECTRICAL

Repair Aircraft Parking Apron (A)

16300 A Electrical Work, Underground

Repair Runway (R)

16302 R Underground Transmission and Distribution
16522 R Airfield Lighting
16900 R Installation of Runway Ice Detection System Upgrade

NOTE: AR = Repair Aircraft Parking Apron/Repair Runway
A = Repair Aircraft Parking Apron
R = Repair Runway

THE FOLLOWING TECHNICAL SPECIFICATIONS APPLY TO BOTH REPAIR AIRCRAFT PARKING AND REPAIR RUNWAY:

Section No.	Section Title
	DIVISION 1 - GENERAL REQUIREMENTS
01001 AR	Supplementary Requirements
01005 AR	Site Specific Supplementary Requirements
01025 AR	Measurement and Payment
01035 AR	Modification Procedures
01061 AR	Environmental Protection
01320 AR	Project Schedule
01330 AR	Submittal Procedures
01451 AR	Contractor Quality Control
01501 AR	Construction Facilities and Temporary Controls
01702 AR	As Built Records and Drawings
01703 AR	Warranty of Construction
01704 AR	FORM 1354 CHECKLIST

This page was intentionally left blank for duplex printing.

SECTION 01001 (AR)

SUPPLEMENTARY REQUIREMENTS

PART 1 GENERAL

1.1 DEFINITIONS

The references listed below are to be defined as indicated wherever they may be used in the TECHNICAL SPECIFICATIONS.

"SUPPLEMENTARY REQUIREMENTS " shall be read to pertain to any of the sections of the DIVISION 1 as required by the content of the section or paragraph containing the reference.

1.2 CONSTRUCTION SCHEDULING

The instructions for preparation and submittal of the Contractor-prepared Network Analysis System are found in SECTION 01320, PROJECT SCHEDULE.

1.3 CORRESPONDENCE

1.3.1 All correspondence shall be addressed to the Contracting Officer, shall be serially numbered commencing with Number 1, with no numbers missing or duplicated and shall be forwarded in quintuplicate, as directed by the authorized representative of the Contracting Officer, and shall include an additional copy forwarded to a separate designated location. All copies provided shall be legible. Enclosures attached or transmitted with the correspondence shall also be furnished with the original and each copy. Each serial letter shall make reference to the contract name, contract number and shall have only one subject.

1.3.2 For submission of Contractor payment requests, See Section 01025, PAYMENT.

1.4 CONTRACTOR'S FILES

Contractor shall maintain "Approved (Action Code "A") and "Approved Except as Noted (Action Code "B") shop drawing files in fabrication shops and at project sites for government use.

1.5 IDENTIFICATION OF EMPLOYEES AND MILITARY REGULATIONS:

(a) The Contractor shall be responsible for compliance with all regulations and orders of the Commanding Officer of the Military Installation, respecting identification of employees, movements on installation, parking, truck entry, and all other military regulations which may affect the work.

(b) The work under this Contract is to be performed at an operating Military Installation with consequent restrictions on entry and movement of nonmilitary personnel and equipment.

(c) Temporary ID's issued by Base Security will be required for construction personnel working on base. The Contractor shall provide a list of employees with driver's license and social security numbers prior to construction. Base Operations will brief all drivers on flightline

driving procedures and will issue Flight Line Vehicle Passes for all vehicles required on the airfield.

(d) Contractor's workmen shall have on either a uniform with the firm name and the workman's last name or shall have a badge displayed and attached securely to other clothing, with both the firm name and the workman's photograph and full name. Mt. Home AFB temporary ID's will be visibly worn/displayed at all times.

(e) All personnel while on the installation may be subject to search.

1.5.1 See Section 01005 (AR) SITE SPECIFIC SUPPLEMENTARY REQUIREMENTS, paragraph 1 for base access requirements.

1.6 PROJECT PHOTOGRAPHS

1.6.1 General

The Contractor shall furnish photographs (35 mm color slides) depicting construction as specified herein. Each slide shall be individually labeled showing date taken, project location, contract title and number, and a brief description of what each slide depicts. Two copies of each slide shall be furnished to the Contracting Officer by the time specified. Slides shall be submitted in 216 mm by 279 mm (8 1/2 by 11 inch) clear plastic slide holders. Duplicate slides shall be collated into separate folders.

1.6.2 Progress Photographs

Construction progress photographs shall be taken between the 1st and 15th of each month and delivered to the Contracting Officer with the payment request for the month taken. Photographs shall be 35 mm color slides, except one copy shall be made in digital format. Photographs shall be taken from 10 positions. Location of positions shall be coordinated with or may be selected by the Contracting Officer. They shall show, inasmuch as practicable, work accomplished during the previous month. Photographic quality and composition of slides shall be such that they can be used for briefings and/or to illustrate articles on the construction progress of the project.

1.6.3 Completion Photographs

Construction completion photographs shall be taken upon completion of construction and delivered to the Contracting Officer not later than 15 days prior to project completion. Photographs shall be 35 mm color slides, except one copy shall be made in digital format. It is the intention of the Government to obtain pictures whose color, clarity, and composition are such that they can be used for briefings and/or to illustrate articles on the completed project. Slides shall be taken from 10 positions. Location of positions shall be coordinated with or may be selected by the Contracting Officer. Pictures shall show the completed project to the best advantage, and shall include overall site photos as well as photos of major features.

1.7 SPECIAL SAFETY REQUIREMENTS:

All construction activities shall be conducted in strict compliance with the Corps of Engineers Safety and Health Requirements Manual EM 385-1-1, and Occupational Safety and Health Administration regulations, as applicable. The manual is available on line at: http://www.usace.army.mil/inet/usace-docs/eng-manuals/em385-1-1/toc.htm

1.7.1 In addition to Safety and Health Requirements Manual EM 385-1-1, and all applicable OSHA standards, the Contractor shall comply with the requirements listed below. Paragraph numbers refer to EM 385-1-1 or are added thereto.

(a) Paragraph 01.A.12: Add new paragraph: Safety Engineer (1985 JAN OCE) (DAM 52.236/103):

(1) The Contractor shall employ at the project site to cover all hours of work at least one Safety and Occupational Health person to manage the Contractor's accident program. Duties which are not germane to the safety program shall not be assigned to the Safety and Health person(s). The principal safety person shall report to and work directly for the Contractor's on-site top manager, higher level official, or corporate safety office. The Safety and Health person(s) shall have the authority to take immediate steps to correct unsafe or unhealthful conditions. The presence of a Safety and Health person will not abrogate safety responsibilities of other personnel.

(2) Qualifications for Safety and Health person(s).

(A) Shall have a degree in engineering or safety in at least a four-year program from an accredited school; or

(B) Shall have legal registration as a Professional Engineer or a Certified Safety Professional and, in addition, shall have been engaged in safety and occupational health for at least one (1) year of experience, no time being credited to this one (1) year unless at least fifty (50) percent of the time each year was devoted to safety and occupational health; or

(C) Shall have a degree other than that specified in (A) above and, in addition, shall have been engaged in safety and occupational health for at least three (3) years' no time being credited to these three (3) years unless fifty (50) percent of the time each year was devoted to safety and occupational health; or

(D) In lieu of a degree, shall have been engaged in safety and occupational health for at least five (5) years, no time being credited to these (5) years unless at least fifty (50) percent of the time each year was devoted to safety and occupational health;

(E) First aid work is not a creditable experience.

(3) The name and qualifications of the nominated safety person(s) shall be furnished to the Contracting Officer for acceptability and a functional description of duties shall be provided prior to the pre-work conference.

(a) Paragraph 01.A.12: Add new paragraph: Safety Personnel. The Contractor shall designate a person on his staff to manage the Contractor's safety and accident prevention

program. This person will provide a point of contact for the Contracting Officer on matters of job safety, and shall be responsible for ensuring the health and safety of on site personnel.

(b) Paragraph 01.D.02, revise as follows:

(1) Replace paragraph 01.D.02c with the following:
"c. Property damage in excess of $2,000.00

(2) Add new paragraph d as follows:
"An injury resulting in a lost workday, not including the day of injury."

1.8 TIME EXTENSIONS FOR UNUSUALLY SEVERE WEATHER (ER 415-1-15 31 OCT 89)

This Paragraph specifies the procedure for the determination of time extensions for unusually severe weather in accordance with the CONTRACT CLAUSE entitled "Default (Fixed Price Construction)". In order for the Contracting Officer to award a time extension under this clause, the following conditions must be satisfied:

1.8.1 The weather experienced at the project site during the contract period must be found to be unusually severe, that is, more severe than the adverse weather anticipated for the project location during any given month.

1.8.2 The unusually severe weather must actually cause a delay to the completion of the project. The delay must be beyond the control and without the fault or negligence of the contractor.

1.8.3 The following schedule of monthly anticipated adverse weather delays is based on National Oceanic and Atmospheric Administration (NOAA) or similar data for the project location and will constitute the base line for monthly weather time evaluations. The contractor's progress schedule must reflect these anticipated adverse weather delays in all weather dependent activities.

MONTHLY ANTICIPATED ADVERSE WEATHER DELAY
WORK DAYS BASED ON (5) DAY WORK WEEK

JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
16	11	8	3	3	2	0	1	1	3	9	14

1.8.4 Upon acknowledgment of the notice to proceed (NTP) and continuing throughout the contract, the contractor will record on the daily QCQ report, the occurrence of adverse weather and resultant impact to normally scheduled work. Actual adverse weather delays must prevent work on critical activities for 50 percent or more of the contractor's scheduled work day.

1.8.5 The number of actual adverse weather delay days shall include days impacted by actual adverse weather (even if adverse weather occurred in previous month), be calculated chronologically from the first to the last day of each month, and be recorded as full days. If the number of actual adverse weather delay days exceeds the number of days anticipated in paragraph 1.15.3, above, the Contracting Officer will convert any qualifying delays to calendar days, giving full consideration for equivalent fair weather work days, and issue a modification in accordance with the contract clause entitled " Default (Fixed Price Construction)".

1.9 COMPLIANCE WITH DAVIS-BACON ACT

1.9.1 Contractor POC

Within 14 days after award of the contract, the Contractor shall designate a point of contact (POC) within their organization who will be responsible for the Davis-Bacon Act Labor Program for the Contractor and all subcontractors under this contract as required by the Contract Clauses and FAR 52.222.

1.9.2 Responsibilities

The designated Contractor POC shall be responsible for Davis-Bacon Act Labor Program activities including, but not limited to:

Documentation and record keeping
Submittal and accuracy of certified payrolls
Submittal of required labor forms including requests for additional classifications and rates, Statements and Acknowledgement, etc.
Posting of the wage determination, approved additional classifications and rates, labor and EEO posters
Coordination with the Contracting Officer's Labor Program POC

Prior to submittal to the Government, payrolls shall be reviewed for compliance to all applicable labor standards, to include, but not be limited to the following items: correct wage rates, correct overtime classification and pay, misclassification of workers for work actually performed, apprentice to journeyman ratios, and registration of apprentice. Corrective actions shall be taken as necessary to ensure Contractor compliance with applicable contract and FAR clauses.

1.9.3 Certification

The Contractor POC shall provide a signed certification stating the following: “I certify that the submitted items being forwarded have been reviewed in detail and are correct and in strict conformance with the Labor Standards of the contract except as otherwise stated.”

PARTS 2 AND 3 NOT USED

END OF SECTION

This page intentionally blank

SECTION 01005 (AR)

SITE SPECIFIC
SUPPLEMENTARY REQUIREMENTS

1. CONDUCT OF WORK

1.1 COORDINATION AND ACCESS TO SITE

1.1.1 Coordination with using agencies shall be made through the Contracting Officer to assist the Contractor in completing the work with a minimum of interference and inconvenience.

1.1.2 All Contractor-owned and privately-owned vehicles require an access pass/vehicle decal. This pass is obtained by showing proof of insurance; the vehicle registration; driver's license valid in the United States; and a letter with original signature of prime Contractor or his superintendent stating the contract name and number, the contract period for which the pass is required, and the employee's name. See Paragraph IDENTIFICATION OF EMPLOYEES AND MILITARY REGULATIONS in SECTION 01001 (AR) for specific requirements.

1.1.2.1 Employee Parking

Contractor employees shall park privately owned vehicles in an area designated by the Contracting Officer. This area will be within reasonable walking distance of the construction site. Contractor employee parking shall not interfere with existing and established parking requirements of the military installation.

1.1.3 Base Access

The Contractor shall use only the Grandview road entrance for access to the base for personnel, materials and equipment, except as specified below. The entrance can be used six (6) days a week, Monday through Saturday, 0600 hrs to 1800 hrs. Requests for variations must be made through the COR and handled on a case by case basis. Privately owned vehicles (POV) may use the main gate after the Grandview gate is closed. Limited construction/delivery vehicles may use the main gate with prior approval coordinated through the COR. The main gate is limited to 14' wide (max) vehicles. Carpooling POVs onto base is encouraged.

1.1.3.1 Contractor shall adequately maintain the Grandview access road and provide dust control. At the Contractor's option, milled AC may be layed (only) on the portion of the access road within the fence line (Government property). Additional treatment and/or water may still be needed for dust control.

1.1.3.2 Other Contractors will also be using Grandview road during this contract.

1.1.3.3 The Contractor shall provide a 100 sq ft tent shelter at the Grandview road entrance with wood floor and portable sanitary facility for use of the base security inspectors. Contractor shall maintain these facilities and remove them at the end of the contract.

1.1.4 Base Access Security Procedures

The following security procedures will be used at all entrances to the base:

1.1.4.1 Contractor access procedures: When a Contractor requires initial access to the base, a Government functional representative will conduct an initial visual recognition/verification of the Contractor personnel. Once verified, the Contractor personnel are considered "first tier trusted Contractors," and are allowed unescorted access to the base for the purpose of conducting contract-related work. These first-tier trusted Contractors are then responsible to verify all remaining Contractor personnel requiring access to the base for the respective contract. When these remaining Contractor personnel initially arrive at the gate, the first-tier trusted Contractors are required to have visual recognition/verification of all the remaining contract personnel. Once verified, they are considered "second-tier trusted Contractor" personnel and must be escorted while on the installation. Escorting the second-tier trusted Contractors onto the installation, to the job site and off the installation is the responsibility of the first-tier trusted Contractors. Each job site must have at least one first-tier trusted Contractor to work/observe the second-tier trusted Contractor personnel. Once the functional representative conducts the initial verification, they are not required to verify on a daily basis, but may be asked to verify more first-tier Contractors if needed.

a. The Contractor shall post a man at the Grandview Gate at all times the Contractor is on base. This person shall have a radio to be in contact with the Control Tower.

1.1.4.2 Entry Access List: An original Entry Access List (EAL) will be built based on all first and second tier trusted Contractors. This EAL will be maintained at the front gate between 366 SFS and 366 CONS. Every time a Contractor representative requires entry to the base, they will be stopped to verify they are listed on the EAL. If all persons in the vehicle are not on the EAL, either a first-tier trusted agent or a functional representative must be contacted to conduct a visual verification prior to access to the base.

1.1.4.3 Vender/Delivery/Distributor access procedure: Vendor/delivery/distributor are defined as those commercial businesses that have single or multiple stops on base (i.e. COCESS deliveries, UPS, FedEx, food and beverage stocking trucks). When a Vendor/delivery/distributor requires access to the base, they will be stopped prior to entering the base. To determine if a delivery is valid; documentation, visual recognition, or confirmation from a base organization expecting delivery is required. If verified, the vehicle will be escorted with a military troop for the entire duration the vehicle is on base. As the vehicle departs, the escort will be dropped off at the gate. If an escort is not available, attempts will be made to contact a base functional representative. The functional representative will provide an escort for the entire time the vehicle is on the installation. If a functional representative is not contacted and an escort is not available, the vehicle wii be denied access.

1.1.4.4 All commercial and private vehicles will be searched. Drivers should anticipate delays.

1.1.4.5 Procedures for commercial and private vehicle access to Mt. Home AFB are subject to change without prior notice.

1.1.5 Other Contractors: Other contractors will be working on the airfield and surrounding areas that will require coordination. Work by others during the same timeframe includes taxiway A

selective slab replacement, runway approach lights, repaving on Alpine Street, and possible utility work north of the runway.

1.1.6 Transporting Construction Materials Option

Contractors have the option of transporting construction materials and equipment to Mountain Home AFB using the Union Pacific Railroad railhead. If contractors wish to use this option they must contact Union Pacific Railroad for an inspection 30 days before use of the railhead to Mountain Home AFB. Security arrangements must be made in advance with the Contracting Officer and Mountain Home AFB.

Inspections can be arranged with Union Pacific Railroad point of contact: Mr. J.C.. "John" Flynn, Manager Track Maintenance, 304 North Rail St., PO Box 661, Shoshone, Id 83352, phone 208-236-5486. Cost for the inspection can be provided by Mr. Flynn.

Use of the Union Pacific line must be coordinated through the Manager Train Operations, Portland Service Unit, Mr. D.D. Ellett at www.uprr.com, 208-736-7086, CO. #: 236-5522, CEL: 208-420-9760, 1139 Falls Ave. East, Suite 2, Twin Falls, Id 83301.

1.1.7 KEYS: When keys are required for access to facilities on this contract, they shall be obtained through the Contracting Officer

1.1.7.1 The Contractor shall be responsible for Government-owned keys issued for access to facilities or areas pertinent to this contract.

1.1.7.2 Upon completion of the work in an area, or upon request of the Contracting Officer, the key or keys relevant to the completed areas shall be returned.

1.1.7.3 Should the Contractor lose a key:

a. the Contracting Officer shall be notified, in writing, within three (3) working days after the loss is discovered and

b. should the key not be found before final acceptance, the final contract payment shall be reduced by $100 for each key not returned.

1.1.8 Work is allowed in the construction area 24 hours a day, 7 days a week, subject to the requirements of Paragraph CONSTRUCTION PHASING.

1.2 UTILITY OUTAGES

The Contractor shall cooperate with Base Utilities to maintain utility services and facilities during the progress of the work. Contractor shall coordinate utility outages with the Contracting Officer at least 14 days in advance. Outages shall be kept to a minimum and any one outage shall not last more than 2 hours. All Contractor's operations shall be controlled to prevent any unscheduled interruptions of utility services and facilities.

1.3 PROTECTION OF GOVERNMENT PROPERTY

In addition to requirements of the CONTRACT CLAUSES, Contractor shall protect all Government property within the site in which he is working, except for such property as is required to be demolished. Property which is to be demolished shall be protected until its scheduled demolition time. Protection shall include, but not be limited to, protection from construction generated dust, debris, water, and vibration.

1.4 COORDINATION, SAFETY AND REGULATORY REQUIREMENTS

1.4.1 Construction traffic entering base via the Grandview gate entrance shall be under control by flagmen in radio contact with base traffic control tower. Construction traffic operating on or crossing taxiways open to aircraft traffic shall be under control by flagmen in radio contact with base traffic control tower. When conflicts arise between construction activities, aircraft operations and safety, aircraft operation and safety shall take precedence and shall govern. Construction sequencing shall be coordinated with airfield management through the Contracting Officer (CO). Continuous sweeping shall be required for pavement to be opened to traffic or areas open to air traffic within construction limits as directed by CO.

1.4.2 Asphalt, broken concrete, and waste aggregate shall be disposed of on airfield property (stockpiled separately) at locations shown on the drawings. The Contractor shall verify the locations with the Contracting Officer prior to using disposal sites.

1.4.3 Vehicles and equipment shall not be allowed within areas 100' from the centerline of active taxiways, except as noted below, and 200' from active runway.

1.4.4 Pavements, drives or turf areas utilized by the construction for access roads or storage areas shall be maintained and repaired by the Contractor to the satisfaction of the Contracting Officer and airfield management. Costs associated with the above work shall be incidental to the contract.

1.4.5 Before construction commences, the Contractor shall contact Base Civil Engineering through the Contracting Officer to locate utilities. Contractor shall allow a minimum of 14 days to obtain permit and shall be responsible for marking limits of construction areas with white paint or white flagging so utilities may be located.

1.4.6 A Digging Permit will be required before construction excavation commences. Digging permits expire 30 days after date issued and must be renewed.

1.4.7 See Section 01001 (AR), paragraph 1.5 for identification of employees working on base.

1.4.8 Concrete batch plant shall be set up and producing approved mix, prior to concrete placement.

1.4.9 Fire extinguishers will be required on construction equipment. A 10 ABC minimum rating is required for fire extinguishers.

1.4.10 Welding permits will be required. The Contractor shall contact the Base Fire Department for required permits.

1.4.11 Blasting is prohibited on air base property.

1.4.12 Airfield Lighting System must be in full operation at the end of each work day, except in areas closed to airfield traffic. All equipment must be parked in contractor's staging area at the end of each working day.

1.4.13 When Contractor is working in areas open to air traffic, barricades shall be placed as shown on the drawings. Barracades shall be lighted with battery operated, red flasher lights and shall remain until construction is completed.

1.4.14 Contractor shall furnish radios, tuned to frequency of the tower, for use during construction. Crews in each work area need to have a radio to be in contact with the tower - specifically crews working on the parking apron and each end of the runway. Contractor shall furnish radios to communicate with employees.

1.4.15 Contractor shall complete a NRC 241 Form prior to use of a nuclear density gauge on airfield.

1.4.16 The Contractor shall submit an evacuation plan detailing how expedient evacuation of his personnel from the flightline or work site will be accomplished if required by the tower or flightline manager. The plan shall address such issues as moving equipment and communication with all personnel.

1.4.17 The Contractor is advised that work will be occurring on an active military installation. Military aircraft will be operating near the construction work areas. Possible conditions that may occur, but are not limited to the following: Aircraft with jammed guns or carrying practice ordance and/or pyrotechnics, and hydrazine leaks.

1.5 CONSTRUCTION PHASING

1.5.1 Construction Period/Base Meeting: All project phasing and work hours have been written with the intent to minimize hindrances to the flying mission, while also minimizing contract interruptions. Contract work schedules shall be coordinated through the Contracting Officer and base agencies responsible for scheduling flying operations and operating the base airfield (including taxiways and parking ramps), to ensure safe uninterrupted flying operations and safe working conditions during the duration of the contract. The Contractor shall hold a brief meeting at Base Operations (Bldg. 262), coordinated through the Contracting Officer, at the beginning of each week and prior to the closing of any portion of the runways, taxiways and parking ramps and at the start of succeeding phases to inform base agencies operating on the airfield of the nature and location of the contract work or closure of airfield areas for that week. The Contractor shall be required to perform all on-site construction activities within the following construction periods:

WORK	CONSTRUCTION PERIOD
• Reconstruct Runway 30 end (Repair Runway Phase 1) • Optional Repair Taxiway E (Repair Runway Phase 1)	Notice to proceed through 19 August 2002
• Repair Aircraft Parking Apron north of Taxiway A (Repair Aircraft Parking Apron Phase 1) • Optional Installation of ductbank under the Aircraft Parking Apron (Repair Aircraft Parking Apron Phase 1)	Notice to proceed through 1 November 2002

WORK (Continued)	CONSTRUCTION PERIOD
• Mill and Overlay Runway 12/30 (Repair Runway Phase 2) • Installation of duct bank under the runway (Repair Runway Phase 2) • Reconstruct Runway 12 end (Repair Runway Phase 3) • Installation of Sewerline, Waterline and Effluent Line (Repair Runway Phase 3) • Optional Repair Taxiway A (Repair Runway Phase 3)	19 June 2002 through 19 August 2002
• Extension of Aircraft Parking Apron onto Taxiway A (Repair Aircraft Parking Apron Phase 2) a/ • Installation of duct bank portion that extends into Taxiway A (Repair Aircraft Parking Apron Phase 2)	19 June 2002 through 1 September 2002
• Runway Grooving and Permanent Pavement Marking (Repair Runway Phase 4)	19 September 2002 through 19 October 2002
• All other work	Not later than 1 November 2002

a. If extension of Aircraft Parking Apron onto Taxiway A is not complete by 1 September 2002, Contractor shall paint a temporary offset Taxiway A centerline along the Aircraft Parking Apron parking area (see Section 02763(A), paragraph 3.2.b).

b. Contractor will be allowed access to the Aircraft Parking Apron construction areas outside the dates shown under "Construction Period" for such intermittent work as permanent pavement markings. The Contractor shall request access from the Contracting Officer at least 24 hours before access is desired for this intermittent work.

c. Concrete pavement must have a minimum of 14 days of cure time prior to the time it is turned over for airfield operations

d. See Section 01010 (R), paragraph 1.13 Construction Phasing (Repair Runway) for additional phasing requirements.

1.5.2 Work Delays

1.5.2.1 Contractor may anticipate a work delay of up to 7 working days during the contract period due to Mt. Home AFB operations, but this will not occur during the 60 day runway closure (19 June 2002 through 19 August 2002). This time is included in the overall contract completion time and will be included in the contractors proposal price. During this work delay, no site access will be allowed. The contracting officer will provide 48 hours notice to the contractor prior to the work delay.

1.5.2.2 During the period from the date the Contractor receives the notice to proceed to 15 June 2002, the Contractor shall expect that he will be required to evacuate the Aircraft Parking Area

(Mobility Ramp) work area for one hour and secure the area for jet blast three (3) times. The Contractor will be given 2 hours notice prior to such an occurrence.

1.5.3 Notification Of Movements: Contractor can expect a minimum of 48 hours notice for additional area and flightline movements and work delays.

1.5.4 Contractor personnel who loose their base priviledges will not constitute valid argument for not meeting any contractual requirements or deadlines.

1.6 PAVEMENT WORKSHOP

The Corps of Engineers will conduct a 3 day pavement workshop held at Mountain Home AFB. It is mandatory that the Contractor and his representatives attend the workshop for the minimum amount of time as listed below. Any other person the Contractor wants to attend is welcome. Everyone is welcome to attend the entire workshop if they desire and it could be beneficial if they attended more than just the minimum they are required to attend. The dates for the workshop will be scheduled after the project is awarded and prior to the start of placing pavement and will be as directed by the Contracting Officer.

Hot Mix Asphalt (HMA) QC:
Project Engineer/Pavements Engineer: 1 Day (3 Days if also PCC)
CQC Chief: 1 Day (3 Days if also PCC)
CQC Assistants: 1 Day (3 Days if also PCC)
CQC CMT Testing Lab (including mix design lab if different from on site lab): 1 Day
HMA Paving Foreman/Supt.: 1 Day
HMA Aggregate Supplier(s): 1/2 Day
HMA Supplier: 1 Day

Portland Cement Concrete (PCC) QC:
Project Engineer/Pavements Engineer: 2 Days (3 Days if also HMA)
CQC Chief: 2 Days (3 Days if also HMA)
CQC Assistants: 2 Days (3 Days if also HMA)
CQC CMT Testing Lab (including mix design lab if different from on site lab): 2 Days
PCC Paving Foreman/Supt.: 2 Days
PCC Aggregate Supplier(s): 1/2 Day
Concrete Supplier: 1 Day
Cement / Flyash / Admixture Supplier(s): 1/2 Day
Sawing / Sealing Contractor(s): 1/2 Day

1.7 MAINTENANCE REQUIREMENTS

1.7.1 The Contractor shall maintain strict dust control to prevent blowing dust at all times. Thorough foreign object debris (FOD) checks will be required whenever the Contractor's vehicles cross taxiways or aprons.

1.7.2 The Contractor shall assure that the hauling route, access route to airfield pavements, and job site are maintained by vacuum-type sweeping as required to assure no damage to Government and personal property during the performance period. All cleanup on airfield pavements shall be done with a vacuum-type airfield sweeper. The Contractor shall employ, full time, through the duration of the project, two vacuum-type sweepers to sweep airfield

pavements and haul routes during construction according to the schedule below. The Contractor shall make a third vacuum-type sweeper available within 24 hours should a sweeper break down.

1.7.2.1 All airfield surfaces and main haul routes: Sweep continually as long as hauling is taking place, the surfaces are being traveled on, or construction is occurring in the area.

1.7.2.2 All other road pavements utilized on the base: Allow no spillage to remain for more than one hour. Sweep all roads used for hauling prior to the end of each shift.

1.7.3 All hauling operations shall cease any time that there are not two operational vacuum sweepers. The one remaining operational vacuum sweeper shall be reserved to sweep airfield pavements. Should the non-operational sweeper be down for more than 24 hours, the third sweeper shall be brought in before the end of the 24 hours. Delays caused by the lack of an operational vacuum sweeper will be the responsibility of the Contractor.

END OF SECTION

This Section revised in it's entirety by amendment R0001

SECTION 01025 (AR)

MEASUREMENT AND PAYMENT

PART 1 GENERAL

1.1 GENERAL

The contract price for each item shall constitute full compensation for furnishing all plant, labor, materials, appurtenances, and incidentals and performing all operations necessary to construct and complete the items in accordance with these specifications and the applicable drawings, including surveying performed by the Contractor. Payment for each item shall be considered as full compensation, notwithstanding that minor features may not be mentioned herein. Work paid for under one item will not be paid for under any other item. No separate payment will be made for the work, services, or operations required by the Contractor, as specified in DIVISION 1, GENERAL REQUIREMENTS, to complete the project in accordance with these specifications; all costs thereof shall be considered as incidental to the work.

1.2 MEASUREMENT

1.2.1 PCC Pavement - Repair Aircraft Parking Apron, Unit of Measurement: Cubic Meter

Measurement will be to the nearest cubic meter. Computation will be by the average-end area cross-sectional methods.

1.2.2 PCC Pavement - Repair Runway, Unit of Measurement: Cubic Yard

The quantity of concrete to be paid for will be the volume of concrete in cubic yards, placed in the completed and accepted pavement. Concrete will be measured in place in the completed and accepted pavement only within the neat line dimensions shown in the plan and cross section. No deductions will be made for rounded or beveled edges or the space occupied by pavement reinforcement, dowel bars, tie bars, or electrical conduits, nor for any void, or other structure extending into or through the pavement slab, measuring 3 cubic feet or less in volume. No other allowance for concrete will be made unless placed in specified locations in accordance with written instructions previously issued by the Contracting Officer.

1.2.3 AC Pavement - Repair Runway, Unit of Measurement: Ton

The amount paid will be for the number of 2,000 pound tons of hot-mix asphalt mixture used in the accepted work. Hot-mix asphalt mixture shall be weighed after mixing, and no separate payment will be made for weight of asphalt cement material incorporated herein.

1.3 PAYMENT

- Lump Sum Payment Items: The lump sum price and payment made for each item listed shall constitute full compensation for furnishing all plant, labor, materials, and equipment, and performing any associated Contractor quality control, environmental protection, meeting

safety requirements, tests and reports, and for performing all work required for which separate payment is not otherwise provided.

- Unit Price Payment Items: The unit price and payment made for each item listed shall constitute full compensation for furnishing all plant, labor, materials, and equipment, and performing any associated Contractor quality control, environmental protection, meeting safety requirements, tests and reports, and for performing all work required for each of the unit price items.

NOTE: THE CONTRACTOR SHALL EQUITABLY DISTRIBUTE IT'S HOME OFFICE AND FIELD OFFICE OVERHEAD AMONG ALL BID ITEMS.

ITEMS 0001 THROUGH 0007 (REPAIR AIRCRAFT PARKING APRON)

1.3.1 ITEM 0001 (BASE ITEM)

Payment will be made at the contract lump sum price for Item No. 0001, All Work to Repair Aircraft Parking Apron, except for Items 0002, 0003, 0004, and 0005, payment of which shall constitute full compensation for Item No. 0001, complete. Work this item includes demolition, rigid base course, aggregate base course, asphalt pavement, joint sealant, pavement markings, grounding/tiedown points, and other work.

1.3.2 ITEM 0002 (BASE ITEM)

Payment will be made at the contract unit prices for Item No. 0002, PCC Placement for Aircraft Parking Apron and Taxiway A, payment of which shall constitute full compensation for Item No. 0002, complete.

1.3.3 ITEM 0003 (OPTIONAL ITEM)

Payment will be made at the contract unit prices for Item No. 0003, Excavation and Disposal of Contaminated Soil, payment of which shall constitute full compensation for Item No. 0003, complete.

1.3.4 ITEM 0004 (OPTIONAL ITEM)

Payment will be made at the contract lump sum price for Item No. 0004, Electrical and Communications Ductbank, payment of which shall constitute full compensation for Item No. 0004, complete.

1.3.5 ITEM 0005 (OPTIONAL ITEM)

Payment will be made at the contract unit prices for Item No. 0005, Rock Excavation for Ductbank, payment of which shall constitute full compensation for Item No. 0005, complete.

ITEMS 0006 THROUGH 0017 (REPAIR RUNWAY)

1.3.6 ITEM 0006 (BASE ITEM)

Payment will be made at the contract lump sum price for Item No. 0006, All Work to Repair Runway 12/30, except for Items 0007, 0008, 0009, 0010, 0011, 0016 and 0017, payment of which shall constitute full compensation for Item No. 0006, complete.

1.3.7 ITEM 0007 (BASE ITEM)

Payment will be made at the contract unit prices for Item No. 0007, Provide Place, and Finish PCC Pavement to Reconstruct Portions of Runway 12/30, payment of which shall constitute full compensation for Item No. 0007, complete.

1.3.8 ITEM 0008 (BASE ITEM)

Payment will be made at the contract unit prices for Item No. 0008, Provide Place, and Compact AC, payment of which shall constitute full compensation for Item No. 0008, complete.

1.3.9 ITEM 0009 (BASE ITEM)

Payment will be made at the contract unit prices for Item No. 0009, Repair Small Asphalt Cracks, payment of which shall constitute full compensation for Item No. 0009, complete.

1.3.10 ITEM 0010 (BASE ITEM)

Payment will be made at the contract unit prices for Item No. 0010, Repair Medium Asphalt Cracks, payment of which shall constitute full compensation for Item No. 0010, complete.

1.3.11 ITEM 0011 (BASE ITEM)

Payment will be made at the contract unit prices for Item No. 0011, Repair Large Asphalt Cracks, payment of which shall constitute full compensation for Item No. 0011, complete.

1.3.12 ITEM 0012 (BASE ITEM)

Payment will be made at the contract unit prices for Item No. 0012, Rock Excavation for Waterline, Sewerline, Sewage Effluent, and Ductbanks, payment of which shall constitute full compensation for Item No. 0012, complete.

1.3.13 ITEM 0013 (BASE ITEM)

Payment will be made at the contract unit prices for Item No. 0013, Excavation, Removal and Replacement of Unsatisfactory Material, payment of which shall constitute full compensation for Item No. 0013, complete.

1.3.14 ITEM 0014 (OPTIONAL ITEM) 1/

Payment will be made at the contract lump sum price for Item No. 0014 All Work to Repair Taxiway A, except for Item 0015 payment of which shall constitute full compensation for Item No. 0014 complete.

1.3.15 ITEM 0015 (OPTIONAL ITEM) 1/

Payment will be made at the contract unit prices for Item No. 0013, Provide, Place and Finish PCC Pavement to Repair Taxiway A, payment of which shall constitute full compensation for Item No. 0013, complete.

1.3.16 ITEM 0016 (OPTIONAL ITEM) 2/

Payment will be made at the contract lump sum price for Item No. 0016, All Work to Repair Taxiway E, except for Item 0017, payment of which shall constitute full compensation for Item No. 0016, complete.

1.3.17 ITEM 0017 (OPTIONAL ITEM) 2/

Payment will be made at the contract unit prices for Item No. 0017, Provide, Place and Finish PCC Pavement to Repair Taxiway E, payment of which shall constitute full compensation for Item No. 0017, complete.

1/ Optional Items 0014 and 0015 are shown as Optional Item #1 on the contract drawings.

2/ Optional Items 0016 and 0017 are shown as Optional Item #2 on the contract drawings.

1.4 PROGRESS PAYMENT INVOICE

Requests for payment shall be submitted in accordance with Federal Acquisition Regulations (FAR) Subpart 32.9, entitled "PROMPT PAYMENT", and Paragraphs 52.232-5 and 52.232-27, entitled "Payments Under Fixed-Price Construction Contracts", and "Prompt Payment for Construction Contracts", respectively. In addition each request shall be submitted in the number of copies and to the designated billing office as shown in the Contract.

1.4.1 When submitting payment requests, the Contractor shall complete Blocks 1 through 12 of the "PROGRESS PAYMENT INVOICE" Form as directed by the Contracting Officer. (A sample form is attached at the end of this Technical Specification Section.) The completed form shall then become the cover document to which all other support data shall be attached.

1.4.2 One additional copy of the entire request for payment, to include the "PROGRESS PAYMENT INVOICE" cover document, shall be forwarded to a separate address as designated by the Contracting Officer.

PARTS 2 and 3 NOT USED

PROGRESS PAYMENT INVOICE

See Federal Acquisition Regulations (FAR) 32.900, 52.232-5, & 52.232-27

1. PROJECT AND LOCATION	2. DATE
3. CONTRACTOR NAME AND ADDRESS (Must be the same as in the Contract)	4. CONTRACT NO. _____ 5. INVOICE NO.
6. DESCRIPTION OF WORK	7. PERIOD OF PERFORMANCE From: To:
8. DISCOUNT TERMS	
9. OFFICIAL TO WHOM PAYMENT IS TO BE FORWARDED Name: Title: Phone: ( ) -	10. OFFICIAL TO BE NOTIFIED OF DEFECTIVE INVOICE Name: Title: Phone ( ) -

11. CERTIFICATION: I hereby certify, to the best of my knowledge and belief, that

(1) The amounts requested are only for the performance in accordance with the specifications, terms, and conditions of this contract;

(2) Payments to subcontractors and suppliers have been made from previous payments received under the contract, and timely payments will be made from the proceeds of the payment covered by this certification, in accordance with subcontract agreements and the requirements of Chapter 39 of Title 31, United States Code; and

(3) This request for progress payment does not include any amounts which the prime contractor intends to withhold or retain from a subcontractor or supplier in accordance with the terms and conditions of the subcontract.

_____ _____ _____

(Signature) (Title) (Date)

12. OTHER INFORMATION OR DOCUMENTATION required by Contract. Provide two (2) copies of each (check and attach if applicable): _____ Updated Progress Chart/Schedule _____ Progress Narrative _____ Certified Payrolls (submitted weekly) _____ Safety Exposure Report _____ Updated Submittal \register _____ Progress Photos _____ Subcontractor/Employee Listings	(FOR GOVERNMENT USE ONLY) Retainage: _____% Amt.: $_____ Withholdings: $ _____ Reason: _____ _____ _____ Following items are current: As-Builts _____ Yes _____ No O & M Manuals _____ Yes _____ No 1354 Data _____ Yes _____ No Submittal Register _____Yes _____No

END OF SECTION

This page intentionally blank

SECTION 01035 (AR)

MODIFICATION PROCEDURES

PART 1 GENERAL

1.1 PROPOSED PROJECT MODIFICATIONS:

Price proposals for proposed modifications shall be submitted in accordance with the requirements of the Contract Clause MODIFICATION PROPOSALS - PRICE BREAKDOWNS. If change order work impacts or delays other unchanged contract work, the costs of such impacts or delays shall be included in the proposals and separately identified. Additional instructions for submitting price proposals can be found in NPSP-415-1-1, INSTRUCTION AND INFORMATION FOR CONTRACTORS, a copy of which will be furnished to the Contractor at the Preconstruction Conference. For information applicable to equipment rates used in contract modifications, refer to 00800 - SPECIAL CLAUSES, clause “EQUIPMENT OWNERSHIP AND OPERATING EXPENSE SCHEDULE”.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION (NOT USED)

END OF SECTION

This page intentionally blank

SECTION 01061 (AR)

ENVIRONMENTAL PROTECTION

PART 1 GENERAL

1.1 SCOPE

This Section covers protection of the environment from work under this contract, compliance with pertinent Air Force, local, state, and federal environmental regulations, and recycling.

1.1.1 Definition

For the purpose of this specification, environmental pollution and damage is defined as the presence of chemical, physical, or biological elements or agents which adversely affect human health or welfare; unfavorably alter ecological balances of importance to human life; affect other species of importance to man; or degrade the utility of the environment for esthetic, cultural, and historical purposes. The control of environment pollution and damage, or environmental protection, requires consideration of air, water, and land, and includes management of esthetics, noise, solid waste, and other pollutants.

1.1.2 Contractor's Responsibility

The Contractor is responsible for complying with all Air Force, local, state, and federal laws and regulations regarding protection of the environment and natural resources.

1.2 QUALITY CONTROL

Establish and maintain quality control for environmental protection of all items set forth in this specification. Record any problems in complying with laws, regulations, ordinances, and corrective actions taken.

1.2.1 Subcontractors

Assurance of compliance with this section by subcontractors shall be the responsibility of the Contractor.

1.2.2 A work plan shall be provided to and approved by the CO and Civil Engineering Environmental Flight (CEV) before any work involving asbestos begins. This work plan shall include the process of EPA notification, waste shipment records, proper engineering controls, transportation and disposal, and safety plans.

1.3 NOTIFICATIONS

1.3.1 Corrective Actions

The Contracting Officer (CO) will notify the Contractor in writing whenever noncompliance with Federal, state, or local laws, regulations, or permits is observed. After receipt of such notice, inform the Contracting Officer of proposed corrective actions and take such actions after approval of the CO. If prompt action to comply with the pertinent law or regulation is not taken, the CO may issue an order stopping all or part of the work until satisfactory corrective action has

been taken. No time extensions will be granted for work stoppage due to noncompliance with environmental laws and regulations. Costs or damage will not be allowed to the Contractor for any such suspension.

1.3.2 Hazardous Waste Transportation

Hazardous Waste Transportation: Notify the CO before transporting any hazardous substance or waste, as determined by the Environmental Protection Agency (EPA), on Mountain Home AFB. Identify the type and quantity of substance, the origin or destination on base, and intended route of travel. By law, hazardous waste cannot be transported onto MHAFB Notify the CO if any hazardous substance or waste is produced as a by-product of work activities. The Contractor shall be responsible for the proper handling, transporting, and disposal of such substances. (Refer to Part 1.4.6 of this Section)

1.3.3 Asbestos

Asbestos: In the event asbestos abatement is required, send copies of each 10-day notification, asbestos manifest, and landfill forms through the CO to the CEV. Submit Notification Revisions if the abatement periods change.

1.3.4 Spill Response

In the event of an uncontrolled spill the contractor shall notify the fire department by calling 911. CEV then receives notification via the established base notification system that is initiated by the fire department.

1.4 PROTECTION OF ENVIRONMENTAL RESOURCES

Protect environmental resources within the project boundaries and those affected outside the limits of permanent work under this contract during the entire period of this contract. Confine activities to areas defined in the drawings and specifications.

1.4.1 Protection of Land Resources

The Contractor shall not remove, cut, deface, injure, or destroy land resources including trees, shrubs, vines, grasses, topsoil, and land forms without special permission from the Contracting Officer except as otherwise specified or indicated. Do not disturb, drive through, or fill areas designated as wetlands.

1.4.2 Disposal and Cleanup

1.4.2.1 Disposal of Garbage

Garbage shall be placed in containers which are emptied on a regular schedule. All handling and
disposal shall be conducted to prevent contamination

1.4.2.2 Refuse Disposal

Refuse shall be defined as debris other than organic materials like trees, brush, leaves, grass, stumps, etc. Include the cost of refuse disposal, such as transportation, handling, dumping fees

as applicable, and similar cost, in the contract price. Place refuse in containers that are emptied on a regular schedule. Conduct all handling and disposal of refuse to prevent contamination of the environment. Dispose of refuse off site, in accordance with all local, state, and federal rules and regulations, at the Contractor's expense. The MHAFB landfill will not be available for use by the Contractor.

1.4.2.3 Asbestos Disposal

Approval may be given by the Contracting Officer for use of the MHAFB Asbestos landfill on a case-by-case basis. In such instances, the contractor shall fill out all necessary forms showing content of materials, location from which the materials have been removed, and quantities. Coordinate with the CO in advance exact times for dumping to allow proper inspection. MHAFB disposal area is noted on the vicinity map on the drawings. Coordinate with contracting officer's representative (COR) for location in landfill for disposal.

1.4.2.4 Base Hard Fill Area

Asphalt shall be milled and Portland Cement Concrete (PCC) shall be crushed. See plans for location of stockpile areas. Dumping of rock rubble and waste materials at the MHAFB Hard Fill Area shall be approved in advance Do not dump at the MHAFB rubble area without specific approval from the Government for the exact location, composition, and quantity of material. This approval must be received in advance by the Contractor from the MHAFB Civil Engineering (BCE) Pavement and Equipment Foreman through the Contracting Officer. All materials dumped at the MHAFB rubble area shall be spread, graded and covered daily as directed by the BCE Pavements and Equipment Foreman

1.4.3 Additional Restrictions

The Contractor shall not be permitted to deposit refuse in existing containers or dumpsters. Do not dispose of any batteries, tires, appliances, recyclable materials, liquids, hazardous materials, or hazardous wastes in the MHAFB landfill. Do not pour, drain, or wash cleaners and other solutions into plumbing fixtures, sanitary sewers, or storm sewers. Refuse shall not be burned. Burning of vegetation or tree stumps will not be allowed unless the work site is in an area approved for burning and approval is obtained from the CO.

1.4.4 Disposal of Chemical or Hazardous Waste

1.4.4.1 Disposal

Hazardous waste generated by construction operations remains the property of the Contractor and shall be removed from Mountain Home AFB for proper disposal. The MHAFB still retains liability. The contractor must complete a uniform hazardous waste manifest as required in paragraph 1.4.4.6 Manifests below.

1.4.4.2 Regulatory Requirements

Contractor operations shall be in compliance with the Resource Conservation and Recovery Act (RCRA), 40 CFR, and Idaho Rules, Regulations and Standards for Hazardous Waste, (Idaho Code 16.01) at all times.

1.4.4.3 Accumulation

a. Repair Aircraft Parking Apron. No more than 142 liters, total, of hazardous waste shall be accumulated by the Contractor on site. Once the 142 liters limit is reached, the Contractor has 72 hours to remove the waste from Mountain Home AFB and dispose of properly.

b. Repair Runway. No more than 55 gallons, total, of hazardous waste shall be accumulated by the Contractor on site. Once the 55-gallon limit is reached, the Contractor has 72 hours to remove the waste from Mountain Home AFB and dispose of properly.

1.4.4.4 Hazardous Materials/Hazardous Waste Control Plan

The Contractor shall submit a Hazardous Materials/Hazardous Waste Control Plan to the CO for approval and coordination with CEV if any materials will be used that are corrosive, flammable, toxic, or reactive.

1.4.4.5 Material Safety Data Sheets

The Contractor shall submit Material Safety Data Sheets (MSDS) to the CO for approval and coordination with CEV for all paints, protective coatings, solvents, adhesives, and all other chemical products. Have available for inspection at the job site MSDS's for all products and materials used for the contract.

1.4.4.6 Manifests

Hazardous wastes shall be manifested off MHAFB and the MHAFB Environmental Office, 366 CE/CEV, shall be the only approval authority.

1.4.5 Disposal of Discarded Materials

Discarded materials, other than those which can be included in the solid waste category, shall be handled as directed by the Contracting Officer.

1.4.6 Protection of Water Resources

The Contractor shall keep construction activities under surveillance, management, and control to avoid pollution of surface and ground waters. If the project disturbs over 5 acres of contiguous land, submit a NPDES storm water permit to the EPA through the CO and base Environmental Office and comply with the conditions of the permit. Projects that will occur after March 10, 2003, or that will still be in work at that date, and that disturb greater than 1 acre must obtain a NPDES storm water permit. In all cases of land disturbance, each storm water removal and treatment structure must be in conformance with the Catalog of Storm water Best Management Practices for Idaho Cities and Counties, and these best management practices will be employed to control storm water runoff. Ensure there are no unauthorized discharges to the storm water collection system. Ensure all discharges to the sanitary sewer system are in accordance with the requirements of the wastewater treatment plant NPDES and wastewater land application permits.

MHAFB project designs that require completion of Idaho Department of Environmental Quality (IDEQ) checklists are:

* Sewer line construction
* Production well construction
* Water lift station construction
* Water line construction

1.4.7 Protection of Air Quality

Dust particles, aerosols, and gaseous by-products from construction and demolition activities, processing, and preparation of materials shall be controlled at all times, including weekends, holidays, and hours when work is not in progress. Hydrocarbons and carbon monoxide emissions from equipment shall be controlled to Federal and state allowable limits at all times.

1.4.8 Recycling

Recycling is required to the maximum extent practicable for all waste generated by the Contractor. See APPENDIX A attached at the end of this specification section for specific requirements for projects at Mountain Home AFB.

1.4.9 Batch and Crushing Plants

If required by the contract, portable concrete batch plant, portable rock crushing plant, hot mix asphalt plant, and associated generators must be permitted in the state of Idaho by the Contractor prior to construction. Copies of the permits must be submitted to the Contracting Office and coordinated through the COR and the Civil Engineering Environmental Flight (CEV). Location of the plant(s) must be coordinated through the CO. The Contractor shall provide monthly through-put quantities and generator hours to CEV through the COR. While operating at MHAFB, contractors are responsible for their own permit requirements/conditions.

1.4.10 Noise

Use low noise emission equipment and products certified by the EPA to the maximum extent possible

1.4.11 Asbestos and Lead-Based Paint

Assume all facilities on Mountain Home AFB contain asbestos and lead-based paint unless otherwise notified by the CO. Brief all employees and subcontractors on the potential presence of asbestos and lead-based paint in facilities before work is started.

1.4.12 Transporting Hazardous Waste and Materials

Comply with all applicable regulations and laws when transporting hazardous waste and materials. These include, but are not limited to, Department of Transportation (DOT), EPA, and Idaho Department of Environmental Quality (IDEQ) regulations (40 CFR, 29 CFR, IDAPA 16.01).

1.4.13 Hazardous Materials

Contractors must submit for approval/disapproval Material Safety Data Sheets (MSDS) to the COR for coordination with HAZMART for potentially hazardous material (including paints, solvents, thinners, etc) intended for use at MHAFB. An inventory of all approved potentially hazardous materials shall be submitted to the COR/HAZMART prior to bringing material onto MHAFB for use. The inventory shall include the material name/trade name, container size, quantity, and intended use. Prior to using the hazardous material at MHAFB, HAZMART will provide bar-code labels for the tracking of hazardous materials. Contractors bringing hazardous materials onto MHAFB without authorization are responsible for any punitive or regulatory actions. The contractor shall be responsible for proper disposal of all containers/hazardous material. Coordination of proper disposal shall be accomplished through the Civil Engineering Inspector/COR.

Hazardous materials shall be properly stored in accordance with all Federal, State, Local and Air Force Regulations.

1.4.14 Ozone Depleting Substances

All Class I ODSs waivers must be obtained from either HQ ACC/LGEM (for logistics) or HQ ACC CES/CEOI (for civil engineering) prior to use at MHAFB. All Class I ODSs approved for use at MHAFB must be obtained from the Department of Defense (DoD) through its Defense Logistics Agency (DLA) which has established an ODS Reserve at the Defense Supply Center Richmond (DSCR). All used ODS obtained through the center must be returned to the DSCR for reclamation. Currently, the only new Class I ODSs waivers being approved for use at MHAFB is for aircraft support (fire suppression systems).

1.4.15 Backflow Prevention

Use backflow protection devices if tapping into a hydrant to gain a water source for activities.

1.4.16 Some concrete utility pipe segments on Mountain Home AFB contain asbestos material. Pipe segments containing asbestos have been identified on the plans using the best information available to the Contracting Officer's representative. The Contractor shall brief all employees and subcontractors on the potential presence of asbestos before work is started.

In the event that the Contractor suspects that they are dealing with pipe containing asbestos and it is not called out on the plans, the Contractor shall be responsible for verifying the presence of asbestos concrete and carrying out the abatement of the material. The Contractor shall be responsible for taking samples and sending them in to an EPA-accredited lab, and providing a copy of the sample results to CEV. For pipe lengths under 1,000 fee the Contractor shall take one sample of the pipe designated for removal. For pipe lengths 1,000 feet and longer, the Contractor shall procure three samples for every 1,000 feet of pipe.

1.5 PROTECTION OF HISTORICAL, ARCHAEOLOGICAL, AND CULTURAL RESOURCES

1.5.1 Definition

Cultural resources shall be defined as historic or prehistoric artifacts, pictographs, human remains, and any other evidence of historic human activity. Existing historical, archaeological,

and cultural resources within the Contractor's work area will be so designated by the Contracting Officer if any have been identified.

1.5.2 Site Protection

The Contractor shall not disturb any site that contains evidence of cultural resources. Contractor shall provide and install protection for these resources and be responsible for their preservation during the life of the contract. If evidence of cultural resources are discovered, all activities that may damage or alter such resources shall be temporarily suspended and the Contracting Officer shall be notified. The Contracting Officer will then notify the Base Cultural Resource Manager at (208) 828-1685 or (208) 828-6351. Work shall not be resumed until notified by the COR or CO. Resources covered by this paragraph include but are not limited to: any human skeletal remains or burials; artifacts; shell, midden, bone, charcoal, or other deposits; rocks or coral alignments, pavings, wall, or other constructed features; and any indication of agricultural or other human activities.

1.6 RADIOACTIVE MATERIALS

Submit requests to bring radioactive materials or nuclear devices on Mountain Home AFB 30 days prior to planned activities using the material or devices. Such devices include those required to test soil density by nuclear methods, lead paint meters, and any apparatus containing radioactive material. Requests shall be submitted to the CO for review by the base Radiation Safety Officer (RSO)

1.6.1 Request

The request shall include the following:

a. A description of the proposed activities on Nuclear Regulatory Commission (NRC) Form 241, Report of Proposed Activities in Non-Agreement States. Include proposed activities, locations of use, and traffic routes to be used.

b. The procedures established to ensure the health and safety of personnel while the device is on MHAFB.

c. A current and valid copy of the applicable NRC or Agreement State license. The license must state Mountain Home AFB by name, or state approval for work at temporary work sites where the NRC or Agreement State maintains jurisdiction. In lieu of a license, submit a written certification of exemption from NRC licensing requirements, and cite the applicable exemption of 10 CFR.

d. The most current leak detection test results. Provide new results to the CO if updating of the leak detection test is required during the Project.

e. A copy of that part of the contract describing work to be done at the base and the inclusive dates of the work.

f. Agreement State licensees using NRC regulated materials shall supply a copy of the NRC Form 241 approved by the base's NRC Region according to 10 CFR 150.20

1.6.2 Storage of Nuclear Devices

Obtain permission from the CO prior to storing the radioactive devices on base overnight.

1.6.3 Inspections

The RSO may make periodic checks to ensure proper radiation safety practices are being followed.

1.7 SPILL PREVENTION AND CONTROL

1.7.1 Spill Response Plan

Develop a Spill Response Plan that addresses prevention and control of spills for each type chemical and fuel used or stored at each site occupied under this Contract. The Plan must be site-specific. Each employee must be familiar with the Plan so risk of spills is minimized and response to spills can be dealt with in a manner to minimize impact to the environment. The Contractor shall be responsible for all costs associated with cleanup and restoration of sites contaminated by chemicals from Contractor activities. The elements of the plan should include the following:

1. Prevention: Methods and procedures established by the Contractor to prevent spills from occurring. Examples include ensuring connections are tight, providing containment when drawing off chemicals from a container or transferring chemicals, closing containers when not in use, and using proper equipment for the job.

2. Control: Procedures to control the spread of a substance or chemical should a spill, release, or leak occur. The intent is to minimize environmental contamination without physical harm to people in the area.

3, Supplies: Provide necessary supplies and equipment on hand to control any spills, leaks, or releases. These include pads and other absorbent material, trays, mats to cover manholes and drains, etc.

1.7.2 Procedure Outline

An outline of expected procedures to be followed in the event of a release or spill of a chemical is provided for the Contractor's use. The Contractor is ultimately responsible for ensuring spills do not occur and responding in a manner to prevent harm to people and minimize environmental contamination.

The person discovering the spill or release is responsible for initiating the Spill Response Plan and providing initial defensive actions without undue risk of personal injury. Implement the following actions as necessary upon discovery of the spill or release.

1. Initiate evacuation if required.

2. Notify the Fire department (828-1117) and provide the following information if known or can be reasonably determined:

a. Name, and company, of individual reporting the spill

b. Location of the spill or release

c. Number of injured personnel and nature of injuries (if applicable)
d. Substance spilled or released, based on knowledge, labels, signs, etc.

e. Estimated rate of substance release

f. Time spill occurred

g. Extent to which spill has traveled

h. Any additional information which might aid the Fire Department, such as other potential hazards at the site

3. Stop the spill or release at the source whenever possible without risking personal injury.

4. Contain the spilled material to prevent further spread and release to drainage ditches, pipes, manholes, storm water drop inlets, etc.

5. Secure the area to ensure unauthorized personnel do not approach or become endangered.

6. Ensure all sources of ignition are restricted and prevented in the area when flammable substances are involved.

7. Contact the CO and CEV (828-6351) and inform them of the situation. The CO is to ensure the proper paperwork is completed for release. If the release is over the reportable quantity, CEV is to make all state and federal notifications.

8. Note: Small spills that can be contained and cleaned up by the Contractor without any damage to the environment may not require all the steps above. Ultimately, the responsibility for proper cleanup to Environmental Protection Agency (EPA) and state of Idaho Department of Environmental Quality (IDEQ) standards rests with the Contractor. In all cases, the CO must be notified as soon as possible.

1.8 MAINTENANCE OF POLLUTION CONTROL FACILITIES

The Contractor shall maintain all constructed facilities and portable pollution control devices for the duration of the contract or for that length of time construction activities create the particular pollutant.

1.9 PERMITS

The Contractor shall obtain all needed permits or licenses. The Government will not obtain any permits for this project; see Contract Clause PERMITS AND RESPONSIBILITIES. The Contractor shall be responsible for implementing the terms and requirements of the appropriate permits as needed and for payment of all fees. The Contractor shall file the following environmental permits and notices (but not necessarily only these permits):

- For Rock Crushers, Hot Mix Asphalt Plants, Concrete Batch Plants, and Associated Generators the Contractors must have a Permit To Construct (PTC) approved by Idaho Department of Environmental Quality (IDEQ) prior to construction - CEV requires copies and through-put quantities to include generator hours.

- IDEQ (Idaho) Wastewater System Checklist - fully coordinated

- IDEQ (Idaho) Drinking Water System Checklist - fully coordinated

- NPDES Storm Water - if project disturbs over 5 acres, and over 1 acre after March 10, 2003. Fully coordinated.

1.10 MAINTENANCE OF POLLUTION CONTROL FACILITIES

Care shall be exercised when excavating trenches near trees. Where roots are 51 mm (Repair Aircraft Parking Apron) or 2 inches in diameter (Repair Runway) or greater, excavate the trench by hand and tunnel under the roots. When large roots are exposed, wrap them with heavy burlap for protection and to prevent drying. Trenches dug by machines adjacent to trees having roots less than 2 inches in diameter shall have the sides hand trimmed making a clean cut of the roots. Trenches having exposed tree roots shall be backfilled within 24 hours unless the roots are adequately protected by moist burlap or canvas.

1.11 RESTORATION OF LANDSCAPE (VEGETATION - SUCH AS TREES, PLANTS, AND GRASS) DAMAGE

All landscape features (vegetation - such as trees, plants, and grass) damaged or destroyed during Contractor operations outside and within the work areas shall be restored to a condition similar to that which existed prior to construction activities unless otherwise indicated on the drawings or in the specifications. This restoration shall be done at no additional cost to the Government. If the Contractor fails or refuses to repair the damage promptly, the Contracting Officer may have the necessary work performed and charge the cost to the Contractor.

All plant material shall meet specifications outlined in ANSI Z60.1 - current publication, "American Standard for Nursery Stock."

Grass areas shall be replaced in kind by sodding or seeding. Sod shall be required in all regularly maintained lawn areas and shall be installed according to American Sod Producers Association Guideline Specifications to Sodding.

Grass seeding shall be installed on a minimum 50 mm topsoil (Repair Aircraft Parking Apron), 2-inch topsoil (Repair Runway), and as recommended by the local county extension service.

Replace trees in kind with a minimum 4-inch caliper nursery stock. Shrubs, vines, and ground cover shall be replaced in kind; size to be approved by the Contracting Officer.

Acceptable replacement plant species will be determined by Contracting Officer.

APPENDIX A

DISPOSAL OF CONSTRUCTION MATERIALS

Base Landfill: The base landfill will not be available for use by the Contractor.

Recycling shall consist of sorting and delivering recyclable items to the appropriate recycle processors. Recyclable items include: wood, glass, metals, cardboard, and paper. All refuse shall be sorted for recycling or removed from the base and disposed of off the base, all at the Contractor's expense. Appropriate recycling processors are private or government entities currently accepting material for the purpose of recycling.

The Contractor shall submit a Waste Disposal and Recycling Plan for the Government's approval prior to any disposal or recycling operations on base. (See sample "Waste Disposal and Recycling Plan" below). When preparing the plan, the Contractor may contact the base Recycle Center at 828-4212 for advice and suggestions on how to best satisfy the recycling requirement. The plan shall be submitted to the Contracting Officer for coordination with 366 CES/CEV. The plan shall include, at a minimum:

- Brief description of work done under the contract,
- Identification of the major waste stream (categories of waste, e.g. wood, fixtures, cardboard, etc) to be generated,
- Intended method and location of disposal or recycling for each waste system

The Contractor may choose to dispose of any or all of the waste streams off-base.
The Contractor may choose to recover any or all of the waste streams by sending them to an off-base recycling company.
The Contractor may choose to turn in some waste streams to the base recycling program with the Government's approval. The acceptance of these waste streams depends on the Government's ability to process the waste stream and the Contractor's ability to adequately prepare the waste stream to meet the Government's condition requirements. The Government is currently encouraging the recycling of:

- Wood
- Scrap Metal
- Corrugated Cardboard
- Glass
- Paper

SAMPLE Waste Disposal and Recycling Plan

CONTRACT # _____

Brief description of Work done under the contract:

Renovate 6000 sq. ft. in building XYZ. Plumbing, electrical, and mechanical systems to be replaced. Floor plan to be changed with new floors, walls, and ceilings. Asbestos abatement planned on existing floor tile mastic and insulation.

Identification of the major waste stream (categories of waste, e.g., wood, fixtures, cardboard, etc.) to be generated.

1. Scrap Metal
2. ACM
3. Wood Waste
4. Fixtures
5. Mixed Demo Debris
6. Inert Debris

Intended method and location of disposal or recycling for each waste stream

1. Scrap Metal: Existing water pipe (copper), ductwork (steel), and electrical wiring (copper) will be turned in to the Base Recycling Center.

2. Asbestos Containing Material: ACM removed prior to renovation will be deposited in the base Asbestos landfill in accordance with all Federal, state, and local regulations.

3. Wood Waste: Contractor will keep re-usable wood scraps and turn in smaller scraps to the Base Recycling Center free of other bulk building material.

4. Plumbing and Electrical Fixtures: Contractor will salvage existing fixtures to be removed for re-use in later projects or sale to others. Fixtures will be removed from Mountain Home AFB prior to the end of the contract.

5. Mixed Demo Debris: Disposed of off base.

6. Inert Debris: Disposed of at the Mountain Home AFB inert debris site as directed by the Chief of Heavy Repair, 366 CES/CEOH.

END OF SECTION

SECTION 01320 (AR)

PROJECT SCHEDULE

PART 1 GENERAL

1.1 SUBMITTALS

Government approval is required for submittals with a "GA" designation; submittals having an "FIO" designation are for information only. The following shall be submitted in accordance with Section 01330 SUBMITTALS:

Schedules

GA Preliminary project schedule, two (2) copies.

GA initial project schedule, two (2) copies
Activity No. Sort
Predecessor/successor listing
Cost Schedule
Floppy Disk with schedule data in Standard Data Exchange Format (SDEF).
Activity Code Dictionary.

FIO Periodic schedules updates, monthly updates two (2) copies.
Floppy Disks with schedule data in Standard Data Exchange Format (SDEF).
Narrative
Activity No. Sort
Cost Schedule
Cash Flow Report (S-Curve)

Statements

Qualifications; GA .

Documentation showing qualifications of personnel preparing schedule reports.

1.2 QUALIFICATIONS

The Contractor shall designate an authorized representative who shall be responsible for the preparation of all required project schedule reports. This person shall have previously created and reviewed computerized schedules. Qualifications of this individual shall be submitted to the Contracting Officer for review with the Preliminary Project Schedule submission.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 GENERAL

Pursuant to the Contract Clause, SCHEDULE FOR CONSTRUCTION CONTRACTS a Project Schedule as described below shall be prepared. The scheduling of construction shall be the responsibility of the Contractor. Contractor management personnel shall actively participate in its development. Subcontractors and suppliers working on the project should also contribute in developing and maintaining an accurate Project Schedule. The approved Project Schedule shall be used to measure the progress of the work, to aid in evaluating time extensions, and to provide the basis of all progress payments.

3.2 BASIS FOR PAYMENT

The schedule shall be the basis for measuring Contractor progress. Lack of an approved schedule or scheduling personnel shall result in an inability of the Contracting Officer to evaluate Contractor progress for the purposes of payment. Failure of the Contractor to provide all information, as specified below, shall result in the disapproval of the entire Project Schedule submission and the inability of the Contracting Officer to evaluate Contractor progress for payment purposes. In the case where Project Schedule revisions have been directed by the Contracting Officer and those revisions have not been included in the Project Schedule, then the Contracting Officer may hold retainage up to the maximum allowed by contract, each payment period, until revisions to the Project Schedule have been made.

3.3 PROJECT SCHEDULE

The computer software system utilized by the Contractor to produce the Project Schedule shall be capable of providing all requirements of this specification including the SDEF (Standard Data Exchange Format). Failure of the Contractor to meet the requirements of this specification shall result in the disapproval of the schedule. Manual methods used to produce any required information shall require approval by the Contracting Officer.

3.3.1 Use of the Critical Path Method

The Critical Path Method (CPM) of network calculation shall be used to generate the Project Schedule. The Contractor shall provide the Project Schedule in Precedence Diagram Method (PDM)

3.3.2 Level of Detail Required

With the exception of the initial and preliminary schedule submission, the Project Schedule shall include an appropriate level of detail. Failure to develop or update the Project Schedule or provide data to the Contracting Officer at the appropriate level of detail, as specified by the Contracting Officer, shall result in the disapproval of the schedule. The Contracting Officer will use, but is not limited to, the following conditions to determine the appropriate level of detail to be used in the Project Schedule.

3.3.2.1 Activity Durations

Contractor submissions shall be required to follow the direction of the Contracting Officer regarding reasonable activity durations. Reasonable durations are those that allow the progress of activities to be accurately determined between payment periods. A rule of thumb, that the Contractor should use, is that less than 2 percent of all non-procurement activities' Original Durations shall be greater than 20 days.

3.3.2.2 Procurement Activities

Tasks related to the procurement of long lead materials or equipment shall be included as separate activities in the project schedule. Long lead materials and equipment are those materials that have a procurement cycle of over 90 days. Examples of procurement process activities include, but are not limited to: submittals, approvals, procurement, fabrication, delivery, installation, start-up, and testing.

3.3.2.3 Government Activities

Government and other agencies activities that could impact progress shall be shown. These activities include, but are not limited to: approvals, inspections, utility tie-in, Government Furnished Equipment (GFE) and notice to proceed for phasing requirements.

3.3.2.4 Responsibility

All activities shall be identified in the project schedule by the party responsible to perform the work. Responsibility includes, but is not limited to, the subcontracting firm, (at the lowest tier), Contractor work force, or Government agency performing a given task. Activities shall not belong to more than one responsible party. The responsible party for each activity shall be identified by the Responsibility Code.

3.3.2.5 Work Areas

All activities shall be identified in the project schedule by the work area in which the activity occurs. Activities shall not be allowed to cover more than one work area. The work area of each activity shall be identified by the Work Area Code.

3.3.2.6 Modification or Claim Number

Any activity that is added or changed by contract modification or used to justify claimed time shall be identified by a mod or claim code that changed the activity. Activities shall not belong to more than one modification or claim item. The modification or claim number of each activity shall be identified by the Mod or Claim Number.

3.3.2.7 Bid Item

All activities shall be identified in the project schedule by the Bid Item to which the activity belongs. An activity shall not contain work in more than one bid item. The bid item for each appropriate activity shall be identified by the Bid Item Code.

3.3.2.8 Category of Work

All Activities shall be identified in the project schedule according to the category of work which best describes the activity. Category of work refers, but is not limited to, to the procurement chain of activities including such items as submittals, approvals, procurement, fabrication, delivery, installation, start-up, and testing. The category of work for each activity shall be identified by the Category of Work Code.

3.3.2.9 Feature of Work

All activities shall be identified in the project schedule according to the feature of work to which the activity belongs. Feature of work refers, but is not limited to a work breakdown structure for the project. The feature of work for each activity shall be identified by the Feature of Work Code.

3.3.2.10 Critical Activities

The following activities shall be listed as separate line activities on a Contractor's project schedule:

- submission and approval of mechanical/electric layout drawings
- submission and approval of as-built drawings
- submission and approval of 1354 data and installed equipment lists
- submission of TAB specialist design review report
- submission and approval of fire protection specialist
- any other systems testing
- prefinal inspection correction of punchlist from prefinal inspection
- final inspection

3.3.3 Scheduled Project Completion

The schedule interval shall extend from notice-to-proceed to the contract completion date.

3.3.3.1 Project Start Date

The schedule shall start no earlier than the date that the Notice to Proceed (NTP) was acknowledged. The Contractor shall include as the first activity in the project schedule an activity called "Start Project". The "Start Project" activity shall have: a "ES" constraint, a constraint date equal to the date that the NTP was acknowledged, and a zero day duration.

3.3.3.2 Constraint of Last Activity

Completion of the last activity in the schedule shall be constrained by the contract completion date. Calculation on project updates shall be such that if the early finish of the last activity falls after the contract completion date, then the float calculation shall reflect a negative float on the critical path. The Contractor shall include as the last activity in the project schedule an activity call "End Project". The "End Project" activity shall have: a "LF" constraint, a constraint date equal to the completion date for the project, and a zero day duration.

3.3.3.3 Early Project Completion

In the event the project schedule shows completion of the project prior to the contract completion date, the Contractor shall identify those activities that have been accelerated and/or those activities that are scheduled in parallel to support the Contractor's "early" completion. Contractor shall specifically address each of the activities noted at every project schedule update period to assist the Contracting Officer to evaluate the Contractor's ability to actually complete prior to the contract period.

3.3.4 Interim Completion Dates

Contractually specified interim completion dates shall also be constrained to show negative float if the early finish date of the last activity in that phase falls after the interim completion date.

3.3.5 Default Progress Data Disallowed

Actual Start and Finish dates shall not be automatically updated by default mechanisms that may be included in CPM scheduling software systems. Actual Start and Finish dates on the CPM schedule shall match those dates provided from Contractor Quality Control Reports. Failure of the Contractor to document the Actual Start and Finish dates on the Daily Quality Control report for every in progress or completed activity and insure that the data contained on the Daily Quality Control reports is the sole basis for schedule updating shall result in the disapproval of the Contractor's schedule and the inability of the Contracting Officer to evaluate Contractor progress for payment purposes.

3.3.6 Out-of-Sequence Progress

Activities that have posted progress without predecessors being completed (Out-of-Sequence Progress) shall be allowed only by the case-by-case approval of the Contracting Officer. The Contracting Officer may direct that changes in schedule logic be made to correct any or all out-of-sequence work.

3.3.7 Negative Lags

Lag durations contained in the project schedule shall not have a negative value.

3.4 PROJECT SCHEDULE SUBMISSIONS

The Contractor shall provide the submissions as described below. The data disk, reports, and network diagrams required for each submission are contained in paragraph SUBMISSION REQUIREMENTS.

3.4.1 Preliminary Project Schedule Submission

The Preliminary Project Schedule, defining the Contractor's planned operations for the first 60 calendar days shall be submitted for approval within 10 calendar days after Notice to Proceed is acknowledged. The approved preliminary schedule shall be used for payment purposes not to exceed 60 calendar days after Notice to Proceed.

3.4.2 Initial Project Schedule Submission

The Initial Project Schedule shall be submitted Contractor Proposal Notice to Proceed. The schedule shall provide a reasonable sequence of activities which represent work through the entire project and shall be at a reasonable level of detail.

3.4.3 Periodic Schedule Updates

Based on the result of progress meetings, specified in "Periodic Progress Meetings," the Contractor shall submit periodic schedule updates. These submissions shall enable the Contracting Officer or to assess Contractor's progress. If the Contractor fails or refuses to furnish the information and project schedule data, which in the judgment of the Contracting Officer or authorized representative, is necessary for verifying the contractor's progress, the Contractor shall be deemed not to have provided an estimate upon which progress payment may be made.

3.4.4 Standard Activity Coding Dictionary

The Contractor shall submit, with the Initial Project Schedule, a coding scheme that shall be used throughout the project for all activity codes contained in the schedule. The coding scheme submitted shall list the values for each activity code category and translate those values into project specific designations. For example, a Responsibility Code Value, "ELE", may be identified as "Electrical Subcontractor." Activity code values shall represent the same information throughout the duration of the contract. Once approved with the Initial Project Schedule submission, changes to the activity coding scheme must be approved by the Contracting Officer.

3.5 SUBMISSION REQUIREMENTS

The as noted in paragraph 1.1 items shall be submitted by the Contractor for the initial submission, and every periodic project schedule update throughout the life of the project:

3.5.1 Data Disks

Two data disks containing the project schedule shall be provided. Data on the disks shall be in the format specified in paragraph 3.10 NAS DATA.

3.5.1.1 File Medium

Required data shall be submitted on 89 mm (3.5 inch) disks, formatted to hold 1.44 MB of data.

3.5.1.2 Disk Label

A permanent exterior label shall be affixed to each disk submitted. The label shall indicate the type of schedule (Initial, Update, or Change), full contract number, project name, project location, data date, name and telephone number or person responsible for the schedule, and the version used to prepare the C.P.M.

3.5.1.3 File Name

Each file submitted shall have a name related to either the schedule data date, project name, or contract number. The Contractor shall develop a naming convention that will insure that the names of the files submitted are unique. The Contractor shall submit the file naming convention to the Contracting Officer for approval.

3.5.2 Narrative Report

A Narrative Report shall be provided with each update of the project schedule. This report shall be provided as the basis of the Contractor's progress payment request. The Narrative Report shall include: a description of activities along the critical path, a description of current and anticipated problem areas or delaying factors and their impact, and an explanation of corrective actions taken.

3.5.3 Approved Changes Verification

Only project schedule changes that have been previously approved by the Contracting Officer shall be included in the schedule submission. The Narrative Report shall specifically reference, on an activity by activity basis, all changes made since the previous period and relate each change to documented, approved schedule changes.

3.5.4 Schedule Reports

The format for each activity for the schedule reports listed below shall contain: Activity Numbers, Activity Description, Original Duration, Remaining Duration, Early Start Date, Early Finish Date, Late Start Date, Late Finish Date, Total Float. Actual Start and Actual Finish Dates shall be printed for those activities in-progress or completed.

3.5.4.1 Activity Report

A list of all activities sorted according to activity number. For completed activities the Actual Start Date shall be used as the secondary sort.

3.5.4.2 Logic Report

A list of Preceding and Succeeding activities for every activity in ascending order by activity number and then sorted according to Early Start Date. For completed activities the Actual Start Date shall be used as the secondary sort.

3.5.4.3 Total Float Report

A list of all activities sorted in ascending order of total float. Activities which have the same amount of total float shall be listed in ascending order of Early Start Dates.

3.5.4.4 Earnings Report

A compilation of the Contractor's Total Earnings on the project from the Notice to Proceed until the most recent Monthly Progress Meeting. This report shall reflect the Earnings of specific activities based on the agreements made in the field and approved between the Contractor and Contracting Officer at the most recent Monthly Progress Meeting. Provided that the Contractor

has provided a complete schedule update, this report shall serve as the basis of determining Contractor Payment. Activities shall be grouped by bid item and sorted by activity numbers. This report shall: sum all activities in a bid item and provide a bid item percent; complete and sum all bid items to provide a total project percent complete. The printed report shall contain, for each activity: Activity Number, Activity Description, Original Budgeted Amount, Total Quantity, Quantity to Date, Percent Complete (based on cost), Earnings to Date.

3.5.4.5 Cash Flow Report

A report showing scheduled cost of work-in-place by week (tabular report) and a cash flow curve by week (S-curve plot), both based on early dates.

3.5.5 Network Diagram

The time scaled network diagram shall be required on the initial schedule submission and on quarterly update submissions. The network diagram shall depict and display the order and interdependence of activities and the sequence in which the work is to be accomplished. The Contracting Officer will use, but is not limited to, the following conditions to review compliance with this paragraph:

3.5.5.1 Continuous Flow

Diagrams shall show a continuous flow from left to right with no arrows from right to left. The activity or event number, description, duration, and estimated earned value shall be shown on the diagram.

3.5.5.2 Project Milestone Dates

Dates shall be shown on the diagram for start of project, any contract required interim completion dates, and contract completion dates.

3.5.5.3 Critical Path

The critical path shall be clearly shown.

3.5.5.4 Banding

Activities shall be grouped to assist in the understanding of the activity sequence. Typically, this flow will group activities by category of work, work area and/or responsibility.

3.5.5.5 S-Curves

Earnings curves shall be provided showing projected early and late earnings and earnings to date.

3.6 PERIODIC PROGRESS MEETINGS

Progress meetings to discuss payment shall include a monthly on-site meeting or other regular intervals mutually agreed to at the preconstruction conference. During this meeting the Contractor will describe, on an activity by activity basis, all proposed revisions and adjustments

to the project schedule required to reflect the current status of the project. The Contracting Officer will approve activity progress, proposed revisions, and adjustments as appropriate.

3.6.1 Meeting Attendance

The Contractor's Project Manager and Scheduler shall attend the regular progress meeting.

3.6.2 Update Submission Following Progress Meeting

A complete update of the project schedule containing all approved progress, revisions, and adjustments, based on the regular progress meeting, shall be submitted not later than 4 working days after the monthly progress meeting.

3.6.3 Progress Meeting Contents

Update information, including Actual Start Dates, Actual Finish Dates, Remaining Durations, and Cost to Date shall be subject to the approval of the Contracting Officer. The following minimum set of items which the Contractor shall address, on an activity by activity basis, during each progress meeting.

3.6.3.1 Start and Finish Dates

The Actual Start and Actual Finish dates for each activity currently in-progress or completed activities.

3.6.3.2 Time Completion

The estimated Remaining Duration for each activity in-progress. Time-based progress calculations must be based on Remaining Duration for each activity.

3.6.3.3 Cost Completion

The earnings for each activity started. Payment shall be based on earnings for each in-progress or completed activity. Payment for individual activities shall not be made for work that contains quality defects. A portion of the overall project amount may be retained based on delays of activities.

3.6.3.4 Logic Changes

All logic changes pertaining to Notice to Proceed on change orders, change orders to be incorporated into the schedule, contractor proposed changes in work sequence, corrections to schedule logic for out-of-sequence progress, lag durations, and other changes that have been made pursuant to contract provisions shall be specifically identified and discussed.

3.6.3.5 Other Changes

Other changes required due to delays in completion of any activity or group of activities are those delays beyond the Contractors control such as strikes and unusual weather. Also included are delays encountered due to submittals, Government Activities, deliveries or work stoppage which

makes re-planning the work necessary, and when the schedule does not represent the actual prosecution and progress of the work.

3.7 REQUESTS FOR TIME EXTENSIONS

In the event the Contractor requests an extension of the contract completion date, he shall furnish such justification, project schedule data and supporting evidence as the Contracting Officer may deem necessary for a determination as to whether or not the Contractor is entitled to an extension of time under the provisions of the contract. Submission of proof of delay, based on revised activity logic, duration, and costs (updated to the specific date that the delay occurred) is obligatory to any approvals.

3.7.1 Justification of Delay

The project schedule must clearly display that the Contractor has used, in full, all the float time available for the work involved with this request. The Contracting Officer's determination as to the number of allowable days of contract extension, shall be based upon the project schedule updates in effect for the time period in question and other factual information. Actual delays that are found to be caused by the Contractor's own actions, which result in the extension of the schedule, shall not be a cause for a time extension to the contract completion date.

3.7.2 Submission Requirements

The Contractor shall submit a justification for each request for a change in the contract completion date of under two weeks based upon the most recent schedule update at the time of the Notice to Proceed or constructive direction issued for the change. Such a request shall be in accordance with the requirements of other appropriate Contract Clauses and shall include, as a minimum:

a. A list of affected activities, with their associated project schedule activity number.

b. A brief explanation of the causes of the change.

c. An analysis of the overall impact of the changes proposed.

d. A sub-network of the affected area.

Activities impacted in each justification for change shall be identified by a unique activity code contained in the required data file.

3.7.3 Additional Submission Requirements

For any request for time extension for over 2 weeks, the Contracting Officer may request an interim update with revised activities for a specific change request. The Contractor shall provide this disk within 4 days of the Contracting Officer's request.

3.8 DIRECTED CHANGES

If Notice to Proceed (NTP) is issued for changes prior to settlement of price and/or time, the Contractor shall submit proposed schedule revisions to the Contracting Officer within 2 weeks of

the NTP being issued. The proposed revisions to the schedule will be approved by the Contracting Officer prior to inclusion of those changes within the project schedule. If the Contractor fails to submit the proposed revisions, the Contracting Officer may furnish the Contractor suggested revisions to the project schedule. The Contractor shall include these revisions in the project schedule until the Contractor submits revisions, and final changes and impacts have been negotiated. If the Contractor has any objections to the revisions furnished by the Contracting Officer, then the Contractor shall advise the Contracting Officer within 2 weeks of receipt of the revisions. Regardless of the objections, the Contractor will continue to update their schedule with the Contracting Officer's revisions until a mutual agreement in the revisions may be made. If the Contractor fails to submit alternative revisions within 2 weeks of receipt of the Contracting Officer's proposed revisions, the Contractor will be deemed to have concurred with the Contracting Officer's proposed revisions. The proposed revisions will then be the basis for an equitable adjustment for performance of the work.

3.9 OWNERSHIP OF FLOAT

Float available in the schedule, at any time, shall not be considered for the exclusive use of either the Government or the Contractor.

3.10 NAS DATA

The Contractor shall provide the Government with the means to electronically transfer all required NAS data into the Resident Management System (RMS) program using the Standard Data Exchange Format (SDEF). The Contractor may use network analysis software different from that used by the Contracting Officer in the Resident Office, however, the Contractor shall also furnish the following:

NAS data that complies with the Standard Data Exchange Format (SDEF). This is a standard ASCII format for exchanging scheduling data and is compatible with our resident management system. Many software developers provide the capability to convert and export schedule data to the SDEF at no additional cost. The SDEF specifications are in a separate publication, available from the Internet WWW.CECER.AARMY.MIL/PL/SDEF.

END OF SECTION

This page intentionally blank

SECTION 01330 (AR)

SUBMITTAL PROCEDURES

PART 1 GENERAL

1.1 CONTROL AND SCHEDULING OF SUBMITTALS

1.1.1 Submittal Coordination Meeting

After the preconstruction conference and before any submittals are sent to the Contracting Officer's Representative (COR), the Contractor shall meet with the COR and provide and further develop an approved preliminary submittal register, ENG Form 4288. During the meeting all required items will be identified and grouped into three categories:

- Government Approved (GA)

Government approval is required for extensions of design, critical materials, variations/deviations, an "or equal" decision, equipment whose compatibility with the entire system must be checked, architectural items such as Color Charts/Patterns/Textures, and other items as designated by the COR. Within the terms of the Contract Clause entitled "Specifications and Drawings for Construction," these submittals will be acted on as "shop drawings."

- For Information Only (FIO)

Submittals not requiring Government approval will be for information only. These are items such as Installation Procedures, Certificates of compliance, Samples, Qualifications, etc. Within the terms of the Contract Clause entitled "Specifications and Drawings for Construction," these submittals will not be acted on as "shop drawings."

- Those items that can be visually inspected by the Contractor's Quality Control Representative (CQC) on site or are provided to the Government other than with an ENG Form 4025: The items that fall into this category shall remain on the register but shall not be submitted to the COR. For these items, the "Classification" column on the submittal register shall remain blank.

1.1.2 Final Submittal Register

The final submittal register shall be coordinated with the progress schedule and submitted within 40days of Notice to Proceed. In preparing the final document, adequate time (minimum of 30 days) shall be allowed for review and approval, and possible resubmittal of each item on the register.

1.1.3 Submittal Register Updates

The Contractor's quality control representative shall review the listing at least every 30 days and take appropriate action to maintain an effective system. Copies of updated or corrected listings shall be submitted to the COR at least every 30 days in the quantity specified.

1.2 SUBMITTAL TYPES

Throughout these specifications submittals may be identified with the prefix "SD" (submittal data) followed by a number (category, i.e., data, drawings, reports, etc.). This is for bookkeeping and record sorting in the system:

Data

Submittals which provide calculations, descriptions, or documentation regarding the work.

Drawings

Submittals which graphically show relationship of various components of the work, schematic diagrams of systems, details of fabrication, layouts of particular elements, connections, and other relational aspects of the work.

Instructions

Preprinted material describing installation of a product, system or material, including special notices and material safety data sheets, if any, concerning impedances, hazards, and safety precautions.

Schedules

Tabular lists showing location, features, or other pertinent information regarding products, materials, equipment, or components to be used n the work.

Statements

A document, required of the Contractor, or through the Contractor from a subcontractor, supplier, installer, or manufacturer to confirm the quality or orderly progression of a portion of the work by documenting procedures, acceptability of methods or personnel, qualifications, or other quality verifications.

Reports

Reports of inspections or tests, including analyses and interpretation of test results. Each report shall be properly identified. Test methods used shall be identified and test results shall be recorded.

Certificates

Statement signed by an official authorized to certify on behalf of the manufacturer that a product, system or material meets specified requirements. The statement must be dated after the award of this contract and state the Contractor's name and address, project and location, and list specific requirements which are being certified.

Samples

Fabricated and/or unfabricated physical examples of materials, products, and/or units of work as complete units or as portions of units.

Records

Documentation to record compliance with technical or administrative requirements.

Operation and Maintenance Manuals

Data which forms a part of an operation and maintenance manual.

Submittals required by the Contract Clauses and other non-technical parts of the contract are not necessarily included in this section. These type of submittals can be added to the register before or during the submittal coordination meeting.

1.3 APPROVED SUBMITTALS

The approval of submittals by the COR shall not be construed as a complete check, but will indicate only that the general method of construction, materials, detailing and other information are satisfactory. Approval will not relieve the Contractor of the responsibility for any error which may exist. The Contractor, under the CQC requirements of this contract, is responsible for the dimensions and design of adequate connections, details, and satisfactory construction of all work. After submittals have been approved by the COR, no resubmittal for the purpose of substituting materials or equipment will be given consideration.

1.4 DISAPPROVED SUBMITTALS

The Contractor shall make all corrections required by the COR and promptly furnish a corrected submittal in the format and number of copies specified for the initial submittal. If the Contractor considers any correction indicated on the submittals to constitute a change to the contract, written notice, as required under the Contract Clause entitled "Changes," shall be given to the COR.

1.5 PAYMENT

Separate payment will not be made for submittals, and all costs associated therein shall be included in the applicable unit prices or lump sum prices contained in the schedule. Payment will not be made for any material or equipment which does not comply with contract requirements.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 GENERAL

Prior to submittal, all items shall be checked and approved by the Contractor's CQC and each item of the submittal shall be stamped, signed, and dated. Each respective transmittal form (ENG Form 4025) shall be signed and dated by the CQC certifying that the accompanying submittal complies with the contract requirements. This procedure applies to all submittals. Submittals shall include items such as: Contractor's, manufacturer's, or fabricator's drawings; descriptive literature including, but not limited to, catalog cuts, diagrams; operating charts or curves; test reports; test cylinders; samples; O&M manuals including parts lists; certifications; warranties and other such required items. Units of weights and measures used on all submittals

shall be the same as the contract drawings. Each submittal shall be complete and in sufficient detail to allow ready determination of compliance with contract requirements. GA submittals shall be scheduled and made prior to the acquisition of the material or equipment covered thereby. The COR may request submittals in addition to those listed when deemed necessary to adequately describe the work covered in the respective sections. The Contractor shall maintain a complete and up-to-date file of all submittals/items on site for use by both the Contractor and the Government.

3.2 SUBMITTAL REGISTER (ENG Form 4288)

The submittal register - ENG Form 4288 – for Divisions 1 through 16 shall be developed by the Contractor prior to the submittal coordination meeting and list each item of equipment and material for which submittals are required in the Technical Specifications. (See paragraph SUBMITTALS at the beginning of each specification section. A blank form ENG 4288 is attached at the end of this specification section.) The Contractor shall approve all items listed on the submittal register. During the submittal coordination meeting, a preliminary submittal register will be created by annotating this Form 4288. When the final submittal register is submitted for approval, the Contractor shall complete the column entitled “Item No.” and all data under “Contractor Schedule Dates” and return five completed copies to the COR for approval. The Contractor shall review the list to ensure its completeness and may expand general category listings to show individual entries for each item. The numbers in column “Item No.” are to be assigned sequentially starting with "1" for each specification section. DO NOT preassign transmittal numbers when preparing the submittal register. When a conflict exists between the submittal register and a submittal requirement in the technical sections, other than those submittals referenced in Paragraph 3.9: Field Test Reports, the approved submittal register shall govern. The preliminary, and then the final approved submittal register, will become the scheduling documents and will be updated monthly and used to control submittals throughout the life of the contract. Names and titles of individuals authorized by the Contractor to approve shop drawings shall be submitted to COR with the final 4288 form. Supplier or subcontractors certifications are not acceptable as meeting this requirement.

3.3 SCHEDULING

Submittals covering component items forming a system, or items that are interrelated, shall be coordinated and submitted concurrently. Certifications shall be submitted together with other pertinent information and/or drawings. Additional processing time beyond 30 days, or number of copies, may be shown by the COR on the submittal register attached in the “Remarks” column, or may be added by the COR during the coordination meeting. No delays damages or time extensions will be allowed for time lost due to the Contractor not properly scheduling and providing submittals.

3.4 TRANSMITTAL FORM (ENG Form 4025)

Transmittal Form 4025 (sample at end of this section) shall be used for submitting both GA and FIO submittals in accordance with the instructions on the reverse side of the form. Transmittal numbers shall be assigned sequentially. Electronic generated 4025 forms shall be printed on carbonless paper and be a reasonable facsimile of the original 4025. If electronic forms are not used, the original 4025 forms shall be used (do not photo copy) and will be furnished by the COR. These forms shall be filled in completely prior to submittal. Special care shall be exercised to ensure proper listing of the specification paragraph and/or sheet number of the contract drawings pertinent to the data submitted for each item.. Each submittal item shall be

listed separately on the form, naming subcontractor, supplier, or manufacturer, applicable specification paragraph number(s), drawing/sheet number, pay item number, and any other information needed to identify the item, define its use, and locate it in the work. One or more 4025 forms may be used per specification section, however, DO NOT include more than one specification section per transmittal.

3.5 CROSS-REFERENCE (ENG FORM 4288/ENG FORM 4025)

To provide a cross-reference between the approved submittal register and transmittal forms, the Contractor shall record the "transmittal numbers" assigned when submitting items in column “Transmittal No.” of the ENG FORM 4288. The item numbers in column “Item No.” of submittal register shall correspond to the item numbers on ENG Form 4025.

3.6 SUBMITTAL PROCEDURE

3.6.1 General

Shop drawings with 4025 forms shall be submitted in the number of copies specified in subparagraphs "Government Approved Submittals" and "Information Only Submittals," or as indicated on the submittal register in the “Remarks” column. Submit a complete collated “reviewers copy” with one 4025 form and attachments (not originals). The remaining copies (4 for GA, 2 for FIO) of 4025 forms and attachments shall not be collated. This would not apply to a series of drawings.

3.6.2 Approval of Submittals by the Contractor

Before submittal to the COR, the Contractor shall review and correct shop drawings prepared by subcontractors, suppliers, and itself, for completeness and compliance with plans and specifications. The Contractor shall not use red markings for correcting material to be submitted. Red markings are reserved for COR’s use. Approval by the Contractor shall be indicated on each shop drawing by an approval stamp containing information as shown in this section. Submittals not conforming to the requirements of this section will be returned to the Contractor for correction and resubmittal.

3.6.3 Variations

For submittals which include proposed variations requested by the Contractor, column “h” of ENG Form 4025 shall be checked and the submittal shall be classified as GA, and submitted accordingly. The Contractor shall set forth in writing the justification for any variations and annotate such variations on the transmittal form in the REMARKS block. Variations are not approved unless there is an advantage to the Government. The Government reserves the right to rescind inadvertent approval of submittals containing unnoted variations.

3.6.4 Drawings

Each drawing shall be not larger than A1 size (841 mm wide by 594 mm high), with a title block in lower right hand corner and a 75 mm by 100 mm (3 by 4 inch) clear area adjacent. The title block shall contain the subcontractor's or fabricator's name, contract number, description of item(s), bid item number, and a revision block. Provide a blank margin of 20 mm (3/4 inch) at bottom, 50 mm (2 inches) at left, and 10 mm (1/2 inch) at top and right. Where drawings are submitted for assemblies of more than one piece of equipment or systems of components

dependent on each other for compatible characteristics, complete information shall be submitted on all such related components at the same time. The Contractor shall ensure that information is complete and that sequence of drawing submittal is such that all information is available for reviewing each drawing. Drawings for all items and equipment, of special manufacture or fabrication, shall consist of complete assembly and detail drawings. All revisions after initial submittal shall be shown by number, date, and subject in revision block.

3.6.4.1 Submittals Containing Drawings Larger than A3 size (297 mm high by 420 mm wide)

For GA submittals containing drawings larger than A3 size, one reproducible and one blue line copy will be required to be submitted with five copies of the ENG Form 4025. The marked-up reproducible (and/or any review comments contained on the page-size comment sheet(s) at the Government's option) will be returned to the Contractor upon review. The Contractor shall provide three copies of blue line drawings (generated from the reviewed reproducible) to the Government within 10 days of Contractor's receipt of the reviewed reproducible. The Contractor shall not incorporate approved work into the project until the Government has received the three blue line copies. The Contractor shall use the marked-up reproducible to make any additional copies as needed. For FIO submittals, one reproducible and two blue line copies shall be submitted with the appropriate number of copies of ENG Form 4025.

3.6.5 Printed Material

All requirements for shop drawings shall apply to catalog cuts, illustrations, printed specifications, or other data submitted, except that the 75 mm by 100 mm (3 inch by 4 inch) clear area adjacent to the title block is not mandatory. Inapplicable portions shall be marked out and applicable items such as model numbers, sizes, and accessories shall be indicated by arrow or highlighted.

3.7 SAMPLES REQUIRING LABORATORY ANALYSIS

See Section 01451CONTRACTOR QUALITY CONTROL for procedures and address for samples requiring Government testing.

3.8 SAMPLES REQUIRING VISUAL INSPECTION

Samples requiring only physical inspection for appearance and suitability shall be coordinated with the on-site Government quality assurance representative (QAR).

3.9 FIELD TEST REPORTS

Routine tests such as soil density, concrete deliveries, repetitive pressure testing shall be delivered to the QAR with the daily Quality Control reports. See SECTION: 01451 CONTRACTOR QUALITY CONTROL.

3.10 CONTROL OF SUBMITTALS

The Contractor shall carefully control his procurement operations to ensure that each individual submittal is made on or before the Contractor scheduled submittal date shown on the approved "Submittal Register."

3.11 GOVERNMENT APPROVED SUBMITTALS (GA)

The Contractor shall submit 5 copies of GA submittals with 5 corresponding 4025 forms. Upon completion of GA submittal review, copies as specified below will be marked with an action code, dated, and returned to the Contractor. See “Drawings” above for special instructions if drawings larger than size A3 are used.

3.11.1 Processing of GA Submittals

Submittals will be reviewed and processed as follows:

a. Approved as Submitted (Action Code "A"): Shop drawings which can be approved without correction will be stamped "Approved" and two copies will be returned to the Contractor. No resubmittal required.

b. Approved Except as Noted (Action Code "B"): Shop drawings which have only minor discrepancies will be annotated in red to indicate necessary corrections. Marked material will be stamped "Approved Except as Noted" and two copies returned to the Contractor for correction. No resubmittal required.

c. Approved Except as Noted (Action Code "C"): Shop drawings which are incomplete or require more than minor corrections will be annotated in red to indicate necessary corrections. Marked material will be stamped "Approved Except as Noted - Resubmission Required" and two copies returned to the Contractor for correction. Resubmittal of only those items needing correction required.

d. Disapproved (Action Code "E"): Shop drawings which are fundamentally in error, cover wrong equipment or construction, or require extensive corrections, will be returned to the Contractor stamped "Disapproved." An explanation will be furnished on the submitted material or on ENG Form 4025 indicating reason for disapproval. Complete resubmittal required.

e. Resubmittal will not be required for shop drawings stamped "A" or "B" unless subsequent changes are made by Contractor or a contract modification. For shop drawings stamped "C" or "E," Contractor shall make corrections required, note any changes by dating the revisions to correspond with the change request date, and promptly resubmit the corrected material. Resubmittals shall be associated with the “parent” by use of sequential alpha characters (for example, resubmittal of transmittal 8 will be 8A, 8B, etc). Government costs incurred after the first resubmittal may be charged to the Contractor.

3.12 INFORMATION ONLY SUBMITTALS (FIO)

The Contractor shall submit three copies of data and four copies of ENG Form 4025. FIO submittals will not be returned. Government approval is not required on FIO submittals. These submittals will be used for information purposes. The Government reserves the right to require the Contractor to resubmit any item found not to comply with the Contract. This does not relieve the Contractor from the obligation to furnish material conforming to the plans and specifications and will not prevent the COR from requiring removal and replacement if nonconforming material is incorporated in the work. This does not relieve the Contractor of the requirement to furnish samples for testing by the Government laboratory or check testing by the Government in those instances where the technical specifications so prescribe.

3.12.1 Processing of FIO Submittals

FIO submittals shall be submitted prior to delivery of the material or equipment to the job site. ENG Form 4025 shall be marked with the words "contractor approved - information copy only" in the REMARKS block of the form. Submittals will be monitored and spot checks made. When such checks indicate noncompliance, the Contractor will be notified by the same method used for GA submittals. Resubmittal of nonconforming FIO submittals shall be reclassified GA and shall be in five copies.

3.13 CONTRACTOR APPROVAL STAMP

The stamp used by the Contractor on the submittal data to certify that the submittal meets contract requirements shall be similar to the following:

CONTRACTOR:
_____
CONTRACT NUMBER
_____

TRANSMITTAL NUMBER _____
ITEM NUMBER _____
SPECIFICATION SECTION _____
PARAGRAPH NUMBER _____
_____ APPROVED AS SUBMITTED
_____ APPROVED WITH CORRECTIONS AS NOTED

SIGNATURE: _____
TITLE: _____
DATE _____

CONTRACTORS REVIEW STAMP

MAXIMUM SIZE:

3 INCHES BY 3 INCHES

TRANSMITTAL OF SHOP DRAWINGS, EQUIPMENT DATA, MATERIAL SAMPLES, OR MANUFACTURER'S CERTIFICATES OF COMPLIANCE *(Read instructions on the reverse side prior to initiating this form)*	DATE	TRANSMITTAL NO.

SECTION I - REQUEST FOR APPROVAL OF THE FOLLOWING ITEMS *(This section will be initiated by the contractor)*

TO:	FROM:	CONTRACT NO.	CHECK ONE: ☐ THIS IS A NEW TRANSMITTAL ☐ THIS IS A RESUBMITTAL OF TRANSMITT/_____
SPECIFICATION SEC. NO. *(Cover only one section with each transmittal)*	PROJECT TITLE AND LOCATION		CHECK ONE: THIS TRANSMITTAL IS FOR ☐ FIO ☐ GOV'T. APPROVAL

ITEM NO. *a.*	DESCRIPTION OF ITEM SUBMITTED *(Type size, model number/etc.) b.*	MFG OR CONTR. CAT., CURVE DRAWING OR BROCHURE NO. *(See instruction no. 8) c.*	NO. OF COPIES *d.*	CONTRACT REFERENCE DOCUMENT		FOR CONTRACTOR USE CODE *g.*	VARIATION *(See instruction No. 8) h.*	FOR CE USE CODE *i.*
				SPEC. PARA. NO. *e.*	DRAWING SHEET NO. *f.*			

REMARKS

I certify that the above submitted items have been reviewed in detail and are correct and in strict conformance with the contract drawings and specifications except as otherwise stated.

_____

NAME AND SIGNATURE OF CONTRACTOR

SECTION II - APPROVAL ACTION

ENCLOSURES RETURNED *(List by Item No.)*	NAME, TITLE AND SIGNATURE OF APPROVING AUTHORITY	DATE

INSTRUCTIONS

1. Section I will be initiated by the Contractor in the required number of copies.

2. Each transmittal shall be numbered consecutively in the space provided for "Transmittal No.". This number, in addition to the contract number, will form a serial number for identifying each submittal. For new submittals or resubmittals mark the appropriate box; on resubmittals, insert transmittal number of last submission as well as the new submittal number.

3. The "Item No." will be the same "Item No." as indicated on ENG FORM 4288-R for each entry on this form.

4. Submittals requiring expeditious handling will be submitted on a separate form.

5. Separate transmittal form will be used for submittals under separate sections of the specifications.

6. A check shall be placed in the "Variation" column when a submittal is not in accordance with the plans and specifications--also, a written statement to that effect shall be included in the space provided for "Remarks".

7. Form is self-transmittal, letter of transmittal is not required.

8. When a sample of material or Manufacturer's Certificate of Compliance is transmitted, indicate "Sample" or "Certificate" in column c, Section I.

9. U.S. Army Corps of Engineers approving authority will assign action codes as indicated below in space provided in Section I, column i to each item submitted. In addition they will ensure enclosures are indicated and attached to the form prior to return to the contractor. The Contractor will assign action codes as indicated below in Section I, column g. to each item submitted.

THE FOLLOWING ACTION CODES ARE GIVEN TO ITEMS SUBMITTED

A	--	Approved as submitted.	E	--	Disapproved (See attached).
B	--	Approved, except as noted on drawings.	F	--	Receipt acknowledged.
C	--	Approved, except as noted on drawings. Refer to attached sheet resubmission required.	FX	--	Receipt acknowledged, does not comply as noted with contract requirements.
D	--	Will be returned by separate correspondence.	G	--	Other *(Specify)*

10. Approval of items does not relieve the contractor from complying with all the requirements of the contract plans and specifications.

(Reverse of ENG Form 4025-R)

SUBMITTAL REGISTER

(ER 415-1-10)

CONTRACT NUMBER

TITLE AND LOCATION

CONTRACTOR

SPECIFICATION SECTION

					TYPE OF SUBMITTAL											CLASSIFICATION			CONTRACTOR SCHEDULE DATES			CONTRACTOR ACTION			GOVERNMENT ACTION		
ACTIVITY NO.	TRANSMITTAL NO	ITEM NO	SPECIFICATION PARAGRAPH NUMBER	DESCRIPTION OF ITEM SUBMITTED	DATA	DRAWINGS	INSTRUCTIONS	SCHEDULES	STATEMENTS	REPORTS	CERTIFICATES	SAMPLES	RECORDS	OPERATION AND MAINTENANCE	INFORMATION ONLY	GOVERNMENT APPROVED	REVIEWER	SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	CODE	DATE	SUBMIT TO GOVERNMENT	CODE	DATE	REMARKS
a.	b.	c.	d.	e.	f.	g.	h.	i.	j.	k.	l.	m.	n.	o.	p.	q.	r.	s.	t.	u.	v.	w.	x.	y.	z.	aa.

End of Section 01300-10

ENG FORM 4288-R, JAN 97 EDITION OF MAR 95 IS OBSOLETE PAGE 1 OF _____ PAGES (Proponent: CEMP-CE)

This page intentionally blank

SECTION 01451 (AR)

CONTRACTOR QUALITY CONTROL

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 3740	(1999b) Minimum Requirements for Agencies Engaged in the Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction
ASTM E 329	(1998a) Agencies Engaged in the Testing and/or Inspection of Materials Used in Construction

1.2 PAYMENT

Separate payment will not be made for providing and maintaining an effective Quality Control program, and all costs associated therewith shall be included in the applicable unit prices or lump-sum prices contained in the Bidding Schedule.

1.3 LABORATORY VALIDATION

The testing laboratory shall be validated by Corps of Engineers Material Testing Center (MTC) for all tests required by contract. See paragraph 3.7 TESTS.

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

The Contractor is responsible for quality control and shall establish and maintain an effective quality control system in compliance with the Contract Clause titled "Inspection of Construction." The quality control system shall consist of plans, procedures, and organization necessary to produce an end product which complies with the contract requirements. The system shall cover all construction operations, both onsite and offsite, and shall be keyed to the proposed construction sequence. The site project superintendent will be held responsible for the quality of work on the job and is subject to removal by the Contracting Officer for non-compliance with quality requirements specified in the contract. The site project superintendent in this context shall be the highest level manager responsible for overall construction activities at the site, including quality and production. The site project superintendent shall maintain a physical presence at the site at all times, except as otherwise acceptable to the Contracting Officer, and shall be responsible for all construction and construction related activities at the site.

3.2 QUALITY CONTROL PLAN

3.2.1 General

The Contractor shall furnish for review by the Government, not later than 10 days after receipt of notice to proceed, the Contractor Quality Control (CQC) Plan proposed to implement the requirements of the Contract Clause titled "Inspection of Construction." The plan shall identify personnel, procedures, control, instructions, test, records, and forms to be used. The Government will consider an interim plan for the first 60 days of operation. Construction will be permitted to begin only after acceptance of the CQC Plan or acceptance of an interim plan applicable to the particular feature of work to be started. Work outside of the features of work included in an accepted interim plan will not be permitted to begin until acceptance of a CQC Plan or another interim plan containing the additional features of work to be started.

3.2.2 Content of the CQC Plan

The CQC Plan shall include, as a minimum, the following to cover all construction operations, both onsite and offsite, including work by subcontractors, fabricators, suppliers, and purchasing agents:

a. A description of the quality control organization, including a chart showing lines of authority and acknowledgment that the CQC staff shall implement the three phase control system for all aspects of the work specified. The staff shall include a CQC System Manager who shall report to the project manager. If the project manager and project superintendent are the same person, the CQC System Manager shall report to someone higher in the Contractor’s organization than the project manager.

b. The name, qualifications (in resume format), duties, responsibilities, and authorities of each person assigned a CQC function.

c. A copy of the letter to the CQC System Manager signed by an authorized official of the firm which describes the responsibilities and delegates sufficient authorities to adequately perform the functions of the CQC System Manager, including authority to stop work which is not in compliance with the contract. The CQC System Manager shall issue letters of direction to all other various quality control representatives outlining duties, authorities, and responsibilities. Copies of these letters shall also be furnished to the Government.

d. Procedures for scheduling, reviewing, certifying, and managing submittals, including those of subcontractors, offsite fabricators, suppliers, and purchasing agents. These procedures shall be in accordance with Section 01330 SUBMITTAL PROCEDURES.

e. Control, verification, and acceptance testing procedures for each specific test to include the test name, specification paragraph requiring test, feature of work to be tested, test frequency, and person responsible for each test. Laboratory facilities will be validated by the Corps of Engineers Material Testing Center and approved by the Contracting Officer.

f. Procedures for tracking preparatory, initial, and follow-up control phases and control, verification, and acceptance tests including documentation.

g. Procedures for tracking construction deficiencies from identification through acceptable corrective action. These procedures shall establish verification that identified deficiencies have been corrected.

h. Reporting procedures, including proposed reporting formats.

i. A list of the definable features of work. A definable feature of work is a task which is separate and distinct from other tasks, has separate control requirements, and may be identified by different trades or disciplines, or it may be work by the same trade in a different environment. Although each section of the specifications may generally be considered as a definable feature of work, there are frequently more than one definable features under a particular section. This list will be agreed upon during the coordination meeting.

3.2.3 Acceptance of Plan

Acceptance of the Contractor's plan is required prior to the start of construction. Acceptance is conditional and will be predicated on satisfactory performance during the construction. The Government reserves the right to require the Contractor to make changes in his CQC Plan and operations including removal of personnel, as necessary, to obtain the quality specified.

3.2.4 Notification of Changes

After acceptance of the CQC Plan, the Contractor shall notify the Contracting Officer in writing of any proposed change. Proposed changes are subject to acceptance by the Contracting Officer.

3.3 COORDINATION MEETING

After the Preconstruction Conference, before start of construction, and prior to acceptance by the Government of the CQC Plan, the Contractor shall meet with the Contracting Officer or Authorized Representative and discuss the Contractor's quality control system. The CQC Plan shall be submitted for review a minimum of 5 calendar days prior to the Coordination Meeting. During the meeting, a mutual understanding of the system details shall be developed, including the forms for recording the CQC operations, control activities, testing, administration of the system for both onsite and offsite work, and the interrelationship of Contractor's Management and control with the Government's Quality Assurance. Minutes of the meeting shall be prepared by the Government and signed by both the Contractor and the Contracting Officer. The minutes shall become a part of the contract file. There may be occasions when subsequent conferences will be called by either party to reconfirm mutual understandings and/or address deficiencies in the CQC system or procedures which may require corrective action by the Contractor.

3.4 QUALITY CONTROL ORGANIZATION

3.4.1 Personnel Requirements

The requirements for the CQC organization are a CQC System Manager and sufficient number of additional qualified personnel to ensure safety and contract compliance. The Safety and Health manager shall receive direction and authority from the CQC System manager and shall serve as a member of the CQC staff. The Contractor shall provide a CQC organization which shall be at the site at all times during progress of the work and with complete authority to take any action necessary to ensure compliance with the contract. All CQC staff members shall be subject to acceptance by the Contracting Officer. The Contractor shall provide adequate office space , filing systems and other resources as necessary to maintain an effective and fully functional CQC organization. Complete records of all letters, material submittals, shop drawings submittals, schedules and all other project documentation shall be promptly furnished to the CQC organization by the Contractor. The CQC organization shall be responsible to maintain these documents and records at the site at all times, except as otherwise acceptable to the Contracting Officer.

3.4.2 CQC System Manager

The Contractor shall identify as CQC System Manager an individual within the onsite work organization who shall be responsible for overall management of CQC and have the authority to act in all CQC matters for the Contractor. The CQC System Manager shall be a graduate engineer, graduate architect, or a graduate of construction management, with a minimum of 5 years construction experience on construction similar to this contract or a construction person with a minimum of 10 years in related work. This CQC System Manager shall have the qualifications shown below in the Experience Matrix. This CQC System Manager shall be on the site at all times during construction and shall be employed by the prime Contractor. The CQC System Manager shall be assigned no other duties. An alternate for the CQC System Manager shall be identified in the plan to serve in the event of the System Manager's absence. The requirements for the alternate shall be the same as for the designated CQC System Manager.

3.4.3 CQC Personnel

In addition to CQC personnel specified elsewhere in the contract, the Contractor shall provide as part of the CQC organization specialized personnel to assist the CQC System Manager for the following areas: electrical and civil/materials technician. These individuals may be employees of the prime or subcontractor; be responsible to the CQC System Manager; be physically present at the construction site during work on their areas of responsibility; have the necessary education and/or experience in accordance with the experience matrix listed herein. These individuals shall have no other duties other than quality control. An alternate for the CQC System Manager shall be identified in the plan to serve in the event of the System Manager's absence. The requirements for the alternate shall be the same as for the designated CQC System Manager.

	Experience Matrix	
	Area	**Qualifications**
A	Civil, AC Concrete and	A minimum of 2 years experience in the type of airfield pavement work being performed on this project, or a materials

	Pavements	technician with a minimum 5 years related experience in airfield pavement construction and testing. The individual(s) who perform the inspection of concrete shall have demonstrated a knowledge and ability equivalent to the ACI minimum guidelines for certification of Concrete Construction Inspector, Level II.

3.4.4 CQC Organizational Staffing: The Contractor shall maintain the CQC staff at full strength at all times during progress, with complete authority to take any action necessary to ensure compliance with the contract.

3.4.5 Organizational Changes

When it is necessary to make changes to the CQC staff, the Contractor shall revise the CQC Plan to reflect the changes and submit the changes to the Contracting Officer for acceptance. Requests shall include the names, qualifications, duties and responsibilities of each proposed replacement.

3.5 SUBMITTALS AND DELIVERABLES

Submittals shall be made as specified in Section 01330 SUBMITTAL PROCEDURES. The CQC organization shall be responsible for certifying that all submittals are in compliance with the contract requirements. All Contractor forms for submitting test results are subject to Contracting Officer approval.

3.6 CONTROL

Contractor Quality Control is the means by which the Contractor ensures that the construction, to include that of subcontractors and suppliers, complies with the requirements of the contract. The controls shall be adequate to cover all construction operations, including both on-site and off-site fabrication, and will be keyed to the proposed construction. At least three phases of control shall be conducted by the CQC System Manager for each definable feature of work as follows:

3.6.1 Preparatory Phase

This phase shall be performed prior to beginning work on each definable feature of work, after all required plans/documents/materials are approved/accepted, and after copies are at the work site. This phase shall include:

a. A review of each paragraph of applicable specifications, reference codes, and standards. A copy of those sections of referenced codes and standards applicable to that portion of the work to be accomplished in the field shall be made available by the Contractor at the preparatory inspection. These copies shall be maintained in the field and available for use by Government personnel until final acceptance of the work.

b. A review of the contract drawings.

c. A check to assure that all materials and/or equipment have been tested, submitted, and approved.

d. Review of provisions that have been made to provide required control inspection and testing.

e. Examination of the work area to assure that all required preliminary work has been completed and is in compliance with the contract.

f. A physical examination of required materials, equipment, and sample work to assure that they are on hand, conform to approved shop drawings or submitted data, and are properly stored.

g. A review of the appropriate activity hazard analysis to assure safety requirements are met.

h. Discussion of procedures for controlling quality of the work including repetitive deficiencies. Document construction tolerances and workmanship standards for that feature of work.

i. A check to ensure that the portion of the plan for the work to be performed has been accepted by the Contracting Officer.

j. Discussion of the initial control phase.

k. The Government shall be notified at least 48 hours in advance of beginning the preparatory control phase. This phase shall include a meeting conducted by the CQC System Manager and attended by the superintendent, other CQC personnel (as applicable), and the foreman responsible for the definable feature. The results of the preparatory phase actions shall be documented by separate minutes prepared by the CQC System Manager and attached to the daily CQC report. The Contractor shall instruct applicable workers as to the acceptable level of workmanship required in order to meet contract specifications.

3.6.2 Initial Phase

This phase shall be accomplished at the beginning of a definable feature of work. The following shall be accomplished:

a. A check of work to ensure that it is in full compliance with contract requirements. Review minutes of the preparatory meeting.

b. Verify adequacy of controls to ensure full contract compliance. Verify required control inspection and testing.

c. Establish level of workmanship and verify that it meets minimum acceptable workmanship standards. Compare with required sample panels as appropriate.

d. Resolve all differences.

e. Check safety to include compliance with and upgrading of the safety plan and activity hazard analysis. Review the activity analysis with each worker.

f. The Government shall be notified at least 24 hours in advance of beginning the initial phase. Separate minutes of this phase shall be prepared by the CQC System Manager and attached to the daily CQC report. Exact location of initial phase shall be indicated for future reference and comparison with follow-up phases.

g. The initial phase should be repeated for each new crew to work onsite, or any time acceptable specified quality standards are not being met.

3.6.3 Follow-up Phase

Daily checks shall be performed to assure control activities, including control testing, are providing continued compliance with contract requirements, until completion of the particular feature of work. The checks shall be made a matter of record in the CQC documentation. Final follow-up checks shall be conducted and all deficiencies corrected prior to the start of additional features of work which may be affected by the deficient work. The Contractor shall not build upon nor conceal non-conforming work.

3.6.4 Additional Preparatory and Initial Phases

Additional preparatory and initial phases shall be conducted on the same definable features of work if the quality of on-going work is unacceptable, if there are changes in the applicable CQC staff, onsite production supervision or work crew, if work on a definable feature is resumed after a substantial period of inactivity, or if other problems develop.

3.7 TESTS

3.7.1 Testing Procedure

The Contractor shall perform specified or required tests to verify that control measures are adequate to provide a product which conforms to contract requirements, see Table 1 – Minimum Testing, attached at the end of this specification section. Contractor shall submit all materials test reports on forms standard to industry standards such as ACI, ASTM and AASHTO or with laboratory accreditation forms such as AALA, NIST or NVLAP. Upon request, the Contractor shall furnish to the Government duplicate samples of test specimens for possible testing by the Government. Testing includes operation and/or acceptance tests when specified. The Contractor shall procure the services of a Corps of Engineers validated testing laboratory or establish a testing laboratory at the project site which can be validated by the Corps of Engineers in advance of any and all required testing; and in addition, submit proof of validation for approval. The Contractor shall perform the following activities and record and provide the following data:

a. Verify that testing procedures comply with contract requirements.

b. Verify that facilities and testing equipment are available and comply with testing standards.

c. Check test instrument calibration data against certified standards.

d. Verify that recording forms and test identification control number system, including all of the test documentation requirements, have been prepared.

e. Results of all tests taken, both passing and failing tests, shall be recorded on the CQC report for the date taken. Specification paragraph reference, location where tests were taken, and the sequential control number identifying the test shall be given. If approved by the Contracting Officer, actual test reports may be submitted later with a reference to the test number and date taken. An information copy of tests performed by an offsite or commercial test facility shall be provided directly to the Contracting Officer. Failure to submit timely test reports as stated may result in nonpayment for related work performed and disapproval of the test facility for this contract.

3.7.2 Testing Laboratories

a. Validation

The testing laboratory shall be validated by the Corps of Engineers Materials Testing Center (MTC) for all tests required by the contract prior to the performance of any such testing. The validation of a laboratory is site specific and cannot be transferred or carried over to a facility at a different location. Any and all costs associated with this Government laboratory validation shall be borne by the laboratory and/or the Contractor. Validation of a laboratory is not granted for the entire laboratory activity, but only for the specific procedures requested by the inspected laboratory. The inspected laboratory has full choice of the procedures to be inspected except that the Quality Assurance portion of ASTM E 329 is mandatory to be inspected.

(1) Validation Procedures

Validation of a laboratory may consist of either an inspection or audit as defined herein. Validation of all material testing laboratories shall be performed by the MTC. Validation may be accomplished by one of the following processes:

(a) Inspection. Inspection shall be performed by the MTC in accordance with American Society for Testing and Materials (ASTM) standards E329 and D3740.

(b) Audit. A laboratory may be validated by auditing if it has been accredited by the Concrete and Cement Reference Laboratory (CCRL) or AASHTO Materials Reference Laboratory (AMRL) within the past two years in accordance with ASTM E329. Audit shall be performed by the MTC. Inspection by MTC may be required after auditing if one or more of the critical testing procedures required in the project specification were not included in the CCRL or AMRL inspection report or if there is any concern that the laboratory may not be able to provide required services.

b. Standards of Acceptability

(1) Aggregate, concrete, bituminous materials, soil, and rock. Laboratories for testing aggregate, concrete, bituminous materials, soil, and rock shall be validated for compliance with ASTM E 329, Engineer Manual (EM) 1110-2-1906, or project specifications, as applicable.

(2) Water, sediment, and other samples. Laboratories engaged in analysis of water, sediment, and other samples for chemical analysis shah be inspected to assure that they have the capability to perform analyses and quality control procedures described in references in Appendix A as appropriate. The use of analytical methods for procedures not addressed in these references will be evaluated by the CQAB for conformance with project or program requirements.

(3) Steel and other construction materials, Laboratories testing steel and other construction materials shall be validated for capabilities to perform tests required by project requirements and for compliance with ASTM E329.

c. Validation Schedule

(1) For all contracted laboratories and project Quality Assurance (QA) laboratories testing aggregate, concrete, bituminous materials, soils, rock, and other construction materials, an initial validation shall be performed prior to performance of testing and at least every two (2) years thereafter.

(2) Laboratories performing water quality, wastewater, sludge, and sediment testing shall be approved at an interval not to exceed eighteen (18) months.

(3) All laboratories shall be revalidated at any time at the discretion of the Corps of Engineers when conditions are judged to differ substantially from the conditions when last validated.

d. Validation Process

If a validated laboratory is unavailable or the Contractor selects to use a laboratory which has not been previously validated, Contractor shall coordinate with Corps of Engineers Material Testing Center (MTC) to obtain validation and pay all associated costs. Point of contact at MTC is Daniel Leavell, telephone (601) 634-2496, fax (601) 634-4656, email daniel.a.leavell@erdc.usace.army.mil, at the following address:

U.S. Army Corps of Engineers
Materials Testing Center
Waterways Experiment Station
3909 Hall Ferry Road
Vicksburg, MS 39180-6199

Procedure for Corps of Engineers validation, including qualifications and inspection/audit request forms are available at the MTC web site:

http://www.wes.army.mil/SL/MTC/mtc.htm
Contractor shall coordinate directly with the MTC to obtain validation. Contractor is cautioned the validation process is complicated and lengthy, may require an onsite inspection by MTC staff, correction of identified deficiencies, and the submittal and approval of significant documentation. Estimate a minimum of 60 days to schedule an inspection/submittal and receive a validation. Cost of onsite inspections is $2500 plus travel time and cost from Vicksburg MS. Cost of audits is $1500. If an onsite inspection is required following an audit, the cost of the inspection shall be $1500 plus travel time and cost. The Contractor will be invoiced for actual travel costs and shall submit

payment direct to the MTC made payable to the ERDC Finance and Accounting Officer prior to the scheduling of the inspection and/or audit. The Contractor shall copy the Contracting Officer of all correspondence and submittals to the MTC for purposes of laboratory validation.

3.7.3 Onsite Laboratory

The Government reserves the right to utilize the Contractor's control testing laboratory and equipment to make assurance tests and to check the Contractor's testing procedures, techniques, and test results at no additional cost to the Government.

3.7.4 Furnishing or Transportation of Samples for Testing

Costs incidental to the transportation of samples or materials will be borne by the Contractor. Samples of materials for test verification and acceptance testing by the Government shall be delivered to the Corps of Engineers Division Laboratory, f.o.b., at the following address:

U.S. Army Corps of Engineers
Materials Testing Center
Waterways Experiment Station
3909 Hall Ferry Road
Vicksburg, MS 39180-6199
Phone: (610) 634-2496 or (601) 634-3261

ATTN: Project _____, Contract Number _____

Coordination for each specific test, exact delivery location and dates will be made through the Area Office. If samples are scheduled to arrive at the laboratory on a weekend (after 1700 Friday through Sunday) notify the laboratory at least 24 hours in advance at (601) 634-3974 to arrange for delivery.

3.8 COMPLETION INSPECTION

3.8.1 Punch-Out Inspection

Near the completion of all work or any increment thereof established by a completion time stated in the Special Clause entitled "Commencement, Prosecution, and Completion of Work," or stated elsewhere in the specifications, the CQC System Manager shall conduct an inspection of the work and develop a punch list of items which do not conform to the approved drawings and specifications. Such a list of deficiencies shall be included in the CQC documentation, as required by paragraph DOCUMENTATION below, and shall include the estimated date by which the deficiencies will be corrected. The CQC System Manager or staff shall make a second inspection to ascertain that all deficiencies have been corrected and so notify the Government. These inspections and any deficiency corrections required by this paragraph will be accomplished within the time stated for completion of the entire work or any particular increment thereof if the project is divided into increments by separate conpletion dates. Once this is accomplished, the Contractor shall notify the Government that the facility is ready for the Government Pre-Final inspection.

3.8.2 Pre-Final Inspection

The Government will perform this inspection to verify that the facility is complete and ready to be occupied. A Government Pre-Final Punch List may be developed as a result of this inspection. The Contractor's CQC System Manager shall ensure that all items on this list have been corrected before notifying the Government so that a Final inspection with the customer can be scheduled. Any items noted on the Pre-Final inspection shall be corrected in a timely manner. These inspections and any deficiency corrections required by this paragraph shall be accomplished within the time slated for completion of the entire work or any particular increment thereof if the project is divided into increments by separate completion dates.

3.8.3 Final Acceptance Inspection

The Contractor's Quality Control Inspection personnel, plus the superintendent or other primary management person, and the Contracting Officer's Representative shall be in attendance at this inspection. Additional Government personnel including, but not limited to, those from Base/Post Civil Facility Engineer user groups, and major commands may also be in attendance. The final acceptance inspection will be formally scheduled by the Contracting Officer based upon results of the Pre-Final inspection. Notice shall be given to the Contracting Officer at least 14 days prior to the final acceptance inspection and shall include the Contractor's assurance that all specific items previously identified to the Contractor as being unacceptable, along with all remaining work performed under the contract, will be complete and acceptable by the date scheduled for the final acceptance inspection. Failure of the Contractor to have all contract work acceptably complete for this inspection will be cause for the Contracting Officer to bill the Contractor for the Government's additional inspection cost in accordance with the contract clause titled "Inspection of Construction".

3.9 DOCUMENTATION

The Contractor shall maintain current records providing factual evidence that required quality control activities and/or tests have been performed. These records shall include the work of subcontractors and suppliers and shall be on an acceptable form that includes, as a minimum, the following information:

a. Contractor/subcontractor and their area of responsibility.

b. Operating plant/equipment with hours worked, idle, or down for repair.

c. Work performed each day, giving location, description, and by whom. When Network Analysis (NAS) is used, identify each phase of work performed each day by NAS activity number.

d. Test and/or control activities performed with results and references to specifications/drawings requirements. The control phase should be identified (Preparatory, Initial, Follow-up). List deficiencies noted along with corrective action.

e. Quantity of materials received at the site with statement as to acceptability, storage, and reference to specifications/drawings requirements.

f. Submittals reviewed, with contract reference, by whom, and action taken.

g. Off-site surveillance activities, including actions taken.

h. Job safety evaluations stating what was checked, results, and instructions or corrective actions.

i. Instructions given/received and conflicts in plans and/or specifications.

j. Contractor's verification statement.

These records shall indicate a description of trades working on the project; the number of personnel working; weather conditions encountered; and any delays encountered. These records shall cover both conforming and deficient features and shall include a statement that equipment and materials incorporated in the work and workmanship comply with the contract. The original and one copy of these records in report form shall be furnished to the Government daily within 24 hours after the date covered by the report, except that reports need not be submitted for days on which no work is performed. As a minimum, one report shall be prepared and submitted for every 7 days of no work and on the last day of a no work period. All calendar days shall be accounted for throughout the life of the contract. The first report following a day of no work shall be for that day only. Reports shall be signed and dated by the CQC System Manager. The report from the CQC System Manager shall include copies of test reports and copies of reports prepared by all subordinate quality control personnel.

3.10 SAMPLE FORMS

Sample forms are attached at the end of this specification section.

3.11 NOTIFICATION OF NONCOMPLIANCE

The Contracting Officer will notify the Contractor of any detected noncompliance with the foregoing requirements. The Contractor shall take immediate corrective action after receipt of such notice. Such notice, when delivered to the Contractor at the work site, shall be deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders shall be made the subject of claim for extension of time or for excess costs or damages by the Contractor.

TABLE 1

MINIMUM SAMPLING AND TESTING FREQUENCY (REPAIR AIRCRAFT PARKING APRON)

Materials	Test	Minimum Sampling and Testing Frequency
Fills, Embankments, Subgrade, and Aggregate Base Course Material for Flexible Pavement		
Fill and Embankment	Field Density 2/12/	Two tests per lift for each increment or fraction of 1,672 square meters (2000 sy) and any time material type changes.
	Lab Density 3/	One test initially per each type of materials or blended material and any time material type changes, and one every 10 field density tests.
	Gradation 1/	One test every 153 cubic meters (200 cubic yards) of fill for each type of materials or blended material and any time material type changes.
Subgrade	Field Density 2/12/	One test per each increment or fraction of 1672 square meters (20,000 s.y.)
	Lab Density 3/	One test every 10 field density tests.
Backfill for Culverts, Trenches, Buildings and Walls, Pavements, and Other Structures	Field Density 2/12/	Culverts: One test per each lift.
		Trenches: One test per lift for each increment or fraction of 152 lineal meters (500 linear feet) for backfill. Under pavements, one test every lift and at every crossing.
		Walls and Buildings Perimeters, Including Footings: One test per lift for each increment or fraction of 61 lineal meters (200 linear feet) of backfill.

Materials	Test	Minimum Sampling and Testing Frequency
		Buildings Slabs on Grade: One test per lift for each increment or faction of 93 square meters (1000 s.f.) Areas enclosed by grade beams, compacted with power driven hand operated compactors: One test per lift for each increment or fraction of 46 square meters (500 s.f.) Pavements: Two tests per lift for each increment or fraction of 1,672 square meters (2000 s.y.) Other Structures: One test per lift for each increment or fraction of 61 lineal meters (200 linear feet) of backfill.
	Lab Density3/	One test initially per each type of material or blended material and one every 10 field density tests.
	Gradation1/	One test per each type of material or blended material and one every 10 field density tests.
	Subgrade and Rigid Base for Rigid Airfield Pavements	
Subgrade and Fill or Embankment	In-Place Density12/	1 every 4,181 square meters (5,000 sy) (subgrade) 1 every 1,911 cubic meters (2,500 cy) and 1 for each type of material or an apparent change in moisture. (Fill or embankment)
	Moisture-Density Relationship	1 every 20 density tests or if material type changes.
	Gradation1/	1 every moisture-density test.
	Moisture	1 for every density test.
	Atterberg Limit	1 for every moisture-density test.
Base Material	In-Place Density12/	1 every 1,000 cy per lift (1 per day min.).

Materials	Test	Minimum Sampling and Testing Frequency
		1 every 2 inplace density tests.
	Gradation (and Fractured Faces if applicable)[1/]	
	Moisture-Density Relationship	1 every 20 density tests.
	Moisture	1 for every density test.

Portland Cement Concrete for Airfields

(See specifications for testing requirement)

TABLE 1

MINIMUM SAMPLING AND TESTING FREQUENCY (REPAIR RUNWAY)

Materials	Test	Minimum Sampling and Testing Frequency
Fills, Embankments, Backfills, Subgrade, Subbase, and Base Course Material		
Fill and Embankment	Field Density 2/12/	One test per lift for each increment or fraction of 2000sy and any time Material changes
	Lab Density 3/	One test initially per each type of materials or blended material and any time material type changes, and one every 10 field density tests.
	Gradation 1/	One test every 500 cubic yards of fill for each type of materials or blended material and any time material type changes.
Subgrade	Field Density 2/12/	One test per each increment or fraction of 2000 sy.
	Lab Density 3/	One test every 10 field density tests.
Backfill for Culverts Trenches, Buildings and Walls, Pavements and other Structures	Field Density 2/12/	Culverts: One test per each lift. Trenches: One test per lift for each Increment or fraction of 500 linear feet for backfill. Under pavements, two tests every lift and at every crossing. Areas enclosed by grade beams, compacted with power driven hand operated compactors: One test per lift for each increment or fraction of 500 sf.

Pavements: Two tests per lift for each increment or fraction of 2000 sy.

Materials	Test	Minimum Sampling and Testing Frequency
		Other Structures: One test per lift for each increment or fraction of 200 linear feet of back-fill.
	Lab Density 3/	One test initially per each type of material or blended material and one every 10 field density tests.
	Gradation 1/	One test per each type of material or blended material and one every 10 field density tests.
Subbase and Base	Gradation 1/(in-cluding .02mm particles size limits.	1 sample for every 500 cy.
	In-Place Density 2/ 12/	1 sample every 1,000 sy.
	Moisture-Density Relationship 3/	1 initially and every 20 density tests.
Subgrade, Subbase, and Base for Rigid and flexible Airfield Pavements and Heliports		
Subgrade and Fill or Embankment	In-Place Density 12/	1 every 2,000 sy (subgrade)
		1 every 2,000 cy and 1 for each type of material or an apparent change in moisture. (Fill or embankment)
	Moisture-Density Relationship	1 every 20 density tests or if material type changes.
	Gradation 1/	1 every 500 c.y.-
	Moisture	1 for every density test.
	Atterberg Limit	1 for every material type.

Materials	Test	Minimum Sampling and Testing Frequency
Subbase and Base material	In-Place Density 12/	1 every 1,000 sy per lift.
	Gradation (and Fractured Faces if applicable)	1 every 500 c.y.
	Moisture-Density Relationship	1 every 20 density tests.
	Moisture	1 for every density test.

Asphaltic and Portland Cement Concrete for Airfields

(See specifications for testing requirements)

NOTES:

1/All acceptance tests shall be conducted from in-place samples.

2/Additional tests shall be conducted when variations occur due to the contractors operations, weather conditions, site conditions, etc.

3/Classification (ASTM D-2487), moisture contents, Atterberg limits and specific gravity tests shall be conducted for each compaction test if applicable.

4/Materials to be submitted only upon request by the Contracting Officer.

5/Tests can substitute for same tests required under "Aggregates" (from bins or source), although gradations will be required when blending aggregates.

6/Increase quantities by 50 percent for Paving mixes and by 100 percent for Government testing of admixtures. Include standard deviation for similar mixes from the intended batch plant and data from a minimum of 30 tests, if available. Refer to ACI 214.

7/A petrographic report for aggregate is required with the sample for source approval. If the total amount of all types of concrete is less than 153 cubic meters (200 c.y.) service records from three separate structures in similar environments which used the aggregates may substitute for the petrographic report.

8/Aggregate moisture tests are to be conducted in conjunction with concrete strength tests for w/c calculations.

9/For less than 1,000 units, the above test may be waived at the discretion of the Contracting Officer and acceptance based on manufacturers certification and test report.

10/Additional tests shall be performed when changes are made either in the manufacturing processes or in materials used in the production of the masonry units.

11/If adequate storage protection is not provided at the jobsite, additional tests shall be made to determine that the allowable moisture condition has not been exceeded before the blocks can be placed in the structure.

12/The nuclear densometer, if properly calibrated, may be used but only in addition to the required testing frequency and procedures using sandcones. The densometer shall be calibrated and is recommended for use when the time for complete results becomes critical.

(sample of typical Contractor's Daily Report)
DAILY CONSTRUCTION QUALITY CONTROL REPORT

Contract Number: _____ Date: _____ Rpt. No._____

Contract Title: _____ Location: _____

Weather: Clear __ P. Cloudy __ Cloudy __ Rainfall __ (__% of workday)

Temperature during workday: High ____ degrees F. Low ___ degrees F.

1. WORK PERFORMED BY CONTRACTOR/SUBCONTRACTOR(S):

Contractor Name	No. of Workers	Crafts/Hours	Work performed

2. EQUIPMENT DATA:

Type, Size, Etc.	Owned/Rented	Hours Used	Hours Standby

3. QUALITY CONTROL INSPECTIONS AND RESULTS: (Include a description of preparatory, initial, and/or follow up inspections or meetings; check of subcontractors work and materials delivered to the site compared to submittals and/or specifications; comments on the proper storage of materials; include comments on corrective actions to be taken):

_____

_____

_____

_____

4. QUALITY CONTROL TESTING AND RESULTS (comment on tests and attach test reports):

_____

_____

_____

5. DAILY SAFETY INSPECTIONS (Include comments on new hazards to be added to the Hazard Analysis and corrective action of any safety issues):

_____

_____

6. REMARKS (Include conversations with or instructions from the Government representatives; delays of any kind that are impacting the job; conflicts in the contract documents; comments on change orders; environmental considerations; etc.):

_____

_____

_____

_____

_____

CONTRACTOR'S VERIFICATION: The above report is complete and correct. All material, equipment used, and work performed during this reporting period are in compliance with the contract documents except as noted above.

_____
CONTRACTOR QC REPRESENTATIVE

(Sample of Typical Contractor's Test Report)

TEST REPORT

STRUCTURE OR BUILDING _____

CONTRACT NO. _____

DESCRIPTION OF ITEM, SYSTEM, OR PART OF SYSTEM TESTED:
_____

_____

DESCRIPTION OF TEST: _____

_____

_____
NAME AND TITLE OF PERSON IN CHARGE OF PERFORMING TESTS FOR THE CONTRACTOR:

NAME_____

TITLE_____

SIGNATURE_____

I HEREBY CERTIFY THAT THE ABOVE DESCRIBED ITEM, SYSTEM, OR PART OF SYSTEM HAS BEEN TESTED AS INDICATED ABOVE AND FOUND TO BE ENTIRELY SATISFACTORY AS REQUIRED IN THE CONTRACT SPECIFICATIONS.

SIGNATURE OF CONTRACTOR
QUALITY CONTROL INSPECTOR_____

DATE_____

REMARKS
_____

_____

_____

END OF SECTION

SECTION 01501 (AR)

CONSTRUCTION FACILITIES AND TEMPORARY CONTROLS

PART 1 GENERAL

1.1 SITE PLAN

The Contractor shall prepare a site plan indicating the proposed location and dimensions of any area to be fenced and used by the Contractor, the number of trailers to be used, avenues of ingress/egress to the fenced area and details of the fence installation. Any areas which may have to be graveled to prevent the tracking of mud shall also be identified. The Contractor shall also indicate if the use of a supplemental or other staging area is desired.

1.2 AVAILABILITY OF UTILITY SERVICES

1.2.1 Water

The Government will make available to Contractor, from existing outlets and supplies, reasonable amounts of potable water without charge. Contractor shall reasonably conserve potable water furnished. Contractor, at its own expense, shall install and maintain necessary temporary connections and distribution lines and shall remove the connections and lines prior to final acceptance of construction.

a. Contractor may connect to a fire hydrant located at Building 1340, the water fill stand at the water plant, and across from Wasterwater Treatment plant 3, after coordinating with the Fire Department. The Government will supply a water meter to measure the consumption, but there will be no charge for the water used.

1.2.2 Electricity

Subject to available supply, reasonable amounts of electric current will be furnished by the Government, without charge, to the Contractor for performing work at the work area. The Contractor shall carefully conserve electricity furnished. The Contractor, at its own expense and in a workmanlike manner satisfactory to the Contracting Officer, shall install and maintain necessary temporary connections and shall remove the same prior to final acceptance of the construction.

a. Contractor shall connect to existing power service at locations designated by the Contracting Officer (CO). Power consumption shall not disrupt continuous service to the Government. Contractor may hook up to the overhead power running along Liberator St., on the northerly side of the area/batch plant lot. This is a 7200/12470, 4 wire, "Y" system. No meter required.

b. The Government will pay the cost of energy used for the Contractor's office trailer. The Contractor shall exercise measures to conserve energy. The Contractor is responsible for providing power for operation of concrete batch plant, asphalt mixing plant and crushing plant.

c. Contractor shall not use electrical energy supplied by the Government for resistance heating except in the field office or trailer.

d. The Contractor is responsible to determine if the characteristics of the available power are suitable for the Contractor's office trailer.

e. The Contractor is responsible for determining and providing necessary hardware for connecting office trailer to available power source.

f. Permanent convenience receptacles shall not be utilized during construction.

1.2.3 Sanitary Provisions

Contractor shall provide sanitary accommodations for the use of employees as may be necessary, shall maintain accommodations approved by the Contracting Officer and shall comply with the requirements and regulations of the State Health Department, County Sanitarian, or other authorities having jurisdiction.

1.2.4 Telephone Service

Contractor shall make arrangements and pay all costs for telephone facilities desired. Use of Government telephone service will not be permitted except in emergency situations or otherwise approved by the Contracting Officer.

1.3 TEMPORARY ELECTRIC WIRING

1.3.1 Temporary Power and Lighting

The Contractor shall provide construction power facilities in accordance with the safety requirements of the National Electric Code NFPA No. 70 and the SAFETY AND HEALTH REQUIREMENTS MANUAL EM 385-1-1. The Contractor, or its delegated subcontractor, shall enforce the safety requirements of electrical extensions for the work of subcontractors. Work shall be accomplished by skilled electrical tradesmen.

1.3.1.1 Contractor shall provide branch wiring from power source to distribution boxes with lighting conductors, pigtails, and lamps as required.

1.3.1.2 Contractor shall maintain lighting and provide routine repairs.

1.3.2 Meters and Temporary Connections

The Contractor, at its expense and in a manner satisfactory to the Contracting Officer, shall provide and maintain necessary temporary connections and distribution lines. The Contractor shall notify the Contracting Officer, in writing, 5 working days before final electrical connection is desired. The Government will make the final hot connection after inspection and approval of the Contractor's temporary wiring installation. The Contractor shall not make the final electrical connection.

1.3.3 Construction Equipment

In addition to the requirements of SAFETY AND HEALTH REQUIREMENTS MANUAL, EM 385-1-1, temporary wiring conductors installed for operation of construction tools and equipment shall be either Type TW or THW contained in metal raceways, or shall be hard usage or extra hard usage multiconductor cord. Temporary wiring shall be secured above the ground or floor in a workmanlike manner and shall not present an obstacle to persons or equipment. Open wiring may only be used outside of buildings, and then only in accordance with the provisions of the National Electric Code.

1.3.4 Submittals

Submit detailed drawings of temporary power connections. Drawings shall include, but not be limited to, main disconnect, grounding, service drops, service entrance conductors, feeders, GFCI'S, and all site trailer connections.

1.4 CONNECTIONS

a. Connections to existing utilities, when approved by the Contracting Officer, shall be done by the Contractor at no cost to the Government.

b. Contractor shall remove temporary connections at the completion of the project and restore utilities to original condition. Repair damage to utilities caused by temporary connections.

1.5 REMOVAL OF TEMPORARY UTILITIES, FACILITIES, AND CONTROLS

a. Remove temporary above grade or buried utilities, equipment, facilities, and materials prior to the Final Inspection.

b. Clean and repair damage caused by installation or use of temporary work.

c. Restore existing facilities used during construction and work activities to original condition or better.

1.6 BARRIERS

a. Provide barriers and signs to prevent unauthorized vehicular and pedestrian entry to construction and work areas. Barriers and signs shall conform to the Manual on Uniform Traffic Control Devices (MUTCD). Barriers to close airfield pavements shall conform to the project drawings.

b. Provide barriers to protect existing facilities and adjacent properties from damage from demolition, preparation, and construction operations under this Contract.

c. Provide protection for plant life adjacent to the construction and work area. Replace damaged plant life.

1.7 WATER CONTROL

a. Grade site to drain. Maintain excavations free of water. Provide, operate, and maintain pumping equipment as required.

b. Protect site from puddling or running water.

1.8 PROTECTION OF INSTALLED WORK

a. Protect installed Work and provide special protection where specified in individual specification sections.

b. Provide temporary and removable protection for installed products. Control activity in immediate work area to minimize risk of damage.

c. Prohibit traffic from landscaped areas.

1.9 FIRE PROTECTION

During the construction period, the Contractor shall provide fire extinguishers in accordance with the safety requirements of the SAFETY AND HEALTH REQUIREMENTS MANUAL, EM 385-1-1, OCT 92. The Contractor shall remove the fire extinguishers at the completion of construction.

1.10 STAGING/STORAGE AREA

Contractor will be provided adequate open staging area as directed by the Contracting Officer. Area is unsecured, and Contractor shall make provisions for its own security.

Contractor shall be responsible for keeping staging/Storage area clean and free of weeds and uncontrolled vegetation growth. Weeds shall be removed by pulling or cutting to within 1-inch of ground level. Lawn areas shall be mown to keep growth to less than 2-inches. All loose debris and material subject to being moved by prevailing winds in the area shall be picked up or secured at all times.

If the area is not maintained in a safe and clean condition as defined above, the Contracting Officer may have the area cleaned by others with the costs being deducted from the contractor's payment.

1.10.1 Maintenance of Storage Area

Should the Contractor elect to traverse, with construction equipment or other vehicles, grassed or unpaved areas which are not established roadways, such areas shall be covered with a layer of rotomillings or crushed concrete as necessary to prevent rutting and the tracking of mud onto paved or established roadways; gradation shall be at the Contractor's discretion.

1.10.2 Appearance of Trailers

Trailers utilized by the Contractor for administrative or material storage purposes shall present a clean and neat exterior appearance and shall be in a state of good repair. Trailers which, in the

opinion of the Contracting Officer, require exterior painting or maintenance will not be allowed on the military property.

1.10.3 Restoration of Storage Area

Upon completion of the project and after removal of trailers, materials, and equipment from within the fenced area, the fence shall be removed and will become the property of the Contractor. Areas used by the Contractor for the storage of equipment or material, or other use, shall be restored to the original or better condition. Gravel used to traverse grassed areas shall be removed and the area restored to its original condition, including top soil and seeding as necessary.

1.11 HOUSEKEEPING AND CLEANUP

Pursuant to the requirements of Clause CLEANING UP and Clause ACCIDENT PREVENTION, of the CONTRACT CLAUSES, the Contractor shall assign sufficient personnel to insure compliance. The Contractor shall submit a detailed written plan for implementation of this requirement. The plan will be presented as part of the preconstruction safety plan and will provide for keeping the total construction site, structures, and accessways free of debris and obstructions at all times. Work will not be allowed in those areas that, in the opinion of the Contracting Officer, have unsatisfactory cleanup and housekeeping at the end of the preceding day's normal work shift. At least once each day all areas shall be checked by the Quality Control person of the Contractor and the findings recorded on the Quality Control Daily Report. In addition, the Quality Control person shall take immediate action to insure compliance with this requirement. Housekeeping and cleanup shall be assigned by the Contractor to specific personnel. The name(s) of the personnel shall be available at the project site.

a. Construction debris, waste materials, packaging material and the like shall be removed from the work site daily. Any dirt or mud which is tracked onto paved or surfaced roadways shall be cleaned away. Materials resulting from demolition activities which are salvageable shall be stored within the fenced area described above or at the supplemental storage area. Stored material not in trailers, whether new or salvaged, shall be neatly stacked when stored.

1.12 DIGGING PERMIT

Before performing any onsite excavation, Contractor shall obtain a digging permit from the Base Utilities through coordination with Corps of Engineers office. The Contractor shall mark the construction limits and submit it with the digging permit application. It may take up to 14 days to obtain the permit.

1.13 CONSTRUCTION NEAR COMMUNICATIONS CABLES

1.13.1 Excavation Near Communication Cables

Digging within 3 feet of communication cables shall be performed by hand digging until the cable is exposed. The Contracting Officer shall be notified a minimum 3 days prior to digging within a 3-foot area near cable. The cable route will be marked by the Government prior to excavation in the area. A digging permit shall be obtained by the Contractor before performing any excavation. The Contractor shall be held responsible for any damage to the cable by excavation procedures.

Once the cable is exposed, mechanical excavation may be used if there is no chance of damage occurring to the cable.

1.13.2 Reburial of Exposed Utilities

When existing utility lines are reburied a tape and insulated tracer wire, detectable by pipe detector systems, shall be installed above the uncovered length of the utility at a depth of 12 inches below grade. Tape shall be a minimum 5 mil plastic tape with metallic tracer, minimum 3 inches wide, lettering on tape to show buried utility, and brightly colored.

1.13.3 Access to Communications Manhole or Handhole

No communications manhole or handhole shall be entered without first obtaining a fiber optic cable briefing. Coordinate through the Contracting Officer with the Base Communications Officer.

1.13.4 Cable Cuts or Damage

If a communications cable is cut or damaged the Contractor shall immediately notify the Contracting Officer (CO) and begin gathering personnel and equipment necessary to repair the cut or damage. Contractor shall begin repairs within one hour of the cut or damage, unless notified otherwise, and continue repairs without interruption until full service is restored.

1.14 BULLETIN BOARD, PROJECT SIGN, AND PROJECT SAFETY SIGN

1.14.1 Bulletin Board

Immediately upon beginning of work, the Contractor shall provide a weatherproof glass-covered bulletin board not less than 36 by 48 inches in size for displaying the Equal Employment Opportunity poster, a copy of the wage decision contained in the contract, Wage Rate Information poster, and other information approved by the Contracting Officer. The bulletin board shall be located at the project site in a conspicuous place easily accessible to all employees, as approved by the Contracting Officer. Legible copies of the aforementioned data shall be displayed until work is completed. Upon completion of work the bulletin board shall be removed by and remain the property of the Contractor.

1.14.2 Project and Safety Signs

The requirements for the signs, their content, and location shall be as shown on the drawings, except the Project Sign shall be as shown at the end of this specification section. The signs shall be erected within 15 days after receipt of the notice to proceed. The data required by the safety sign shall be corrected daily, with light colored metallic or non-metallic numerals. Upon completion of the project, the signs shall be removed from the site.

1.15 Traffic Control Plan

The Contractor shall submit a Traffic Control Plan for moving traffic through and around the construction zone in a manner that is conducive to the safety of motorists, pedestrians, and workers. This plan shall indicate scheduling, placement, and maintenance of traffic control devices in accordance with the U.S. Department of Transportation, Federal Highway

Administration publication, Manual on Uniform Traffic Control Devices. The Contractor shall obtain, in writing, from the Base Civil Engineer through the Contracting Officer, approval of the Traffic Control Plan. The Contractor shall submit his Traffic Control Plan at least 15 working days prior to commencement of street or road work. Streets (except dead end) may be closed to traffic temporarily (except at least one access lane shall be kept open to traffic) by approved written request to the Contracting Officer at least 10 working days prior to street closure. Excavations shall not remain open for more than 1 working day without approval. The Contractor shall identify by site inspection and indicate on the plan all roads and trails used by military or civilian wheeled and tracked vehicular traffic and, by traffic control devices, prevent this traffic from entering the construction zone.

1.15.1 Protection and Maintenance of Traffic

During construction the Contractor shall provide access and temporary relocated roads as necessary to maintain traffic. The Contractor shall maintain and protect traffic on all affected roads during the construction period except as otherwise specifically directed by the Contracting Officer. Measures for the protection and diversion of traffic, including the provision of watchmen and flagmen, erection of barricades, placing of lights around and in front of equipment and the work, and the erection and maintenance of adequate warning, danger, and direction signs, shall be as required by the State and local authorities having jurisdiction. The traveling public shall be protected from damage to person and property. The Contractor's traffic on roads selected for hauling material to and from the site shall interfere as little as possible with public traffic. The Contractor shall investigate the adequacy of existing roads and the allowable load limit on these roads. The Contractor shall be responsible for the repair of any damage to roads caused by construction operations.

1.15.2 Haul Roads

The Contractor shall, at its own expense, construct access and haul roads necessary for proper prosecution of the work under this contract. Haul roads shall be constructed with suitable grades and widths; sharp curves, blind corners, and dangerous cross traffic shall be avoided. The Contractor shall provide necessary lighting, signs, barricades, and distinctive markings for the safe movement of traffic. The method of dust control, although optional, shall be adequate to ensure safe operation at all times. Location, grade, width, and alignment of construction and hauling roads shall be subject to approval by the Contracting Officer. Lighting shall be adequate to assure full and clear visibility for full width of haul road and work areas during any night work operations. Upon completion of the work, haul roads designated by the Contracting Officer shall be removed.

1.15.3 Barricades

The Contractor shall erect and maintain temporary barricades to limit public access to hazardous areas. Such barricades shall be required whenever safe public access to paved areas such as roads, parking areas or sidewalks is prevented by construction activities or as otherwise necessary to ensure the safety of both pedestrian and vehicular traffic. Barricades shall be securely placed, clearly visible with adequate illumination to provide sufficient visual warning of the hazard during both day and night.

1.16 Utilities Not Shown

The Contractor can expect to encounter, within the construction limits of the entire project, utilities not shown on the drawings and not visible as to the date of this contract, and/or utilities at different locations than shown on the drawings. The Contractor shall make his own field investigation to determine the exact location of the underground utilities at critical points to avoid any damage. If such utilities will interfere with construction operations, he shall immediately notify the Contracting Officer verbally and then in writing to enable a determination by the Contracting Officer as to the necessity for removal or relocation. If such utilities are removed or relocated as directed, the Contractor shall be entitled to equitable adjustment for any additional work or delay. The types of utilities the Contractor may encounter are waterlines, sewerlines (storm and sanitary), gaslines, fueling lines, steamlines, buried fuel tanks, other buried tanks, communication lines, and powerlines. These utilities may be active or abandoned utilities.

Should the Contractor damage or interrupt the operation of a utility service or facility by accident or otherwise, he shall immediately notify the Contracting Officer and shall take all reasonable measures to prevent further damage or interruption of service. The Contractor, in such events, shall cooperate with the Base Utilities through the Contracting Officer continuously until such damage has been repaired and service restored to the satisfaction of Base Utilities.

1.17 GOVERNMENT WITNESSING AND SCHEDULING OF TESTING

The Contractor shall notify the Contracting Officer, by serial letter, of dates and agenda of all performance testing of the mechanical and electrical systems (including fire protection) not later than 10 calendar days prior to start of such testing. In this notification, the Contractor shall certify that all equipment, materials, and personnel necessary to conduct such testing will be available on the scheduled date and that the systems have been prechecked by him and are ready for performance and/or acceptance testing. Contractor shall also confirm that all operations and maintenance manuals have been submitted and approved. NO PERFORMANCE AND/OR ACCEPTANCE TESTING WILL BE PERMITTED UNTIL THE OPERATIONS AND MAINTENANCE MANUALS HAVE BEEN APPROVED.

Government personnel, at the option of the Government, will travel to the site to witness testing. If the testing must be postponed or cancelled for whatever reason not the fault of the government, the Contractor shall provide the Government not less than 3 working days advance notice (notice may be faxed) of this postponement or cancellation. Should this 3 working day notice not be given, the Contractor shall reimburse the Government for any and all out of pocket expenses incurred for making arrangements to witness such testing including, but not limited to airline, rental car, meal, and lodging expenses. Should testing be conducted, but fail and have to be rescheduled for any reason not the fault of the Government, the Contractor shall similarly reimburse the Government for all expenses incurred.

1.18 CONTRACTOR'S FIELD OFFICE

1.18.1 Trailer-Type Mobile Office

The Contractor shall furnish and maintain a trailer-type mobile office approximately 200 square feet in floor area, acceptable to the Contracting Officer. The trailer shall be securely anchored to the ground at all four corners to guard against movement during high winds. The trailer shall be located and the site prepared as shown on the drawings. Government office and warehouse facilities will not be available to the Contractor's personnel.

1.19 PROJECT IDENTIFICATION

a. Mark all equipment and temporary offices, sheds, and trailers with the name and telephone number of the Contractor or Subcontractor.

b. Markings shall be conspicuous, neat, and easy to read.

c. No other signs are allowed except those required by law or by this Contract.

1.20 PLANT COMMUNICATION

Whenever the Contractor has the individual elements of its plant so located that operation by normal voice between these elements is not satisfactory, the Contractor shall install a satisfactory means of communication, such as telephone or other suitable devices. The devices shall be made available for use by Government personnel.

1.21 PROJECT SIGN

Contractor shall furnish and install one project sign in accordance with conditions hereinafter specified and layout shown on drawing No. 49s-40-05-15, Sheets 1 and 2, except Corps of Engineers' castle and Department of Air Force seal will be Government furnished. All letters shall be block type, upper case. Letters shall be painted as indicated using exterior-type paint. Sign shall be maintained in excellent condition throughout the life of job. Project sign shall be located as directed. Upon completion of project, sign shall be removed and shall remain the property of Contractor.

1.22 HARD HAT SIGNS

The Contractor shall provide 24 x 24 inch square Hard Hat Area signs at each entry to the project or work area as directed and coordinated through the Contracting Officer with the Base Operations. A minimum of two signs will be required. Signs shall be in accordance with the sketch at the end of this section.

PART 2 PRODUCTS AND PART 3 EXECUTION (NOT APPLICABLE)



- SIGN SHALL BE FABRICATED FROM .125 THICK 6061-T6 ALUMINUM PANEL
- COLOR
    1. SAFETY RED (SR)
    2. WHITE
    3. WHITE
    4. BLACK
- LETTERING SHALL BE HELVETICA BOLD TYPOGRAPHY.
- LETTERS AND BACKGROUND SHALL BE REFLECTIVE SHEETING MATERIAL.
- SIGNS SHALL BE POSTED AT 6'-6" (BOTTOM SIGN TO GRADE) OR AS DIRECTED BY THE CONTRACTING OFFICER.
- LETTERING TO BE CENTERED ON PANEL.



SAMPLE CONSTRUCTION SIGN FOR MCP PROJECTS

SCHEDULE

SPACE	HT.	LINE	DESCRIPTION	LETTER HT.	STROKE
A	2"	1	LOCATION	2 3/8"	1/4"
B	2 5/8	2	PROJECT NOMENCLATURE *	2 3/4"	3/8"
C	5 3/4"	3	U.S. AIR FORCE PROJECT	4"	1/2"
D	8"	4	CONSTRUCTION UNDER SUPERVISION OF	1 1/2"	1/8"
E	4"	5	CONSTRUCTION AGENCY *	2 3/8"	1/4"
F	4"	6	GENERAL CONTRACTOR *	1 3/8"	3/16"
G	1"	7	GENERAL CONTRACTOR *	1 3/8"	3/16"
H	2 7/8"		* WILL VARY TO SUIT PROJECT REQUIREMENTS		
I	2"		SEATTLE DISTRICT		

U.S. AIR FORCE

PROJECT
CONSTRUCTION SIGN

Sheet 1 OF 2 Scale: As shown
U.S. Army Engr. Dist., Seattle, WA.
Dri A.L.W. Transmitted with report
Tri A.L.W. DATED: 20 JUNE 84
Chi A.L.W. File No. 49s / 40-05-15



NOTES:

1. Signboard 4' x 8' x 5/8" grade A-C exterior type plywood with medium density overlay on both sides.

2. Paint both sides and edges with one prime coat and two coats of paint, color white exterior type enamel. Lettering shall be as shown on drawing and shall be black gloss exterior type enamel.

3. Lettering shall be Helvetica medium.

4. Acceptable abbreviations may be used for Contractor's name.

5. Department of Air Force Seal and Corps of Engineers' Castle to be Government furnished.

6. No company logo shall be used.

7. Sign posts and 1-½" wood trim shall be painted white.

8. Upon completion of work under this contract, the project sign shall be removed from the job site and shall remain the property of the Contractor.

END OF SECTION

SECTION 01702

AS BUILT RECORDS AND DRAWINGS

PART 1 GENERAL

1.1 SUBMITTALS

Data listed in PART 3 of this section shall be submitted in accordance with section 01330 SUBMITTAL PROCEDURES. Due dates shall be as indicated in applicable paragraphs and all submittals shall be completed before final payment will be made.

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION

3.1 AS-BUILT FIELD DATA

3.1.1 General

The Contractor shall keep at the construction site two complete sets of full size prints of the contract drawings, reproduced at Contractor expense, one for the Contractor's use, one for the Government. During construction, both sets of prints shall be marked to show all deviations in actual construction from the contract drawings. The color red shall be used to indicate all additions and green to indicate all deletions. The drawings shall show the following information but not be limited thereto:

a. The locations and description of any utility lines and other installations of any kind or description known to exist within the construction area. The location includes dimensions and/or survey coordinates to permanent features.

b. The locations and dimension of any changes within the building or structure, and the accurate location and dimension of all underground utilities and facilities.

c. Correct grade or alignment of roads, structures, and utilities if any changes were made from contract plans.

d. Correct elevations if changes were made in site grading from the contract plans.

e. Changes in details of design or additional information obtained from working drawings specified to be prepared and/or furnished by the Contractor including, but not limited to, fabrication erection, installation, and placing details, pipe sizes, insulation material, dimensions of equipment foundations, etc.

f. The topography and grades of all drainage installed or affected as part of the project construction.

g. All changes or modifications from the original design and from the final inspection.

h. Where contract drawings or specifications allow options, only the option actually used in the construction shall be shown on the as-built drawings. The option not used shall be deleted.

These deviations shall be shown in the same general detail utilized in the contract drawings. Marking of the prints shall be pursued continuously during construction to keep them up to date. In addition, the Contractor shall maintain full size marked-up drawings, survey notes, sketches, nameplate data, pricing information, description, and serial numbers of all installed equipment. This information shall be maintained in a current condition at all times until the completion of the work. The resulting field-marked prints and data shall be referred to and marked as "As-Built Field Data," and shall be used for no other purpose. They shall be made available for inspection by the Contracting Officer's representative whenever requested during construction and shall be jointly inspected for accuracy and completeness by the Contracting Officer's representative and a responsible representative of the Contractor prior to submission of each monthly pay estimate. Failure to keep the As-Built Field Data (including Equipment-in-Place lists) current shall be sufficient justification to withhold a retained percentage from the monthly pay estimate.

3.1.2 Submittal of the As-Built Field Data

Two sets of the full size As-Built Field Data shall be submitted to the Contracting Officer for review and approval a minimum of 20 calendar days prior to the date of final inspection. If review of the preliminary as-built drawings reveals errors and/or omissions, the drawings will be returned to the Contractor for corrections. The Contractor shall make all corrections and return the drawings for backcheck to the Contracting Officer within 10 calendar days of receipt. When submitted drawings are accepted, one set of marked drawings will be returned to the Contractor for the completion of the as-built drawings.

3.2 AS-BUILT ELECTRONIC FILE DRAWINGS

3.2.1 No earlier than 30 days after award the Government will have available for the Contractor one set of MicroStation electronic file format contract drawings for the Repair Aircraft Parking Apron portion of the contract and one set of AutoCAD electronic file format contract drawings for the Repair Runway portion of the contract, to be used for preparation of as-built drawings. The electronic file drawings will be available on ISO-9660 CD-ROM. The Contractor has 30 days after the receipt of the electronic file to verify the usability of the MicroStation files, and bring any discrepancies to the attention of the Contracting Officer. Any discrepancies will be corrected within 15 days and files returned to the Contractor. The Contractor shall incorporate all deviations from the original contract drawings as recorded in the approved 'As-built Field Data' (see paragraph 3.1.2). The Contractor shall also incorporate all the written modifications to the contract drawings which were issued by amendment or contract modification. All revisions and changes shall be incorporated, i.e. items marked "deleted" shall be deleted, clouds around new items shall be removed, etc. The drafting work shall be performed by Certified Engineering Technicians and/or individuals with a minimum of 5 years drafting experience. The names and qualifications of these individuals shall be submitted in writing to the Contracting Officer for approval.

3.2.2 No later than 30 days after final acceptance a complete set of as-built drawings shall be submitted in AutoCAD electronic file format. The electronic file format, layering standards and submittal requirements are specified in paragraphs below. The as-built drawings shall be done in a quality equal to that of the originals. Line work, line weights, lettering, and use of symbols shall be the same as the original line work, line weights, and lettering, and symbols. If additional drawings are required they shall be prepared in electronic file format under the same guidance. When final revisions have been completed, each drawings shall be identified with the words "AS-BUILT" in block letters at least 3/8-inch high placed above the title block if space permits, or if not, below the title block between the border and the trim line. The date of completion and the

words “REVISED AS-BUILT” shall be placed in the revision block above the latest revision notation.

3.2.3 Electronic File Submittal Requirements

3.2.3.1 The AutoCAD electronic file(s) deliverable shall be in AutoCAD release 14 'DWG' binary format. All support files required to display or plot the file(s) in the same manner as they were developed shall be delivered along with the files. These files include but are not limited to Font files, Menu files Plotter Setup, and Referenced files. It is the Contractor's responsibility to translate the design Microstation files to AutoCad files for as-built drawings.

3.2.3.2 Layering shall conform to the guidelines defined by the "MHAFB Civil Engineerind Cad Layering Standards", attached at the end of this specification section. An explanatory list of which layer is used at which drawing and an explanatory list of all layers which do not conform to MHAFB Civil Engineerind CAD Layering Standards, including any user definable fields permitted by the guidelines, shall be provided with each submittal.

3.2.3.3 Electronic File Deliverable Media: All electronic files shall be submitted in ISO 9660 format CD-ROM (CD). Zip drive disks shall not be provided. Two complete sets of CD(s) shall be submitted along with one complete set prints and one complete set of full size mylars taken from the CD. See paragraph 3.2.4 below. Each floppy disk shall have a clearly marked label stating the Contractor’s firm name, project name and location, submittal type (AS-BUILT), and date the CD was made. Each submittal shall be accompanied by a hard copy transmittal sheet that contains the above information along with a tabulated information about each file, as shown below:

Electronic File Name	Plate Number	Drawing Title

Electronic version of the table shall be included with each submittal set of disks.

3.2.4 Submittal of the Final As-Built Drawings

The final as-built record drawings shall be completed and returned together with the approved preliminary as-built drawings to the COE, Seattle District Office, Technical Branch, Records and Information Section, within 30 calendar days of final acceptance. All drawings from the original contract drawings set shall be included, including the drawings where no changes were made. The Government will review all final as-built record drawings for accuracy and conformance to the drafting standards and other requirements contained in DIVISION 1 GENERAL REQUIREMENTS. The drawings will be returned to the Contractor if corrections are necessary. The Contractor shall make all corrections and shall return the drawings to the same office within 7 calendar days of receipt.

3.3 All costs incurred by the Contractor in the preparation and furnishing of as-built drawings in electronic file format shall be included in the contract price and no separate payment will be made for this work. Approval and acceptance of the final as-built record drawings shall be accomplished before final payment is made to the Contractor.

3.4 One set of marked-up as-built prints shall be furnished at the time of system acceptance testing. These as-built prints shall be in addition to the submittals of marked-up as-built prints specified elsewhere in the contract.

MHAFB CIVIL ENGINEERING CAD LAYERING STANDARDS

GENERAL GUIDELINES

1. There will be no numerical layer names. All layers will be in an abbreviated format; example: utilities = util, text = txt.

2. All New buildings will be located by their Geodetic Coordinates.

3. All blocks will be created on layer O.

4. The Contractor shall provide all projects in .DWG file format compatible with autoCAD Release 13 (or Microstation 5.0, if so directed by the Contracting Officer) on 89 mm (3-1/2 inch) floppy disks: low or high density is acceptable.

5. The Contractor shall provide a typed copy of layer names, limits, Lt scale, pen configurations, etc., and contents submitted as part of the Design Analysis and the final submittal of the disks.

6. All information shall be drawn at full scale. (1:1)

7. All text shall be in mono.

MANDATORY LAYER NAMES (CIVIL SITE PLANS ONLY)

LAYER NAME	TO INCLUDE	COLOR
BORDER	Border, Title Block, N Arrow, Scale	8 (Dark Grey)
TXT	Title Block, Text, Notes, Dims	11 (Dark Green)
STRUCT	Bldg. Outlines	4 (Cyan)
STRUCT T	Bldg. Numbers	(Red)
CONTOURS	Index & Intermediate Index/ Intermediate/	4 (Cyan) 1 (Red)
UTILS	All	7 (White)
PAVED	Paved Roads	2 (Yellow)
PAVED T	Street Names	1 (Red)
UNPAVED	Unpaved Roads	1 (Red)

Any specific questions regarding layering standards may be referred to the project engineer.

RECOMMENDED LAYER TITLES

Proposed Layers for a CIVIL/SITE Drawing:

Layer List: O (Not Used), BORDER, KEYMAP, SITEPLAN, FTPRINT, SOILBOR, CONTOURS, GRADING, LANDSCP, LAWNSPR, PAVING, WATER, SEWER, STDRAIN, ELECT, COMM, PHONE, NATGAS, SECTIONS, DETAILS, DEMOL, NEW, DIMS, TXT, MISC

Proposed Layers for a FOUNDATION Drawing:

Layer List: O (Not Used), BORDER, DEMOL, EXISTING, NEW, DIMS, TXT, MISC, KEYMAP, FDPLAN, SECTIONS, DETAILS, MISC

Proposed Layers for an ARCHITECTURAL Drawing:

Layer List: O (Not Used), BORDER, KEYMAP, FLPLAN, DOORS (SWINGS), WDWS, DIMS, TXT,DEMOL, NEW, SECT, DETAILS, SCHED, INTELV, MISC

Proposed Layers for a STRUCTURAL Drawing:

Layer List: O (Not Used), BORDER, KEYMAP, FLPLAN, DEMOL, NEW, BLDGSECT, STRDET, DIMS, TXT, MISC

Proposed Layers for a Roof Drawing:

Layer List: O (Not Used). BORDER, KEYMAP, FLPLAN, ROOFPLAN, ROOFFRMG, DEMOL, NEW, DIMS, TXT, MISC

Proposed Layers for an EXTERIOR ELEVATIONS Drawing:

Layer List: O (Not Used), BORDER, KEYMAP, NELEV, SELEV, EELEV, WELEV, DIMS, TXT, MISC

Proposed Layers for a MECHANICAL DRAWING:

Layer List: O (Not Used), BORDER, KEYMAP, FLPLAN, DIMS, TXT, WATER, SEWER, HVAC, SPRINKLER, SCHED, MISC

Proposed Layers for a HVAC Drawing:

Layer List: O (Not Used), BORDER, KEYMAP, FLPLAN, DIMS, TXT, HVAC, CONTROLS, SCHED, MISC

Proposed Layers for a LIGHTING Drawing:

Layer List: O (Not Used), BORDER, KEYMAP, FLPLAN, ELEDT, DIMS, TXT, DIAG/SCHEM (DIAGRAMS/SCHEMATICS), SCHED, MISC

Proposed Layers for an ELECTRICAL Drawing:

Layer List: O (Not Used), BORDER, KEYMAP, FLPLAN, ELECT, DIMS, TXT, DETAILS, DIAGRAMS, SCHED, MISC

Proposed Layers for a COMMUNICATIONS / TELEPHONE Drawing:

Layer List: O (not Used), BORDER, KEYMAP, FLPLAN, PHONEJCK, COMMDEV, CIRCUITS, PANELS, DIMS, TXT, DETAILS,DIAGRAMS, SCHED, MISC

END OF SECTION

This page intentionally blank

SECTION 01703 (AR)

WARRANTY OF CONSTRUCTION

PART 1 GENERAL

1.1 SUBMITTALS

Submittals shall be made in accordance with SECTION 01330: SUBMITTALS. Submittal dates shall be as defined in PART 3 of this section.

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION

3.1 WARRANTY OF CONSTRUCTION (APR 1984) (FAR52.246-21):

3.1.1 In addition to any other warranties in this contract, the Contractor warrants, except as provided in paragraph 3.1.9 of this Clause, that work performed under this contract conforms to the contract requirements and is free of any defect in equipment, material, or design furnished, or workmanship performed by the Contractor or any subcontractor or supplier at any tier.

3.1.2 This warranty shall continue for a period of 1 year from the date of final acceptance of the work. If the Government takes possession of any part of the work before final acceptance, this warranty shall continue for a period of 1 year from the date the Government takes possession.

3.1.3 The Contractor shall remedy at the Contractor's expense, any failure to conform, or any defect. In addition, the Contractor shall remedy, at the Contractor's expense, any damage to Government-owned or controlled real or personal property, when that damage is the result of:

a. the Contractor's failure to conform to contract requirements or

b. any defect of equipment, material, workmanship, or design furnished.

3.1.4 The Contractor shall restore any work damaged in fulfilling the terms and conditions of this clause. The Contractor's warranty with respect to work repaired or replaced will run for 1 year from the date of repair or replacement.

3.1.5 The Government will notify the Contractor, in writing or by telephone, after the discovery of any failure, defect, or damage and the Contractor shall respond and be on-site to correct the problem within 1 working day after notification. The Contractor shall furnish, and maintain, a 24 hour emergency telephone number as the point of contact. For failures, defects, or damage causing loss of power or heat, the Contractor shall respond within 4 hours.

3.1.6 If the Contractor fails to remedy any failure, defect, or damage within a reasonable time as determined by the Government, after receipt of notice, the Government will have the right to replace, repair, or otherwise remedy the failure, defect, or damage at the Contractor's expense.

3.1.7 With respect to all warranties, express or implied, from subcontractors, manufacturers, or suppliers for work performed and materials furnished under this contract, the Contractor shall:

a. obtain all warranties that would be given in normal commercial practice;

b. require all warranties to be executed, in writing, for the benefit of the Government, if directed by the Contracting Officer; and

c. enforce all warranties for the benefit of the Government, if directed by the Contracting Officer.

3.1.8 In the event the Contractor's warranty under paragraph 3.1.2 of this clause has expired, the Government may bring suit at its expense to enforce a subcontractor's, manufacturer's, or supplier's warranty.

3.1.9 Unless a defect is caused by the negligence of the Contractor or subcontractor or supplier at any tier, the Contractor shall not be liable for the repair of any defects of material or design furnished by the Government nor for the repair of any damage that results from any defect in Government-furnished material or design.

3.1.10 This warranty shall not limit the Government's rights under the Inspection and Acceptance clause of this contract with respect to latent defects, gross mistakes, or fraud.

3.1.11 After final acceptance of the work, the Contractor shall furnish and install an Equipment Warranty Sticker on Contractor-installed equipment. (Same equipment as listed on the Equipment-In-Place List required under Section 01705) Lettering shall be block-type upper case and easily readable. Sticker shall be of a durable type material and of a type that can be written on. Sticker shall state the following:

a. The title "Equipment Warranty."

b. Contractor's name and Contract Number.

c. Date warranty expires.

d. Point of contact, including name and telephone number.

e. Manufacturer.

END OF SECTION

SECTION 01704 (AR)

FORM 1354 CHECKLIST

PART 1 GENERAL

1.1 Procedures

The form which is a part of this specification section shall be completed for any project having revisions to real property. The following page contains the basic instructions applicable to the form.

1.2 Submittal

This form shall be submitted for approval, and be approved a minimum of 30 days before final inspection of the project. Failure to have this form completed and approved in time for the final inspection will result in delay of the inspection until the checklist is completed.

PARTS 2 AND 3 NOT USED

INSTRUCTIONS FOR DD FORM 1354 CHECKLIST

The following checklist is only a guide to describe various parts of new and modified construction. Alter this form as necessary or create your own document to give complete accounting of the real property added or deleted for this contract. All items added, deleted, replaced, or relocated within the building 1.5 meter (5 foot line), or on site 1.5 meters (5 feet) beyond the building perimeter must be accounted for completely. Only a few of the most common items beyond the 1.5 meter (5 foot) line are included on the checklist under UTILITIES/SURFACE CONSTRUCTION, add additional items as required by the construction accomplished.. Attach a continuation sheet and use the checklist format to describe other work related to this particular project. Listed on the last page are additional items with units of measure and descriptive terms.

Costs for each item must include material, tax, installation, overhead and profit, bond and insurance costs. This form should be filled out as each item is installed or each phase of work is completed.

TOTAL FOR ALL ITEMS INCLUDING CONTRACT MODIFICATION COSTS ADDED TOGETHER SHOULD EQUAL THE TOTAL CONTRACT PRICE.

NOTE: USE METRIC UNITS OF MEASURE INSTEAD OF ENGLISH UNITS SHOWN.

KEY TO ABBREVIATIONS

AC - Acres
BL - Barrels, Capacity
BTU - British Thermal Unit
CY - Cubic Yards
EA - Each
GA - Gallons, Capacity
HD - Head
kV - Kilovolt-Amperes, Capacity (kVA)
kW - Kilowatts, Capacity
SE - Seats
SF - Square Feet
SY - Square Yard
MB - Million British Thermal Units
Ml - Miles
LF - Linear Feet
KG - Thousand Gallons Per Day, Capacity
TN - Ton
- Number; How Many

DD FORM 1354 CHECKLIST

Transfer of Real Property

CONTRACT NUMBER:_____

CONTRACT TITLE:_____

LOCATION:_____

1. **DEMOLITION** (Describe each item removed and the cost of removal.)*

2. **RELOCATION** (Describe each item relocated and the cost of relocation.)*

3. **REPLACEMENTS** (Describe each item replaced and replacement cost.)*

*Use a continuation sheet if more space is required. Items should be described by quantity and the correct unit of measure.

4. **NEW CONSTRUCTION OVERVIEW: BUILDING(S)/ADDITION(S) TO A BUILDING** - Use a separate checklist for each building and/or addition.

(1) **Outside Dimensions: Length x Width**

(a) Main Building_____
(b) Offsets_____
(c) Wings_____
(d) Basement_____
(e) Attic_____

(2) **Number of Usable Floors**: _____

(3) **Construction: Exterior Materials Used**

(a) Foundation (such as concrete)_____
(b) Floors (such as wood, concrete)_____
(c) Walls (such as wood siding, metal, CMU)_____
(d) Roof (such as metal, comp., built-up)_____

(4) **Utilities ENTERING Building**: Measure lineal meters (LF) from building entry to next larger
size of pipe

(a) Water (size & type of pipe; number of lineal meters (LF)_____
(b) Gas (size & type of pipe; number of lineal meters (LF)_____
(c) Sewer (size & type of pipe; number of lineal meters (LF)_____
(d) Electric (phase, voltage, size & type of wire, connected load in amps_____

(5) **Air Conditioning**:

(a) Type_____
(b) Capacity Kilograms (TONS)_____
(c) SQ METERS (SQ YDS) covered by system_____

(6) **Heating**:

(a) Source_____
(b) Fuel_____

(7) **Hot Water Facilities**:

(a) Capacity Liters (GAL)_____
(b) Temperature Rise_____

BUILDING COST:_____

5. **BUILDING SYSTEMS (INTERIOR)**

A. **FIRE PROTECTION**:

Property Code

(1) (880 50/880-211) CLOSED HEAD AUTO SPRINKLERS - Square Meters (SF) & HD (wet or dry pipe; # of Lineal Meters (LF) of service pipe; type of pipe & # of heads; # of Square Meters (SF) covered by system)
DESCRIPTION:
_____
_____
_____
COST: _____

(2) (880 50/880-212) OPEN HEAD DELUGE SYSTEM - Square Meters (SF) & HD (# of Lineal Meters (LF) of service pipe; type of pipe; # of heads; # of Square Meters (SF) covered)
DESCRIPTION:
_____
_____
_____
COST: _____

(3) (880 10/880-221) AUTO FIRE DETECTION SYSTEM - Square Meters (SF) & EA (# of alarms-horns, bells, etc.; # of smoke detectors; # of heat detectors; # of fire alarm panels; # of radio transmitters/antennae)
DESCRIPTION:
_____
_____
_____
COST: _____

(4) (880 20/880-222) MANUAL FIRE ALARM SYSTEM - EA (# of pull stations; # of alarm horns; # of fire extinguisher cabinets)
DESCRIPTION:
_____
_____
_____
COST: _____

(5) (880 60/880-231) CO2 FIRE SYSTEM (# of bottles & size of bottles in kilograms (lbs.))
DESCRIPTION:
_____
_____
_____
COST: _____

(6) (880 60/880-232) FOAM FIRE SYSTEM - EA (# of tanks - capacity in kilograms (lbs.))
DESCRIPTION:
_____
_____
_____
COST: _____

(7) (880 60/880-233) OTHER FIRE SYSTEM - EA
DESCRIPTION:
_____
_____
_____
COST: _____

(8) (880 60/880-234) HALON 1301 FIRE SYSTEM - EA (# of bottles & size of bottles in kilograms (lbs.))
DESCRIPTION:
_____
_____
_____
COST: _____

B. **SECURITY**:

(1) (880 40/872-841) SECURITY ALARM SYSTEM - EA (name of system installed)
DESCRIPTION:
_____
_____
_____
COST: _____

C. **HEATING/COOLING SYSTEMS**

(1) (826 10/890-126) A/C WINDOW UNITS - kilograms (TN) & Square Meters (SF)-(# of units installed; amount of Square Meters (SF) covered per unit; size & capacity of each unit)
DESCRIPTION:
_____
_____
_____
COST: _____

(2) (826 14/890-125) A/C PLT LESS THAN 4,536 kilograms (5 TN) - kilograms (TN) & square meters (SF)-(# of kilograms (TN); # of square meters (SF) covered)
DESCRIPTION:
_____
_____
COST: _____

(3) (826 13/890-121) A/C PLT 4,536 to 22,680 kilograms (5 TO 25 TN) - kilograms (TN)-(# of kilograms (TN); # of square meters (SF) covered)
DESCRIPTION:
_____
_____
_____
COST: _____

(4) (826 12/826-122) A/C PLT 22,680 to 2,267,962 kilograms (25 TO 100 TN) - kilograms (TN)-(# of kilograms (TN); # of square meters (SF) covered)
DESCRIPTION:
_____
_____
_____
COST: _____

(5) (826 11/826-123) A/C PLT OVER 2,267,962 kilograms (100 TN) - kilograms (TN)-(# of kilograms (TN); # of square meters (SF) covered)
DESCRIPTION:
_____
_____
_____
COST: _____
(6) (821 33/821-115) HEATING PLT 220/1026 W (750/3500 MB) - W (MB)-(# of kW (MBH); type of heating system - Ex: Warm air furnace, central)
DESCRIPTION:
_____
_____
_____
COST: _____

(7) (821 32/821-116) HEATING PLT OVER 1026 W (3500 MB) - W(MB)-(# of kW (MBH); type of heating system)
DESCRIPTION:
_____
_____
COST: _____

(8) (811 60/811-147) ELEC EMERGENCY POWER GENERATOR-KW-(size of engine; rating of generator in kilowatts & voltage)
DESCRIPTION:
_____
_____

_____
COST: _____

(9) (81190 or 82320-gas) STORAGE TANK FOR HEATING or GENERATOR FUEL-Liters (GA); TYPE; FUEL-(Size, type of tank, kind of fuel & # of liters (gallons))
DESCRIPTION:
_____
_____
_____
COST: _____

SITE WORK

6. **UTILITIES/SURFACE CONSTRUCTION**:

(1) (812 41/812-223) PRIM DISTR LINE OH-Lineal Meters (LF)-(# Lineal Meters (LF) of wire; size & type of wire; # of poles; voltage)
DESCRIPTION:
_____
_____
_____
COST: _____

(2) (812/81360) TRANSFORMERS-KVA
POWER POLES-Lineal Meters (LF)
(# poles; # transformers - pad or pole mounted; kVA of wire; # Lineal Meters (LF) of wire)
DESCRIPTION:
_____
_____
_____
COST: _____

(3) (812 40/812-224) SEC DISTR LINE OH-Lineal Meters (LF)-(voltage; size & type of wire; # transformers; kVA; # Lineal Meters (LF) of wire; # of service drops; # poles)
DESCRIPTION:
_____
_____
_____
COST: _____

(4) (812 42/812-225) PRIM DISTR LINE UG-Lineal Meters (LF)-(kVA; voltage; type of conduit & size(encased or direct burial); size & kind of wire inside conduit; Lineal Meters (LF) of wire & conduit)
DESCRIPTION:
_____
_____
_____
COST: _____

(5) (812 42/812-226) SEC DISTR LINE UG-Lineal Meters (LF)-(type of conduit & size; type & size of wires in conduit; Lineal Meters (LF) of conduit & wire inside conduit; voltage)
DESCRIPTION:

_____
_____
_____
COST: _____

(6) (812 30/812-926) EXTERIOR LIGHTING-EA-(streets or parking area lights) (# & type of lights; whether pole mounted or not; # Lineal Meters (LF) of connecting wire if pole mounted)
DESCRIPTION:

_____
_____
_____
COST: _____

(7) (824 10/824-464) GAS MAINS-Lineal Meters (LF) (size, type, & # of Lineal Meters (LF) of pipe)
DESCRIPTION:

_____
_____
_____
COST: _____

(8) (831 90/831-169) SEWAGE SEPTIC TANK-thousand liters (KG)-(size, kind of material, & capacity)
DESCRIPTION:

_____
_____
_____
COST: _____

(9) (832 10/832-266) SANITARY SEWER-Lineal Meters (LF)-(sizes & types of pipes - # of Lineal Meters (LF) of each; # of cleanouts; # & size of manholes)
DESCRIPTION:

_____
_____
_____
COST: _____

(10) (842 10/842-245) WATER DISTR MAINS (POTABLE)-Lineal Meters (LF)-(# Lineal Meters (LF) & size, type of pipe)
DESCRIPTION:

_____
_____
_____
COST: _____

(11) (843 11/843-315) FIRE HYDRANTS-EA-(#; size & type)
DESCRIPTION:

_____
_____
_____
COST: _____

(12) (851 90/851-143) CURBS & GUTTERS-Lineal Meters (LF)-(# Lineal Meters (LF); material; width & height)
DESCRIPTION: (Is curb extruded or standard?)

_____
_____
_____
COST: _____

(13) (851 90/851-145) DRIVEWAY-Square Meters (SY)-Square Meters (SY); material used; thickness)
DESCRIPTION:

_____
_____
_____
COST: _____

(14) (851 10/12/851-147) ROAD-Square Meters (SY) & Lineal Meters (LF)-Square Meters (SY); material used; thickness; Lineal Meters (LF))
DESCRIPTION:

_____
_____
_____
COST: _____

(15) (85210/11 /852-262) VEHICLE PARKING-Square Meters (SY)-Square Meters (SY); material used; thickness; # of bollards; # of wheel stops; # of regular parking spaces; # of handicap spaces)
DESCRIPTION:

_____
_____
_____
COST: _____

(16) (852 20/852-289) SIDEWALKS-Square Meters (SY) & Lineal Meters (LF)-(# Square Meters (SF) & Lineal Meters (LF); dimensions of each section & location; thickness; material used)
DESCRIPTION:

_____
_____
_____
COST: _____

(17) (871 10/871-183) STORM DRAIN DISPOSAL-Lineal Meters (LF)-(# Lineal Meters (LF) of pipe; sizes & types of pipe; # of catch basins & manholes & sizes of each)
DESCRIPTION:

_____
_____
_____
COST: _____

(18) (872 15/872-247) FENCE, SECURITY (ARMS)-Lineal Meters (LF)-(# of Lineal Meters (LF); fence material; # & type of gate(s); # strands of barbed wire on top)
DESCRIPTION:

_____
_____
_____
COST: _____

(19) (87210/12/872-248) FENCE, INTERIOR-Lineal Meters (LF)-(# of Lineal Meters (LF); fence material; # & kind of gate(s)
DESCRIPTION:

_____
_____
_____
COST: _____

(20) (890 70/890-187) UTILITY VAULT(4 or more transformers)- Square Meters (SF) (# Square Meters (SF); dimensions of vault; # of transformers)
DESCRIPTION:

_____
_____
_____
COST: _____

(21) (135 10/135-583) TEL DUCT FACILITY-Lineal Meters (LF)-(# of Lineal Meters (LF); size & type of conduit; type of wire)
DESCRIPTION:

_____
_____
_____
COST: _____

(22) (135 10/135-586) TEL POLE FACILITY-Lineal Meters (LF)-(# Lineal Meters (LF) & type of wire; # of poles)
DESCRIPTION:

_____
_____
_____
COST: _____

7. **INSTALLED EQUIPMENT**: Furnish an Equipment-In-Place List. Any price related to equipment should already be included in this checklist.

8. **SYSTEMS NOT PREVIOUSLY LISTED**: Attach a separate sheet and use the same format to describe the system(s). Example: CATV system, intercom system, or other utilities and surface construction not described on this checklist.

9. **ASBESTOS REMOVAL**: Furnish a description by building of the number of Lineal Meters (LF) of asbestos removed, number of Lineal Meters (LF) of reinsulation, number of Square Meters (SF) of soil encapsulation, and number and size of tanks, etc., where asbestos was removed. Also, identify buildings by their numbers and use.

10. **MAINTENANCE/RENOVATIONS**: List by building number and describe all additions and deletions by quantity and the correct unit of measure. Furnish a cost per building.

UTILITIES/SURFACE CONSTRUCTION - Listed below are some additional items which may or may not apply to your contract. EACH item installed on site should be listed and priced separately even if not included on this checklist.

(1) IRRIGATION SYSTEM(-Lineal Meters (LF) of pipe; size & type of pipe; number and type of heads)
(2) UNDERGROUND/ABOVEGROUND STORAGE TANKS(-Liters (GA), type of tank; material stored)
(3) (833-354) DUMPSTER ENCLOSURE(-Square Meters (SF) & dimensions)
(4) (890-152) UNLOADING PAD(-Square Meters (SY); material)
(5) SIGNAGE-(Dimensions; material)
(6) (12580) CATHODIC PROTECTION(kilometers; Lineal Feet) (MI; LF)
(7) (87270 LIGHTNING PROTECTION-Lineal Feet (LF)
(8) (81290) POLE DUCT RISER(-Lineal Feet (LF, type of material)
(9) RAMPS-Square Meters (SF), material; Cubic Meters (CY) if concrete-use code for sidewalk if concrete)
(10) (89080/890-158) LOAD AND UNLOAD PLATFORM-Square Meters (SF)
(11) (83240/832-255) INDUSTRIAL WASTE MAIN-Lineal Meters (LF)
(12) WHEEL STOPS-(EA; size & material)
(13) (81350) OUTDOOR INTEGRAL DISTR CTR-(kVA)
(14) (45110) OUTDOOR STORAGE AREA-Square Meters (SF)
(15) (73055/730-275) BUS/WAIT SHELTER-Square Meters (SF)
(16) (690-432) FLAGPOLE-(EA; dimensions)
(17) (93210) SITE IMPROVEMENT-(JOB)
(18) (93220) LANDSCAPE PLANTING (Hectare (Acre); EA; Square Meters (SF))
(19) (93230) LANDSCAPE BERMS/MOUNDS-Square Meters (SY)
(20) (93410) CUT AND FILL-Cubic Meters (CY)
(21) (843-315) FIRE HYDRANTS-(EA; Type)
(22) (14970) LOADING AND UNLOADING DOCKS AND RAMPS (not connected to a building)-Square Meters (SF) (23) BICYCLE RACK-(EA)
(24) (85140/812-928) TRAFFIC SIGNALS-(EA)
(25) (87210) FENCING OR WALLS-Lineal Meters (LF)
(26) (15432) RIPRAP-Lineal Meters & Square Meters (LF & SY)
(27) (75061) GRANDSTAND OR BLEACHERS-(EA; SE)
(28) 87150/871-187) RETAINING WALLS-Lineal Meters; Square Meters (LF; SY); material

NOTE: 5 Digit Codes-Army; 6 Digit Codes-Air Force

END OF SECTION

This page intentionally blank

THE FOLLOWING TECHNICAL SPECIFICATIONS APPLY TO
REPAIR AIRCRAFT PARKING APRON ONLY:

Section No.	Section Title
	DIVISION 1 - GENERAL REQUIREMENTS
	Repair Aircraft Parking Apron
01415 A	Metric Measurements
01450 A	Chemical Data Quality Control

This page was intentionally left blank for duplex printing.

SECTION 01415 (A)

METRIC MEASUREMENTS

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM E 380	(1993) Practice for Use of the International System of Units (SI)
ASTM E 621	(1994) Practice for Use of Metric (SI) Units in Building Design and Construction

1.2 GENERAL

This project includes metric units of measurements. The metric units used are the International System of Units (SI) developed and maintained by the General Conference on Weights and Measures (CGPM); the name International System of Units and the international abbreviation SI were adopted by the 11th CGPM in 1960. A number of circumstances require that both metric SI units and English inch-pound (I-P) units be included in a section of the specifications. When both metric and I-P measurements are included, the section may contain measurements for products that are manufactured to I-P dimensions and then expressed in mathematically converted metric value (soft metric) or, it may contain measurements for products that are manufactured to an industry recognized rounded metric (hard metric) dimensions but are allowed to be substituted by I-P products to comply with the law. Dual measurements are also included to indicate industry and/or Government standards, test values or other controlling factors, such as the code requirements where I-P values are needed for clarity or to trace back to the referenced standards, test values or codes. For American Society for Testing and Materials (ASTM) references in the technical specifications, the Contractor shall use the metric publication, if one is available (For example: ASTM A 36, use ASTM A 36M). An acceptable substitute to hard Metric SI Concrete Masonry Units (CMU) and Recessed Lighting Fixtures (RLF) is English in-pound (soft metric) CMU and RLF. The Contractor shall be responsible for any adjustments required to accommodate these alternative English in-pound units at no additional cost to the Government.

1.3 USE OF MEASUREMENTS

Measurements shall be either in SI or I-P units as indicated, except for soft metric measurements or as otherwise authorized. The Contractor shall be responsible for all associated labor and materials when authorized to substitute one system of units for another and for the final assembly and performance of the specified work and/or products.

1.3.1 Hard Metric

A hard metric measurement is indicated by an SI value with no expressed correlation to an I-P value, i.e., where an SI value is not an exact mathematical conversion of an I-P value, such as the use of 100 mm in lieu of 4 inches. Hard metric products are required when only metric dimensions are indicated, except for Contractor's options as outlined in paragraph GENERAL above. Hard metric measurements are often used for field data such as distance from one point to another or distance above the floor. Products are considered to be hard metric when they are manufactured to metric dimensions or have an industry recognized metric designation.

1.3.2 Soft Metric

a. A soft metric measurement is indicated by an SI value which is a mathematical conversion of the I-P value shown in parentheses e.g. 38.1 mm (1-1/2 inches). Soft metric measurements are used for measurements pertaining to products, test values, and other situations where the I-P units are the standard for manufacture, verification, or other controlling factor. The I-P value shall govern while the metric measurement is provided for information.

b. A soft metric measurement is also indicated for products that are manufactured in industry designated metric dimensions but are required by law to allow substitute I-P products. These measurements are indicated by a manufacturing hard metric product dimension followed by the substitute I-P equivalent value in parentheses e.g., 190 x 190 x 390 mm (7-5/8 x 7-5/8 x 15-5/8 inches).

1.3.3 Neutral

A neutral measurement is indicated by an identifier which has no expressed relation to either an SI or an I-P value (e.g., American Wire Gage (AWG) which indicates thickness but in itself is neither SI nor I-P).

1.4 COORDINATION

Discrepancies, such as mismatches or product unavailability, arising from use of both metric and non-metric measurements and discrepancies between the measurements in the specifications and the measurements in the drawings shall be brought to the attention of the Contracting Officer for resolution.

1.5 RELATIONSHIP TO SUBMITTALS

Submittals for Government approval or for information only shall cover the SI or I-P products actually being furnished for the project. The Contractor shall submit the required drawings and calculations in the same units used in the contract documents describing the product or requirement unless otherwise instructed or approved. The Contractor shall use ASTM E 380 and ASTM E 621 as the basis for establishing metric measurements required to be used in submittals. For quick reference the :METRIC REFERENCE CHARTS" and "METRIC CONVERSION CHARTS" attached herein may be used.

PART 2 PRODUCTS & PART 3 EXECUTION (NOT APPLICABLE)

END OF SECTION

SECTION 01450 (A)

CHEMICAL DATA QUALITY CONTROL

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

CODE OF FEDERAL REGULATIONS (CFR)

40 CFR 261	Identification and Listing of Hazardous Waste
40 CFR 262	Standards Applicable to Generators of Hazardous Waste
40 CFR 268	Land Disposal Restrictions
49 CFR 172	Hazardous Materials Table, Special Provisions, Hazardous Materials Communications, Emergency Response Information, and Training Requirements
49 CFR 178	Specifications for Packagings

ENGINEERING MANUALS (EM)

EM 200-1-1	(1994) Validation of Analytical Chemistry Laboratories
EM 200-1-3	(1994) Requirements for the Preparation of Sampling and Analysis Plans Ch 1
EM 200-1-6	(1997) Chemical Quality Assurance

ENGINEERING REGULATIONS (ER)

ER 1110-1-263	(1996) Data Quality Management for Hazardous, Toxic, Radioactive Waste Remedial Activities

ENVIRONMENTAL PROTECTION AGENCY (EPA)

EPA 540/R 94-012	(1994) Contract Laboratory Program National Functional Guidelines for Inorganic Data Review
EPA 540/R 94-013	(1994) Contract Laboratory Program National Functional Guidelines for Organic Data Review
EPA SW-846	(Rev O; updates I, II, IIA, IIB, and III) Test Methods for Evaluating Solid Waste (Vol IA, IB, IC, and II)

U.S. ARMY ENVIRONMENTAL HYGIENE AGENCY (USAEHA)

USAEHA Sample Protocol	(1993) Sampling Protocol Building Demolition Debris and Buildings Painted with Lead-Based Paint

1.2 ACRONYMS

The definition of acronyms used by the Contractor that pertain to chemical data quality control shall be clearly defined for all contract related products and communications.

1.3 MEASUREMENT AND PAYMENT

Separate payment will not be made for providing and maintaining the chemical data quality requirements including the chemical data quality management, chemical data validation, minimum chemical data reporting requirements, and chemical data quality submittal requirements; these costs shall be included in the applicable unit prices or lump sum prices contained in the bidding schedule.

1.4 CHEMISTRY REQUIREMENTS

Chemical Data Quality Control (CDQC) shall be as defined in ER 1110-1-263; this ER, which integrates USACE guidance on the subject, shall be supplemented by EM 200-1-6 for detail technical guidance on CDQC. Tables and charts defining Design Analysis (DA), ROD, and remedial technology specific chemistry shall be according to or consistent with EM 200-1-3.

1.4.1 Site History

Mountain Home Air Force Base is home to the 366th Wing, Air Combat Command. The Wing stands ready to rapidly deploy worldwide as a composite air expeditionary wing flying fighter, bomber, and refueling/support aircraft. Aircraft from the 366th Wing, as well as transient aircraft utilize the parking apron also known as the “Mobility Ramp” between Base Operations, and Taxiways “C” and “D”. This project is to repair the Mobility Ramp. Petroleum hydrocarbon contamination, in the form of jet fuel (JP-4, JP-5, and JP-8), is suspected in subsurface soils underlying the existing Mobility Ramp. A site investigation conducted in August 2001 showed no levels of benzene, toluene, ethylbenzene, and xylenes (BTEX) or polynuclear aromatic hydrocarbons (PAHs) associated with jet fuel above Idaho Department of Environmental Quality (IDEQ) Tier 0 Soil Cleanup Levels. However, not all proposed locations were sampled.

1.4.2 Data Quality Objectives (DQO)

Sample acquisition, chemical analysis and chemical parameter measurements shall be performed so that the resulting data meet and support data use requirements.

The data objectives are: to determine whether contamination remains in excavations of contaminate sub-surface soils underlying the existing paved aircraft parking and taxiway areas within project boundaries and to determine whether remaining contamination meets IDEQ Tier 0 soil cleanup levels.

The chemical data shall be acquired, documented, verified and reported to ensure that the specified precision, accuracy, representativeness, comparability, completeness and sensitivity requirements are achieved.

1.4.3 Sampling, Analysis and Measurement

1.4.3.1 Soil Samples

Soil samples shall be collected and analyzed and shipped to a primary laboratory according to Section 2111A - EXCAVATION AND HANDLING OF CONTAMINATED MATERIAL.

1.4.3.5 Manifesting Samples (NOT USED)
1.4.3.6 Process Gas and Particulate Emission Samples (NOT USED)
1.4.3.7 Real-Time Instrumental Measurement Samples (NOT USED)
1.4.3.8 Perimeter Air Monitoring Samples (NOT USED)
1.4.3.9 Compatibility Field Testing for Bulking Operations (NOT USED)
1.4.3.10 Demolition Samples (NOT USED)

1.4.3.11 Field Screening

Field screening shall include photoionization detector or flame ionization detector or similar methods.

1.5 QUALITY ASSURANCE ELEMENTS

The Contractor shall be responsible for the following QA elements necessary to monitor and ensure the quality of chemical data produced.

1.5.1 Laboratory Validation Requirements

The Contractor shall propose the minimum number of laboratories that can attain or have attained U.S. Army Corps of Engineers (USACE) validation in accordance with EM 200-1-1 and consistent with contract required chemical data quality. The Contractor may propose laboratories that shall subsequently be validated by the USACE, or select currently validated USACE laboratories. The Contractor shall identify all proposed project laboratories in the sampling and analysis plan (SAP). If a proposed analytical laboratory cannot meet specified analytical requirements or achieve the required validation, the Contractor shall select another laboratory. If not currently validated, the USACE laboratory validation process requires a nominal 120 day process.

1.5.2 Quality Assurance Sample Collection and Analysis

The Contractor shall be responsible for collection and transportation of QA samples to the QA laboratory. Samples for all analyses (except volatiles) shall be taken as splits of homogenized samples. Samples for volatiles shall be collected as discrete duplicates/triplicates. Samples shall be collected at a rate of 10 percent per matrix per analysis per sampling event.

1.5.4 Review of Primary Laboratory Data

The Contractor shall be responsible for the independent data review of the entire primary data set.

To ensure that project data are sufficient to meet both qualitative and quantitative DQOs, laboratory data deliverables permitting a data quality assessment are required.

Information provided will be sufficient to review the data with respect to:

- Holding times and conditions
- Detection/quantitation limits
- Initial and continuing calibration
- Surrogate recoveries
- Laboratory duplicates and MS/MSDs
- Precision and accuracy
- Representativeness
- Comparability
- Completeness
- Method SOP adherence

1.6 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Product Data

Sampling and Analysis Plan; G,.

The SAP including the Field Sampling Plan (FSP) and the Quality Assurance Project Plan (QAPP), no later than 14 days after receipt of notice to proceed.

Test Reports

Chemistry Data Package; FIO,

The chemistry data package shall be provided as an attachment to the CDFR at the end of the project.

Chemical Data Final Report; G,

The CDFR, within 14 days of completing work at the site, before final payment. Each report shall be labeled with the contract number, project name and location.

1.7 QUALIFICATIONS

1.7.1 Chemical Quality Control Officer

As a minimum, the Contractor's Chemical Quality Control Officer shall have: an MS degree in Chemistry; 5 years of experience related to investigations, studies, design and remedial actions at HTRW sites; and 2 field seasons (or one continuous calendar year experience) in calibration and operation of various field monitoring devices as well as standard analytical chemistry methods common for analyzing soil, water, air and other materials for chemical contamination assessment, including hazardous waste manifesting. The Chemical Quality Control Officer shall ensure that all chemistry related objectives including responsibilities for DQO definitions, sampling and analysis, project requirements for data documentation and validation, and final project reports are attained. The Chemical Quality Control officer need not be present onsite during routine sampling, but shall be available for consultation with Government and Contractor personnel.

1.7.2 Project Chemist

As a minimum, the Contractor's Senior Chemist shall have: an MS degree in Chemistry; 5 years of experience related to investigations, studies, design and remedial actions at HTRW sites; 2 field seasons experience in calibrating and operating various field monitoring devices; and 4 years of experience in the operation of an HTRW commercial laboratory with standard analytical chemistry methods common for analyzing soil, water, air and other materials for chemical contamination assessment, including data for hazardous waste manifesting. The project chemist shall ensure that all chemistry related goals of the program are attained. The project chemist shall be onsite during all sampling events and shall also be available for consultation with Government personnel.

1.7.3 Environmental Sampler

As a minimum, the Contractor's Environmental Sampler shall have: a BS degree in Chemistry, Environmental Science, Engineering, Geology, Hydrology, or a related field; 4 years of experience in the development and preparation of SAP and work plans; 4 years of experience in and knowledge of EPA methods for collecting environmental and hazardous waste samples; 4 years of experience in operation of field screening equipment (e.g. PID, FID, infrared spectrometer, immunoassay, etc.); and 2 field seasons of experience with the particular field screening techniques for use on this project. The Environmental Sampler shall collect all onsite samples and perform all field screening tests. The Environmental Sampler shall review the sampling results, and provide recommendations for the Contractor's sampling program. The Environmental Sampler shall be onsite during excavation and stockpiling operations involving contaminated soil or soil to be checked for contamination.

1.8 COORDINATION MEETING

After the preconstruction conference, before any sampling or testing, the Contractor and the Contracting Officer will meet at the construction site to discuss the CQC Plan and the SAP. The coordination meeting will be simultaneous to any CQC coordination meeting required in Section 01451 CONTRACTOR QUALITY CONTROL unless otherwise indicated or directed. A list of definable features that involve chemical measurements shall be agreed upon. At a minimum, each matrix (soil, water, air, containerized wastes, radioactive wastes, instrumental chemical parameter measurement, etc.) shall be a definable work feature. Management of

the chemical data quality system including project DQO, project submittals, chemical data documentation, chemical data assessment, required sampling and analysis protocols, and minimum data reporting requirements shall be agreed upon. The meeting will serve to establish an interrelationship between the Contractor's chemical data quality management and Government chemical quality assurance requirements. Minutes of the meeting will be documented by the Government and shall be signed by both the Contractor and the Contracting Officer. The minutes will include any or all unresolved chemical issues along with the conditions for resolution and will become a part of the contract file.

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

The Contractor shall be responsible for chemical sample acquisition, sample analysis, instrumental measurements of chemical parameters and for chemical data quality control. An effective chemical data quality control system shall be established that meets the requirements for the chemical measurement DQO applicable to the project. The system shall cover chemical measurements pertaining to and required for Contractor and subcontractor produced chemical data. The Contractor shall control field screening, sampling, and testing in conjunction with remedial activities to meet all DQO; minimize the amount of excavated material requiring temporary storage; prevent dilution of contaminated soils with clean soils; and ensure completion of work within the required time.

3.2 QUALITY CONTROL PLAN

3.2.1 Additional Requirements

In addition to the quality control requirements specified in Section 01451 CONTRACTOR QUALITY CONTROL, the CQC Plan shall incorporate the qualifications, authority and responsibilities of all chemical quality management and support personnel. Chemical measurements including sampling and/or chemical parameter measurement will not be permitted to begin until after production and acceptance of the CQC Plan, and Government approval of the SAP.

3.2.2 Chemistry Elements of the CQC Plan

To cover contract related chemical measurements by the Contractor and all subcontractors, the CQC Plan shall include the following as a minimum.

3.2.2.1 Qualifications

Names, education, experience qualifications, authorities, and decision-making responsibilities of all chemical quality management and support personnel. The CQC Plan shall contain a copy of a letter from the project QC manager designating and authorizing a Chemical Quality Control Officer and chemical quality control organization staff.

3.2.2.2 Authority and Responsibility

A diagram, flow chart, or figure clearly depicting the chemical data quality management and support staff and the authority and responsibility of each for chemical sampling and analysis, procedures for corrective actions, deliverables and submittals, deviations and changes, chemical quality documentation, data validation, minimum data reporting requirements, and DQO for chemical parameter measurement by the Contractor and subcontractors. The contents of this section of the CQC Plan shall be included in the applicable "Project Organization" elements of the FSP and the QAPP.

3.3 SAMPLING AND ANALYSIS PLAN

The SAP shall be prepared in accordance with CDQC requirements and EM 200-1-3. The SAP shall be a single document that contains two distinct elements: FSP and QAPP. Sections of the FSP and QAPP shall be cross referenced. The SAP shall confirm the Contractor's understanding of the contract requirements for chemical data quality control, and shall describe procedures for field sampling and sample submittal for analysis, field chemical parameter measurement, data documentation, data assessment and data reporting requirements. The SAP shall delineate the methods the Contractor intends to use to accomplish the chemical quality control items to assure accurate, precise, representative, complete, legally defensible and comparable data. The SAP shall describe all chemical parameter measurements for all matrices for all phases of the remediation contract. As a single interrelated document, the SAP shall be provided to field and laboratory personnel. The Contractor may propose original/innovative approaches to chemical parameter measurements for cost reduction and remediation efficiency by abbreviated sampling, contingency sampling and/or contingency analysis, indicator or tracer analysis, onsite analytical services, equivalency or screening methods. The SAP shall clearly identify the Contractor obtained laboratories. The Contractor shall furnish copies of the Government approved SAP to all laboratories and the Contractor's field sampling crew. The SAP shall address all levels of the investigation with enough detail to become a document which may be used as an audit guide for field and laboratory work.

3.3.1 Field Sampling Plan

The FSP shall contain necessary technical detail and direction for the field personnel to understand sampling and field measurement requirements. The FSP shall provide a comprehensive description and full detail for personnel to perform all onsite activities required to attain project DQO, including: locations of samples, sampling procedures for onsite and offsite chemical analysis, summaries of analyses to be performed on samples, shipment of samples for offsite analyses, performance of onsite and offsite instrumental parameter measurements, data documentation and reporting requirements.

3.3.2 Quality Assurance Project Plan

The QAPP shall contain necessary technical detail and direction for field and laboratory personnel to understand project sample analysis, quality control and data reporting requirements, analytical methods, required detection limits, QC requirements, and data validation and reporting requirements.

3.4 CHEMISTRY DATA PACKAGE

The chemistry data package shall be produced and provided through USACE CO as an attachment to the CDFR. The chemistry data package shall contain information to demonstrate that the project's DQO have been fulfilled. The QA function will compare QA sample results to corresponding primary sample results, will assess the Contractor's compliance with the SAP, and will recommend corrective action as necessary.

3.5 CONTROL OF CHEMICAL DATA QUALITY

Contractor chemical data quality control shall ensure that a quality control program is in place that assures sampling and analytical activities and the resulting chemical parameter measurement data comply with the DQO and the requirements of the SAP. The Contractor shall utilize the three-phase control system that includes a preparatory, initial and follow-up phase for each definable feature of work. The Contractor's three-phase chemical data control process shall ensure that data reporting requirements are achieved and shall be implemented according to Section 01451 CONTRACTOR QUALITY CONTROL. The three-phase chemical data control process shall be combined with that under Section 01451CONTRACTOR QUALITY CONTROL.

3.6 ANALYTICAL TESTING LABORATORIES

The Contractor shall propose the analytical laboratories to be used for the primary samples analyses. Laboratory validation requirements shall be in accordance with paragraph Laboratory Validation Requirements. The Contractor may utilize its own laboratory or utilize subcontract laboratories to achieve the primary required sample analyses.

3.6.1 Laboratory Analytical Requirements

The Contractor shall provide the specified chemical analyses by the Contractor's laboratory. The Contractor shall provide chemical analyses to achieve the project DQO for all parameters specified by the methods. To give the USACE programs the greatest flexibility in the execution of its projects, the EPA SW-846 methods are generally the methods employed for the analytical testing of environmental samples. These methods are flexible and shall be adapted to individual project-specific requirements.

3.6.2 Laboratory Performance

The Contractor shall provide continued acceptable analytical performance and shall establish a procedure to address data deficiencies noted by review and/or quality assurance sample results. The Contractor shall provide and implement a mechanism for providing analytical labs with the SAP or QAPP portion of the SAP, for monitoring the lab's performance and for performing corrective action procedures. The Contractor shall acquire analytical services with additional USACE validated laboratories in the event a project lab loses its validation status during the project.

3.7 CHEMICAL DATA FINAL REPORT

The CDFR shall be produced including a summary of quality control practices employed and all chemical parameter measurement activities after project completion. As a minimum, the CDFR shall contain the following:

a. Summary of project scope and description.

b. Summary of any deviations from the design chemical parameter measurement specifications.

c. Summary of chemical parameter measurements performed as contingent measurements.

d. Summary discussion of resulting data including achieving data reporting requirements.

e. Summary of achieving project specific DQO.

f. Presentation and evaluation of the data to include an overall assessment on the quality of the data for each method and matrix.

g. Internal QC data generated during the project, including tabular summaries correlating sample identifiers with all blank, matrix spikes, surrogates, duplicates, laboratory control samples, and batch identifiers.

h. A list of the affected sample results for each analyte (indexed by method and matrix) including the appropriate data qualifier flag (J, B, R, etc.), where sample results are negatively impacted by adverse quality control criteria.

i. Summary of field and laboratory oversight activities, providing a discussion of the reliability of the data, QC problems encountered, and a summary of the evaluation of data quality for each analysis and matrix as indicated by the laboratory QC data and any other relevant findings.

j. Conclusions and recommendations.

k. Appendices containing: (1) Chemistry data package, and (2) Results of the Chemical Quality Assurance Report (CQAR). The CQAR is a Government produced document achieved through the inspection and analysis of QA samples and corresponding project sample data. The CQAR will include review of all QC parameters such as holding times, detection limits, method blanks, surrogate recoveries, matrix spikes and duplicates, and inter-laboratory and intra-laboratory data comparisons.

3.8 DOCUMENTATION

Documentation records shall be provided as factual evidence that required chemical data has been produced and chemical data quality has been achieved. The documentation shall comply with the requirements specified in paragraphs SAMPLING AND ANALYSIS PLAN, CHEMISTRY DATA PACKAGE, and CHEMICAL DATA FINAL REPORT.

3.9 NOTIFICATION OF NON-COMPLIANCE

The Contracting Officer will notify the Contractor of any detected noncompliance with the foregoing requirements. The Contractor shall take immediate corrective action after receipt of such notice.

END OF SECTION

This page intentionally blank

THE FOLLOWING TECHNICAL SPECIFICATIONS APPLY TO
REPAIR RUNWAY ONLY:

Section No.	Section Title
	DIVISION 1 - GENERAL REQUIREMENTS
	Repair Runway
01010 R	General Requirements
01051 R	Contractor Furnished Construction Surveying and Staking
01110 R	Airfield Project Safety Procedures
01356 R	Storm Water Pollution Prevention Measures

This page was intentionally left blank for duplex printing.

SECTION 01010 (R)

GENERAL REQUIREMENTS
(Repair Runway)

1 GENERAL

1.1 PROJECT DESCRIPTION

The project to repair Runway 12/30 at Mountain Home Air Force Base, Idaho consists of the demolition and replacement of portland cement concrete slabs to reconstruct the 12 and 30 ends of the runway. The project also includes mill and overlay the existing asphalt pavement of Runway 12/30.

1.1.1 The work includes but is not limited to:

1.1.1.1 Place temporary relocated threshold marking for use during reconstruction of the 12 and 30 ends of the runway.

1.1.1.2 Complete demolition and removal of all identified slabs, to include removal of existing base course.

1.1.1.3 Crush and screen demolished concrete to be reused as base course.

1.1.1.4 Place, grade and compact crushed concrete base course in compliance with these specifications.

1.1.1.5 Place, cure and finish new Portland Cement Concrete (PCC). Saw joints and install joint sealant.

1.1.1.6 Mill, repair cracks and overlay the Asphaltic Concrete (AC) runway surface.

1.1.1.7 Place, grade and compact crushed concrete base course and pave Asphaltic Concrete (AC) shoulders.

1.1.1.8 Install untra-high molecular (UHMW) polyethylene panels under the aircraft arresting system barrier cable as shown on the drawings.

1.1.1.9 Install Runway Ice Detection System. Installation shall include all work necessary to repair and upgrade the system, including sensors, wires, processing units, hardware and software. All work shall be accomplished in accordance with manufacturer's recommendations.

1.1.1.10 Replace a limited number of high intensity runway edge lights, to include new light, light base and concrete vault.

1.1.1.11 Paint pavement markings as shown on drawings. This includes temporary markings before construction and permanent markings after construction is complete. All temporary markings will be removed after the project is complete.

1.1.1.12 Groove reconstructed runway pavement.

1.1.1.13 Optional Bid Items 0012 and 0013: Repair Taxiway A in conjunction with mill and overlay existing Runway 12/30 asphalt pavement.

1.1.1.14 Optional Bid Items 0014 and 0015: Repair Taxiway E in conjunction with reconstruct Runway 30.

1.1.2 Definitions

The following terms relate to this project:

1.1.2.1 Contracting Officer (CO):

This shall refer to the person or persons on base authorized to enter into, administer and terminate contracts and make related determinations and findings. The term includes certain Authorized Representatives of the CO acting within the limits of their authority as delegated by the CO. As defined in the Federal Acquisition Regulation (FAR) 52.201-1 (b).

1.1.2.2 Flightline:

This term refers to the general area where aircraft operations, including taxiing, flying, maintenance and related activities, take place. Includes not only areas where aircraft park and operate, but also roads and buildings adjacent to the airfield associated with the support of aircraft operations.

1.1.2.3 Area of work:

The limits of the project as shown on the drawings. The area where the Contractor may operate equipment and perform tasks associated with the project. Does not include access roads and haul routes.

1.1.2.4 Runway 30:

For the purpose of this project, this shall refer to the southeast end of the active runway at Mountain Home Air Force Base.

1.1.2.5 Runway 12:

The northwest end of the runway at Mountain Home Air Force Base.

1.2 CONTRACTOR USE OF PREMISES

Limit use of the premises to construction activities in areas indicated; allow for Government occupancy and access.

1.2.1 Work Areas

Confine operations to areas within Contract limits indicated. Portions of the site beyond areas in which construction operations are indicated are not to be disturbed.

1.2.2 Access and Deliveries

Contractor shall access the site by designated haul routes only.Keep driveways and entrances serving the premises clear and available to the Government at all times. Do not use these areas for parking or storage of materials. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on site.

1.2.3 Hauling and Haul Route Maintenance

Sweep job site and designated haul routes daily as required to remove all spillage, mud and soil tracked from work site or dump site. Cover all loads subject to spilling such as earth fill, aggregates, portland cement concrete materials, asphalt cement concrete materials, rubble, trash, materials taken to land fill, etc. during hauling to prevent spillage. Sweep spills immediately. Spills of hazardous materials shall be responded to in accordance with Section 01061. Haul routes shall be approved by the Contracting Officer's representative to minimize impact to the base

1.2.4 Government Operations

Perform the Work so as not to interfere with the Government's operations.

1.2.5 Utility Outages and Shutdown

Utility outages and shutdowns, should they be required for the performance of the work, shall be scheduled 14 working days in advance with the Contracting Officer. Outages shall be on weekends or weekdays specified by the Contracting Officer's representative at no additional cost to the Government. Outages shall be limited to one day duration.

1.2.6 Protection of Government Property

Protect all Government property within the site in which working, except for such property as is required to be demolished. Protect property which is to be demolished until its scheduled demolition time. Protection shall include, but not be limited to, protection from construction generated dust, debris, water, and vibration.

1.2.7 Maintenance and Repair of Pavements

Maintain and repair pavements, drives or turf areas utilized during construction for access roads or storage areas, to the satisfaction of the Contracting Officer. Costs associated with the above work shall be incidental to the contract. Where landscape rock areas are repaired or installed, provide weed barrier under rock to prevent weed growth. Weed barrier shall be DeWITT PRO 5 Weed Barrier, 5 oz. Woven needle-punched material, or approved equal. Make sure landscape rock is free from dirt and debris if reused, and repair all wheel ruts, etc.

1.3 FIRE PROTECTION DURING CONSTRUCTION

1.3.1 Compliance

Comply with the following:

a. Army Corps of Engineers Manual EM 385-1-1, General Safety Requirements

b. National Fire Protection Association (NFPA) 241, Standard for Safeguarding Construction, Alteration, and Demolition Operations

c. Mountain Home Air Force Base Fire Regulations

1.3.2 Welding

During welding operations, daily permits shall be obtained. See PERMITS, below.

1.3.3 Fire Extinguishers

Fire extinguishers are required on construction equipment. A 10 ABC minimum rating is required for fire extinguishers.

1.3.4 Use of Explosives

The use of explosives is not allowed on base property.

1.4 STAGING AREA

1.4.1 On-Site Storage Area

On - site storage of construction materials and equipment is limited. Location of an on-base storage area will be identified at the preconstruction meeting or as shown on the project drawings. Contractor is responsible for keeping weeds cut, debris picked up, and storage site clean.

1.4.2 Vehicles and Equipment

All vehicles and equipment must be stored at the staging area or other approved area when not in use.

1.4.3 Storage Area Security

The staging area is unsecured. The Contractor is responsible for securing all equipment and supplies, at no additional cost to the Government.

1.5 UTILITIES ON SITE

1.5.1 Electricity

Electricity will be available at the designated location for the Contractor's office trailer. The Contractor is responsible for all connections. Cost for connections are incidental to other work in the Contract. A detailed plan showing how and where connections will be made will be approved by the Contracting Officer before any work is done. Power required for the operation of Contractor's concrete batch plant, crushing plant and asphalt mixing plant is the Contractor's responsibility.

1.5.2 Construction Water

Water is available on base for filling trucks and equipment, at the location shown on the plans. There is no charge for consumption in amounts reasonable for the construction. Cost for connection is incidental to other work in the Contract. It shall be the Contractor's responsibility to determine fittings and equipment necessary to connect to the designated water source. The Contractor is encouraged to provide an elevated tank to fill his water truck(s). An alternative water source, as designated on the plans, is available for use by the Contractor to supplement the primary water source if necessary.

1.6 DISPOSAL AREAS

1.6.1 Base Landfill

See Section 01061(AR), Paragraph 1.4.2.2.

1.6.2 Base Hardfill Area

See Section 01061(AR), Paragraph 1.4.2.4.

1.7 BIOENVIRONMENTAL REQUIREMENTS

See Section 01061(AR), Paragraph 1.6.

1.8 WARRANTY

See Section 01703 (AR).

1.9 PERMITS

1.9.1 Welding Permits

Daily welding permits are required for all on site welding and cutting operations. Contact Base Fire Department for permit issues; 828-6292 or 828-6005.

1.9.2 Excavation Permits

See Section 01501(AR), Paragraph 1.12, “Digging Permits”.

1.9.3 Flightline Requirements

The Contractor shall obtain flightline driver's briefing and Contractor owned vehicle passes from Base Operations in Building 262 prior to working on or near the flightline. Advise Base Operations daily at the beginning and end of the work shift. Advise Base Operations when equipment taller than 20 feet will be operating on or near the flightline. Special sweeping procedures are required for work adjacent to or on the flightline. Coordinate with the Contracting Officer and Base Operations for specific requirements.

1.9.4 Closures and Outages

Prior to any road closure or utility outage, Contractor must coordinate 2 (two) weeks in advance through the Contracting Officer Representative (COR). The COR will then route the request through the appropriate offices to confirm the proposed closure/outage. The contractor must have a signed copy of the coordination/approval sheet in his possession prior to the closure or outage.

1.9.5 Other Permits

The Contractor shall file a Notice of Intent (NOI) for storm water discharges associated with construction activity under a NPDES General Permit. The NOI shall be filed with the EPA with a copy submitted to the Contracting Officer. The Contractor shall prepare a Storm Water Pollution Prevention Plan (SWPPP)that incorporates the requirements of Section 01356R Storm Water Pollution Prevention Measures. The SWPPP shall be submitted to the Contracting Officer for review by the base Environmental Office. The Contractor shall make modifications to the SWPPP as directed by the Environmental Office and shall have a copy on site for the duration of the project.

The Contractor is responsible to determine the necessary Federal, State, and local permits required for construction activities associated with the project and to obtain those permits.

1.10 SAFETY

1.10.1 Contractor's Responsibility

The Contractor shall be solely and completely responsible for conditions of the job site, including safety of all persons and property during performance of the work. This requirement will apply continuously and not be limited to normal working hours. The Contractor shall comply with Mountain Home Air Force Base fire regulations, Army Corps of Engineers Manual EM 385-1-1, *General Safety Requirements*,and with NFPA 241, *Safeguarding Construction, Alteration and Demolition Operations*.

1.10.2 Safety Plan

Prior to starting work, the Contractor shall prepare and submit to the Contracting Officer a Health and Safety plan specifically prepared for this project. In addition to the OSHA regulations, the plan shall also address or require the following:

a. Placement of barricades and warning signs.

b. Systems for detection and monitoring combustible vapor and oxygen or carbon monoxide levels.

c. Emergency procedures and emergency evacuation routes.

1.10.3 Protection of Excavation

The Contractor shall provide and maintain barriers around all open excavations. If the excavation is to be left for more than 24 hours, a minimum of a plastic safety fence shall be erected around the excavation. Provide barriers at all entrances to any closed street. Road

closure barricades shall be Type III as defined in the Standards For Work Zone Traffic Control, part 6 of the Manual on Uniform Traffic Control Devices.

1.10.4 Closed Streets

The Contractor shall provide barriers at all entrances to any closed street. Road closure barricades shall be Type III as defined in the Standards For Work Zone Traffic Control, part 6 of the Manual on Uniform Traffic Control Devices.

1.10.5 Material Safety Data Sheets

The Contractor shall submit a copy of Material Safety Data Sheets for all materials used in the project to the Contracting Officer and shall maintain a file of these reference materials at the construction site, available for review by the Contracting Officer and the Contractor's employees.

1.10.6 Hazardous Wastes

All hazardous wastes generated as a result of this project shall be identified in writing to the Contracting Officer and shall be handled and disposed of in accordance with all applicable local, Federal, and State Regulations. Hazardous wastes shall be manifested off of the base and 366 CES/CEV, Civil Engineering Environmental Flight shall be the approval authority.

1.11 SPECIAL REQUIREMENTS OF AIRFIELD CONSTRUCTION

This project involves work on an active military airfield. Aircraft will be operating near and directly over the project site. Following are special requirements of working in this environment.

1.11.1 Foreign Object Damage

Special care shall be given to the prevention of Foreign Object Damage (FOD). FOD is damage caused to aircraft by debris such as dust, rubble, gravel, etc. Take every precaution to prevent such items spilling or blowing onto active aircraft surfaces. Any items dropped or blown onto aircraft surfaces shall be cleaned up immediately. See also Paragraph 1.2 CONTRACTOR USE OF PREMISES and Paragraph 1.12 DUST CONTROL of this section.

1.11.2 FOD Checks

Thorough FOD checks will be required whenever the Contractor's vehicles enter the flightline from roadways and worksites. FOD checks shall incude removing gravel and rocks from tire treads and removing or securing loose parts and debris on the vehicle undercarriage.

1.11.3 Construction Traffic

Control construction traffic operating on or crossing taxiways open to aircraft traffic by flagmen in radio control with base traffic control tower. When conflicts arise between construction activities and aircraft operations and safety, aircraft operation and safety shall take precedence and shall govern. Coordinate construction sequencing and airfield management through the Contracting Officer (CO). Continuous sweeping shall be required

for pavement to be opened to traffic or areas open to air traffic within construction limits as directed by CO.

1.11.4 Radios

Furnish radios for each person in charge of each work area. Radios shall be programmable for Government supplied frequency. Frequency shall be deleted at completion of project.

1.11.5 Evacuation Plan

The Contractor shall develop and submit an evacuation plan detailing expedient evacuation of personnel from the flightline or work site if required by the tower or flightline manager. The plan shall address such issues as moving equipment and communication with all personnel.

1.11.6 Barricades

Place lighted barricades of the type and in the locations shown on the drawings. Place barricades at the intervals shown on the drawings.

1.11.7 Secured Areas

Aircraft parking areas are secured and authorization is required for access. Do not cross red lines, red ropes, or entry control points on the pavement without prior approval and an authorized escort, unless the area has been designated a "free zone" by base security police.

1.11.8 Equipment Height

Do not use any equipment or erect any structure greater than 20 feet high in the flightline project area without prior approval from the CO.

1.11.9 Project Limits

Do not operate equipment or permit personnel to work outside the project limits without approval from the Contracting Officer.

1.12 DUST CONTROL

Maintain strict dust control to prevent blowing dust at all times.

1.12.1 Saw-Cutting

When saw-cutting concrete, contractor shall flush and clean the area so the paste does not dry and flake.

1.12.2 Sweeping of Haul Routes

Assure that the hauling route, access route to airfield pavements, and job site are maintained by vacuum-type sweeping at least daily to assure no damage to Government and personal property during the performance period. Employ, full-time, through the duration of the project, one vacuum-type sweeper to sweep airfield pavements. An additional vacuum-type sweeper shall be available within 24 hours should a sweeper break down.

1.12.3 Sweeping of Airfield Surfaces

Sweep continually all airfield surfaces and main haul routes while hauling is taking place, the surfaces are being travelled on, or construction is occuring in the area. All haul routes and other swept areas shall be inspected every night after hauling has stopped. If additional sweeping is required, this shall be accomplished before the contractor leaves the base for the day.

1.12.4 Delays

All hauling operations shall cease any time there is not an operational vacuum sweeper. Should the non-operational sweeper be down for more than 24 hours, the back-up sweeper shall be brought into service before the end of the 24 hours. Delays caused by the lack of an operational vacuum sweeper shall be the responsibility of the Contractor.

1.13 CONSTRUCTION PHASING

Project phasing and work hours have been written with the intent to minimize hindrances to the flying mission while also minimizing contract interruptions. Coordinate contract work schedules through the Contracting Officer and base agencies responsible for scheduling flying operations and operating the base airfield (including taxiways and parking ramps), to ensure safe uninterrupted flying operations and safe working conditions during the duration of the contract. Hold a meeting at Base Operations (Bldg. 262), coordinated through the Contracting Officer, at the beginning of each week and at least one week before the closing of any portion of the runway or taxiways and at the start of succeeding phases to inform base agencies operating on the airfield of the nature and location of the contract work or closure of airfield areas for that week. The construction season runs approximately from April through October. The Base will give 30 days advance notice before releasing any area of work to the Contractor.

The Repair Runway portion of the project will be phased as follows:

1.13.1 Phase 1, “Reconstruct 30 End”

Phase 1 consists of all work necessary to reconstruct the 30 End of Runway 12/30. Work included in Phase 1 is described in the following subparagraphs and shall be constructed during the period shown in Section 01005 (AR), paragraph 1.5.1.

1.13.1.1 Work Areas And Access

The Contractor shall limit all operations to the work areas and access designated on the drawing for Phase 1.

1.13.1.2 Aircraft Operations

During Phase 1, Runway 12/30 will be open and aircraft will be operating adjacent to and directly over the job site.

1.13.1.3 Preparation

Phase 1 includes work related to mobilizing to the project site and preparing to work. Complete temporary relocated threshold markings and temporary arresting system markings. Place barricades prior to beginning work.

1.13.1.3 Included Work

Accomplish all work necessary to repair pavement in the Runway 30 end, including pavement removal, crushing demolished concrete, excavate and prepare subgrade, place base course, construct concrete pavement, install UHMW panels, and painting temporary markings in the work area.

1.13.1.4 Optional Items 0014 and 0015

If awarded, Optional Items 0014 and 0015 (Repair Taxiway E) will be constructed concurrent with Phase 1.

1.13.2 Phase 2, “Mill and Overlay Runway 12/30”

Phase 2 consists of all work necessary to mill and overlay the asphalt portion of Runway 12-30 and associated work. Work included in Phase 2 is described in the following subparagraphs and shall be constructed during the period shown in Section 01005 (R), paragraph 1.5.1.

1.13.2.1 Work Areas and Access

The Contractor shall limit all operations to the work areas and access designated on the drawings for Phase 2. Barricades and other safety measures shall be in place before work begins.

1.13.2.2 Aircraft Operations

During Phase 2, the runway will be completely closed. The Contractor shall maintain closure markings at all times, but aircraft will not be operating adjacent to or over the work area.

1.13.2.2 Preparation

Install runway closure markings and maintain throughout construction.

1.13.2.3 Included Work

Accomplish all work necessary to overlay Runway 12/30, including mill pavement, repair pavement cracks, excavate and prepare shoulder subgrade, place shoulder base course, install utility corridor, install 12” water sleeve, place asphalt pavement overlay, and place temporary pavement markings.

1.13.3 Phase 3, “Reconstruct 12 End”

Phase 3 consists of all work necessary to reconstruct the 12 End of Runway 12-30. Work included in Phase 3 is described in the following paragraphs and shall be constructed during the period shown in Section 01005 (AR), paragraph 1.5.1.

1.13.3.1 Work Areas and Access

The Contractor shall limit all operations to the work areas and access designated on the drawings for Phase 3. Barricades and other safety measures shall be in place before work begins.

1.13.3.2 Aircraft Operations

Construction of Phase 3 may take place concurrent with Phase 2, when the runway is closed. If Phase 3 extends beyond Phase 2, Runway 12/30 will be open and aircraft will be operating adjacent to and directly over the job site.

1.13.3.3 Included Work

Accomplish all work necessary to repair pavement in the Runway 12 end, including pavement removal, crushing demolished concrete, excavate and prepare subgrade, replace water and sewer lines, place base course, construct concrete pavement, install UHMW panels, and place temporary pavement markings.

1.13.3.4 Optional Items 00124 and 00135

If Optional Items 00124 and 00135 (Repair Taxiway A) is awarded, associated work shall be completed in conjunction with Phase 3.

1.13.4 Phase 4, “Runway Grooving and Permanent Pavement Marking”

Phase 4 consists of all work necessary to groove and permanently mark the entire runway, as well as the installation of the Runway Ice Detection System upgrade. Phase 4 includes the work elements described below and shall be constructed during the periow shown in Section 01005 (AR), paragraph 1.5.1.

1.13.4.1 Work Areas and Access

The Contractor shall limit all operations to the work areas and access designated on the drawings for Phase 4. Phase 4 will be constructed during temporary nighttime and weekend closures, as coordinated with the Contracting Officer.

1.13.4.2 Scheduling

Grooving work in Phase 4 will be completed at night by closing Runway 12/30 at 10:00 p.m. by placing closure "X"s and disconnecting the runway lighting circuit. Runway 12/30 shall be reopened each morning no later than 6:00 a.m. Prior to opening the runway, the Contractor shall remove closure markings, enable the lighting circuit and ensure the pavement is clean. Work on the runway related to painting and installation of the Runway Ice Detection System

shall be accomplished during daytime, weekend closures of the runway. Not more than 3 total daytime closures will be provided.

1.13.4.3 Included Work

Accomplish all work necessary to groove Runway 12/30, working at night, and complete permanent pavement markings.

1.14 MOBILIZATION AND DEMOBILIZATION

1.14.1 Description

Included are the requirements for mobilizing equipment and facilities to the project site in preparation for the work to be accomplished under this contract as well as removal of equipment and facilities at the completion of the project. In addition, mobilization shall include bond and insurance premiums required for the execution of the work under this contract.

1.14.2 Included Items

Mobilization shall consist of preparatory work and operations necessary for the movement of personnel, equipment, supplies and incidentals to the project site and for all other work and operations which must be performed or cost incurred before beginning projection work on contract items. Mobilization shall include obtaining all permits, insurance and bonds; moving equipment onto the site; furnishing and erecting plants, temporary buildings and other construction facilities all as required for the proper performance and completion of the work. Such work shall include but not be limited to the following principal items:

a. Moving onto the site all Contractor's plant and equipment required for the first month's operations.

b. Develop water supply.

c. Provide on-site sanitary facilities as required.

d. Prepare Contractor's staging and storage area.

e. Submit all required insurance certificates and bonds.

f. Obtain all required permits.

g. Post all required health and safety and labor notices.

h. Retain contractor's superintendent at jobsite full time.

1.14.3 Excluded Items

Not included in mobilization are expendable supplies such as fuel, lubricants, spare parts and materials which become a part of permanent physical features constructed as part of this contract.

1.14.4 Supplier and Subcontractor Requirement

Mobilization for all subcontracted or supplied work shall be considered to be included in the contract unit prices bid by the contractor.

1.15 ACCESS AND ACCESS ROADS

Access to or around Mountain Home Air Force Base shall be coordinated with and require approval of the Contracting Officer a minimum of 24 hours in advance. The Contractor, his suppliers and subcontractors shall conduct operations in a manner that adheres to the requirements of this section, the Project Safety Plan and the project drawings.

1.15.1 Construction Access

The designated access to the project site is from Idaho State Highway 67. The Contractor shall be responsible for coordination with the appropriate local authorities or agencies and shall determine which permits are required to use public roads to reach the designated access point.

All hauling of equipment and materials must be through the designated access gate. The Main Gate may be used for access by light duty vehicles and personnel only, hauling equipment or materials through the Main Gate will not be permitted.

Dust control on roads shall be the Contractor's responsibility. All work associated with maintaining and watering roads utilized by the Contractor is indicental to other project work.

1.15.2 Access Control

Access to Mountain Home Air Force Base will be controlled at all times by Government personnel. All construction vehicles are subject to search. It shall be the responsibility of the Contractor to keep the Contracting Officer informed of access requirments.

1.15.3 Existing Conditions

The Contractor and Contracting Officer will visually inspect the current condition of all designated haul routes that cross or travel on existing pavement. The Contractor will be responsible to restore damaged pavement to pre-construction condition at not cost to the Government. The Contractor will be responsible to maintain designated access roads in pre-construction condition at no cost to the Government.

1.15.4 Construct and Improve Access Roads

The Contractor shall construct a new access road and improve existing roads at the lcoations shown on the plans. Access road construction and improvements shall be according to the typical sections for access roads as shown on the plans. Exact locations of access and haul routes shall be identified by the Contracting Officer before construction begins.

New roads shall be cleared and grubbed to a depth of four with this material replaced with crushed concrete. New access roads and improved existing roads ahall be 20 feet wide and shall be constructed to a minimum of six inches thick using crushed concrete from the existing stockpile. The Contracting Officer shall designate the suitable material to be used for

road construction. The Contractor shall cover the access road with a minimum of three inches of asphalt millings generated by asphalt removal by pavement rotomilling in the project area. it may be necessary for the Contractor to temporarily stockpile rotomillings prior to placing on the access road. The access road shall be crowned and tight-bladed. the construction access road shall be constructed and maintained in a conditon suitable for use by construction equipment and vehicles. Dust control shall be the Contractor's responsiblity. The access road shall remain in-place at the completion of this project.

1.16 CLEAN UP

Throughout the construction period and at the completion of the work, the Contractor shall maintain the prject site to the standard of cleanliness described in this section. In addition to the general standards described in this section, the Contractor shall comply with all specific requirement for cleaning or clean up as described in various sections of these specifications.

1.16.1 Inspection

The Contraction Officer and the Contractor shall conduct regular inspections to verify that requirements of cleanliness are being met. In addition to the standards described in this section, the Contractor shall comply with all pertinent requirements of other agencies having jurisdiction.

1.16.2 Cleaning Materials and Equipment

Provide all required personnel, equipment, and materials needed to maintain the specified standards of cleanliness. Use only the cleaning materials and equipment which are compatible with the surface being cleaned, as recommended by the manufacturer of the material or as accepted by the Contracting Officer.

1.16.3 Periodic Cleanup

During the performance of the required work or any related operations, the Contractor shall furnish all labor, equipment, materials and means required for cleanup. The Contractor shall also carry out proper and efficient measures wherever and as often as necessary or as directed to clean up waste, debris or spillage which has originated from his operations from causing a nuisance or safety hazard to persons or aircraft.

Refer to Specification Section 01010 (R) General Requirements, paragraphs 1.12.3 and 1.12.4 for vacuum sweeper requirements.

The Contractor shall not allow the accumulation of scrap, debris, waste material, and other items not required for construction of the project to accumulate on the work site.

At least twice each month, and more often if necessary, all scrap, debris, and waste material shall be collected and removed from the job site and disposed of in an off-site disposal approved for the contractor's use.

Storage of all items awaiting removal from the job site, shall be done in such a manner as to minimize fire hazard or environmental damage.

1.16.4 Final Clean Up

Prior to completion of the work, remove from the work site all tools, surplus materials, equipment, scrap, debris, and waste.

Unless otherwise specifically directed by the Contracting Officer, broom clean all paved areas on the site and all public paved areas directly adjacent to the site. Completely remove all resultant debris.

Grassed areas within or adjacent to the work site shall be scraped and raked clean to the original grass or soil level. All stones larger than 3/4 inches in diameter and other loose debris shall be picked up and removed.

Schedule final cleaning and cleanup to enable the Government to accept a clean, finished project.

1.17 COMPACTION WATERING

The Contractor is responsible for determining amounts of water necessary for moisture control in the compaction process for subgrade and base course in accordance with the requirements of these specifications.

1.17.1 Water Application

Water, when required, shall be applied at the locations, in the amounts, and during the times as required to achieve compliance and specification requirements. The equipment used for watering shall be of ample capacity and of such design as to assure uniform application of water.

1.17.2 Water Supply

Water for compaction shall be supplied by the Government, refer to paragraph 1.5.2 Construction Water, above.

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION (NOT APPLICABLE)

END OF SECTION

This page intentionally blank

SECTION 01051 (R)

CONTRACTOR FURNISHED CONSTRUCTION SURVEYING AND STAKING

PART 1 GENERAL

1.1 DESCRIPTION

1.1.1 Work Included:

This specification describes the Contractor's responsibilities for surveying and field engineering necessary to construct the work. The Work shall consist of staking lines and grades for runway lights, striping, excavation, shoulders, subbase, base, concrete pavement and asphalt. It shall also include remeasurement or reestablishment work as required, should the Contracting Officer (CO) determine that any portion of the work does not conform with line, grade and/or dimensions shown on the plans or as directed by the CO.

1.1.2 Surveyor Qualification:

All surveying and construction staking shall be under the direction and supervision of a qualified Surveyor with knowledge of construction surveying and volumetric calculation for the work described in this specification. The standard of care and knowledge of the surveyor shall be that of a licensed surveyor. Being licensed as a surveyor in the State of Idaho is not required nor is it a prerequisite. The Contractor shall submit the surveyors' qualifications, as well as evidence of the surveyors' competency to the CO for review and comment at the Pre-Construction conference and prior to commencing any surveying or staking activities at the site.

PART 2 PRODUCTS

2.1 MATERIALS AND INFORMATION - OWNER

The Engineer shall provide the initial horizontal and vertical control points, as noted on the project plans, for the Contractor's Surveyor to establish all additional control points needed to construct the facilities identified in these specifications and drawings

2.2 MATERIALS AND INFORMATION - CONTRACTOR'S SURVEYOR

2.2.1 Documentation and Records

The Surveyor shall provide all field notebooks and forms to be used for construction staking. The field notebooks and forms shall become the property of the CO upon completion of the Work. The field notebooks used for the Work shall also be made available to the CO upon request at any time during the execution of the Work. Such requests may be in verbal or written form and shall be complied with immediately by the Contractor or his/her Surveyor.

2.2.2 Material and Equipment

The Surveyor shall furnish all stakes, surveying equipment and other devices necessary for establishing, setting, marking and maintaining the required control and reference points to construct the Work. All lumber shall have the following minimum dimensions:

Hubs	1" x 2" x 8"
Stakes	1" x 2" x 16"
Lath	" x 2" x 48"

Plastic marking, flagging and paint shall be of highly visible type supplied in the colors of red, white, blue, yellow and orange.

PART 3 EXECUTION

3.1 CONSTRUCTION STAKING

3.1.1 Except for the control points mentioned in Section 2.1, all surveying shall be provided by the Contractor at his/her expense.

3.1.2 Surveying Control and Tolerances:

Construction staking by the Surveyor shall include all items described in Paragraph 1.1A, above, as well as any other control or elevations deemed necessary for proper control to construct the work.

The positional tolerances for staking shall conform to the following guidelines:

Description	Vertical Tolerance	Horizontal Tolerance
Excavation	0.02 foot	0.5 foot
Embankment	0.02 foot	0.1 foot
Subbase	0.02 foot	0.1 foot
Base	0.01 foot	0.1 foot
Slope Stakes	0.1 foot	0.1 foot
Paving Surfaces	0.01 foot	N/A
Drainage and Other Structures	0.01 foot	0.1 foot
Electrical Lights/Signs	0.02 foot	0.1 foot

3.1.3 Field Documentation Requirements:

Field notes shall be kept in a standard format on forms supplied by the Surveyor and acceptable to the Engineer. Lettering shall be at least 0.15 inch and legible from a distance of 1.5 feet. Errors shall be deleted by lining the errors out. Erasures in the field notes will not be an acceptable practice of correcting errors. After completion and acceptance of the work, the Surveyor shall submit to the CO all survey and design data. The Surveyor is required to maintain daily diaries detailing the work completed each day. Crew names, positions and dates shall be recorded in the field books on the beginning sheet of each day's work. All notes, including the originals, shall be signed and sealed by the licensed Surveyor and then become the property of the CO. Copies of all field notes and diaries shall be submitted to the CO on a weekly basis or as directed by the CO.

3.1.4 Surveyor Technician Requirements:

The Surveyor shall employ sufficient qualified personnel experienced in construction surveying to conduct the work as required. Supervision of such personnel is the responsibility of the Surveyor. The Surveyor at the expense of the Contractor shall correct any error or omission by such personnel. The Surveyor is responsible for the calculations of the grades and alignment for all staking. Any discrepancies in grade, alignment locations and/or dimensions detected by the Surveyor shall immediately be brought to the attention of the CO.

Major differences found between the horizontal or vertical alignment data shown on the plans and the alignment observed on the ground shall be brought to the attention of the CO immediately. Staking of these areas shall be deferred until the CO reconciles these differences. The Surveyor shall compare the staked centerline cut and fill depth with the design data. Differences exceeding one foot at any two or more consecutive points shall be reported to the Engineer for possible evaluation and correction.

3.1.5 Construction Staking Requirements and Criteria

The Engineer may check the accuracy of the Surveyor's construction stakes, lines, grades and layouts, but will not assume responsibility for the accuracy of the final result. All stakes shall be legibly marked with a stake pencil that leaves a depression or a waterproof black marker. The top two inches of all slope, guard, reference, clearing and structure stakes shall be painted or marked with plastic flagging. Stakes shall be painted or marked with the following colors:

TYPES OF STAKES	COLORS
Right of Way	Yellow
Control Points	Red/White/Blue
Misc. Stakes	Red/White
Slope Stakes	White
Conduit Stakes	Orange/White
Reference Points/Easements	Orange

The Contractor and Surveyor shall maintain and protect all construction stakes and marks until the work is completed and accepted by the Engineer. In the event that the construction staking or control points are obliterated during the execution of the work the Surveyor shall establish or reestablish all construction stakes and controls points, as necessary.

Minimum Control Points

P.I. Point of Intersection of Tangents
P.C. Point of Curvature
P.O.C. Point on Curve
P.T. Point of Tangency
P.O.T. Point on Tangent
R.P. Reference Point
B.M. Bench Mark
T.B.M. Temporary Bench Mark

3.1.6 Surveying Control Items (minimum requirements)

3.1.6.1 Vertical Control:

Bench marks established for the project by the Government shall be checked and/or reestablished by the Surveyor. Bench marks falling within the clearing limits of the project shall be reset in a safe location by the Surveyor. After resetting any bench marks, a level circuit meeting the precision of the original survey shall be run to all bench marks and datum elevations computed and/or checked.

3.1.6.2 Horizontal Control:

Centerline stakes shall be set at 50-foot intervals, (including all 100-foot stations) at significant breaks in the ground, at conduit locations, at P.C.'s and P.T.'s, points of radiuses and at approaches. Stakes shall be marked with appropriate identification or location on the side of the stake facing the initial station on the project

3.1.6.3 Cross-Sections:

Cross-section measurements, original and remeasure, shall be taken by the Contractor's Surveyor at locations necessary for computing pay items that require volume calculations. This data shall be computed, checked and plotted into cross-section format using both the CO's design survey and remeasured section data surveyed by the Contractor's Surveyor, verified by the CO and signed and sealed by the Contractor's Surveyor. The purpose of these cross-sections is for measurement and payment of quantities. The Contractor's Surveyor shall compute the earthwork cut and fill volume quantities and submit these calculations to the Engineer for verification to support the respective progress payment request by the Contractor. The CO may utilize his survey crew to verify Contractor's survey at his option. In case of conflict, the calculations resulting from the CO's survey will prevail.

3.1.6.4 Subgrade Stakes and Reference Stakes:

Subgrade stakes shall be established at cut and fill catch points on both sides of centerline at every staked point in the centerline system. The cut or fill to subgrade, shoulder, back-of sidewalk or curb along with distance to centerline and offset distance to centerline shall be marked on the stakes and recorded in the field notebooks.

3.1.6.5 Finishing Stakes

Runway and taxiways: Finishing stakes shall be set when subgrade or base course is within 0.2 foot of the final grade. The stakes shall be set to the nearest 0.01 foot of the finish grade elevation. Finishing stakes shall be required for all surfaces requiring finish grading including (but not limited to) subgrade, base courses, approaches and pavement surfaces. Finishing stakes shall be hubs placed transversely and longitudinally on the runway template line at 25-foot intervals, in addition to centerline, flowlines and at each edge of pavement. The finishing stakes shall be marked with guard stakes or with plastic blue top flags or chasers.

3.1.6.6 Conduit Staking

All conduits shall be staked on 15-foot offset line at 100- foot intervals. Guard stakes shall also be set and marked with the following:

a. Diameter, length and type of conduit.

b. The vertical and horizontal distance from the hub/nail to the invert of the conduit.

c. Flow line grade of the conduit.

The hub shall be referenced to both horizontal and vertical control well beyond the anticipated construction limits and cut of the flow line, as necessary.

3.1.6.7 Structures:

Major structures (bridges and retaining walls) shall be staked by setting hubs and tacks with guard stakes on each side of the structural components, or as requested by the CO. Minor structures (headwalls, drop inlets and manholes) shall be staked by setting a hub with guard stake on each side of the culvert on line with the face or center of the structure.

3.1.6.8 Miscellaneous Staking:

Staking will be required for location and installation of all illumination and traffic control facilities including, but not limited to: poles, conduits, boxes, traffic signs, etc.

3.1.7 Drawings of Record:

3.1.7.1 Drawings:

The Contractor will be furnished one complete set of prints of all of the Contract Drawings upon which the Contractor shall maintain a neat and accurate record of all contract work. The Contractor shall promptly record the as-built quantities and dimensions of all contract work as it is performed on this set of prints. At the completion of project work, the entire set of prints plus any additional drawings necessary shall be submitted to the Engineer for review and comment. The Contractor shall correct or amplify information and assist the Engineer as may be required to complete the as-built record in a manner satisfactory to the Engineer.

3.1.7.2 Information Required

The Contractor's record shall include for example, locations of fittings, connections, service lines and manholes. Locations are to be established by three point ties to physical objects, which will remain undisturbed, where feasible. Materials and fittings used; relative placement of fittings, with dimensions; depths of conduit and location of lines or other important items which enter into structures or pass under foundation walls or paved surfaces are to be clearly defined.

END OF SECTION

This page intentionally blank

SECTION 01110 (R)

AIRFIELD PROJECT SAFETY PROCEDURES

PART 1 GENERAL

1.1 DESCRIPTION

Work included under this section establishes guidelines and standards which the Contractor is to follow when conducting project work to assure that a desirable level of operational safety is maintained during construction and related activities.

1.3 COMPLIANCE

1.3.1 Coordination:

The Contractor shall coordinate construction activities with the Contracting Officer and other parties as appropriate prior to commencing construction and as needed throughout the course of the work.

Operational Safety and the construction schedule are to be addressed at the Pre-Performance Conference.

1.3.2 Notice to Airman (NOTAMS):

The airfield manager shall issue the necessary NOTAMS to reflect hazardous conditions. It is important that NOTAMS be reviewed periodically and revised to reflect the current conditions.

1.3.3 Inspection:

Frequent inspections may be made by the Contracting Officer (CO) or Contracting Officer's Representative (COR) during all phases of the work to ensure that the Contractor is following the recommended safety procedures.

1.3.4 Special Circumstances:

Special or unique considerations of the Government or of the project which may be identified in Section 1010 of the Specifications or in the drawings shall be considered and incorporated into the Contractor's Safety Plan and construction schedule.

1.4 SUBMITTALS

1.4.1 Operational Safety Plan:

Prior to commencing work, the Contractor shall submit for review and approval a detailed Operation and Safety Plan coordinated with the construction schedule. The plan shall include, but not be limited to:

1.4.1.1 Maintenance of air operations and direction of aircraft on air operations surfaces during each construction sequence and estimated duration of impact to the area.

1.4.1.2 The designation of the Contractor's Safety Officer responsible for liaison with CO and the COR and execution of safety, consistent with the terms of this specification

1.4.1.3 Marking of vehicles/equipment and communications (radios).

1.4.1.4 Training of personnel and safety meeting schedule.

1.4.1.5 Location, type and quantity of barricades, cones, signs, etc. to be on-hand prior to issuance of NOTAMS and start of work.

1.4.1.6 Safety precautions or measures required to control Contractor's forces and traffic.

1.4.2 Safety Plan Submittal

A draft of the Safety Plan shall be provided to the Contracting Officer along with the construction schedule a minimum of five calendar days prior to the Pre-Performance Conference.

1.5 CONSIDERATIONS FOR OPERATIONAL SAFETY

1.5.1 Safety Considerations

The following is a partial list of safety considerations which experience indicates will need attention during airfield safety planning and construction.

1. Minimum disruption of standard operating procedures for aeronautical activity.

2. Clear routes from fire fighting and rescue stations to active airfield operations areas and safety areas.

3. Chain of notification and authority to change safety-oriented aspects of the construction plan.

4. Initiation, currency and cancellation of Notice to Airmen (NOTAMs).

5. Suspension or restriction of aircraft activity on airfield operations areas.

6. Threshold displacement and appropriate temporary lighting and marking.

7. Installation and maintenance of temporary lighting and marking for closed or diverted aircraft routes on airfield operations areas.

8. Revised vehicular control procedures or additional equipment and manpower.

9. Marking/lighting of construction equipment.

10. Storage of construction equipment and materials when not in use.

11. Designation of responsible representatives of all involved parties and their availability.

12. Location of construction personnel parking and transportation to and from the work site.

13. Marking/lighting of construction areas.

14. Location of construction offices.

15. Location of Contractor's plants.

16. Debris cleanup responsibilities and schedule.

17. Identification of construction personnel and equipment.

18. Location of haul roads.

19. Noise pollution.

20. Dust control.

21. Location of utilities.

22. Provision for temporary utilities and/or immediate repairs in the event of disruption.

23. Location of power and control lines for electronic-visual navigational aids.

24. Marking and lighting of closed airfield pavement areas.

25. Shutdown and/or protection of airport electronic-visual navigational aids.

26. Notify crash/fire/rescue personnel when working on water lines.

27. Provide traffic directors etc., as needed to assure clearance in construction areas.

1.6 HAZARDS AND CONDITIONS

1.6.1 Identified Hazards:

The Contractor is cautioned that analysis of past accidents and incidents have identified numerous contributing hazards and conditions, some of which are as follows:

1. Excavation adjacent to runways, taxiways, and aprons.

2. Mounds or stockpiles of earth, construction material, temporary structures and other obstacles in proximity to airport operations areas and approach zones.

3. Runway surfacing projects resulting in excessive lips greater than 1 inch for runways and 3 inches for edges between old and new surfaces at runway edges and ends.

4. Heavy equipment, stationary or mobile, operating or idle near airport operations areas or in safety areas.

5. Improper or malfunctioning lights or unlighted airfield hazards.

6. Holes, obstacles, loose pavement, trash and other debris on or near airport operations areas.

7. Failure to maintain fencing during construction to deter human and animal intrusions into the airfield operation areas.

8. Open trenches alongside pavement.

9. Attractions for birds such as trash, grass seeding or ponded water on or near airports.

10. Inadequate or improper methods of marking temporarily closed airport operations areas, including improper and unsecured barricades.

11. Obliterated markings on active operational areas.

PART 2 PRODUCTS

2.1 PRODUCTS AND MATERIALS AS REQUIRED FOR IMPLEMENTATION OF THE SAFETY PLAN ARE IDENTIFIED OR REFERENCED IN OTHER PORTIONS OF THIS SECTION OR IN THE DRAWINGS.

PART 3 EXECUTION

3.1 VEHICLES ON THE AIRFIELD

3.1.1 General:

Vehicular activity on airfield movement areas should be kept to a minimum. Where vehicular traffic on airfield operation areas cannot be avoided, it should be carefully controlled. A basic guiding principle is: The aircraft always has the right-of-way. If Contractor's vehicular traffic activity on airfield movement surfaces causes a deposit of loose soil or aggregate material on those surfaces, Contractor will be required to sweep or clean such deposit to the satisfaction of the CO or COR. Several important aspects of vehicle control and identification are discussed in the following sections.

3.1.2 Visibility:

Vehicles which routinely operate on airport operations areas should be marked/flagged for high daytime visibility and if appropriate, lighted for nighttime operations. Vehicles which are not marked and lighted should be escorted by one that is equipped with temporary marking and lighting devices.

3.1.3 Identification:

It is usually desirable to be able to visually identify specific vehicles from a distance. It is recommended that radio equipped vehicles which routinely operate on airport operations areas be permanently marked with identifying characters on the sides and roof. Vehicles needing intermittent identification could be marked with tape or with magnetically attached markers which are commercially available.

3.1.4 Warning Devices:

Construction vehicles/equipment shall have automatic signaling devices to sound an alarm when moving in reverse.

3.1.5 Movement:

The control of vehicular activity on airport operations areas is of the highest importance. The Contractor is responsible for developing procedures, procuring equipment and providing employee training regarding vehicle operations to ensure aircraft safety during construction. This requires coordination with airfield users and air traffic control. Consideration should be given to the use of two-way radio, signal lights, traffic signs, flagmen, escorts, or other means suitable for the particular airfield. It should be remembered that even with the most sophisticated procedures and equipment, systematic training of vehicle operators is necessary to achieve safety. Special consideration should be given to training intermittent operators, such as construction workers, even if escort service is being provided. The Contractor shall access the construction site area from designated locations shown on the plans or as directed at the Pre-Performance Conference.

3.1.6 Vehicle Marking:

Vehicles other than those that routinely traverse any portion of the AOA under air traffic control (ATC) should be provided with a flag on a staff attached to the vehicle so that the flag will be readily visible. The flag should be at least a 3 foot square having a checkered pattern of International Orange and White squares at least 1 foot on each side. In lieu of a flag, such vehicles may either be escorted by a vehicle properly equipped to operate in the AOA or be in constant two way radio communication with ATC.

3.1.7 Vehicle Lighting:

The standard for identification lighting of vehicles routinely operating in the AOA is an appropriately sized flashing or steady burning beacon, mounted on the uppermost part of the vehicle such that it is conspicuous from any direction including from the air. Color specifications for vehicle identification beacons are noted below. Vehicles not routinely operating on the AOA should be identified during periods of low visibility by a beacon or be escorted by a properly lighted vehicle.

3.1.7.1 Characterictics:

Flashing and steady burning beacons will have:

a. low-intensity lighting with an upper limit of 400 candelas (effective) to avoid damage to night vision. The minimum effective intensity range in the horizontal plane should be at least 40 candelas, but not more than 400 candelas;

b. 360 azimuth (horizontal) coverage;

c. peak intensity from 0 to 10 above the horizontal and reduced intensity to 1/10 of peak intensity from 10 to 15 above the horizontal; and

d. for flashing beacons, a flash rate of 75 (15) flashes per minute.

3.1.7.2 Color:

a. Ambulances. In accordance with Federal Specification KKK-A-1822B.

b. Aircraft Rescue and Fire Fighting Vehicles. Red or a combination of red-and-white flashing beacons.

c. Airfield Service Vehicles. Yellow flashing beacons.

d. Aircraft Support Vehicles. Yellow or red steady burning beacons. Steady burning beacons are a means of distinguishing apron and aircraft support vehicles from airfield service vehicles.

e. Airport Security Vehicles. Signal Blue or a combination of red-and Signal Blue flashing beacons.

f. Other Vehicles. Yellow flashing beacons.

3.2 COORDINATION WITH AIRCRAFT MOVEMENTS

During the time that the Contractor is performing the work, portions of the aprons, taxiways and runways at the airport may remain in use by aircraft, except when work is actually being accomplished. To the extent feasible and convenient in the opinion of the Airfield Manager, CO and COR, the use by aircraft of runways and taxiways adjacent to areas where the Contractor is working, will be scheduled as to reduce disturbance to the Contractor's operations. Aircraft operations, unless otherwise specified in the contract specifications, shall always have priority over any and all of the Contractor's operations and the Contractor shall not allow his/her employees, subcontractors, materials or any other persons over whom he/she has control, to enter or remain upon or allow any plant or materials to be brought or to remain upon any part of the airport, which in the opinion of the CO or COR, would be a hazardous location. Should aprons, runways or taxiways be required for use of aircraft and should the CO or COR deem the Contractor to be too close to the portion used by aircraft for safety, he may, at his sole discretion, order the Contractor to suspend operations and remove personnel, plant, equipment, and materials to a safe distance and stand by until the runway and taxiways are no longer required for use by aircraft.

3.3 SPECIAL PROVISIONS FOR PROTECTION OF CABLES, CONTROLS, LIGHTING FIXTURES, NAVAIDS, AND WEATHER BRUEAU FACILITIES

3.3.1 General:

The Contractor is hereby informed that there are or may be installed on the airport NAVAIDS, which may include, without limitation, ASR, UHF, and VHF Receivers and Transmitters; U.S. Weather Bureau facilities; electric cables and controls relating to NAVAID and facilities; and other electric power cables serving other facilities. Such NAVAIDS, Weather Bureau and other facilities, and electric cables must be fully protected during the entire construction time. Work under this contract can be accomplished in the vicinity of these facilities and cables only at approved periods of time. Approval is subject to withdrawal at any time because of changes in weather, emergency conditions on the existing airfield areas, anticipation of emergency conditions, and for any other reason determined by the COR acting under the orders and instructions of the airport management and/or the designated government

representative. Any instructions to this Contractor to clear any given area, at any time, by the COR or the airport management (by radio or other means) shall be immediately executed. Construction work shall be commenced in the cleared area only when additional instructions are issued by the proper authorities

3.3.2 Location:

Power and control cables leading to and from any NAVAIDS, Weather Bureau and other facilities, will be marked, if possible and upon request, in the field by the appropriate personnel for the information of the Contractor, before any work in their general vicinity is started. Thereafter, through the entire time of this construction, they shall be protected from any possible damage, including crossing with unauthorized equipment, etc.

3.3.3 Repairs:

The Contractor shall immediately repair, with identical material by skilled workmen, any underground cables serving NAVAIDS, Weather Bureau and other airfield facilities, which are damaged by his workmen, equipment or work. Prior approval of the CO must be obtained for the materials, workers, time of day or night, method of repairs and for any temporary or permanent repairs the Contractor proposes to make to any NAVAIDS and facilities damaged by the Contractor. Prior approval of the CO or of the COR must be obtained for the materials, workers, time of day or night and for the method of repairs for any temporary or permanent repairs the Contractor proposes to make to any other airport facilities and cables damaged by this Contractor.

3.3.4 Costs for Disruption:

It is recognized that the Government will incur costs for employees' salaries, engineering fees and otherwise in connection with the damage, inspection and repair of any such damage caused by the Contractor; and consequently, that the Government may incur loss by reason of the diversion of aircraft traffic from the airfield, resulting from interruption of the use of airfield facilities; and that such expenses and loss are not measurable now and may not be reasonably ascertainable at the time of any incident caused by this Contractor. The Government and the Contractor hereby agree to the assessment of liquidated damages in lieu of such expenses or other damages incurred by the Government.

3.4 TEMPORARY RUNWAY OR TAXIWAY CLOSURE

3.4.1 Runway:

When runway closure is required by construction activities, the following procedures shall apply:

During the period the runway is closed, it will be necessary to place a closed runway "X" on both ends of the runway. The dimensions of the closed runway "X" are shown in the plans.

If an entire runway is involved in construction, closed runway "X"s should be placed immediately off runway ends.

The markings may consist of plywood or other material as approved by the CO. Project specific operational conditions may require painting of closure "X"s.

The closed runway markings must remain in place at all times during the time the runway is closed and shall be maintained in a good condition and firmly secured to the satisfaction of the CO until the runway is reopened.

The closed runway markings shall be highly visible, yellow in color and provide a good, essentially solid contrast to the runway or adjacent surface at all times.

3.4.2 Taxiway:

Temporary taxiway closures shall be accomplished in accordance with paragraph 3.8.2 and the requirements of the Safety Plan drawings.

3.5 CONSTRUCTION AREA MARKING

3.5.1 Flag lines, traffic cones, flashers and/or signs shall be used as necessary to clearly separate all construction-maintenance from other parts of active air operations areas and to identify isolated hazards, such as open manholes, excavation, areas under construction, stockpiled material, waste areas and to identify, airfield and other government facilities, cables, power lines, ILS critical and other sensitive areas. Materials and placement shall be subject to the review and approval of the CO or COR.

3.5.2 All barricades, temporary markers, flagline supports and other objects placed or left in the safety area of an open runway, taxiway or taxilane shall be as low as feasible (maximum of 18 inches unless otherwise approved). These materials shall be of low mass and easily collapsible if impacted by an aircraft or component thereof. These materials shall be weighted down or attached to the surface to reduce the chance of movement by prop wash, jet blast, wing vortex or other wind currents. If affixed to the surface, these materials shall be frangible at the ground.

3.5.3 Where feasible, cones should be used in lieu of barricades.

3.5.4 Where construction activities are adjacent to active air operations areas and must remain closed and marked through nighttime hours, barricades equipped with totally operational flashers shall be utilized to sufficiently protect aircraft from entering closed areas. The Contractor shall have a designated representative on call 24 hours per day for emergency maintenance of airport hazard lighting and marking.

3.6 EXCAVATION AND TRENCHES

3.6.1 Runways:

Excavations and open trenches may be permitted up to 200 feet from the centerline of an active runway, provided they are adequately signed, lighted and marked. In addition, excavation and open trenches may be permitted within 200 feet of the runway centerline on a case-by-case basis, i.e., cable trenches, pavement tie-ins, etc., with the approval of the CO, the COR and the Airfield manager.

3.6.2 Taxiways and Aprons:

Excavation and open trenches may be permitted up to the edge of structural taxiway and apron pavements, provided the drop-off is adequately signed, lighted and marked. Coordinate on a case-by-case basis with the Engineer and the Safety Officer.

3.7 STOCKPILED MATERIAL

Extensive stockpiled materials will not be permitted within the construction areas without prior approval. Temporary stockpiles of material designated for reuse shall be located outside the safety areas of active air operation surfaces and at maximum heights below the primary surface and 7:1 transitional surfaces originating at the outer extent of the primary surface. The CO shall approve locations and elevations of temporary stockpiled material and haul routes to and from temporary stockpiles. Haul routes shall also be outside the safety area of operational surfaces. Temporary stockpiles may be permitted within otherwise restricted areas of runways and or taxiways when closed for extended periods of time.

3.8 MARKING AND LIGHTING OF CLOSED OR HAZARDOUS AREAS ON AIRFIELDS

3.8.1 Permanently Closed Runways and Taxiways:

For runways and taxiways which have been permanently closed, the lighting circuits should be disconnected. The threshold markings, runway designation marking and touchdown zone markings should be obliterated and crosses should be placed at each end at 1,000-foot intervals on closed runways. A cross is placed at each entrance of the closed taxiway.

3.8.2 Temporarily Closed Runways and Taxiways:

Temporarily closed runways are treated in the same manner as in paragraph 3.8.A, except runway markings are not obliterated. Rather, crosses are usually of the temporary type (constructed of material such as fabric or plywood) and they are required only at runway ends. The crosses should be located on top of the runway numerals. For temporary marking, the dimensions of the crosses may be reduced to permit use of standard sheets of 4 by 8-foot plywood. Temporarily closed taxiways are usually treated as a hazardous area as explained in paragraph 3.8.4.

3.8.3 Closed Airfields:

When all runways are closed temporarily, the runways are marked as in paragraph 3.8.2 and the airport beacon is turned off. When all runways are closed permanently, the runways are marked as in paragraph 3.8.A, the airport beacon is disconnected and a cross is placed in the segmented circle or at central location if no segmented circle exists.

3.8.4 Hazardous Areas:

Hazardous areas, in which no part of an aircraft may enter, are indicated by use of barricades with alternate orange and white markings. If the project drawings show that the barricades are to be supplemented with flags, the flags shall be orange, at least 20 by 20 inches square and made and installed so that they are always in the extended position and properly oriented. For nighttime use, the barricades are supplemented with flashing yellow lights. The intensity of the lights and spacing for barricades, flags and lights must be such to delineate adequately the hazardous area.

3.9 LIMITATIONS ON CONSTRUCTION

3.9.1 Restrictions:

The following restrictions shall pertain at all times:

3.9.1.1 When construction work is being accomplished adjacent to an active runway during visual flight rule (VFR weather conditions), men, equipment, or other construction-related material shall not be permitted to penetrate a 7:1 slope, originating from the edge of the runway safety area at any active runway.

3.9.1.2 All work which is too close to the runway for accomplishment during VFR conditions (Item 1 above) shall be performed during periods when the runway is not in use. (REF. NOTAM requirements paragraph 1.3.2.)

3.9.1.3 When construction work is being accomplished adjacent to an active runway during VFR weather conditions, equipment below the VFR 7:1 slope but penetrating the IFR 7:1 slope shall be obstruction marked and lighted.

3.9.1.4 Men, equipment or other construction-related material will be permitted in the approach or departure zones of active runways, provided that the construction activity is conducted below a 20:1 (where visibility minimums are below 3/4 mile) approach plane, as applicable to the particular runway, originating 200 feet from end of runway. Any construction activity which is contemplated in the approach zones which will violate these planes will require special consideration (runway displacement, lighting, etc.).

3.9.1.5 Open-flame welding or torch-cutting operations should be prohibited unless adequate fire and safety precautions are provided and have been approved by the airfield manager. All vehicles are to be parked and serviced in the Contractor's work area and/or in an area approved by the CO.

3.9.1.6 Open trenches, excavations, and stockpiled material at the construction site should be prominently marked barricades conforming to the detail shown on the project drawings and lighted with flashing yellow light units acceptable to the CO during hours of restricted visibility and/or darkness. Barricade spacing shall be as indicated on the project drawings. Under no circumstances are flare pots to be used near aircraft operating areas.

3.9.1.7 Stockpiled material should be constrained in a manner to prevent movement as a result of aircraft blast or wind. Material should not be stored near aircraft operating or movement areas.

END OF SECTION

SECTION 01356 (R)

STORM WATER POLLUTION PREVENTION MEASURES

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 4439	(1997) Standard Terminology for Geosynthetics
ASTM D 4491	(1996) Water Permeability of Geotextiles by Permittivity
ASTM D 4533	(1991; R 1996) Trapezoid Tearing Strength of Geotextiles
ASTM D 4632	(1991; R 1996)) Grab Breaking Load and Elongation of Geotextiles
ASTM D 4751	(1995) Determining Apparent Opening Size of a Geotextile
ASTM D 4873	(1995) Identification, Storage, and Handling of Geosynthetic Rolls

1.2 GENERAL

The Contractor shall implement the storm water pollution prevention measures specified in this section in a manner which will meet the requirements of Section 01061 (AR) ENVIRONMENTAL PROTECTION, and the requirements of the National Pollution Discharge Elimination System (NPDES) ~~permit attached to that Section~~. Contractor is required to obtain NPDES permit.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section ~~01300~~ 01330 (AR) SUBMITTAL PROCEDURES:

Certificates

Affidavit; G

Certificate attesting that the Contractor has met all specified requirements.

1.4 EROSION AND SEDIMENT CONTROLS

The controls and measures required by the Contractor are described below.

1.4.1 Stabilization Practices

The stabilization practices to be implemented shall include temporary seeding, mulching, geotextiles, erosion control matts, preservation of mature vegetation, etc. On his daily CQC Report, the Contractor shall record the dates when the major grading activities occur, (e.g., excavation, embankment, and grading); when construction activities temporarily or permanently cease on a portion of the site; and when stabilization practices are initiated. Except as provided in paragraphs UNSUITABLE CONDITIONS and NO ACTIVITY FOR LESS THAN 21 DAYS, stabilization practices shall be initiated as soon as practicable, but no more than 14 days, in any portion of the site where construction activities have temporarily or permanently ceased.

1.4.1.1 Unsuitable Conditions

Where the initiation of stabilization measures by the fourteenth day after construction activity temporarily or permanently ceases is precluded by unsuitable conditions caused by the weather, stabilization practices shall be initiated as soon as practicable after conditions become suitable.

1.4.1.2 No Activity for Less Than 21 Days

Where construction activity will resume on a portion of the site within 21 days from when activities ceased (e.g., the total time period that construction activity is temporarily ceased is less than 21 days), then stabilization practices do not have to be initiated on that portion of the site by the fourteenth day after construction activity temporarily ceased.

1.4.2 Structural Practices

Structural practices shall be implemented to divert flows from exposed soils, temporarily store flows, or otherwise limit runoff and the discharge of pollutants from exposed areas of the site. Structural practices shall be implemented in a timely manner during the construction process to minimize erosion and sediment runoff. Structural practices shall include the following devices. Location and details of installation and construction are shown on the drawings.

1.4.2.1 Silt Fences

The Contractor shall provide silt fences as a temporary structural practice to minimize erosion and sediment runoff. Silt fences shall be properly installed to effectively retain sediment immediately after completing each phase of work where erosion would occur in the form of sheet and rill erosion (e.g. clearing and grubbing, excavation, embankment, and grading). Silt fences shall be installed in the locations indicated on the drawings. Final removal of silt fence barriers shall be upon approval by the Contracting Officer.

1.4.2.2 Straw Bales

The Contractor shall provide bales of straw as a temporary structural practice to minimize erosion and sediment runoff. Bales shall be properly placed to effectively retain sediment immediately after completing each phase of work (e.g., clearing and grubbing, excavation, embankment, and grading) in each independent runoff area (e.g., after clearing and grubbing in a area between a ridge and drain, bales shall be placed as work progresses, bales shall be removed/replaced/relocated as needed for work to progress in the drainage area). Areas where straw bales are to be used are shown on the drawings. Final removal of straw bale barriers shall be upon approval by the Contracting Officer. Rows of bales of straw shall be provided as follows:

a. Along the downhill perimeter edge of all areas disturbed.

b. Along the top of the slope or top bank of drainage ditches, channels, swales, etc. that traverse disturbed areas.

c. Along the toe of all cut slopes and fill slopes of the construction areas.

d. Perpendicular to the flow in the bottom of existing drainage ditches, channels, swales, etc. that traverse disturbed areas or carry runoff from disturbed areas. Rows shall be spaced as shown on the drawings.

e. Perpendicular to the flow in the bottom of new drainage ditches, channels, and swales. Rows shall be spaced as shown on the drawings.

f. At the entrance to culverts that receive runoff from disturbed areas.

1.4.2.3 Diversion Dikes

Diversion dikes shall have a maximum channel slope of 2 percent and shall be adequately compacted to prevent failure. The minimum height measured from the top of the dike to the bottom of the channel shall be 18 inches. The minimum base width shall be 6 feet and the minimum top width shall bee 2 feet. The Contractor shall ensure that the diversion dikes are not damaged by construction operations or traffic. Diversion dikes shall be located as shown on the drawings.

PART 2 PRODUCTS

2.1 COMPONENTS FOR SILT FENCES

2.1.1 Filter Fabric

The geotextile shall comply with the requirements of ASTM D 4439, and shall consist of polymeric filaments which are formed into a stable network such that filaments retain their relative positions. The filament shall consist of a long-chain synthetic polymer composed of at least 85 percent by weight of ester, propylene, or amide, and shall contain stabilizers and/or inhibitors added to the base plastic to make the filaments resistance to deterioration due to ultraviolet and heat exposure. Synthetic filter fabric shall contain ultraviolet ray inhibitors and stabilizers to provide a minimum of six months of expected usable construction life at a temperature range of 0 to 120 degrees F. The filter fabric shall meet the following requirements:

FILTER FABRIC FOR SILT SCREEN FENCE

PHYSICAL PROPERTY	TEST PROCEDURE	STRENGTH REQUIREMENT
Grab Tensile	ASTM D 4632	100 lbs. min.
Elongation (%)		30 % max.
Trapezoid Tear	ASTM D 4533	55 lbs. min.
Permittivity	ASTM D 4491	0.2 sec-1
AOS (U.S. Std Sieve)	ASTM D 4751	20-100

2.1.2 Silt Fence Stakes and Posts

The Contractor may use either wooden stakes or steel posts for fence construction. Wooden stakes utilized for silt fence construction, shall have a minimum cross section of 2 inches by 2 inches when oak is used and 2 inches by 4 inches when pine is used, and shall have a minimum length of5 feet. Steel posts (standard "U" or "T" section) utilized for silt fence construction, shall have a minimum weight of 1.33 pounds per linear foot and a minimum length of 3 feet.

2.1.3 Mill Certificate or Affidavit

A mill certificate or affidavit shall be provided attesting that the fabric and factory seams meet chemical, physical, and manufacturing requirements specified above. The mill certificate or affidavit shall specify the actual Minimum Average Roll Values and shall identify the fabric supplied by roll identification numbers. The Contractor shall submit a mill certificate or affidavit signed by a legally authorized official from the company manufacturing the filter fabric.

2.1.4 Identification Storage and Handling

Filter fabric shall be identified, stored and handled in accordance with ASTM D 4873.

2.2 COMPONENTS FOR STRAW BALES

The straw in the bales shall be stalks from oats, wheat, rye, barley, rice, or from grasses such as byhalia, bermuda, etc., furnished in air dry condition. The bales shall have a standard cross section of 14 inches by 18 inches. All bales shall be either wire-bound or string-tied. The Contractor may use either wooden stakes or steel posts to secure the straw bales to the ground. Wooden stakes utilized for this purpose, shall have a minimum dimensions of 2 inches x 2 inches in cross section and shall have a minimum length of 3 feet. Steel posts (standard "U" or "T" section) utilized for securing straw bales, shall have a minimum weight of 1.33 pounds per linear foot and a minimum length of 3 feet.

PART 3 EXECUTION

3.1 INSTALLATION OF SILT FENCES

Silt fences shall extend a minimum of 16 inches above the ground surface and shall not exceed 34 inches above the ground surface. Filter fabric shall be from a continuous roll cut to the length of the barrier to avoid the use of joints. When joints are unavoidable, filter fabric shall be spliced together at a support post, with a minimum 6 inch overlap, and securely sealed. A trench shall be excavated approximately 4 incheswide and 4 inches deep on the upslope side of the location of the silt fence. The 4-inch x 4-inch trench shall be backfilled and the soil compacted over the filter fabric. Silt fences shall be removed upon approval by the Contracting Officer.

3.2 INSTALLATION OF STRAW BALES

Straw bales shall be placed in a single row, lengthwise on the contour, with ends of adjacent bales tightly abutting one another. Straw bales shall be installed so that bindings are oriented around the sides rather than along the tops and bottoms of the bales in order to prevent deterioration of the bindings. The barrier shall be entrenched and backfilled. A trench shall be excavated the width of a bale and the length of the proposed barrier to a minimum depth of 4inches After the bales are staked and chinked (gaps filled by wedging with straw), the excavated soil shall be backfilled against the barrier. Backfill soil shall conform to the ground level on the downhill side and shall be built up to4 inches against the uphill side of the barrier. Loose straw shall be scattered over the area immediately uphill from a straw bale barrier to increase barrier efficiency. Each bale shall be securely anchored by at least two stakes driven through the bale. The first stake or steel post in each bale shall be driven toward the previously laid bale to force the bales together. Stakes or steel pickets shall be driven a minimum 18 inches deep into the ground to securely anchor the bales.

3.3 MAINTENANCE

The Contractor shall maintain the temporary and permanent vegetation, erosion and sediment control measures, and other protective measures in good and effective operating condition by performing routine inspections to determine condition and effectiveness, by restoration of destroyed vegetative cover, and by repair of erosion and sediment control measures and other protective measures. The following procedures shall be followed to maintain the protective measures.

3.3.1 Silt Fence Maintenance

Silt fences shall be inspected in accordance with paragraph INSPECTIONS. Any required repairs shall be made promptly. Close attention shall be paid to the repair of damaged silt fence resulting from end runs and undercutting. Should the fabric on a silt fence decompose or become ineffective, and the barrier is still necessary, the fabric shall be replaced promptly. Sediment deposits shall be removed when deposits reach one-third of the height of the barrier. When a silt fence is no longer required, it shall be removed. The immediate area occupied by the fence and any sediment deposits shall be shaped to an acceptable grade.

3.3.2 Straw Bale Maintenance

Straw bale barriers shall be inspected in accordance with paragraph INSPECTIONS. Close attention shall be paid to the repair of damaged bales, end runs and undercutting beneath bales. Necessary repairs to barriers or replacement of bales shall be accomplished promptly. Sediment deposits shall be removed when deposits reach one-half of the height of the barrier. Bale rows used to retain sediment shall be turned uphill at each end of each row. When a

straw bale barrier is no longer required, it shall be removed. The immediate area occupied by the bales and any sediment deposits shall be shaped to an acceptable grade.

3.3.3 Diversion Dike Maintenance

Diversion dikes shall be inspected in accordance with paragraph INSPECTIONS. Close attention shall be paid to the repair of damaged diversion dikes and necessary repairs shall be accomplished promptly. When diversion dikes are no longer required, they shall be shaped to an acceptable grade.

3.4 INSPECTIONS

3.4.1 General

The Contractor shall inspect disturbed areas of the construction site, areas used for storage of materials that are exposed to precipitation that have not been finally stabilized, stabilization practices, structural practices, other controls, and area where vehicles exit the site at least once every seven (7) calendar days and within 24 hours of the end of any storm that produces 0.5 inches or more rainfall at the site. Where sites have been finally stabilized, such inspection shall be conducted at least once every month.

3.4.2 Inspections Details

Disturbed areas and areas used for material storage that are exposed to precipitation shall be inspected for evidence of, or the potential for, pollutants entering the drainage system. Erosion and sediment control measures identified in the Storm Water Pollution Prevention Plan shall be observed to ensure that they are operating correctly. Discharge locations or points shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving waters. Locations where vehicles exit the site shall be inspected for evidence of offsite sediment tracking.

3.4.3 Inspection Reports

For each inspection conducted, the Contractor shall prepare a report summarizing the scope of the inspection, name(s) and qualifications of personnel making the inspection, the date(s) of the inspection, major observations relating to the implementation of the Storm Water Pollution Prevention Plan, maintenance performed, and actions taken. The report shall be furnished to the Contracting Officer within 24 hours of the inspection as a part of the Contractor's daily CQC REPORT. A copy of the inspection report shall be maintained on the job site.

END OF SECTION

THE FOLLWING TECHNICAL SPECIFICATIONS APPLY TO
REPAIR AIRCRAFT PARKING APRON ONLY:

Section No.	Section Title
	DIVISION 2 - SITEWORK
	Repair Aircraft Parking Apron
02111 A	Excavation and Handling of Contaminated Material
02220 A	Demolition
02300 A	Earthwork
02316 A	Excavation, Trenching, and Backfilling for Utilities Systems
02390 A	Tiedown Points for Aircraft
02721 A	Rigid Base Course
02722 A	Aggregate Base Course for Flexible Pavement
02741 A	Hot-Mix Asphalt (HMA) For Roads
02748 A	Bituminous Tack and Prime Coats
02753 A	Concrete Pavement for Airfields
02760 A	Field Molded Sealants for Sealing Joints in Rigid Pavements
02762 A	Compression Joint Seals for Concrete Pavements
02763 A	Pavement Markings
02964 A	Cold Milling of Bituminous Pavements

This page was intentionally left blank for duplex printing.

SECTION 02111 (A)

EXCAVATION AND HANDLING OF CONTAMINATED MATERIAL

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 422	(1963; R 1998) Particle-Size Analysis of Soils
ASTM D 698	(1991; R 1998) Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/cu. ft. (600 kN-m/cu. m.))
ASTM D 1556	(1990; R 1996el) Density and Unit Weight of Soil in Place by the Sand-Cone Method
ASTM D 1557	(1991; R 1998) Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/cu. ft. (2,700 kN-m/cu. m.))
ASTM D 2167	(1994) Density and Unit Weight of Soil in Place by the Rubber Balloon Method
ASTM D 2487	(1998) Classification of Soils for Engineering Purposes (Unified Soil Classification System)
ASTM D 2922	(1996el) Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth)
ASTM D 4318	(1998) Liquid Limit, Plastic Limit, and Plasticity Index of Soils
ASTM D 5434	(1997) Standard Guide for Field Logging of Subsurface Explorations of Soil and Rock

CODE OF FEDERAL REGULATIONS (CFR)

40 CFR 302	Designation, Reportable Quantities, and Notification

1.2 MEASUREMENT AND PAYMENT

1.2.1 Measurement

Measurement for excavation shall be based on the actual number of cubic meters of contaminated material excavated ~~in-place, prior to excavation~~. Determination of the volume of contaminated material excavated shall be based on ~~cross-sectional volume determination reflecting the differential between the original elevations of the top of the contaminated material and the final elevations~~ truck volume~~after removal of the contaminated material~~.

1.2.2 Payment

1.2.2.1 Excavation and Transportation

Compensation for excavation and onsite transportation of contaminated material will be paid as a unit cost. This unit cost shall include any other items incidental to excavation and handling not defined as having a specific unit cost.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Shop Drawings

Surveys; G,

Cross-sections and areas of excavation.

Product Data

Excavation and Handling Work Plan; G,

Work Plan within 30 calender days after notice to proceed. No work at the site, with the exception of site inspections and surveys, shall be performed until the Work Plan is approved. The Contractor shall allow 30 calendar days in the schedule for the Government's review. No adjustment for time or money will be made if resubmittals of the Work Plan are required due to deficiencies in the plan. At a minimum, the Work Plan shall include:

a. Schedule of activities.

b. Method of excavation and equipment to be used.

c. Shoring or side-wall slopes proposed.

d. Dewatering plan.

e. Storage methods and locations for liquid and solid contaminated material.

f. Haul routes.

g. Decontamination procedures.

h. Spill contingency plan.

i. Sampling and Analysis plan

Closure Report; G,

5 copies of Closure Report within 14 calendar days of work completion at the site.

Test Reports

Surveys; G,
Confirmation Sampling and Analysis; G,
Sampling of Stored Material; G,
Sampling Liquid; G,
Chemical Testing; G,

Test results.

1.4 SURVEYS

Surveys shall be performed immediately prior to and after excavation of contaminated material to determine the volume of contaminated material removed. The Contractor shall provide cross-sections on 7.6 meter intervals and at obvious break points for all excavated areas. Locations of confirmation samples shall also be surveyed.

1.5 REGULATORY REQUIREMENTS

1.5.1 Permits and Licenses

The Contractor shall obtain required federal, state, and local permits for the excavation ~~and storage~~ of contaminated material. Permits shall be obtained at no additional cost to the Government.

1.6 DESCRIPTION OF WORK

The project area is a parking apron for aircraft. During the removal of the existing pavement of the parking apron, contaminated material may be encountered. Contaminated material encountered shall be excavated to a depth of 300 millimeters below the existing pavement. The work shall consist of excavation of contaminated material located in the southwest corner of the parking apron. Suspected contamination shall be determined by visual observation and through the use of a photoionization detector (PID). Chemical analysis has been performed by the Government within the project area ~~and is shown in Appendix B of the Design Analysis~~. The Field Investigation Report (containing the Environmental and Geotechnical Field Investigation Report and the Chemical Analysis Report) is attached at the end of this specification section as Appendix A. After the excavation of contaminated material, chemical analysis of material remaining in the excavation shall be performed by the Contractor. Subsurface conditions are shown on the drawings. The Contracting Officer shall

be notified within 48 hours if contaminated material is discovered which has not been previously identified or if other discrepancies between data provided and actual field conditions are discovered. Ground water is not expected to be encountered during excavation activities.

1.7 CHEMICAL TESTING

Required sampling and chemical analysis shall be conducted in accordance with Paragraph 3.3 Confirmation Sampling and Analysis and Section 01450 CHEMICAL DATA QUALITY CONTROL.

1.8 SCHEDULING

The Contractor shall notify the Contracting Officer 7 calendar days prior to the start of excavation of contaminated material. The Contracting Officer will be responsible for contacting regulatory agencies in accordance with the applicable reporting requirements.

PART 2 PRODUCTS

2.1 BACKFILL MATERIAL

Backfill material shall be in accordance with Section 2316 (A) EXCAVATION, TRENCHING, AND BACKFILLING FOR UTILITIES SYSTEMS and be free of contamination.

2.2 SPILL RESPONSE MATERIALS

The Contractor shall provide spill response materials including, but not limited to the following: containers, adsorbents, shovels, and personal protective equipment. Spill response materials shall be available at all times in which hazardous materials/wastes are being handled or transported. Spill response materials shall be compatible with the type of materials and contaminants being handled.

PART 3 EXECUTION

3.1 EXISTING STRUCTURES AND UTILITIES

No excavation shall be performed until site utilities have been field located. The Contractor shall take the necessary precautions to ensure no damage occurs to existing structures and utilities. Damage to existing structures and utilities resulting from the Contractor's operations shall be repaired at no additional cost to the Government. Utilities encountered that were not previously shown or otherwise located shall not be disturbed without written approval from the Contracting Officer.

3.2 CLEARING AND GRUBBING (NOT USED)

3.2 CONTAMINATED MATERIAL REMOVAL

3.2.1 Excavation

Areas of contamination shall be excavated to within 60 mm of the depth required in Paragraph 1.6 or as directed by the Contracting Officer. Excavation shall be performed in a

manner that will limit the potential for contaminated material to be mixed with uncontaminated material. The Contractor shall maintain an excavation of sufficient size to allow workers ample room to complete the work. A log of the materials and any visible signs of contamination encountered during excavation shall be maintained for each area of excavation. Excavation logs shall be prepared in accordance with ASTM D 5434.

3.2.3 Shoring

Sheeting, bracing, or shoring shall be installed in the absence of adequate side slopes if there is a need for workers to enter the excavated area.

3.2.4 Dewatering

Surface water shall be diverted to prevent entry into the excavation. Dewatering shall be limited to that necessary to assure adequate access, a safe excavation, and to ensure that compaction requirements can be met.

3.3 CONFIRMATION SAMPLING AND ANALYSIS

The Contracting Officer shall be present to inspect the removal of contaminated material from the site. After all material suspected of being contaminated has been removed, the excavation shall be examined for evidence of contamination and, if appropriate, field analysis used to determine the presence of volatile and/or semi-volatile contamination using a real time vapor monitoring instrument (PID). Excavation of additional material shall be as directed by the Contracting Officer. After all suspected contaminated material is removed, confirmation samples shall be collected and analyzed for the following contaminants:

Chemical Parameter	Chemical Analysis
BTEX	EPA Method 8021
PAHs	EPA Method 8270

Confirmation sample results shall be compared to Idaho Department of Environmental Quality Tier 0 Soil Cleanup Levels as shown below.

Chemical Parameter	Action Level (mg/kg)
Benzene	0.06
Toluene	5.4
Ethylbenzene	10
Xylenes	7
PAHs	
Acenapthene	1.1
Anthracene	0.8
Benzo(a)pyrene	0.12
Benzo(b)fluoranthene	1.22
Benzo(k)fluoranthene	4.4
Benzo(a)anthracene	1.22
Benzo(g,h,i)perylene	0.4
Chyrsene	0.5
Fluorene	4.2

Fluoranthene	4.4
Naphthalene	5.5
Phenanthrene	8.4
Pyrene	10

Samples shall be collected at a frequency of one per 1200 cubic meters from the bottom and each of the side walls or as directed by the Contracting Officer. A minimum of one sample shall be collected from the bottom and each side wall of the excavation. Based on test results, the Contractor shall propose any additional excavation which may be required to remove material which is contaminated above action levels. Additional excavation shall be subject to approval by the Contracting Officer. Locations of samples shall be marked in the field and documented on the as-built drawings.

3.4 CONTAMINATED MATERIAL STORAGE

Contaminated material shall be placed in a contaminated soil disposal site on the Mountain Home AFB (location shown on drawings) immediately after excavation. Prior to placement of material into disposal site, the Contractor shall coordinate with the Contracting Officer who will coordinate placement location with Base Environmental. Base Environmental POC is Paula Jo Miller, (208) 828-6666. A written log shall be kept to track the amount of contaminated material placed in the soil farm.

3.5 SAMPLING

3.5.1 Sampling of Excavated Material

Samples of excavated material shall be collected at a frequency of once per 1200 cubic meters. Samples shall be tested for the parameters described in Paragraph 3.3 above.

Material with contaminant levels that exceed the action levels shall be treated by the Government at the disposal area described in Paragraph 3.4 of this Section. Analyses for contaminated material shall be performed by the Contractor and shall conform to local, state, and federal criteria as well as to the requirements of the treatment facility. Documentation of all analyses performed shall be furnished to the Contracting Officer. Additional sampling and analyses to the extent required by the ~~approved treatment, storage or disposal (TSD) facility~~ treatment facility shall be the responsibility of the Contractor and shall be performed at no additional cost to the Government.

3.6 SPILLS

In the event of a spill or release of a hazardous substance (as designated in 40 CFR 302), pollutant, contaminant, or oil (as governed by the Oil Pollution Act (OPA), 33 U.S.C. 2701 et seq.), the Contractor shall notify the Contracting Officer immediately. If the spill exceeds the reporting threshold, the Contractor shall follow the pre-established procedures as described in the Base Wide Contingency Plan for immediate reporting and containment. Immediate containment actions shall be taken to minimize the effect of any spill or leak. Cleanup shall be in accordance with applicable federal, state, and local regulations. As directed by the Contracting Officer, additional sampling and testing shall be performed to verify spills have been cleaned up. Spill cleanup and testing shall be done at no additional cost to the Government.

3.7 BACKFILL

3.7.1 Confirmation Test Results

Excavations shall be backfilled immediately after all contaminated materials have been removed and confirmation test results have been approved.

3.7.2 Compaction

Compaction shall be in accordance with Section 2300 (A) EARTHWORK and Section 2316 EXCAVATION, TRENCHING, AND BACKFILLING FOR UTILITIES SYSTEMS.

3.8 DISPOSAL REQUIREMENTS

~~Offsite disposal~~Disposal of contaminated material shall be in accordance with ~~Section 01061 (AR) ENVIRONMENTAL PROTECTION~~this specification Section.

3.9 CLOSURE REPORT

5 copies of a Closure Report shall be prepared and submitted within 21 calendar days of completing work at the site. The report shall be labeled with the contract number, project name, location, date, name of general contractor, and the Corps of Engineers District contracting for the work. The Closure Report shall include the following information as a minimum:

a. A cover letter signed by a Professional Engineer registered in the State of Idaho, who is a responsible company official certifying that all services involved have been performed in accordance with the terms and conditions of the contract documents.

b. A narrative report including, but not limited to, the following:

(1) site conditions, ground water elevation, and cleanup criteria;

(2) excavation logs;

(3) field screening readings;

(4) quantity of materials removed from each area of contamination;

(5) quantities of water/product removed during dewatering;

(6) sampling locations and sampling methods;

(7) collection data such as time of collection and method of preservation;

(8) sample chain-of-custody forms; and

(9) source of backfill.

c. Copies of all chemical and physical test results.

d. Copies of all manifests and land disposal restriction notifications.

e. Copies of all certifications of final disposal signed by the responsible disposal facility official.

f. Waste profile sheets.

g. Scaled drawings showing limits of each excavation, limits of contamination, known underground utilities within 15 m 50 feet of excavation, sample locations, and sample identification numbers.

h. Progress Photographs. Color photographs shall be used to document progress of the work. A minimum of four views of the site showing the location of the area of contamination, entrance/exit road, and any other notable site conditions shall be taken before work begins. After work has been started, activities at each work location shall be photographically recorded daily. Photographs shall be a minimum of 76.2 x 127.0 mm 3 x 5 inches and shall include:

(1) Soil removal, handling, and sampling.

(2) Unanticipated events such as discovery of additional contaminated material.

(3) Contaminated material storage.

(4) Site or task-specific employee respiratory and personal protection.

(5) Fill placement and grading.

(6) Post-construction photographs. After completion of work at each site, the Contractor shall take a minimum of four views of each excavation site.

Photographs shall be mounted back-to-back in double face plastic sleeves punched to fit standard three ring binders. Each print shall have an information box attached. The box shall be typewritten and arranged as follows:

Project Name:	Direction of View:
Location:	Date/Time:
Photograph No.:	Description of View:

~~END OF SECTION~~

Appendix A added by amendment R0004

APPENDIX A

FIELD INVESTIGATION REPORT

PART I: Environmental and Geotechnical Field Investigation Report

PART II: Environmental Sampling Chemical Analysis Report

This page intentionally blank

FIELD INVESTIGATION REPORT

PAGE

PART I: ENVIRONMENTAL AND GEOTECHNICAL FIELD INVESTIGATION REPORT 1

1.0 BACKGROUND 1

1.1 BACKGROUND 1
1.2 OBJECTIVE 1
1.3 INVESTIGATION LOCATION 1

2.0 FIELD INVESTIGATION SUMMARY 1

3.0 DESCRIPTION OF INVESTIGATION 2

3.1 CONCRETE CORING 2
3.2 ENVIRONMENTAL SOIL SAMPLING 2

TABLE 1: ENVIRONMENTAL SAMPLES 3

3.2.1 Air Monitoring 4
3.2.2 Decontamination 4
3.3 GEOTECHNICAL SOIL SAMPLING 5

TABLE 2: GEOTECHNICAL SAMPLES 5

3.4 SOIL CLASSIFICATION 6
3.5 INVESTIGATION DERIVED WASTE MANAGEMENT AND BORE HOLE CLOSURE 9

4.0 LABORATORY ANALYSIS 9

5.0 PACKAGING AND SHIPMENT 10

6.0 PROTECTION LEVEL 10

7.0 PERSONNEL EXPOSURE TIME 10

8.0 ADDITIONAL INFORMATION 10

9.0 REFERENCES 10

ATTACHMENTS:

Site Location, Vicinity, and Sampling Location Maps, Photo Sheets 1-4

This page intentionally blank

Part I: Environmental and Geotechnical Field Investigation Report

1.0 BACKGROUND

1.1 Background

Mountain Home Air Force Base is home to the 366th Wing, Air Combat Command. The Wing stands ready to rapidly deploy worldwide as a composite air expeditionary wing flying fighter, bomber, and refueling/support aircraft. Aircraft from the 366th Wing, as well as transient aircraft utilize the parking apron also known as the "Mobility Ramp" between Base Operations, and Taxiways "C" and "D". Seattle District, US Army Corps of Engineers, was tasked to repair this parking apron.

Seattle District was also tasked to provide supporting geotechnical and environmental sampling and analysis of soils underlying the parking apron area prior to conducting the repair project. Geotechnical and environmental field sampling for this project was planned for 20 discrete locations as determined by the design team. However, due to unforeseen Air Force ramp requirements and actual field conditions, geotechnical and environmental samples were only collected from 9 out of the planned 20 discrete locations (see Appendix A, Figure 3).

Previous subsurface soil sampling under the adjoining E Ramp (1995) revealed petroleum hydrocarbon contamination as a result of JP-4 refueling pit leakage. JP-5 and JP-8 was also a suspected contaminant within sub-surface soils due to known use of these fuels at Mountain Home AFB.

1.2 Objective

The objective of this site investigation was to determine if petroleum hydrocarbon (primarily JP-4, JP-5, and JP-8 jet aircraft fuel) contamination exists in sub-surface soils underlying the existing paved aircraft parking and taxiway areas within project boundaries (see Appendix A Figure 3). Determination of potential release and contaminant concentrations was achieved by analyzing the results of a combination of: olfactory; visual, and laboratory analyses of collected soil samples.

1.3 Investigation Location

The Mountain Home AFB Mobility Ramp is a large concrete paved aircraft parking area with an Asphaltic concrete overlay approximately 72,500 square meters in size. The ramp is prominently situated southwest of the Base Operations building. Mountain Home AFB is located near Mountain Home, and south of Boise, Idaho (Appendix A, Figures 1-3).

2.0 FIELD INVESTIGATION SUMMARY

A geotechnical/environmental field sampling team comprised of Glen Terui and Joseph Marsh, Technical Services Branch, Seattle District USACE, accomplished the subsurface soil sampling investigation described in this report. Glen Terui supervised all concrete coring

activities on the aircraft apron prior to drilling and sampling. Glen Terui was responsible for coordinating and directing all soil sampling activities, geotechnical soil classification and sampling, transmittal of materials documentation, and sample delivery to the soil testing laboratory for determination of geotechnical soil properties. Joseph Marsh was responsible for air monitoring, preparation, collection and containerization of the environmental soil samples, chain of custody documentation, labeling and packing of samples, and sample shipment to the laboratory for chemical analysis.

Concrete coring was performed on August 1 and 2, 2001 and geotechnical and environmental soil sampling was conducted on August 6 and 7, 2001.

All work was accomplished in accordance with the Management Plan for Subsurface Soil Sampling in support of Repair Aircraft Parking Apron (Mobility Ramp) Project, Mountain Home Air Force Base (April 2001), prepared by the Technical Services Branch, Seattle District USACE.

3.0 DESCRIPTION OF INVESTIGATION

3.1 Concrete Coring

Eleven sampling locations on the mobility ramp, and one sampling location on the flightline road was saw cut to expose the subsurface soil for drilling and sample collection. In addition to the 12 sampling locations, two test holes were cored: one on the flightline road, and one on the ramp to determine pavement thickness only. A 304.8 mm diameter concrete core cutter was used. Peninsula Sawing and Drilling, Inc. of Mountain Home, Idaho (POC: Joe Curry, (208) 587-9071) performed the concrete coring work.

3.2 Environmental Soil Sampling

The nine test holes drilled and sampled for environmental laboratory analysis were as follows: 01-CC-PA-101, 01-CC-PA-103, 01-CC-PA-106, 01-CC-PA-107, 01-CC-PA-109, 01-CC-PA-110, 01-CC-PA-111, 01-HTRW-01, and 01-HTRW-02. Three test holes (01-CC-PA-108, 01-HTRW-03, and 01-HTRW-04) encountered bedrock at shallow depths of 610 mm, 540 mm, and 498 mm, respectively, and were not sampled.

Each test hole was drilled using a BK 81 truck-mounted hollow-stem power auger with an inside diameter of 107.9 mm. Once the auger approached the desired sampling depth, a sample was collected using a 457.2 mm long by 50.8 mm outside diameter, stainless steel split-spoon sampler. After the split-spoon sampler was retrieved, it was opened and scanned by sight, smell, and with a photoionization detector (PID) for fuel contamination. The drill cuttings and soil samples revealed no apparent visual or olfactory evidence of fuel contamination (refer to Section 3.2.1 Air Monitoring).

HazTech Drilling, Meridian, Idaho (POC: Bob Corn, (208) 888-4790 performed the drilling and soil sample retrieval work.

The environmental samples for VOC (BTEX) analysis were placed directly into certified clean 8-ounce wide mouth glass sample jars to minimize loss of volatiles. The environmental samples for PAH's were placed into a dedicated foil mixing pan, homogenized using a dedicated clean stainless steel scoop, then transferred into certified clean 8-ounce wide mouth glass sample jars. The filled jars were securely capped, labeled with sample ID number, analysis, sampler name, date, and time. The samples were then bagged in bubble wrap bags, and placed into pre-iced sample shipping coolers for delivery to the analytical laboratory.

Groundwater was not encountered in any of the drilled boreholes.

Sample identification, borehole numbers, and sample depths are shown at Table 1. The sampled borehole locations are shown at Appendix A, Figure 3. Chain of custody information can be viewed at Appendix B.

TABLE 1: ENVIRONMENTAL SAMPLES

SAMPLE ID	BOREHOLE	SAMPLE DEPTH	REMARKS
801MHMR01	01-CC-PA-101	609-1219 mm BPS	Primary samples for VOCs (BTEX) and PAHs
801MHMR02	01-HTRW-2	762 – 1371 mm BPS	Primary samples for VOCs (BTEX) and PAHs
801MHMR03	01-HTRW-2	1371 – 1676 mm BPS	Primary samples for VOCs (BTEX) and PAHs
-	01-HTRW-3	Not Collected	Rock approx. 540 mm BPS. No primary samples collected.
-	01-HTRW-4	Not Collected	Weathered rock approx. 498 mm BPS. No Primary or QC samples collected as planned.
801MHMR09	01-CC-PA-103	609-1219 mm BPS	Primary samples for VOCs (BTEX) and PAHs
801MHMR10	01-HTRW-1	457 – 1524 mm BPS	Primary samples for VOCs (BTEX) and PAHs
801MHMR11	01-HTRW-1	1524 – 3048 mm BPS	Primary samples for VOCs (BTEX) and PAHs
801MHMR12	01-CC-PA-106	609-1219 mm BPS	Primary samples for VOCs (BTEX) and PAHs
801MHMR13	01-CC-PA-107	609-1219 mm BPS	Primary samples for VOCs (BTEX) and PAHs
801MHMR14	01-CC-PA-107	609-1219 mm BPS	QC samples for VOCs (BTEX) and PAHs
-	01-CC-PA-108	Not Collected	Rock encountered at 610 mm - no primary sample collected.

SAMPLE ID	BOREHOLE	SAMPLE DEPTH	REMARKS
801MHMR16	01-CC-PA-109	609-1219 mm BPS	Primary/MS-MSD samples for VOCs (BTEX) and PAHs
801MHMR17	01-CC-PA-110	609-1219 mm BPS	Primary samples for VOCs (BTEX) and PAHs
801MHMR18	01-CC-PA-111	609 mm – 1524 mm BPS	Primary samples for VOCs (BTEX) and PAHs
801MHMR19	01-CC-PA-111	609 mm – 1524 mm BPS	QC samples for VOCs (BTEX) and PAHs

NOTE: BPS indicates Below Pavement Surface

3.2.1 Air Monitoring

Air monitoring was conducted for worker health and safety, and also for detecting possible petroleum hydrocarbon vapors in recovered soil samples. A PID was used each day to measure total organic vapors near the breathing zone, emanating from each open borehole, and from soils immediately upon opening the split spoon samplers. The PID was calibrated with 100 parts per million (PPM) isobutylene span gas daily. Air monitoring results were to be recorded in the environmental field logbook as total organic vapors in PPM. However, no organic vapors were detected over any borehole or soil sample during this field investigation.

3.2.2 Decontamination

The stainless steel split-spoon samplers and auger flights were decontaminated prior to drilling and sampling operations by high-pressure hot water cleaning performed off-base. The entire split-spoon sampler assembly (drive shoe, sample barrel, and collar) was hand washed using a phosphate-free soap solution, tap water rinse, and a distilled water final rinse between each sample depth and sample borehole. All decontamination water used during this field investigation was transferred into a nearby sanitary storm sewer manhole at the direction of the base Environmental Flight.

The dedicated stainless steel sampling scoops were decontaminated at the Seattle District, USACE office prior to use at the project site using the same methods described in the previous paragraph. One scoop was dedicated to each sample to be collected, eliminating the requirement for field decontamination of the scoops. To prevent contamination, the scoops were wrapped with aluminum foil and packaged in plastic bags for transportation to the Mobility Ramp project site. The used scoops were sealed in plastic bags and transported back to the Seattle District for proper decontamination at the conclusion of field investigation. New, dedicated, disposable aluminum foil mixing pans were used for each sample interval at each sample borehole. These pans were discarded in a garbage receptacle at the conclusion of field investigation.

3.3 Geotechnical Soil Sampling

The nine test holes drilled and sampled for soil classification and geotechnical analysis were identified as follows: 01-CC-PA-101, 01-CC-PA-103, 01-CC-PA-106, 01-CC-PA-107, 01-CC-PA-109, 01-CC-PA-110, 01-CC-PA-111, 01-HTRW-01, and 01-HTRW-02. Test holes 01-CC-PA-108, 01-HTRW-03, and 01-HTRW-04 encountered bedrock at shallow depths of 610 mm, 540 mm, and 498 mm, respectively, and were not sampled for geotechnical analysis.

As described in Section 3.2, each test hole was drilled using a BK 81 truck-mounted hollow-stem power auger with an inside diameter of 107.9 mm. Once the auger approached the desired sampling depth, a sample was collected using a 457.2 mm long by 50.8 mm outside diameter, stainless steel split-spoon sampler. A standard penetration test (number of blows to drive the split-spoon sampler 304.8 mm using a 63.5 kg hammer dropped 762 mm), to determine the relative density and/or consistency of the soil, was also performed at each depth sampled.

California bearing ratio, mechanical analysis, modified proctor, and moisture content soil analyses were performed on the geotechnical samples.

The geotechnical soil samples were placed in 5-gallon plastic pails for California bearing ratio and modified proctor soil tests and placed in doubled, Ziploc bags for mechanical analysis and moisture content determination.

Geotechnical sample identifications, collection dates, test hole number, sample depths, and tests performed are shown on Table 1. The sampled test hole locations are shown at Appendix A, Figure 3.

TABLE 2: GEOTECHNICAL SAMPLES

Sample ID	Collection Date (2001)	Test Hole ID	Sample Depths	Tests Performed
01CCPA101A	7 Sept	01-CC-PA-101	350 to1264 mm	CBR, Modified Proctor, Mechanical Analysis, Moisture Content
01CCPA101B	7 Sept	01-CC-PA-101	1500 to 3048 mm	Moisture Content
01CCPA103A	7 Sept	01-CC-PA-103	800 to1540 mm	Moisture Content
01CCPA106A	7 Sept	01-CC-PA-106	427 to1241 mm	Moisture Content
01CCPA107A	6 Sept	01-CC-PA-107	480 to1372 mm	CBR, Modified Proctor, Mechanical Analysis, Moisture Content
01CCPA109A	6 Sept	01-CC-PA-109	391 to 2438 mm	CBR, Modified Proctor, Mechanical Analysis, Moisture Content

Sample ID	Collection Date (2001)	Test Hole ID	Sample Depths	Tests Performed
01CCPA109B	6 Sept	01-CC-PA-109	1524 to 2743 mm	Moisture Content
01CCPA110A	6 Sept	01-CC-PA-110	545 to1524 mm	CBR, Modified Proctor, Mechanical Analysis, Moisture Content
01CCPA110B	6 Sept	01-CC-PA-110	1676 to 2896 mm	Moisture Content
01CCPA111A	6 Sept	01-CC-PA-111	685 to1524 mm	CBR, Modified Proctor, Mechanical Analysis, Moisture Content
01CCPA111B	6 Sept	01-CC-PA-111	1828 to 3048 mm	Moisture Content
01HTRW1A	7 Sept	01-HTRW-1	630 to 1549 mm	CBR, Modified Proctor, Mechanical Analysis, Moisture Content
01HTRW2A	7 Sept	01-HTRW-2	785-1242 mm	Moisture Content

3.4 Soil Classification

To ensure that a consistent terminology for soil characterization is used, the Unified Soil Classification System was used for all sampled test holes. Soils recovered during this investigation were classified as follows.

Test Hole 01-CC-PA-101

0.0 – 130 mm: Asphaltic Pavement

130 – 350 mm: Concrete Pavement

350 – 450 mm: SP, Sand, medium, moist, tan

450 – 807 mm: SM, Silty Sand, medium, moist, brown

807 – 1264 mm: SP-SM, Sand with silt, medium, moist, tan

1264 – 3048 mm: SP, Sand, dense, moist, tan

Test Hole 01-CC-PA-103

0.0 – 108 mm: Asphaltic Pavement
108 – 346 mm: Concrete Pavement
346 – 490 mm: SP, Sand, loose, moist, tan
490 – 800 mm: SP-SM, Sand with silt, loose, moist, light brown

800 – 1210 mm: SP, Sand medium, wet, brown
1210 – 1540 mm: SM, Silty Sand with gravel (20 mm), very dense, moist, tan
1540 – 1828 mm: Bedrock (basalt)

Test Hole 01-CC-PA-106

0.0 – 121 mm: Asphaltic Pavement
121 – 327 mm: Concrete Pavement
327 – 427 mm: SP, Sand with occasional gravel (15 mm), medium, moist, brown
427 – 1241 mm: ML, Silt with fine sand, hard, moist, grayish brown
1241 mm: Bedrock (basalt)

Test Hole 01-CC-PA-107

0.0 – 100 mm: Asphaltic Pavement
100 – 480 mm: SP, Sand with gravel (30 mm), medium, moist, brown
480 – 1372 mm: ML, Silt with fine sand, stiff, moist, olive gray
1372 – 1600 mm: Bedrock (basalt)

Test Hole 01-CC-PA-108

0.0 – 135 mm: Asphaltic Pavement
135 – 500 mm: Concrete Pavement
500 – 610 mm: SP-SM, Sand with silt and occasional gravel, medium to dense, moist, brown
610 – 1372 mm: Bedrock (basalt)

Test Hole 01-CC-PA-109

0.0 – 121 mm: Asphaltic Pavement
121 – 341 mm: Concrete Pavement
341 – 493 mm: SP, Sand with occasional gravel (10 mm), medium, moist, tan
493 – 1676 mm: ML, Silt with fine sand, stiff, moist, brown
1676 – 1981 mm: SP-SM, Sand with silt, medium, moist, brown
1981 – 3048 mm: SP, Sand, dense, moist, brown

Test Hole 01-CC-PA-110

0.0 – 115 mm: Asphaltic Pavement

115 – 335 mm: Concrete Pavement

335 – 545 mm: SP, Sand, medium, moist, tan

545 – 914 mm: ML, Silt, very stiff, moist, olive gray

914 – 2400 mm: ML, Silt with fine sand, stiff, medium to very stiff, moist to wet, olive gray

2400 – 2884 mm: SP, Sand, dense, moist, brown

2884 – 2896 mm: Caliche with gravel

Test Hole 01-CC-PA-111

0.0 – 135 mm: Asphaltic Pavement

135 – 565 mm: Concrete Pavement (concrete disintegrated during coring)

565 – 685 mm: SP, Sand, medium, moist, brown

685 – 2500 mm: SM, Silty Sand, medium, moist, brown

2500 – 3048 mm: SP, Sand, stiff, medium, moist, brown

Test Hole 01-CC-112

0.0 – 135 mm: Asphaltic Pavement

115 – 360 mm: Concrete Pavement

Test Hole 01-CC-115

0.0 – 125 mm: Asphaltic Pavement

125 – 360 mm: Concrete Pavement

Test Hole 01-HTRW-01

0.0 – 128 mm: Asphaltic Pavement

128 – 630 mm: SP-SM, Gravelly Sand with silt, dense, moist, tan

630 – 1550 mm: ML, Silt with fine sand, very stiff, moist, olive gray

1550 – 2055 mm: SM, Silty Sand, very dense, moist, tan

2055 – 2896 mm: SM, Silty Sand with occasional rock fragments, very dense, moist, tan

Test Hole 01-HTRW-02

0.0 – 115 mm: Asphaltic Pavement
115 – 328 mm: Concrete Pavement
328 – 460 mm: SP, Sand, medium, brown
460 – 1240 mm: ML, Silt with organic debris (roots and wood), stiff, moist, olive gray
1240 – 2003 mm: SM, Silty Sand with occasional gravel (15 mm), medium, moist, tan
2003 – 2100 mm: Bedrock (basalt)

Test Hole 01-HTRW-03

0.0 – 110 mm: Asphaltic Pavement
110 – 312 mm: Concrete Pavement
312 – 540 mm: SP, Sand, dense, moist, brown
540 – 640 mm: Bedrock (basalt)

Test Hole 01-HTRW-04

0.0 – 280 mm: Asphaltic Pavement
280 – 442 mm: Concrete Pavement
442 – 498 mm: SP, Sand with occasional gravel, medium, moist, brown
498 – 800 mm: Weathered Bedrock (basalt)

3.5 Investigation Derived Waste Management and Bore Hole Closure

All drill cuttings were returned to the original boreholes because contaminated soil was not detected by visual, olfactory, or photoionization detector field screening. Each borehole was topped-off with approximately 300 mm of fresh quick-setting concrete, which was troweled smooth to match the level of the existing pavement.

4.0 LABORATORY ANALYSIS

Collected soil samples were analyzed for the following based on potential JP-4, JP-5, an/or JP-8 contamination: **VOC's** (BTEX) – Method EPA 8021; and **PAH's** – Method EPA 8270.

Primary and Quality Control environmental soil samples were analyzed by Sound Analytical Services, 5755 8th Street East Tacoma, WA 98242 (POC: Dawn Werner, (253) 922-2310).

5.0 PACKAGING AND SHIPMENT

Following proper collection and labeling, the sample jars were sealed in plastic bubble wrap bags and placed into two sample shipping coolers. Each pre-prepared cooler was lined with a large plastic garbage bag, and contained a layer of bubble wrap sheeting at the bottom and sides for shock absorption. Within each cooler, eight double-bagged gallon size Ziploc bags filled with cubed ice were placed between and on top of the sample containers to cool down the samples to 4 degrees centigrade. The completed chain of custody (COC) form was placed in a Ziploc bag and taped to the inside of each cooler lid. Two custody seals were numbered, dated, signed, and affixed to the outside of each cooler. The seals, taped over with clear tape, were placed across the lid opening so that the coolers could not be opened without breaking the seals. Finally, the coolers were sealed with fiber strapping tape.

Joseph Marsh delivered the two coolers containing the primary and quality control samples, and COC forms, to the Mountain Home AFB Resident Office on 8 August 2001 to await pickup and delivery by Federal Express (air bill no. 8827256847555). At the time of shipment, the laboratory was notified of the coolers sent and the anticipated delivery time.

The two sample coolers arrived on 9 August 2001 at Sound Analytical Services, 5755 8th Street East Tacoma, WA 98242 (POC: Dawn Werner, (253) 922-2310).

The geotechnical soil samples were placed and transported to the soil testing laboratory in five-gallon plastic pails for California bearing ratio and modified proctor soil tests and in doubled, Ziploc bags for mechanical and moisture content analysis.

Glen Terui delivered the samples along with the Transmittal of Materials Samples forms, on 6 and 7 August 2001 to TERRCON, 11848 West Executive Drive, Suite G, Boise, Idaho. (POC: Michael Merhar, P.E., (208) 323-9520).

6.0 PROTECTION LEVEL

Soil sampling was conducted under worker protection level D.

7.0 PERSONNEL EXPOSURE TIME

Total exposure time for sampling team members were as follows: Glen Terui (34 hours) and Joseph Marsh (18 hours).

8.0 ADDITIONAL INFORMATION

Additional information on the field investigation detailed in this report can be obtained from the Geology and Instrumentation Section, Technical Services Branch.

9.0 REFERENCES

USACE 2001a, *Engineering Manual 200-1-3, Environmental Quality, Requirements for the Preparation of Sampling and Analysis Plans*, February 2001.

USACE 2001b, *Management Plan for Sub-Surface Soil Sampling in Support of Repair Aircraft Parking Apron (Mobility Ramp) Project*, June 2001.



Figure 1 of 3

LOCATION MAP
AIRCRAFT PARKING APRON (MOBILITY RAMP)
MOUNTAIN HOME AFB, IDAHO

Not to Scale

US Army Corps of Engineers
Seattle District



Figure 2 of 3

SITE VICINITY MAP
AIRCRAFT PARKING APRON (MOBILITY RAMP)
MOUNTAIN HOME AFB, IDAHO

US Army Corps of Engineers ®
Seattle District

Not to Scale



SUBSURFACE SOIL SAMPLING LOCATION MAP
REPAIR AIRCRAFT PARKING RAMP PROJECT
MOUNTAIN HOME AFB, IDAHO
6-7 AUGUST 2001

Figure 3 of 3

US Army Corps of Engineers
Seattle District

This project was designed by the Seattle District U.S. Army Corps of Engineers. The initials or signatures and registration designations of individuals appearing on the design documents are affirmation of responsible charge and creditable performance of work within the scope of their employment as required by ER 1110-1-8152, Professional Registrations.

US Army Corps of Engineers
Seattle District

SITE PLAN

Plate number: C-1

DATE AND TIME PLOTTED: 18-APR-2001 10:28 DESIGN FILE: I:\DESIGNS\MFSC\MENTER\PLAN\MP2CSP0.DGN

Figure 1

Figure 2



Figure 1 shows preparations made for drilling and sampling at sample point 01-CC-PA-109. Note the photoionization detector and soil mixing pan and spoon in foreground. Figure 2 Shows hollow-stem auger drilling in progress through cored concrete pavement.

Photographer: Joseph Marsh

US Army Corps of Engineers
Seattle District

Figure 3



In photo above, an open split spoon sampler with enclosed soil core sample is quickly scanned with a photoionization detector for traces of organic vapors.

Figure 4



Figure 4 shows soil core sample split and being scanned for organic vapors. The instrument did not detect organic vapors in any recovered soil core.

Photographer: Joseph Marsh

US Army Corps of Engineers
Seattle District

Figure 5



Soils designated for laboratory analysis are quickly homogenized in dedicated foil pans using dedicated steel scoops prior to being placed into sample containers.

Figure 6

Decontamination of sampling equipment between boreholes is shown in photo above.

US Army Corps of Engineers ®
Seattle District

Photographer: Joseph Marsh

Figure 7

Figure 8

Figure 7 shows soil in open split-spoon sampler being examined for geotechnical classification. The geotechnical soil samples were placed into 5-gallon buckets for CBR and Proctor tests (Figure 8), and into one-gallon Ziploc plastic bags for moisture content and mechanical analysis.

Figure 9

At completion of sampling at each location, the boreholes were backfilled, then topped with quick setting concrete.

US Army Corps of Engineers
Seattle District

Photographer: Joseph Marsh

This page intentionally blank

CHEMICAL ANALYSIS REPORT

PAGE

PART II: ENVIRONMENTAL SAMPLING CHEMICAL ANALYSIS REPORT 13

1.0 BACKGROUND AND PURPOSE 13

2.0 SUMMARY OF DATA QUALITY OBJECTIVES 13

3.0 SUMMARY OF SAMPLING ACTIVITIES 13

4.0 DESCRIPTION OF ANALYSIS 13

5.0 DATA ADEQUACY 14

6.0 COMPARISON OF DATA TO IDEQ STANDARDS 14

7.0 CONCLUSIONS 14

8.0 REFERENCES 14

This page intentionally blank

Part II: Environmental Sampling Chemical Analysis Report

1.0 Background and Purpose

Mountain Home Air Force Base is preparing to repair a section of an aircraft parking apron (known as the mobility ramp). The Seattle District was tasked to provide supporting environmental sampling and analysis of soils underlying the parking apron area for use in future contract documents (see Part I, Section 1.0 Background for more details).

2.0 Summary of Data Quality Objectives

The primary objective of the environmental soil investigation was to determine the type and extent of petroleum hydrocarbon contamination in soils underlying the parking apron area. A secondary data objective was to determine whether the soil concentrations met the Idaho Division of Environmental Quality (IDEQ) Risk-Based Corrective Action (RBCA) Tier 0 Cleanup Levels for petroleum sites. IDEQ Tier 0 cleanup levels apply to sites where impacts are limited to the soil and the potential for groundwater impacts are low, and where the need for rapid cleanup and closure is desired. Tier 0 levels were derived for each contaminant of concern (COC) assuming a residential exposure scenario and typical soil exposure pathways. Tier 0 levels are intended to be conservative so that, if achieved, there is a high degree of certainty that little or no risk to any current or potential future receptors remains at the site (IDEQ 1997a). Data quality indicators including precision, accuracy, and completeness are described in the Quality Assurance Project Plan (QAPP), a part of the Management Plan (USACE 2001b).

3.0 Summary of Sampling Activities

Sampling activities are described in Part I: Section 3 of this field investigation report. Sampling activities describe site conditions, sample locations, the number of samples collected, sampling procedures, and any deviations from the approved Management Plan.

4.0 Description of analysis

Chemical analyses were selected to satisfy data quality objectives described above. Fuels of concern at the parking apron were JP-4, JP-5, and JP-8. Eleven primary, two quality control (QC), and one matrix spike/matrix spike duplicate (MS/MSD) environmental samples were collected. The environmental soil samples were sent to Sound Analytical Services in Tacoma, WA for analysis by EPA Method 8021B and EPA Method 8270. These analyses determine concentrations of benzene, toluene, ethylbenzene, xylenes (BTEX) and polynuclear aromatic hydrocarbons (PAHs), respectively. PAHs reported using Method 8270 include: naphthalene, 2-methyl-naphthalene, 2-chloro-naphthalene, acenaphthene, acenaphthalyene, fluorene, phenanthrene, anthracene, fluoranthene, pyrene, benzo(a)anthracene, chrysene, benzo(a)pyrene, indeno(1,2,3-cd)pyrene, dibenzo(a,h)anthracene, and benzo(g,h,i)perylene.

5.0 Data Adequacy

Laboratory quality control was performed in accordance with USACE Shell for Analytical Chemistry Requirements (EM 200-1-3, App. I). Review of the data shows that laboratory quality control parameters were met with the exception of three samples, where results were outside laboratory parameters for surrogate recovery (801MHMR09, 801MHMR12, and 801MHMR14). This may be attributed to matrix affects (i.e. the soil properties may have affected the analysis). Also, three samples had estimated values for at least one PAH (801MHMR03, 801MHMR14, and 801MHMR16). These values were estimated because the compound was detected (i.e. concentration greater than the method detection limit (MDL)). However, the concentration was less than the practical quantitation limit (PQL).

Samples were received by the laboratory with the appropriate sample controls and cooler temperature and analyzed within the holding limits. Sample handling procedures and quality assurance/quality control parameters are described in the Management Plan (USACE 2001b). The sample results where surrogate recoveries were outside laboratory control parameters will be considered estimates. Field duplicates where analytes were detected, exceeded the relative percent difference (RPD) of 50 percent, stated in the management plan (2001b). Typically field duplicates are used to determine precision and effectiveness of field sampling procedures. In evaluating field sampling procedures and sample container analysis by the laboratory, it appears that the discrepancy in analytical results may be due to a non-homogenous sample and will be considered estimates. Overall, the data is useable for site characterization.

6.0 Comparison of Data to IDEQ standards

Sample results show that BTEX was not detected in any samples. PAHs were detected in eight of the thirteen samples collected. However, no concentrations of PAHs were above IDEQ Tier 0 cleanup levels. Table 1 shows a summary table of the sample results and a comparison to the Tier 0 cleanup levels.

7.0 Conclusions

Overall the data is useable. Comparing the results with IDEQ Tier 0 cleanup levels show that detected levels of PAHs were orders of magnitude below cleanup levels. Therefore, little or no risk to current or potential future receptors remains at this site.

8.0 References

IDEQ 1997a. Idaho Division of Environmental Quality, *Idaho Risk-Based Corrective Action (RBCA) Cleanup Requirements for Petroleum Releases, Information Series #1*, August 1997.

IDEQ 1997b. Idaho Division of Environmental Quality, *Recommended Practices for Site Assessments, Information Series #3*, August 1997.

USACE 1997, Engineering Manual 200-1-6, *Environmental Quality – Chemical Quality Assurance for Hazardous, Toxic and Radioactive Wastes (HTRW) Projects*. October 1997.

USACE 2001a, Engineering Manual 200-1-3, *Environmental Quality – Requirements for the Preparation of Sampling and Analysis Plans*. February 2001.

USACE 2001b, *Management Plan for Sub-Surface Soil Sampling in Support of Repair Aircraft Parking Apron (Mobility Ramp) project*. June 2001.

Table 1. Summary of Analytical Results

	Sample Results (mg/kg)								IDEQ cleanup levels (mg/kg)*
Sample ID	801MHMR13	801MHMR14 ?	801MHMR16	801MHMR17	801MHMR18	801MHMR19	801MHMR09 ?	801MHMR12 ?	
Sample Location	01CCPA107	01CCPA107	01CCPA109	01CCPA110	01CCPA111	01CCPA111	01CCPA03	01CCPA106	
Analyte									
Benzene	ND(0.0047)	ND(0.0047)	ND (0.0048)	ND (0.0048)	ND (0.0047)	ND (0.0046)	ND (0.0049)	ND (0.0045)	0.06
Toluene	ND(0.0076)	ND(0.0074)	ND (0.0077)	ND (0.0077)	ND (0.0075)	ND (0.0074)	ND (0.0078)	ND (0.0072)	5.4
Ethylbenzene	ND(0.0071)	ND(0.007)	ND (0.0072)	ND (0.0072)	ND (0.007)	ND (0.0069)	ND (0.0073)	ND (0.0067)	10
o-xylene	ND(0.0033)	ND (0.0033)	ND (0.0034)	ND (0.0033)	ND (0.0033)	ND (0.0032)	ND (0.0034)	ND (0.0031)	7
m&p-xylene	ND(0.009)	ND (0.0088)	ND (0.0091)	ND (0.0091)	ND (0.0089)	ND (0.0088)	ND (0.0092)	ND (0.0085)	7
Naphthalene	ND(0.00072)	ND (0.00071)	ND (0.00066)	ND (0.00073)	ND (0.00072)	ND (0.00074)	ND (0.00071)	ND (0.00065)	5.5
2-Methyl naphthalene	ND(0.00024)	ND (0.00024)	ND (0.00022)	ND (0.00024)	ND (0.00024)	ND (0.00025)	ND (0.00024)	ND (0.00022)	NA
2 Chloro naphthalene	ND(0.0046)	ND (0.00045)	ND (0.00042)	ND (0.00047)	ND (0.00046)	ND (0.00047)	ND (0.00046)	ND (0.00042)	NA
Acenaphthene	ND(0.00076)	ND (0.00075)	ND (0.0007)	ND (0.00077)	ND (0.00076)	ND (0.00078)	ND (0.00075)	ND (0.00069)	1.1
Acenaphthylene	ND(0.00067)	ND (0.00066)	ND (0.00062)	ND (0.00068)	ND (0.00067)	ND (0.00069)	ND (0.00066)	ND (0.00061)	NA
Fluorene	ND(0.00072)	ND (0.00071)	ND (0.00066)	ND (0.00073)	ND (0.00072)	ND (0.00074)	ND (0.00071)	ND (0.00065)	4.2
Phenanthrene	0.012	0.005	ND (0.0003)	ND (0.00033)	ND (0.00033)	ND (0.00034)	ND (0.00032)	ND (0.0003)	8.4
Anthacene	0.0038	ND (0.00038)	ND (0.00036)	ND (0.00039)	ND (0.00039)	ND (0.0004)	ND (0.00038)	ND (0.00035)	0.8
Fluoranthene	0.042	0.014	ND (0.00066)	ND (0.00073)	0.0021	ND (0.00074)	ND (0.00071)	ND (0.00065)	4.4
Pyrene	0.018	0.0056	0.0037	ND (0.00033)	0.002	ND (0.00052)	ND (0.0005)	ND (0.00046)	10
Benzo(a) anthracene	0.012	ND (0.00092)	0.0016 J	ND (0.00039)	ND (0.00094)	ND (0.00096)	ND (0.00093)	ND (0.00085)	1.22
Chrysene	0.016	0.0027 J	0.0027 J	ND (0.00073)	ND (0.0009)	ND (0.00093)	ND (0.00089)	ND (0.00082)	0.5
Benzo(b) fluoranthene	0.018	0.003	0.003	ND (0.00051)	0.0041	0.0019	ND (0.00032)	ND (0.0003)	1.22
Benzo(k) fluoranthene	0.0086	0.0017	0.0023	ND (0.00095)	ND (0.00067)	ND (0.00069)	ND (0.00066)	ND (0.00061)	4.4
Benzo(a)pyrene	0.018	ND (0.00089)	0.003	ND (0.00092)	0.0023	ND (0.00093)	ND (0.00089)	ND (0.00082)	0.12
Ideno(1,2,3-cd) pyrene	0.006	ND (0.00035)	0.002	ND (0.00036)	ND (0.00036)	ND (0.00037)	ND (0.00035)	ND (0.00032)	NA
Dibenzo(a,h) anthracene	ND(0.00036)	ND (0.00035)	ND (0.00033)	ND (0.00036)	ND (0.00036)	ND (0.00037)	ND (0.00035)	ND (0.00032)	NA
Benzo(g,h,i) perylene	0.0066	ND (0.00025)	0.003	ND (0.00026)	0.0029	ND (0.00026)	ND (0.00025)	ND (0.00023)	0.4

	Sample Results (mg/kg)					IDEQ cleanup levels (mg/kg)*
Sample ID	801MHMR01	801MHMR02	801MHMR03	801MHMR10	801MHMR11	
Sample Location	01CCPA101	01HTRW2	01HTRW2	01HTRW1	01HTRW1	
Analyte						
Benzene	ND (0.0046)	ND (0.0046)	ND (0.0044)	ND (0.0045)	ND (0.0046)	0.05
Toluene	ND (0.0074)	ND (0.0073)	ND (0.007)	ND (0.0071)	ND (0.0074)	5.4
Ethylbenzene	ND (0.0069)	ND (0.0068)	ND (0.0066)	ND (0.0067)	ND (0.007)	10
m&p-xylene	ND (0.0032)	ND (0.0032)	ND (0.0031)	ND (0.0031)	ND (0.0033)	7
o-xylene	ND (0.0088)	ND (0.0087)	ND (0.0083)	ND (0.0085)	ND (0.0088)	7
Naphthalene	ND (0.00066)	ND (0.0007)	ND (0.00057)	ND (0.00067)	ND (0.00072)	5.5
2-Methyl naphthalene	ND (0.00022)	ND (0.00023)	ND (0.00019)	ND (0.00022)	ND (0.00024)	NA
2-Chloro naphthalene	ND (0.00042)	ND (0.00045)	ND (0.00037)	ND (0.00043)	ND (0.00046)	NA
Acenapthene	ND (0.0007)	ND (0.00074)	ND (0.00061)	ND (0.00071)	ND (0.00077)	1.1
Acenaphthylene	ND (0.00062)	ND (0.00065)	ND (0.00053)	ND (0.00063)	ND (0.00067)	NA
Fluorene	ND (0.00066)	ND (0.0007)	ND (0.00057)	0.0022	ND (0.00072)	4.2
Phenanthrene	0.028	ND (0.00032)	ND (0.00026)	0.036	ND (0.00033)	8.4
Anthracene	0.0075	ND (0.00038)	ND (0.00031)	0.0047	ND (0.00039)	0.8
Fluoranthene	0.1	ND (0.0007)	0.0033	0.11	0.0028	4.4
Pyrene	0.097	ND (0.00049)	0.0027	0.033	0.0026	10
Benzo(a)anthracene	0.041	ND (0.00091)	ND (0.00075)	ND (0.00087)	ND (0.00094)	1.22
Chyrsene	0.052	ND (0.00088)	0.0018 J	0.0096	ND (0.00091)	0.5
Benzo(b)fluoranthene	0.063	ND (0.00032)	0.0022	0.007	0.0022	1.22
Benzo(k)fluoranthene	0.019	ND (0.00065)	ND (0.00053)	0.0036	ND (0.00067)	4.4
Benzo(a)pyrene	0.056	ND (0.00088)	ND (0.00072)	0.0059	ND (0.00091)	0.12
Indeno(1,2,3-cd)pyrene	0.024	ND (0.00035)	ND (0.00028)	ND (0.00033)	ND (0.00036)	NA
Dibenzo(a,h)anthracene	ND (0.00033)	ND (0.00035)	ND (0.00028)	ND (0.00033)	ND (0.00036)	NA
Benzo(g,h,i)perylene	0.033	ND (0.00025)	ND (0.0002)	0.0036	ND (0.00026)	0.4

NOTES:
ND- Not detected (method detection limits shown in parentheses)
NA- No cleanup level available for this analyte
J – Analyte detected but value is an estimated quantity
* - Refers to IDEQ Tier 0 cleanup levels. (IDEQ 1997b)
? - Outside surrogate recoveries

END OF SECTION

This page intentionally blank

SECTION 02220 (A)

DEMOLITION

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

ENGINEERING MANUALS (EM)

EM 385-1-1	(1996) U.S. Army Corps of Engineers Safety and Health Requirements Manual

1.2 GENERAL REQUIREMENTS

The work includes demolition, salvage of identified items and materials, and removal of resulting rubbish and debris. Rubbish and debris shall be removed from Government property daily, unless otherwise directed, to avoid accumulation at the demolition site. Materials that cannot be removed daily shall be stored in areas specified by the Contracting Officer. In the interest of occupational safety and health, the work shall be performed in accordance with EM 385-1-1, Section 23, Demolition, and other applicable Sections. In the interest of conservation, salvage shall be pursued to the maximum extent possible; salvaged items and materials shall be disposed of as specified.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 (AR) SUBMITTAL PROCEDURES:

Product Data

Work Plan; G, RE

The procedures proposed for the accomplishment of the work. The procedures shall provide for safe conduct of the work, including procedures and methods to provide necessary supports, lateral bracing and shoring when required, careful removal and disposition of materials specified to be salvaged, protection of property which is to remain undisturbed, coordination with other work in progress, and timely disconnection of utility services. The procedures shall include a detailed description of the methods and equipment to be used for each operation, and the sequence of operations in accordance with EM 385-1-1.

1.4 DUST CONTROL

The amount of dust resulting from demolition shall be controlled to prevent the spread of dust to occupied portions of the construction site and to avoid creation of a nuisance in the surrounding area. Use of water will not be permitted when it will result in, or create, hazardous or objectionable conditions such as ice, flooding and pollution.

1.5 PROTECTION

1.5.1 Protection of Personnel

During the demolition work the Contractor shall continuously evaluate the condition of the pavement structure being demolished and take immediate action to protect all personnel working in and around the demolition site. No area, section, or other pavement structure will be allowed to be left standing without sufficient bracing, shoring, or lateral support to prevent collapse or failure while workmen remove debris or perform other work in the immediate area.

1.5.3 Protection of Existing Property

Before beginning any demolition work, the Contractor shall survey the site and examine the drawings and specifications to determine the extent of the work. The Contractor shall take necessary precautions to avoid damage to existing items to remain in place, to be reused, or to remain the property of the Government; any damaged items shall be repaired or replaced as approved by the Contracting Officer. The Contractor shall coordinate the work of this section with all other work and shall construct and maintain shoring, bracing, and supports as required. The Contractor shall ensure that pavement structures are not overloaded and shall be responsible for increasing structural supports or adding new supports as may be required as a result of any cutting, removal, or demolition work performed under this contract.

1.5.6 Environmental Protection

The work shall comply with the requirements of Section ~~01410~~01061 ENVIRONMENT PROTECTION.

1.6 BURNING

The use of burning at the project site for the disposal of refuse and debris will not be permitted.

1.7 USE OF EXPLOSIVES

Use of explosives will not be permitted.

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION

3.1 EXISTING STRUCTURES

Existing pavement structures indicated shall be removed as indicated. Sidewalks, curbs, gutters, or other non-pavement items shall be removed as indicated.

3.2 UTILITIES

Existing utilities shall be removed as indicated. When utility lines are encountered that are not indicated on the drawings, the Contracting Officer shall be notified prior to further work in that area.

3.4 DISPOSITION OF MATERIAL

Title to material and equipment to be demolished, except Government salvage and historical items, is vested in the Contractor when the material or equipment is removed from Government property. The Government will not be responsible for the condition, loss or damage to such property after notice to proceed.

3.4.1 Salvageable Items and Material

Contractor shall salvage items and material to the maximum extent possible.

3.4.1.1 Material Salvaged for the Contractor

Material salvaged for the Contractor shall be stored as approved by the Contracting Officer and shall be removed from Government property before completion of the contract. Material salvaged for the Contractor shall not be sold on the site.

3.4.2 Unsalvageable Material

Concrete and other noncombustible material, except concrete permitted to remain in place, shall be disposed of in designated disposal areas as indicated on the contract drawings. The disposal area shall be uniformly graded to drain. Combustible material shall be disposed of off the site.

3.5 CLEAN UP

Debris and rubbish shall be removed from basement and similar excavations. Debris shall be removed and transported in a manner that prevents spillage on streets or adjacent areas. Local regulations regarding hauling and disposal shall apply.

3.6 PAVEMENTS

Existing pavements designated for removal shall be saw cut and removed in accordance with the details shown on the drawings and to the limits and depths indicated on the drawings.

3.6.1 Concrete Pavements

Acceptable methods of concrete pavement removal adjacent to existing concrete pavements to remain shall be as specified in Section 02753 (A), CONCRETE PAVEMENT FOR AIRFIELDS. All other concrete pavement removal methods shall be submitted for approval. The Contractor shall process the demolished concrete pavement for re-use as base course material or recycled concrete pavement material. The processed concrete material shall meet the requirements of either Section 02721 (A) RIGID BASE COURSE or Section 02753 CONCRETE PAVEMENT FOR AIRFIELDS prior to incorporation into the project.

3.6.2 Asphalt Concrete Pavements

All asphalt concrete pavements designated for removal shall be milled in accordance with Section 02964 (A) COLD MILLING OF BITUMINOUS PAVEMENTS. Milled material shall become the property of the Government; delivered and stockpiled by the Contractor in the designated area indicated on the contract drawings.

END OF SECTION

SECTION 02300 (A)

EARTHWORK

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO T 180	(1997) Moisture-Density Relations of Soils Using a 4.54-kg (10-lb) Rammer and an 457 mm (18-in) Drop
AASHTO T 224	(1996) Correction for Coarse Particles in the Soil Compaction Test

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 136	(1996a) Sieve Analysis of Fine and Coarse Aggregates
ASTM D 422	(1963; R 1998) Particle-Size Analysis of Soils
ASTM D 1140	(1997) Amount of Material in Soils Finer than the No. 200 (75-micrometer) Sieve
ASTM D 1556	(1990; R 1996el) Density and Unit Weight of Soil in Place by the Sand-Cone Method
ASTM D 1557	(1991; R 1998) Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/cu. ft. (2,700 kN-m/cu. m.))
ASTM D 2167	(1994) Density and Unit Weight of Soil in Place by the Rubber Balloon Method
ASTM D 2487	(1998) Classification of Soils for Engineering Purposes (Unified Soil Classification System)
ASTM D 2922	(1996el) Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth)
ASTM D 3017	(1988; R 1996el) Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth)
ASTM D 4318	(1998) Liquid Limit, Plastic Limit, and Plasticity Index of Soils

1.2 MEASUREMENT (NOT APPLICABLE)

1.3 PAYMENT (NOT APPLICABLE)

1.4 DEFINITIONS

1.4.1 Satisfactory Materials

Satisfactory materials shall comprise any materials classified by ASTM D 2487 as GW, GP, GP-GM, GW-GM, SW, SP, SW-SM, SP-SM. Satisfactory materials for grading shall be comprised of stones less than 75 mm in any dimension.

1.4.2 Unsatisfactory Materials

Materials which do not comply with the requirements for satisfactory materials are unsatisfactory. Unsatisfactory materials also include man-made fills; trash; refuse; backfills from previous construction; and material classified as satisfactory which contains root and other organic matter or frozen material. The Contracting Officer shall be notified of any contaminated materials.

1.4.3 Cohesionless and Cohesive Materials

Cohesionless materials include materials classified in ASTM D 2487 as GW, GP, SW, and SP. Cohesive materials include materials classified as GC, SC, ML, CL, MH, and CH. Materials classified as GM and SM will be identified as cohesionless only when the fines are nonplastic. Testing required for classifying materials shall be in accordance with ASTM D 4318, ASTM C 136, ASTM D 422, and ASTM D 1140.

1.4.4 Degree of Compaction

Degree of compaction required, except as noted in the second sentence, is expressed as a percentage of the maximum density obtained by the test procedure presented in ASTM D 1557 abbreviated as a percent of laboratory maximum density. Since ASTM D 1557 applies only to soils that have 30 percent or less by weight of their particles retained on the 19.0 mm sieve, the degree of compaction for material having more than 30 percent by weight of their particles retained on the 19.0 mm sieve shall be expressed as a percentage of the maximum density in accordance with AASHTO T 180 Method D and corrected with AASHTO T 224. To maintain the same percentage of coarse material, the "remove and replace" procedure as described in the NOTE 8 in Paragraph 7.2 of AASHTO T 180 shall be used.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Product Data

Earthwork.

Procedure and location for disposal of unused satisfactory material. Proposed source of borrow material.

Notification of encountering rock in the project. Advance notice on the opening of excavation. Advance notice on shoulder construction for rigid pavements.

Test Reports

Testing; G RE

Within 24 hours of conclusion of physical tests, 5 copies of test results, including calibration curves and results of calibration tests.

Certificates

Testing; G RE.

Qualifications of the commercial testing laboratory.

1.6 SUBSURFACE DATA

Subsurface exploration logs are shown on the drawings. These data represent the best subsurface information available; however, variations may exist in the subsurface between exploration locations.

1.7 CLASSIFICATION OF EXCAVATION

Excavation specified shall be be unclassified regardless of the materials encountered.

1.8 BLASTING

Blasting will not be permitted.

1.9 UTILIZATION OF EXCAVATED MATERIALS

Unsatisfactory materials removed from excavations shall be disposed of in the designated disposal areas. Satisfactory material removed from excavations shall be used, insofar as practicable, in the construction of fills, embankments, subgrades, shoulders, bedding, and for similar purposes. No satisfactory excavated material shall be wasted without specific written authorization. Satisfactory material authorized to be wasted shall be disposed of in designated areas approved for surplus material storage or designated waste areas as directed. Newly designated waste areas on Government-controlled land shall be cleared and grubbed before disposal of waste material thereon. No excavated material shall be disposed of to obstruct the flow of any stream, endanger a partly finished structure, impair the efficiency or appearance of any structure, or be detrimental to the completed work in any way.

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION

3.1 STRIPPING OF TOPSOIL (NOT APPLICABLE)

3.2 GENERAL EXCAVATION

The Contractor shall perform excavation of every type of material encountered within the limits of the project to the lines, grades, and elevations indicated and as specified. Grading shall be in conformity with the typical sections shown and the tolerances specified in paragraph FINISHING. Satisfactory excavated materials shall be transported to and placed in fill or embankment within the limits of the work. Unsatisfactory materials encountered within the limits of the work shall be excavated below grade and replaced with satisfactory materials as directed. Such excavated material and the satisfactory material ordered as replacement shall be included in excavation. Surplus satisfactory excavated material not required for fill or embankment shall be disposed of in areas approved for surplus material storage or designated waste areas as directed. Unsatisfactory excavated material shall be disposed of in designated waste or spoil areas. During construction, excavation and fill shall be performed in a manner and sequence that will provide proper drainage at all times. Material required for fill or embankment in excess of that produced by excavation within the grading limits shall be obtained from sources outside the limits of Government-controlled land as directed. Borrow materials shall be subject to approval by the Contracting Officer.

3.2.1 Ditches, Gutters, and Channel Changes

Excavation of ditches, gutters, and channel changes shall be accomplished by cutting accurately to the cross sections, grades, and elevations shown. Ditches and gutters shall not be excavated below grades shown. Excessive open ditch or gutter excavation shall be backfilled with satisfactory, thoroughly compacted, material or with suitable stone or cobble to grades shown. Material excavated shall be disposed of as shown or as directed, except that in no case shall material be deposited less than 1 meter from the edge of a ditch. The Contractor shall maintain excavations free from detrimental quantities of leaves, brush, sticks, trash, and other debris until final acceptance of the work.

3.2.2 Drainage Structures

Excavations shall be made to the lines, grades, and elevations shown, or as directed. Trenches and foundation pits shall be of sufficient size to permit the placement and removal of forms for the full length and width of structure footings and foundations as shown. Rock or other hard foundation material shall be cleaned of loose debris and cut to a firm, level, stepped, or serrated surface. Loose disintegrated rock and thin strata shall be removed. When concrete or masonry is to be placed in an excavated area, the bottom of the excavation shall not be disturbed. Excavation to the final grade level shall not be made until just before the concrete or masonry is to be placed.

3.3 SELECTION OF BORROW MATERIAL

Borrow material shall be selected to meet the requirements and conditions of the particular fill or embankment for which it is to be used. Borrow material shall be obtained from sources outside the limits of Government-controlled land. The Contractor shall obtain from the owners

the right to procure material, pay royalties and other charges involved, and bear the expense of developing the sources, including rights-of-way for hauling.

3.4 GRADING AREAS

Where indicated, work will be divided into grading areas within which satisfactory excavated material shall be placed in embankments, fills, and required backfills. The Contractor shall not haul satisfactory material excavated in one grading area to another grading area except when so directed in writing.

3.5 BACKFILL

Backfill adjacent to any and all types of structures shall be placed and compacted to at least 90 percent laboratory maximum density for cohesive materials or 95 percent laboratory maximum density for cohesionless materials to prevent wedging action or eccentric loading upon or against the structure. Ground surface on which backfill is to be placed shall be prepared as specified in paragraph PREPARATION OF GROUND SURFACE FOR EMBANKMENTS. Compaction requirements for backfill materials shall also conform to the applicable portions of paragraphs PREPARATION OF GROUND SURFACE FOR EMBANKMENTS, EMBANKMENTS, and SUBGRADE PREPARATION and Section 02316 EXCAVATION, TRENCHING, AND BACKFILLING FOR UTILITIES SYSTEMS. Compaction shall be accomplished by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment.

3.6 PREPARATION OF GROUND SURFACE FOR EMBANKMENTS

3.6.1 General Requirements

Ground surface on which fill is to be placed shall be stripped of live, dead, or decayed vegetation, rubbish, debris, and other unsatisfactory material; plowed, disked, or otherwise broken up to a depth of 150 mm; pulverized; moistened or aerated as necessary; thoroughly mixed; and compacted to at least 90 percent laboratory maximum density for cohesive materials or 95 percent laboratory maximum density for cohesionless materials. Compaction shall be accomplished by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment. The prepared ground surface shall be scarified and moistened or aerated as required just prior to placement of embankment materials to assure adequate bond between embankment material and the prepared ground surface.

3.6.2 Frozen Material

Embankment shall not be placed on a foundation which contains frozen material, or which has been subjected to freeze-thaw action. This prohibition encompasses all foundation types, including the natural ground, all prepared subgrades (whether in an excavation or on an embankment) and all layers of previously placed and compacted earth fill which become the foundations for successive layers of earth fill. All material that freezes or has been subjected to freeze-thaw action during the construction work, or during periods of temporary shutdowns, such as, but not limited to, nights, holidays, weekends, winter shutdowns, or earthwork operations, shall be removed to a depth that is acceptable to the Contracting Officer and replaced with new material. Alternatively, the material will be thawed, dried, reworked, and recompacted to the specified criteria before additional material is placed. The Contracting

Officer will determine when placement of fill shall cease due to cold weather. The Contracting Officer may elect to use average daily air temperatures, and/or physical observation of the soils for his determination. Embankment material shall not contain frozen clumps of soil, snow, or ice.

3.6 EMBANKMENTS

3.6.1 Earth Embankments

Earth embankments shall be constructed from satisfactory materials free of organic or frozen material and rocks with any dimension greater than 75 mm. The material shall be placed in successive horizontal layers of loose material not more than 200 millimeters in depth. Each layer shall be spread uniformly on a soil surface that has been moistened or aerated as necessary, and scarified or otherwise broken up so that the fill will bond with the surface on which it is placed. After spreading, each layer shall be plowed, disked, or otherwise broken up; moistened or aerated as necessary; thoroughly mixed; and compacted to at least 90 percent laboratory maximum density for cohesive materials or 95 percent laboratory maximum density for cohesionless materials. Compaction requirements for the upper portion of earth embankments forming subgrade for pavements shall be identical with those requirements specified in paragraph SUBGRADE PREPARATION. Compaction shall be accomplished by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment.

3.6.2 Rock Embankments (NOT APPLICABLE)

3.7 SUBGRADE PREPARATION

3.7.1 Construction

Subgrade shall be shaped to line, grade, and cross section, and compacted as specified. This operation shall include plowing, disking, and any moistening or aerating required to obtain specified compaction to a depth of 300 mm. Soft or otherwise unsatisfactory material shall be removed and replaced with satisfactory excavated material or other approved material as directed. Rock encountered in the cut section shall be excavated to a depth of 150 mm below finished grade for the subgrade. Low areas resulting from removal of unsatisfactory material shall be brought up to required grade with satisfactory materials, and the entire subgrade shall be shaped to line, grade, and cross section and compacted as specified. After rolling, the surface of the subgrade for roadways shall not show deviations greater than 10 millimeters when tested with a 3.66 meter straightedge applied both parallel and at right angles to the centerline of the area. After rolling, the surface of the subgrade for airfields shall not show deviations greater than 10 millimeters when tested with a 3.66 meter straightedge applied both parallel and at right angles to the centerline of the area. The elevation of the finish subgrade shall not vary more than 15 mm from the established grade and cross section.

3.7.2 Compaction

Compaction shall be accomplished by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment.

3.7.2.1 Subgrade for Railroads (NOT APPLICABLE)

3.7.2.2 Subgrade for Pavements

Subgrade for pavements shall be compacted to at least 95 percentage laboratory maximum density. When more than one soil classification is present in the subgrade, the top 150 mm of subgrade shall be scarified, windrowed, thoroughly blended, reshaped, and compacted.

3.7.2.3 Subgrade for Shoulders

Subgrade for shoulders shall be compacted to at least 95 percentage laboratory maximum density for the full depth of the shoulder.

3.8 SHOULDER CONSTRUCTION

Shoulders shall be constructed of satisfactory excavated or borrow material or as otherwise shown or specified. Shoulders shall be constructed as soon as possible after adjacent paving is complete, but in the case of rigid pavements, shoulders shall not be constructed until permission of the Contracting Officer has been obtained. The entire shoulder area shall be compacted to at least the percentage of maximum density as specified in paragraph SUBGRADE PREPARATION above, for specific ranges of depth below the surface of the shoulder. Compaction shall be accomplished by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment. Shoulder construction shall be done in proper sequence in such a manner that adjacent ditches will be drained effectively and that no damage of any kind is done to the adjacent completed pavement. The completed shoulders shall be true to alignment and grade and shaped to drain in conformity with the cross section shown.

3.9 FINISHING

The surface of excavations, embankments, and subgrades shall be finished to a smooth and compact surface in accordance with the lines, grades, and cross sections or elevations shown. The degree of finish for graded areas shall be within 30 mm of the grades and elevations indicated except that the degree of finish for subgrades shall be specified in paragraph SUBGRADE PREPARATION. Gutters and ditches shall be finished in a manner that will result in effective drainage. The surface of areas to be turfed shall be finished to a smoothness suitable for the application of turfing materials.

3.10 PLACING TOPSOIL (NOT APPLICABLE)

3.11 TESTING

Testing shall be performed by an approved commercial testing laboratory. Field in-place density shall be determined in accordance with ASTM D 1556, ASTM D 2167, or ASTM D 2922. When ASTM D 2922 is used, the calibration curves shall be checked and adjusted using only the sand cone method as described in ASTM D 1556. ASTM D 2922results in a wet unit weight of soil and when using this method ASTM D 3017 shall be used to determine the moisture content of the soil. The calibration curves furnished with the moisture gauges shall also be checked along with density calibration checks as described in ASTM D 3017; the calibration checks of both the density and moisture gauges shall be made at the beginning of a job on each different type of material encountered and at intervals as directed

by the Contracting Officer. When test results indicate, as determined by the Contracting Officer, that compaction is not as specified, the material shall be removed, replaced and recompacted to meet specification requirements. Tests on recompacted areas shall be performed to determine conformance with specification requirements. Inspections and test results shall be certified by a registered professional civil engineer. These certifications shall state that the tests and observations were performed by or under the direct supervision of the engineer and that the results are representative of the materials or conditions being certified by the tests. Minimum sampling and testing requirements are in Table 1, SECTION: CONTRACTOR QUALITY CONTROL.

3.11.6 Tolerance Tests for Subgrades

Continuous checks on the degree of finish specified in paragraph SUBGRADE PREPARATION shall be made during construction of the subgrades.

3.12 SUBGRADE AND EMBANKMENT PROTECTION

During construction, embankments and excavations shall be kept shaped and drained. Ditches and drains along subgrade shall be maintained to drain effectively at all times. The finished subgrade shall not be disturbed by traffic or other operation and shall be protected and maintained by the Contractor in a satisfactory condition until base or pavement is placed. The storage or stockpiling of materials on the finished subgrade will not be permitted. No base course or pavement shall be laid until the subgrade has been checked and approved, and in no case shall base or pavement be placed on a muddy, spongy, or frozen subgrade.

END OF SECTION

SECTION 02316 (A)

EXCAVATION, TRENCHING, AND BACKFILLING FOR UTILITIES SYSTEMS

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 1556	(1990; R 1996) Density and Unit Weight of Soil in Place by the Sand-Cone Method
ASTM D 1557	(1998) Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/cu. ft. (2,700 kN-m/cu. m.))
ASTM D 2167	(1994) Density and Unit Weight of Soil in Place by the Rubber Balloon Method
ASTM D 2487	(1998) Classification of Soils for Engineering Purposes (Unified Soil Classification System)
ASTM D 2922	(1996) Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth)
ASTM D 3017	(1988; R1996el) Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth)

1.2 MEASUREMENT AND PAYMENT

Measurement and payment shall be based on completed work performed in accordance with the drawings and specifications.

1.2.1 Rock Excavation

Rock excavation shall be measured and paid for by the number of cubic meters of acceptably excavated rock material. The material shall be measured in place, but volume shall be based on a maximum 750 mm width for pipes 300 mm in diameter or less, and a maximum width of 400 mm greater than the outside diameter of the pipe for pipes over 300 mm in diameter. The measurement shall include all authorized overdepth rock excavation as determined by the Contracting Officer. For manholes and other appurtenances, volumes of rock excavation shall be computed on the basis of 300 mm outside of the wall lines of the structures. Payment for rock excavation will be made in addition to the price bid for the trench excavation, and will include all incidentals necessary to excavate and dispose of the rock. Backfill replacing rock excavation will be paid for separately.

1.3 DEGREE OF COMPACTION

Degree of compaction shall be expressed as a percentage of the maximum density obtained by the test procedure presented in ASTM D 1557.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Test Reports

Field Density Tests; G RE.
Testing of Backfill Materials; G RE.

Copies of all laboratory and field test reports within 24 hours of the completion of the test.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Satisfactory Materials

Satisfactory materials shall comprise any materials classified by ASTM D 2487 as GW, GP, GM, GP-GM, GW-GM, SW, SP, SP-SM.

2.1.2 Unsatisfactory Materials

Materials which do not comply with the requirements for satisfactory materials are unsatisfactory. Unsatisfactory materials also include man-made fills, trash, refuse, or backfills from previous construction. Unsatisfactory material also includes material classified as satisfactory which contains root and other organic matter, frozen material, and stones larger than 75 mm. The Contracting Officer shall be notified of any contaminated materials.

2.1.3 Cohesionless and Cohesive Materials

Cohesionless materials shall include materials classified in ASTM D 2487 as GW, GP, SW, and SP. Cohesive materials shall include materials classified as GC, SC, ML, CL, MH, and CH. Materials classified as GM and SM shall be identified as cohesionless only when the fines are nonplastic.

2.1.4 Rock

Rock shall consist of boulders measuring 1/2 cubic meter or more and materials that cannot be removed with equipment designed for soil excavation purposes such as rock material in ledges, bedded deposits, unstratified masses and conglomerate deposits, and below ground concrete or masonry structures, exceeding 1/2 cubic meter in volume, except that pavements

shall not be considered as rock. Rock that can be ripped and/or dug out using equipment designed for soil excavation purposes will not be classified as rock excavation.

2.1.5 Unyielding Material

Unyielding material shall consist of rock and gravelly soils with stones greater than 75 millimeters in any dimension or as defined by the pipe manufacturer, whichever is smaller.

2.1.6 Unstable Material

Unstable material shall consist of materials too wet to properly support the utility pipe, conduit, or appurtenant structure.

2.1.7 Select Granular Material

Select granular material shall consist of well-graded sand, gravel, crushed gravel, crushed stone or crushed slag composed of hard, tough and durable particles, and shall contain not more than 10 percent by weight of material passing a 0.075 mm mesh sieve and no less than 95 percent by weight passing the 25 mm sieve. The maximum allowable aggregate size shall be 75 millimeters, or the maximum size recommended by the pipe manufacturer, whichever is smaller.

2.1.8 Initial Backfill Material

Initial backfill shall consist of select granular material or satisfactory materials free from rocks 50 millimeters or larger in any dimension or free from rocks of such size as recommended by the pipe manufacturer, whichever is smaller. When the pipe is coated or wrapped for corrosion protection, the initial backfill material shall be free of stones larger than 25 millimeters in any dimension or as recommended by the pipe manufacturer, whichever is smaller.

2.2 PLASTIC MARKING TAPE

Plastic marking tape shall be acid and alkali-resistant polyethylene film, 152 mm wide with minimum thickness of 0.102 mm. Tape shall have a minimum strength of 12.1 MPa (1750 psi) lengthwise and 10.3 MPa (1500 psi) crosswise. A separate tracer wire shall be installed to enable detection by a metal detector when the tape is buried up to 1 meter deep. The tape shall be of a type specifically manufactured for marking and locating underground utilities. The metallic core of the tape shall be encased in a protective jacket or provided with other means to protect it from corrosion. Tape color shall be as specified in TABLE 1 and shall bear a continuous printed inscription describing the specific utility.

TABLE 1. Tape Color

Red:	Electric
Yellow:	Gas, Oil, Dangerous Materials
Orange:	Telephone, Telegraph, Television, Police, and Fire Communications
Blue:	Water Systems
Green:	Sewer Systems

PART 3 EXECUTION

3.1 EXCAVATION

Excavation shall be performed to the lines and grades indicated. Rock excavation shall include removal and disposition of material defined as rock in paragraph MATERIALS. All other remaining excavation shall be unclassified. During excavation, material satisfactory for backfilling shall be stockpiled in an orderly manner at a distance from the banks of the trench equal to 1/2 the depth of the excavation, but in no instance closer than 600 mm. Excavated material not required or not satisfactory for backfill shall be removed from the site and disposed of in the designated disposal or waste areas as directed. Grading shall be done as may be necessary to prevent surface water from flowing into the excavation, and any water accumulating shall be removed to maintain the stability of the bottom and sides of the excavation. Unauthorized overexcavation shall be backfilled in accordance with paragraph BACKFILLING AND COMPACTION at no additional cost to the Government.

3.1.1 Trench Excavation Requirements

The trench shall be excavated as recommended by the manufacturer of the pipe to be installed. Trench walls below the top of the pipe shall be sloped, or made vertical, and of such width as recommended in the manufacturer's installation manual. Where no manufacturer's installation manual is available, trench walls shall be made vertical. Trench walls more than 1.2 meters high shall be shored, cut back to a stable slope, or provided with equivalent means of protection for employees who may be exposed to moving ground or cave in. Trench walls which are cut back shall be excavated to at least the angle of repose of the soil. Special attention shall be given to slopes which may be adversely affected by weather or moisture content. The trench width below the top of pipe shall not exceed 600 mm plus pipe outside diameter (O.D.) for pipes of less than 600 mm inside diameter and shall not exceed 900 mm plus pipe outside diameter for sizes larger than 600 mm inside diameter. Where recommended trench widths are exceeded, redesign, stronger pipe, or special installation procedures shall be utilized by the Contractor. The cost of redesign, stronger pipe, or special installation procedures shall be borne by the Contractor without any additional cost to the Government.

3.1.1.1 Bottom Preparation

The bottoms of trenches shall be accurately graded to provide uniform bearing and support for the bottom quadrant of each section of the pipe. Bell holes shall be excavated to the necessary size at each joint or coupling to eliminate point bearing. Stones of 75 millimeters or greater in any dimension, or as recommended by the pipe manufacturer, whichever is smaller, shall be removed to avoid point bearing.

3.1.1.2 Removal of Unyielding Material

Where overdepth is not indicated and unyielding material is encountered in the bottom of the trench, such material shall be removed 100 millimeters below the required grade and replaced with suitable materials as provided in paragraph BACKFILLING AND COMPACTION.

3.1.1.3 Removal of Unstable Material

Where unstable material is encountered in the bottom of the trench, such material shall be removed to the depth directed and replaced to the proper grade with select granular material as provided in paragraph BACKFILLING AND COMPACTION. When removal of unstable material is required due to the Contractor's fault or neglect in performing the work, the resulting material shall be excavated and replaced by the Contractor without additional cost to the Government.

3.1.1.4 Excavation for Appurtenances

Excavation for manholes, catch-basins, inlets, or similar structures shall be of sufficient size to permit the placement and removal of forms for the full length and width of structure footings and foundations as shown. Rock shall be cleaned of loose debris and cut to a firm surface either level, stepped, or serrated, as shown or as directed. Loose disintegrated rock and thin strata shall be removed. Removal of unstable material shall be as specified above. When concrete or masonry is to be placed in an excavated area, special care shall be taken not to disturb the bottom of the excavation. Excavation to the final grade level shall not be made until just before the concrete or masonry is to be placed.

3.1.1.5 Jacking, Boring, and Tunneling

Unless otherwise indicated, excavation shall be by open cut except that sections of a trench may be jacked, bored, or tunneled if, in the opinion of the Contracting Officer, the pipe, cable, or duct can be safely and properly installed and backfill can be properly compacted in such sections.

3.1.2 Stockpiles

Stockpiles of satisfactory materials shall be placed and graded as specified. Stockpiles shall be kept in a neat and well drained condition, giving due consideration to drainage at all times. The ground surface at stockpile locations shall be cleared, grubbed, and sealed by rubber-tired equipment, excavated satisfactory and unsatisfactory materials shall be separately stockpiled. Stockpiles of satisfactory materials shall be protected from contamination which may destroy the quality and fitness of the stockpiled material. If the Contractor fails to protect the stockpiles, and any material becomes unsatisfactory, such material shall be removed and replaced with satisfactory material from approved sources at no additional cost to the Government. Locations of stockpiles of satisfactory materials shall be subject to prior approval of the Contracting Officer.

3.2 BACKFILLING AND COMPACTION

Backfill material shall consist of satisfactory material, select granular material, or initial backfill material as required. Backfill shall be placed in layers not exceeding 150 mm loose thickness for compaction by hand operated machine compactors, and 200 mm loose thickness for other than hand operated machines, unless otherwise specified. Each layer shall be compacted to at least 95 percent maximum density for cohesionless soils and 90 percent maximum density for cohesive soils, unless otherwise specified.

3.2.1 Trench Backfill

Trenches shall be backfilled to the grade shown. The trench shall be backfilled to 0.6 meters above the top of pipe prior to performing the required pressure tests. The joints and couplings shall be left uncovered during the pressure test. The trench shall not be backfilled until all specified tests are performed.

3.2.1.1 Replacement of Unyielding Material

Unyielding material removed from the bottom of the trench shall be replaced with select granular material or initial backfill material.

3.2.1.2 Replacement of Unstable Material

Unstable material removed from the bottom of the trench or excavation shall be replaced with select granular material placed in layers not exceeding 150 mm loose thickness.

3.2.1.3 Bedding and Initial Backfill

Bedding shall be of the type and thickness shown. Initial backfill material shall be placed and compacted with approved tampers to a height of at least one foot above the utility pipe or conduit. The backfill shall be brought up evenly on both sides of the pipe for the full length of the pipe. Care shall be taken to ensure thorough compaction of the fill under the haunches of the pipe.

3.2.1.4 Final Backfill

The remainder of the trench, except for special materials for roadways and airfields, shall be filled with satisfactory material. Backfill material shall be placed and compacted as follows:

a. Roadways and Airfields: Backfill shall be placed up to the elevation at which the requirements in Section 02300 EARTHWORK control. Water flooding or jetting methods of compaction will not be permitted.

b. Sidewalks, Turfed or Seeded Areas and Miscellaneous Areas: Backfill shall be deposited in layers of a maximum of 300 mm loose thickness, and compacted to 85 percent maximum density for cohesive soils and 90 percent maximum density for cohesionless soils. Compaction by water flooding or jetting will not be permitted. This requirement shall also apply to all other areas not specifically designated above.

3.2.2 Backfill for Appurtenances

After the manhole, catchbasin, inlet, or similar structure has been constructed and the concrete has been allowed to cure for a minimum of 3 days, backfill shall be placed in such a manner that the structure will not be damaged by the shock of falling earth. The backfill material shall be deposited and compacted as specified for final backfill, and shall be brought up evenly on all sides of the structure to prevent eccentric loading and excessive stress.

3.3 SPECIAL REQUIREMENTS

Special requirements for both excavation and backfill relating to the specific utilities are as follows:

3.3.1 Gas Distribution (NOT APPLICABLE)

3.3.2 Water Lines (NOT APPLICABLE)

3.3.3 Heat Distribution System (NOT APPLICABLE)

3.3.4 Electrical Distribution System

Direct burial cable and conduit or duct line shall have a minimum cover of 600 mm from the finished grade, unless otherwise indicated.

3.3.5 Plastic Marking Tape

Warning tapes shall be installed directly above the pipe, at a depth of 450 millimeters below finished grade unless otherwise shown.

3.4 TESTING

Testing shall be the responsibility of the Contractor and shall be performed at no additional cost to the Government.

3.4.1 Testing Facilities

Tests shall be performed by an approved commercial testing laboratory.

3.4.2 Testing of Backfill Materials

Classification of backfill materials shall be determined in accordance with ASTM D 2487 and the moisture-density relations of soils shall be determined in accordance with ASTM D 1557. Minimum sampling and testing requirements are contained in Table 1, SECTION: CONTRACTOR QUALITY CONTROL.

3.4.3 Field Density Tests

Tests shall be performed in sufficient numbers to ensure that the specified density is being obtained. Field in-place density shall be determined in accordance with ASTM D 1556, ASTM D 2167, or ASTM D 2922. When ASTM D 2922 is used, the calibration curves shall be checked and adjusted using the sand cone method as described in paragraph Calibration of the ASTM publication. ASTM D 2922 results in a wet unit weight of soil and when using this method, ASTM D 3017 shall be used to determine the moisture content of the soil. The calibration curves furnished with the moisture gauges shall be checked along with density calibration checks as described in ASTM D 3017. The calibration checks of both the density and moisture gauges shall be made at the beginning of a job, on each different type of material encountered, at intervals as directed by the Contracting Officer. Copies of calibration curves, results of calibration tests, and field and laboratory density tests shall be furnished to the Contracting Officer. Trenches improperly compacted shall be reopened to the depth

directed, then refilled and compacted to the density specified at no additional cost to the Government.

3.4.4 Displacement of Sewers

After other required tests have been performed and the trench backfill compacted to 0.6 meters above the top of the pipe, the pipe shall be inspected to determine whether significant displacement has occurred. This inspection shall be conducted in the presence of the Contracting Officer. Pipe sizes larger than 900 mm shall be entered and examined, while smaller diameter pipe shall be inspected by shining a light or laser between manholes or manhole locations, or by the use of television cameras passed through the pipe. If, in the judgement of the Contracting Officer, the interior of the pipe shows poor alignment or any other defects that would cause improper functioning of the system, the defects shall be remedied as directed at no additional cost to the Government.

END OF SECTION

SECTION 02390 (A)

TIE DOWN POINTS FOR AIRCRAFT

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 436	(1984; R 1997el) Austenitic Gray Iron Castings
ASTM A 615/A 615M	(1996ael) Deformed and Plain Billet-Steel Bars for Concrete Reinforcement
ASTM B 371	(1996) Copper-Zinc-Silicon Alloy Rod

AMERICAN WELDING SOCIETY (AWS)

AWS D1.4	(1998) Structural Welding Code - Reinforcing steel

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 407	(1996) Aircraft Fuel Servicing

UNDERWRITERS LABORATORIES (UL)

UL 467	(1993; Rev thru Apr 1999) Grounding and Bonding Equipment

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Shop Drawings

As-Built Drawings;

Drawings that provide current factual information, including deviations from and amendments to the drawings and changes in the work, concealed and visible.

Test Reports

Tests; G, RE

An independent testing agency's certified reports of inspections and tests, including analysis and interpretation of test results. Each report shall be properly identified. Test methods used and test standards shall be described.

Certificates

Grounding Rods;

Certificate of compliance stating that the grounding rods meet the specified requirements.

Reinforcing Steel;

Certificate of compliance stating that the reinforcing steel meets the specified requirements.

PART 2 PRODUCTS

2.1 METALS

Combination of materials that forms an electrolytic couple, which accelerates corrosion in the presence of moisture, shall not be used, unless moisture is permanently excluded from the junction of such metals.

2.2 GROUNDING RODS

Grounding rods shall conform to UL 467 and shall be made of copper-clad steel. The rods shall be not less than 19 mm (3/4) inch in diameter and not less than 3 m (10) feet long. The copper cladding shall conform to the applicable requirements of ASTM B 371, Copper Alloy UNS No's. c 69400, c 69430, c 69440 or c 69450. The copper cladding shall be not less than 0.25 mm (0.010) inches thick at any point and shall comply with adherence requirements and the banding requirements of UL 467. The Contractor shall submit certificates of compliance on the grounding rods. Rods shall be provided with a closed eye or shepherd's hook bend having an inside diameter of not less than 32 mm. (1-1/4 inches.) The rods shall be pointed unless used for flexible pavement. For flexible pavement, the rods shall have 19 mm (3/4) inch American standard rolled threads for attachment of a bottom anchor and shall be equipped with a screw-type bottom having a wing diameter of not less than 152 mm. (6 inches.)

2.3 CONCRETE

Concrete shall be in accordance with Section 02753 CONCRETE PAVEMENT FOR AIRFIELDS.

PART 3 EXECUTION

3.1 GROUNDING POINTS ITIEDOWN)

The grounding points shall be located as shown on the contract drawings to within plus or minus 50 mm. (2 inches.)

3.1.1 Pavement Recess

The top of the grounding rod shall be set at or not more than 6 mm (1/4 inch) below the pavement surface grade. A recess 70 mm (2-3/4 inches) wide, and not more than 150 mm (6 inches) long, with a smooth rounded edge shall be provided in the pavement around the grounding point anchor eye to permit the entrance of lines into the eye and to allow for attachment of the grounding cable. The depth of the recess shall be no deeper than the bottom of the opening of the grounding point eye.

3.1.2 Installation

3.1.2.1 New Rigid Pavement

The grounding rod shall be installed by pushing, drilling, or driving the rod through the pavement base courses and subgrade, including rock, prior to concrete placement. The installation technique chosen by the Contractor shall not damage the grounding rod. Hand finishing around the rod shall be kept to a minimum.

3.2 TESTS

Resistance to ground tests shall be measured as specified in NFPA 407. Test results shall be submitted to the Contracting Officer. Any ground rods that have more than 10,000 ohms of resistance shall be reported to the contracting officer immediately.

END OF SECTION

This page intentionally blank

SECTION 02721 (A)

RIGID BASE COURSE

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO T 180	(1997) Moisture-Density Relations of Soils Using a 4.54-kg (10-lb) Rammer and an 457-mm (18-in) Drop

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 29/C 29M	(1997) Bulk Density ("Unit Weight") and Voids in Aggregates
ASTM C 117	(1995) Materials Finer Than 75 micrometer (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C 131	(1996) Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine
ASTM C 136	(1996) Sieve Analysis of Fine and Coarse Aggregates
ASTM D 75	(1987; R 1997) Sampling Aggregates
ASTM D 422	(1963; R 1998) Particle-Size Analysis of Soils
ASTM D 1556	(1990; R 1996el) Density and Unit Weight of Soil in Place by the Sand-Cone Method
ASTM D 1557	(1998) Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/cu. ft. (2,700 kN-m/cu.m.))
ASTM D 2167	(1994) Density and Unit Weight of Soil in Place by the Rubber Balloon Method
ASTM D 2487	(1998) Classification of Soils for Engineering Purposes (Unified Soil Classification System)
ASTM D 2922	(1996el) Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth)

ASTM D 3017	(1988; R 1996el) Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth)
ASTM D 4318	(1998) Liquid Limit, Plastic Limit, and Plasticity Index of Soils
ASTM E 11	(1995) Wire-Cloth Sieves for Testing Purposes

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Product Data

Equipment

List of proposed equipment to be used in performance of construction work, including descriptive data.

Waybills and Delivery Tickets

Copies of waybills and delivery tickets during the progress of the work. Certified waybills and delivery tickets for all aggregates actually used.

Test Reports

Sampling and Testing; G, RE

Copies of initial and in-place test results.

1.4 DEGREE OF COMPACTION

Degree of compaction is a percentage of the maximum density obtained by the test procedure presented in ASTM D 1557 or AASHTO T 180, Method D. ASTM D 1557 will be used for maximum density determinations if the anticipated material gradation would contain less than 30% retained on the 19 mm (3/4 inch) sieve. AASHTO T 180, Method D will be used for the maximum density determinations if the anticipated material gradation would contain more than 30% retained on the 19 mm (3/4 inch) sieve. In this specification, degree of compaction shall be a percentage of laboratory maximum density.

1.5 SAMPLING AND TESTING

Sampling and testing shall be the responsibility of the Contractor. Sampling and testing shall be performed by an approved testing laboratory in accordance with Section 01451 CONTRACTOR QUALITY CONTROL. Tests shall be performed at the specified frequency. No work requiring testing will be permitted until the testing laboratory has been inspected and approved. The materials shall be tested to establish compliance with the specified requirements.

1.5.1 Sampling

Samples for laboratory testing shall be taken in conformance with ASTM D 75. When deemed necessary, the sampling will be observed by the Contracting Officer.

1.5.2 Tests

1.5.2.1 Sieve Analysis

Sieve analysis shall be made in conformance with ASTM C 117, ASTM C 136, and ASTM D 422. Sieves shall conform to ASTM E 11.

1.5.2.2 Liquid Limit and Plasticity Index

Liquid limit and plasticity index shall be determined in accordance with ASTM D 4318.

1.5.2.3 Moisture-Density Determinations

The maximum density and optimum moisture shall be determined in accordance with ASTM D 1557 or AASHTO T 180, Method D. ASTM D 1557 will be used for maximum density determinations if the anticipated material gradation would contain less than 30% retained on the 19 mm (3/4 inch) sieve. AASHTO T 180, Method D will be used for the maximum density determinations if the anticipated material gradation would contain more than 30% retained on the 19 mm (3/4 inch) sieve.

1.5.2.4 Density Tests

Density shall be field measured in accordance with ASTM D 2922. ASTM D 2922. The calibration curves shall be checked and adjusted, if necessary, using only the sand cone method as described in paragraph Calibration, of the ASTM publication. Tests performed in accordance with ASTM D 2922 result in a wet unit weight of soil and, when using this method, ASTM D 3017 shall be used to determine the moisture content of the soil. The calibration curves furnished with the moisture gauges shall also be checked along with density calibration checks as described in ASTM D 3017. The calibration checks of both the density and moisture gauges shall be made by the prepared containers of material method, as described in paragraph Calibration, in ASTM D 2922, on each different type of material to be tested at the beginning of a job and at intervals as directed.

1.5.2.5 Wear Test

Wear tests shall be made on rigid base course material in conformance with ASTM C 131.

1.5.3 Testing Frequency

1.5.3.1 Initial Tests

One of each of the following tests shall be performed on the proposed material prior to commencing construction to demonstrate that the proposed material meets all specified requirements prior to installation.

a. Sieve Analysis, including 0.02 mm size material

b. Liquid limit and plasticity index moisture-density relationship
c. Wear

1.5.3.2 In-Place Tests

One of each of the following tests shall be performed on samples taken from the placed and compacted rigid base course. Samples shall be taken for each 1,000 square meters of each layer of material placed in each area.

a. Sieve Analysis, including 0.02 mm size material
b. Field Density
c. Moisture liquid limit and plasticity index

1.5.4 Approval of Material

The source of the material shall be selected 30 days prior to the time the material will be required in the work. Approval of the materials will be based on tests for gradation, liquid limit, and plasticity index performed on samples taken from the completed and compacted rigid base course.

1.6 WEATHER LIMITATIONS

Construction shall be done when the atmospheric temperature is above 2 degrees C. When the temperature falls below 2 degrees C, the Contractor shall protect all completed areas by approved methods against detrimental effects of freezing. Completed areas damaged by freezing, rainfall, or other weather conditions shall be corrected to meet specified requirements.

1.7 EQUIPMENT

All plant, equipment, and tools used in the performance of the work will be subject to approval before the work is started and shall be maintained in satisfactory working condition at all times. The equipment shall be adequate and shall have the capability of producing the required compaction, meeting grade controls, thickness control, and smoothness requirements as set forth herein.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Rigid base Course

Aggregates shall consist of crushed stone, crushed recycled concrete, crushed gravel, sand, or other sound, durable, approved materials processed and blended or naturally combined. Aggregates shall be durable and sound, free from lumps and balls of clay, organic matter, objectionable coatings, and other foreign material. Material retained on the 4.75 mm sieve shall have a percentage of wear not to exceed 50 percent after 500 revolutions when tested as specified in ASTM C 131. Aggregate shall be reasonably uniform in density and quality. Aggregates shall have a maximum size of 50 mm and shall be within the limits specified as follows:

Maximum Allowable Percentage by Weight
Passing Square-Mesh Sieve

Sieve Designation	
2 mm	85
0.075 mm	5

a. Particles having diameters less than 0.02 mm shall not be in excess of 3 percent by weight of the total sample tested as determined in accordance with ASTM D 422. The portion of any blended component and of the completed course passing the 0.425 mm shall be either nonplastic or shall have a liquid limit not greater than 25 and a plasticity index not greater than 5.

b. Crushed recycled concrete shall consist of previously hardened portland cement concrete or other concrete containing pozzolanic binder material. The recycled material shall be free of all reinforcing steel, bituminous concrete surfacing, and any other foreign material and shall be crushed and processed to meet the required gradations for coarse aggregate. Crushed recycled concrete shall meet all other applicable requirements specified below.

PART 3 EXECUTION

3.1 OPERATION OF AGGREGATE SOURCES

All clearing, stripping and excavating work involved in the opening or operation of aggregate sources shall be performed by the Contractor. Aggregate sources shall be opened to working depth in a manner that produces excavation faces that are as nearly vertical as practicable for the materials being excavated. Materials excavated from aggregate sources shall be obtained in successive cuts extending through all exposed strata. All pockets or strata of unsuitable materials overlying or occurring in the deposit shall be wasted as directed. The methods of operating aggregate sources and the processing and blending of the material may be changed or modified by the Contracting Officer, when necessary, in order to obtain material conforming to specified requirements. Upon completion of work, aggregate sources on Government reservations shall be conditioned to drain readily, and shall be left in a satisfactory condition. Aggregate sources on private lands shall be conditioned in agreement with local laws and authorities.

3.2 STOCKPILING MATERIAL

Prior to stockpiling of material, storage sites shall be cleared and leveled by the Contractor. All materials, including approved material available from excavation and grading, shall be stockpiled in the manner and at the locations designated. Aggregates shall be stockpiled on the cleared and leveled areas designated by the Contracting Officer so as to prevent segregation. Materials obtained from different sources shall be stockpiled separately.

3.3 PREPARATION OF UNDERLYING MATERIAL

Prior to constructing the rigid base course, the underlying course or subgrade shall be cleaned of all foreign substances. The surface of the underlying course or subgrade shall meet specified compaction and surface tolerances. Ruts, or soft yielding spots, in the

underlying courses, subgrade areas having inadequate compaction, and deviations of the surface from the specified requirements, shall be corrected by loosening and removing soft or unsatisfactory material and by adding approved material, reshaping to line and grade, and recompacting to specified density requirements. The finished underlying course shall not be disturbed by traffic or other operations and shall be maintained by the Contractor in a satisfactory condition until the rigid base course is placed.

3.4 GRADE CONTROL

The finished and completed rigid base course shall conform to the lines, grades, and cross sections shown. The lines, grades, and cross sections shown shall be maintained by means of line and grade stakes placed by the Contractor at the work site.

3.5 MIXING AND PLACING MATERIALS

The materials shall be mixed and placed to obtain uniformity of the rigid base material at the water content specified. The Contractor shall make such adjustments in mixing or placing procedures or in equipment as may be directed to obtain the true grades, to minimize segregation and degradation, to reduce or accelerate loss or increase of water, and to insure a satisfactory rigid base course.

3.6 LAYER THICKNESS

The compacted thickness of the completed course shall be as indicated. When a compacted layer of 150 mm is specified, the material may be placed in a single layer; when a compacted thickness of more than 150 mm is required, no layer shall exceed 150 mm nor be less than 75 mm when compacted.

3.7 COMPACTION

Each layer of the rigid base course shall be compacted as specified with approved compaction equipment. Water content shall be maintained during the compaction procedure to within plus or minus 2 percent of optimum water content, as determined from laboratory tests, as specified in paragraph SAMPLING AND TESTING. In all places not accessible to the rollers, the mixture shall be compacted with hand-operated power tampers. Compaction shall continue until each layer is compacted through the full depth to at least 100 percent of laboratory maximum density. The Contractor shall make such adjustments in compacting or finishing procedures as may be directed to obtain true grades, to minimize segregation and degradation, to reduce or increase water content, and to ensure a satisfactory rigid base course. Any materials that are found to be unsatisfactory shall be removed and replaced with satisfactory material or reworked, as directed, to meet the requirements of this specification.

3.9 EDGES

Approved material shall be placed along the edges of the rigid base course in such quantity as will compact to the thickness of the course being constructed. When the course is being constructed in two or more layers, at least a 300 mm width of the shoulder shall be rolled and compacted simultaneously with the rolling and compacting of each layer of the rigid base course, as directed.

3.10 SMOOTHNESS TEST

The surface of each layer shall not show deviations in excess of 10 mm when tested with a 3.6 m (12 foot) straightedge applied parallel with and at right angles to the centerline of the area to be paved. Deviations exceeding this amount shall be corrected by removing material, replacing with new material, or reworking existing material and compacting, as directed.

3.11 THICKNESS CONTROL

The completed thickness of the rigid base course shall be in accordance with the thickness and grade indicated on the drawings. The thickness of each course shall be measured at intervals providing at least one measurement for each 400 square meters or part thereof of rigid base course. The thickness measurement shall be made by test holes, at least 75 mm in diameter through the course. The completed rigid base course shall not be more than 13 mm deficient in thickness nor more than 13 mm above or below the established grade. Where any of these tolerances are exceeded, the Contractor shall correct such areas by scarifying, adding new material of proper gradation or removing material, and compacting, as directed. Where the measured thickness is 13 mm or more thicker than shown, the course will be considered as conforming with the specified thickness requirements plus 13 mm. The average job thickness shall be the average of the job measurements as specified above but within 6 mm of the thickness shown.

3.12 MAINTENANCE

The rigid base course shall be maintained in a satisfactory condition until accepted.

END OF SECTION

This page intentionally blank

SECTION 02722 (A)

AGGREGATE BASE COURSE FOR FLEXIBLE PAVEMENT

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO T 180	(1997) Moisture-Density Relations of Soils Using a 4.54-kg (10-lb) Rammer and an 457 mm (18-in) Drop
AASHTO T 224	(1996) Correction for Coarse Particles in the Soil Compaction Test

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 29/C 29M	(1997) Bulk Density ("Unit Weight") and Voids in Aggregates
ASTM C 88	(1999a) Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate
ASTM C 117	(1995) Materials Finer Than 75 micrometer (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C 127	(1988; R 1993el) Specific Gravity and Absorption of Course Aggregate
ASTM C 128	(1997) Specific Gravity and Absorption of Fine Aggregate
ASTM C 131	(1996) Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine
ASTM C 136	(1996a) Sieve Analysis of Fine and Coarse Aggregates
ASTM D 75	(1987; R 1997) Sampling Aggregates
ASTM D 422	(1963; R 1998) Particle-Size Analysis of Soils
ASTM D 1556	(1990; R 1996el) Density and Unit Weight of Soil in Place by the Sand-Cone Method

ASTM D 1557	(1991; R 1998) Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/cu. ft. (2,700 kN-m/cu.m.))
ASTM D 2167	(1994) Density and Unit Weight of Soil in Place by the Rubber Balloon Method
ASTM D 2487	(1998) Classification of Soils for Engineering Purposes (Unified Soil Classification System)
ASTM D 2922	(1996el) Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth)
ASTM D 3017	(1988; R 1996el) Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth)
ASTM D 4318	(1998) Liquid Limit, Plastic Limit, and Plasticity Index of Soils
ASTM E 11	(1995) Wire-Cloth Sieves for Testing Purposes

1.2 DEFINITIONS

For the purposes of this specification, the following definitions apply.

1.2.1 Aggregate Base Course

Aggregate base course (ABC) is well graded, durable aggregate uniformly moistened and mechanically stabilized by compaction.

1.2.3 Degree of Compaction

Degree of compaction required, except as noted in the second sentence, is expressed as a percentage of the maximum density obtained by the test procedure presented in ASTM D 1557 abbreviated as a percent of laboratory maximum density. Since ASTM D 1557 applies only to soils that have 30 percent or less by weight of their particles retained on the 19.0 mm sieve, the degree of compaction for material having more than 30 percent by weight of their particles retained on the 19.0 mm sieve shall be expressed as a percentage of the maximum density in accordance with AASHTO T 180 Method D and corrected with AASHTO T 224. To maintain the same percentage of coarse material, the "remove and replace" procedure as described in the NOTE 8 in Paragraph 7.2 of AASHTO T 180 shall be used.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Product Data

Plant, Equipment, and Tools
List of proposed equipment to be used in performance of construction work, including descriptive data.

Test Reports

Sampling and testing; G, RE
Field Density Tests

Calibration curves and related test results prior to using the device or equipment being calibrated. Copies of field test results within 24 hours after the tests are performed. Certified copies of test results for approval not less than 30 days before material is required for the work.

1.5 SAMPLING AND TESTING

Sampling and testing shall be the responsibility of the Contractor. Sampling and testing shall be performed by a testing laboratory approved in accordance with Section 01451 CONTRACTOR QUALITY CONTROL. Work requiring testing will not be permitted until the testing laboratory has been inspected and approved. The materials shall be tested to establish compliance with the specified requirements; testing shall be performed at the specified frequency. The Contracting Officer may specify the time and location of the tests. Copies of test results shall be furnished to the Contracting Officer within 24 hours of completion of the tests.

1.5.1 Sampling

Samples for laboratory testing shall be taken in conformance with ASTM D 75. When deemed necessary, the sampling will be observed by the Contracting Officer.

1.5.2 Tests

The following tests shall be performed in conformance with the applicable standards listed.

1.5.2.1 Sieve Analysis

Sieve analysis shall be made in conformance with ASTM C 117 and ASTM D 422. Sieves shall conform to ASTM E 11.

1.5.2.2 Liquid Limit and Plasticity Index

Liquid limit and plasticity index shall be determined in accordance with ASTM D 4318.

1.5.2.3 Moisture-Density Determinations

The maximum density and optimum moisture shall be determined in accordance with ASTM D 1557 or AASHTO T 180, Method D. ASTM D 1557 will be used for maximum density determinations if the anticipated material gradation would contain less than 30% retained on the 19 mm (3/4 inch) sieve. AASHTO T 180, Method D will be used for the maximum density

determinations if the anticipated material gradation would contain more than 30% retained on the 19 mm (3/4 inch) sieve.

1.5.2.4 Field Density Tests

Density shall be field measured in accordance with ASTM D 2922. For the method presented in ASTM D 2922 the calibration curves shall be checked and adjusted if necessary using only the sand cone method as described in paragraph Calibration, of the ASTM publication. Tests performed in accordance with ASTM D 2922 result in a wet unit weight of soil and when using this method, ASTM D 3017 shall be used to determine the moisture content of the soil. The calibration curves furnished with the moisture gauges shall also be checked along with density calibration checks as described in ASTM D 3017. The calibration checks of both the density and moisture gauges shall be made by the prepared containers of material method, as described in paragraph Calibration of ASTM D 2922, on each different type of material being tested at the beginning of a job and at intervals as directed.

1.5.2.5 Wear Test

Wear tests shall be made on ABC course material in conformance with ASTM C 131.

Soundness tests shall be made on GCA in accordance with ASTM C 88.

1.5.3 Testing Frequency

1.5.3.1 Initial Tests

One of each of the following tests shall be performed on the proposed material prior to commencing construction to demonstrate that the proposed material meets all specified requirements when furnished. If materials from more than one source are going to be utilized, this testing shall be completed for each source.

a. Sieve Analysis including 0.02 mm size material.

b. Liquid limit and plasticity index moisture-density relationship.

c. Moisture-density relationship.

d. Wear.

1.5.3.2 In Place Tests

One of each of the following tests shall be performed on samples taken from the placed and compacted ABC. Samples shall be taken and tested at the rates indicated.

a. Density tests shall be performed on every lift of material placed and at a frequency of one set of tests for every 250 square meters, or portion thereof, of completed area.

b. Sieve Analysis, including 0.02 mm size material, shall be performed for every 500 metric tons, or portion thereof, of material placed.

c. Liquid limit and plasticity index tests shall be performed at the same frequency as the sieve analysis.

1.5.4 Approval of Material

The source of the material shall be selected 30 days prior to the time the material will be required in the work. Tentative approval of material will be based on initial test results. Final approval of the materials will be based on sieve analysis, liquid limit, and plasticity index tests performed on samples taken from the completed and fully compacted ABC.

1.6 WEATHER LIMITATIONS

Construction shall be done when the atmospheric temperature is above 2 degrees C. When the temperature falls below 2 degrees C, the Contractor shall protect all completed areas by approved methods against detrimental effects of freezing. Completed areas damaged by freezing, rainfall, or other weather conditions shall be corrected to meet specified requirements.

1.7 PLANT, EQUIPMENT, AND TOOLS

All plant, equipment, and tools used in the performance of the work will be subject to approval before the work is started and shall be maintained in satisfactory working condition at all times. The equipment shall be adequate and shall have the capability of producing the required compaction, meeting grade controls, thickness control, and smoothness requirements as set forth herein.

PART 2 PRODUCTS

2.1 AGGREGATES

The ABC shall consist of clean, sound, durable particles of crushed stone, crushed slag, crushed gravel, crushed recycled concrete, angular sand, or other approved material. ABC shall be free of lumps of clay, organic matter, and other objectionable materials or coatings. The portion retained on the 4.75 mm sieve shall be known as coarse aggregate; that portion passing the 4.75 mm sieve shall be known as fine aggregate.

2.1.1 Coarse Aggregate

Coarse aggregates shall be angular particles of uniform density. When the coarse aggregate is supplied from more than one source, aggregate from each source shall meet the specified requirements and shall be stockpiled separately.

a. Crushed Gravel: Crushed gravel shall be manufactured by crushing gravels, and shall meet all the requirements specified below.

b. Crushed Stone: Crushed stone shall consist of freshly mined quarry rock, and shall meet all the requirements specified below.

c. Crushed Recycled Concrete: Crushed recycled concrete shall consist of previously hardened portland cement concrete or other concrete containing pozzolanic binder material. The recycled material shall be free of all reinforcing steel, bituminous concrete surfacing, and

any other foreign material and shall be crushed and processed to meet the required gradations for coarse aggregate. Crushed recycled concrete shall meet all other applicable requirements specified below.

2.1.1.1 Aggregate Base Course

ABC coarse aggregate shall not show more than 50 percent loss when subjected to the Los Angeles abrasion test in accordance with ASTM C 131. The amount of flat and elongated particles shall not exceed 30 percent. A flat particle is one having a ratio of width to thickness greater than 3; an elongated particle is one having a ratio of length to width greater than 3. In the portion retained on each sieve specified, the crushed aggregates shall contain at least 50 percent by weight of crushed pieces having two or more freshly fractured faces with the area of each face being at least equal to 75 percent of the smallest midsectional area of the piece. When two fractures are contiguous, the angle between planes of the fractures must be at least 30 degrees in order to count as two fractured faces. Crushed gravel shall be manufactured from gravel particles 50 percent of which, by weight, are retained on the maximum size sieve listed in TABLE 1.

2.1.2 Fine Aggregate

Fine aggregates shall be angular particles of uniform density. When the fine aggregate is supplied from more than one source, aggregate from each source shall meet the specified requirements.

2.1.2.1 Aggregate Base Course

ABC fine aggregate shall consist of screenings, angular sand, crushed recycled concrete fines, or other finely divided mineral matter processed or naturally combined with the coarse aggregate.

2.1.3 Gradation Requirements

The specified gradation requirements shall apply to the completed base course. The aggregates shall have a maximum size of 25.0 mm and shall be continuously well graded within the limits specified in TABLE 1. Sieves shall conform to ASTM E 11.

TABLE 1. GRADATION OF AGGREGATES

Percentage by Weight Passing Square-Mesh Sieve

Sieve Designation	
25.0 mm	100
12.5 mm	40-70
4.75 mm	20-50
2.00 mm	15-40
0.425 mm	5-25
0.075 mm	0-5

NOTE 1: Particles having diameters less than 0.02 mm shall not be in excess of 3 percent by weight of the total sample tested.

NOTE 2: The values are based on aggregates of uniform specific gravity. If materials from different sources are used for the coarse and fine aggregates, they shall be tested in accordance with ASTM C 127 and ASTM C 128 to determine their specific gravities. If the specific gravities vary by more than 10 percent, the percentages passing the various sieves shall be corrected as directed by the Contracting Officer.

2.1.4 Liquid Limit and Plasticity Index

Liquid limit and plasticity index requirements shall apply to the completed course and shall also apply to any component that is blended to meet the required gradation. The portion of any component or of the completed course passing the 0.425 mm sieve shall be either nonplastic or have a liquid limit not greater than 25 and a plasticity index not greater than 5.

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

When the ABC is constructed in more than one layer, the previously constructed layer shall be cleaned of loose and foreign matter by sweeping with power sweepers or power brooms, except that hand brooms may be used in areas where power cleaning is not practicable. Adequate drainage shall be provided during the entire period of construction to prevent water from collecting or standing on the working area. Line and grade stakes shall be provided as necessary for control. Grade stakes shall be in lines parallel to the centerline of the area under construction and suitably spaced for string lining.

3.2 OPERATION OF AGGREGATE SOURCES

Aggregate sources shall be cleared, stripped and excavated to working depths producing excavation faces that are as nearly vertical as practicable for the materials being excavated. Strata of unsuitable materials overlying or occurring in the deposit shall be wasted. Methods of operating aggregate sources, and the processing and blending of the materials, shall be changed or modified if necessary to obtain material conforming to the specified requirements. Upon completion of the work, aggregate sources shall be conditioned to drain readily and be left in a satisfactory condition. Aggregates may also be obtained from offsite sources.

3.3 STOCKPILING MATERIAL

Prior to stockpiling of material, storage sites shall be cleared and leveled by the Contractor. All materials, including approved material available from excavation and grading, shall be stockpiled in the manner and at the locations designated. Aggregates shall be stockpiled on the cleared and leveled areas designated by the Contracting Officer to prevent segregation. Materials obtained from different sources shall be stockpiled separately.

3.4 PREPARATION OF UNDERLYING COURSE

Prior to constructing the ABC, the underlying course or subgrade shall be cleaned of all foreign substances. At the time of construction of the ABC, the underlying course shall contain no frozen material. The surface of the underlying course or subgrade shall meet

specified compaction and surface tolerances. The underlying course shall conform to Section 02300 EARTHWORK. Ruts or soft yielding spots in the underlying courses, areas having inadequate compaction, and deviations of the surface from the requirements set forth herein shall be corrected by loosening and removing soft or unsatisfactory material and by adding approved material, reshaping to line and grade, and recompacting to specified density requirements. For cohesionless underlying courses containing sands or gravels, as defined in ASTM D 2487, the surface shall be stabilized prior to placement of the ABC. Stabilization shall be accomplished by mixing ABC into the underlying course and compacting by approved methods. The stabilized material shall be considered as part of the underlying course and shall meet all requirements of the underlying course. The finished underlying course shall not be disturbed by traffic or other operations and shall be maintained by the Contractor in a satisfactory condition until the ABC is placed.

3.5 INSTALLATION

3.5.1 Mixing the Materials

The coarse and fine aggregates shall be mixed in a stationary plant, or in a traveling plant or bucket loader on an approved paved working area. The Contractor shall make adjustments in mixing procedures or in equipment as directed to obtain true grades, to minimize segregation or degradation, to obtain the required water content, and to insure a satisfactory ABC meeting all requirements of this specification.

3.5.2 Placing

The mixed material shall be placed on the prepared subgrade in layers of uniform thickness with an approved spreader. When a compacted layer 150 mm or less in thickness is required, the material shall be placed in a single layer. When a compacted layer in excess of 150 mm is required, the material shall be placed in layers of equal thickness. No layer shall exceed 150 mm or less than 75mm when compacted. The layers shall be so placed that when compacted they will be true to the grades or levels required with the least possible surface disturbance. Where the ABC is placed in more than one layer, the previously constructed layers shall be cleaned of loose and foreign matter by sweeping with power sweepers, power brooms, or hand brooms, as directed. Such adjustments in placing procedures or equipment shall be made as may be directed to obtain true grades, to minimize segregation and degradation, to adjust the water content, and to insure an acceptable ABC.

3.5.3 Grade Control

The finished and completed ABC shall conform to the lines, grades, and cross sections shown. Underlying material(s) shall be excavated and prepared at sufficient depth for the required ABC thickness so that the finished ABC with the subsequent surface course will meet the designated grades.

3.5.4 Edges of Base Course

The ABC shall be placed so that the completed section will be a minimum of 1.5 m wider, on all sides, than the next layer that will be placed above it. Additionally, approved fill material shall be placed along the outer edges of ABC in sufficient quantities to compact to the thickness of the course being constructed, or to the thickness of each layer in a multiple layer course, allowing in each operation at least a 600 mm width of this material to be rolled and

compacted simultaneously with rolling and compacting of each layer of ABC. If this base course material is to be placed adjacent to another pavement section, then the layers for both of these sections shall be placed and compacted along this edge at the same time.

3.5.5 Compaction

Each layer of the ABC shall be compacted as specified with approved compaction equipment. Water content shall be maintained during the compaction procedure to within plus or minus 2 percent of the optimum water content determined from laboratory tests as specified in paragraph SAMPLING AND TESTING. Rolling shall begin at the outside edge of the surface and proceed to the center, overlapping on successive trips at least one-half the width of the roller. Alternate trips of the roller shall be slightly different lengths. Speed of the roller shall be such that displacement of the aggregate does not occur. In all places not accessible to the rollers, the mixture shall be compacted with hand-operated power tampers. Compaction shall continue until each layer has a degree of compaction that is at least 100 percent of laboratory maximum density through the full depth of the layer. The Contractor shall make such adjustments in compacting or finishing procedures as may be directed to obtain true grades, to minimize segregation and degradation, to reduce or increase water content, and to ensure a satisfactory ABC. Any materials that are found to be unsatisfactory shall be removed and replaced with satisfactory material or reworked, as directed, to meet the requirements of this specification.

3.5.6 Thickness

Compacted thickness of the aggregate course shall be as indicated. No individual layer shall exceed 200 mm nor be less than 75 mm in compacted thickness. The total compacted thickness of the ABC course shall be within 13 mm of the thickness indicated. Where the measured thickness is more than 13 mm deficient, such areas shall be corrected by scarifying, adding new material of proper gradation, reblading, and recompacting as directed. Where the measured thickness is more than 13 mm thicker than indicated, the course shall be considered as conforming to the specified thickness requirements. Average job thickness shall be the average of all thickness measurements taken for the job, but shall be within 6 mm of the thickness indicated. The total thickness of the ABC course shall be measured at intervals in such a manner as to ensure one measurement for each 500 square meters of base course. Measurements shall be made in 75 mm diameter test holes penetrating the base course.

3.5.8 Finishing

The surface of the top layer of ABC shall be finished after final compaction by cutting any overbuild to grade and rolling with a steel-wheeled roller. Thin layers of material shall not be added to the top layer of base course to meet grade. If the elevation of the top layer of ABC is 13 mm or more below grade, then the top layer should be scarified to a depth of at least 75 mm and new material shall be blended in and compacted to bring to grade. Adjustments to rolling and finishing procedures shall be made as directed to minimize segregation and degradation, obtain grades, maintain moisture content, and insure an acceptable base course. Should the surface become rough, corrugated, uneven in texture, or traffic marked prior to completion, the unsatisfactory portion shall be scarified, reworked and recompacted or it shall be replaced as directed.

3.5.9 Smoothness

The surface of the top layer shall show no deviations in excess of 10 mm when tested with a 3.66 meter straightedge. Measurements shall be taken in successive positions parallel to the centerline of the area to be paved. Measurements shall also be taken perpendicular to the centerline at 15 meter intervals. Deviations exceeding this amount shall be corrected by removing material and replacing with new material, or by reworking existing material and compacting it to meet these specifications.

3.6 TRAFFIC

Completed portions of the ABC course may be opened to limited traffic, provided there is no marring or distorting of the surface by the traffic. Heavy equipment shall not be permitted except when necessary to construction, and then the area shall be protected against marring or damage to the completed work.

3.7 MAINTENANCE

The ABC shall be maintained in a satisfactory condition until the full pavement section is completed and accepted. Maintenance shall include immediate repairs to any defects and shall be repeated as often as necessary to keep the area intact. Any ABC that is not paved over prior to the onset of winter, shall be retested to verify that it still complies with the requirements of this specification. Any area of ABC that is damaged shall be reworked or replaced as necessary to comply with this specification.

3.8 DISPOSAL OF UNSATISFACTORY MATERIALS

Any unsuitable materials that must be removed shall be disposed of in waste disposal areas indicated. No additional payments will be made for materials that must be replaced.

END OF SECTION

SECTION 02741 (A)

HOT-MIX ASPHALT (HMA) FOR ROADS

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO MP 1	(1998)Provisional Specification for Performance Graded Asphalt Binder
AASHTO MP 2	(1998; Interim 1999) Superpave Volumetric Mix Design
AASHTO TP53	(1998; Interim 1999) Determining Asphalt Content of Hot Mix Asphalt by the Ignition Method

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 29/C 29M	(1997) Bulk Density ("Unit Weight") and Voids in Aggregates
ASTM C 88	(1999a) Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate
ASTM C 117	(1995) Materials Finer than 75 micrometer (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C 131	(1996) Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine
ASTM C 136	(1996a) Sieve Analysis of Fine and Coarse Aggregates
ASTM C 566	(1997) Evaporable Total Moisture Content of Aggregate by Drying
ASTM C 1252	(1998) Uncompacted Void Content of Fine Aggregate (as Influenced by Particle Shape, Surface Texture, and Grading)
ASTM D 140	(1998) Sampling Bituminous Materials
ASTM D 242	(1995) Mineral Filler for Bituminous Paving Mixtures

ASTM D 946	(1999) Penetration-Graded Asphalt Cement for Use in Pavement Construction
ASTM D 995	(1995b) Mixing Plants for Hot-Mixed, Hot-Laid Bituminous Paving Mixtures
ASTM D 1461	(1985)) Moisture or Volatile Distillates in Bituminous Paving Mixtures
ASTM D 1559	(1989) Resistance to Plastic Flow of Bituminous Mixtures Using Marshall Apparatus
ASTM D 2041	(1995) Theoretical Maximum Specific Gravity and Density of Bituminous Paving Mixtures
ASTM D 2172	(1995) Quantitative Extraction of Bitumen from Bituminous Paving Mixtures
ASTM D 2419	(1995) Sand Equivalent Value of Soils and Fine Aggregate
ASTM D 2489	(1984; R 1994el) Degree of Particle Coating of Bituminous-Aggregate Mixtures
ASTM D 2726	(1996el) Bulk Specific Gravity and Density of Non-Absorptive Compacted Bituminous Mixture
ASTM D 2950	(1997) Density of Bituminous Concrete in Place by Nuclear Method
ASTM D 3381	(1999) Viscosity-Graded Asphalt Cement for Use in Pavement Construction
ASTM D 3665	(1999) Random Sampling of Construction Materials
ASTM D 3666	(1998) Minimum Requirements for Agencies Testing and Inspecting Bituminous Paving Materials
ASTM D 4125	(1994el)Asphalt Content of Bituminous Mixtures by the Nuclear Method
ASTM D 4791	(1999) Flat Particles, Elongated Particles, or Flat and Elongated Particles in Coarse Aggregate
ASTM D 4867/D 4867M	(1996) Effect of Moisture on Asphalt Concrete Paving Mixtures
ASTM D 5444	(1998) Mechanical Size Analysis of Extracted Aggregate

ASTM D 6307	(1998) Asphalt Content of Hot Mix Asphalt by Ignition Method

ASPHALT INSTITUTE (AI)

AI MS-2	(1997) Mix Design Methods for Asphalt Concrete and Other Hot-Mix Types
AI MS-22	(1998; 2nd Edition) Construction of Hot-Mix Asphalt Pavements

CALIFORNIA DEPARTMENT OF TRANSPORTATION (CDT)

CDT Test 526	(1978) Operation of California Profilograph and Evaluation of Profiles

CORPS OF ENGINEERS (COE)

COE CRD-C 171	(1995) Test Method for Determining Percentage of Crushed Particles in Aggregate

1.2 DESCRIPTION OF WORK

The work shall consist of pavement courses composed of mineral aggregate and asphalt material heated and mixed in a central mixing plant and placed on a prepared course. HMA designed and constructed in accordance with this section shall conform to the lines, grades, thicknesses, and typical cross sections shown on the drawings. Each course shall be constructed to the depth, section, or elevation required by the drawings and shall be rolled, finished, and approved before the placement of the next course.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Product Data

Mix Design; G, RE.

Proposed JMF.

Contractor Quality Control.

Quality control plan.

Test Reports

Aggregates; G, RE.

QC Monitoring.

Aggregate and QC test results.

Certificates

Asphalt Cement Binder; G, RE.

Copies of certified test data.

Testing Laboratory.

Certification of compliance.

Plant Scale Calibration Certification

1.6 ASPHALT MIXING PLANT

Plants used for the preparation of hot-mix asphalt shall conform to the requirements of ASTM D 995 with the following changes:

a. Truck Scales. The asphalt mixture shall be weighed on approved certified scales at the Contractor's expense. Scales shall be inspected and sealed at least annually by an approved calibration laboratory.

b. Testing Facilities. The Contractor shall provide laboratory facilities at the plant for the use of the Government's acceptance testing and the Contractor's quality control testing.

c. Inspection of Plant. The Contracting Officer shall have access at all times, to all areas of the plant for checking adequacy of equipment; inspecting operation of the plant; verifying weights, proportions, and material properties; checking the temperatures maintained in the preparation of the mixtures and for taking samples. The Contractor shall provide assistance as requested, for the Government to procure any desired samples.

d. Storage Bins. Use of storage bins for temporary storage of hot-mix asphalt will be permitted as follows:

(1) The asphalt mixture may be stored in non-insulated storage bins for a period of time not exceeding 3 hours.

(2) The asphalt mixture may be stored in insulated storage bins for a period of time not exceeding 8 hours. The mix drawn from bins shall meet the same requirements as mix loaded directly into trucks.

1.7 HAULING EQUIPMENT

Trucks used for hauling hot-mix asphalt shall have tight, clean, and smooth metal beds. To prevent the mixture from adhering to them, the truck beds shall be lightly coated with a minimum amount of paraffin oil, lime solution, or other approved material. Petroleum based products shall not be used as a release agent. Each truck shall have a suitable cover to protect the mixture from adverse weather. When necessary to ensure that the mixture will be delivered to the site at the specified temperature, truck beds shall be insulated or heated and covers (tarps) shall be securely fastened.

1.8 ASPHALT PAVERS

Asphalt pavers shall be self-propelled, with an activated screed, heated as necessary, and shall be capable of spreading and finishing courses of hot-mix asphalt which will meet the specified thickness, smoothness, and grade. The paver shall have sufficient power to propel itself and the hauling equipment without adversely affecting the finished surface.

1.8.1 Receiving Hopper

The paver shall have a receiving hopper of sufficient capacity to permit a uniform spreading operation. The hopper shall be equipped with a distribution system to place the mixture uniformly in front of the screed without segregation. The screed shall effectively produce a finished surface of the required evenness and texture without tearing, shoving, or gouging the mixture.

1.8.2 Automatic Grade Controls

If an automatic grade control device is used, the paver shall be equipped with a control system capable of automatically maintaining the specified screed elevation. The control system shall be automatically actuated from either a reference line and/or through a system of mechanical sensors or sensor-directed mechanisms or devices which will maintain the paver screed at a predetermined transverse slope and at the proper elevation to obtain the required surface. The transverse slope controller shall be capable of maintaining the screed at the desired slope within plus or minus 0.1 percent. A transverse slope controller shall not be used to control grade. The controls shall be capable of working in conjunction with any of the following attachments:

a. Ski-type device of not less than 9.14 m in length.

b. Taut stringline set to grade.

c. Short ski or shoe for joint matching.

d. Laser control.

1.9 ROLLERS

Rollers shall be in good condition and shall be operated at slow speeds to avoid displacement of the asphalt mixture. The number, type, and weight of rollers shall be sufficient to compact the mixture to the required density while it is still in a workable condition. Equipment which causes excessive crushing of the aggregate shall not be used.

1.10 WEATHER LIMITATIONS

The hot-mix asphalt shall not be placed upon a wet surface or when the surface temperature of the underlying course is less than specified in Table 1. The temperature requirements may be waived by the Contracting Officer, if requested; however, all other requirements, including compaction, shall be met.

Table 1. Surface Temperature Limitations of Underlying Course

Mat Thickness, mm	Degrees C
75 or greater	4
Less than 75	7

PART 2 PRODUCTS

2.1 AGGREGATES

Aggregates shall consist of crushed stone, crushed gravel, crushed slag, screenings, natural sand and mineral filler, as required. The portion of material retained on the 4.75 mm sieve is coarse aggregate. The portion of material passing the 4.75 mm sieve and retained on the 0.075 mm sieve is fine aggregate. The portion passing the 0.075 mm sieve is defined as mineral filler. All aggregate test results and samples shall be submitted to the Contracting Officer at least 14 days prior to start of construction.

2.1.1 Coarse Aggregate

Coarse aggregate shall consist of sound, tough, durable particles, free from films of material that would prevent thorough coating and bonding with the asphalt material and free from organic matter and other deleterious substances. All individual coarse aggregate sources shall meet the following requirements:

a. The percentage of loss shall not be greater than 40 percent after 500 revolutions when tested in accordance with ASTM C 131.

b. The percentage of loss shall not be greater than 18 percent after five cycles when tested in accordance with ASTM C 88 using magnesium sulfate.

c. At least 75 percent by weight of coarse aggregate shall have at least two or more fractured faces when tested in accordance with COE CRD-C 171. Fractured faces shall be produced by crushing.

d. The particle shape shall be essentially cubical and the aggregate shall not contain more than 20% percent, by weight, of flat and elongated particles (3:1 ratio of maximum to minimum) when tested in accordance with ASTM D 4791.

2.1.2 Fine Aggregate

Fine aggregate shall consist of clean, sound, tough, durable particles. The aggregate particles shall be free from coatings of clay, silt, or any objectionable material and shall

contain no clay balls. All individual fine aggregate sources shall have a sand equivalent value not less than 45 when tested in accordance with ASTM D 2419.

The fine aggregate portion of the blended aggregate shall have an uncompacted void content not less than 43.0 percent when tested in accordance with ASTM C 1252 Method A.

2.1.3 Mineral Filler

Mineral filler shall be nonplastic material meeting the requirements of ASTM D 242.

2.1.4 Aggregate Gradation

The combined aggregate gradation shall conform to gradations specified in Table 2, when tested in accordance with ASTM C 136 and ASTM C 117, and shall not vary from the low limit on one sieve to the high limit on the adjacent sieve or vice versa, but grade uniformly from coarse to fine.

Table 2. Aggregate Gradations

Sieve Size, mm	Percent Passing by Mass
19.0	100
12.5	76-96
9.5	69-89
4.75	53-73
2.36	38-60
1.18	26-48
0.60	18-38
0.30	11-27
0.15	6-18
0.075	3-6

2.2 ASPHALT CEMENT BINDER

Asphalt cement binder shall conform to AASHTO MP 1 Performance Grade (PG) 70-28. Test data indicating grade certification shall be provided by the supplier at the time of delivery of each load to the mix plant. Copies of these certifications shall be submitted to the Contracting Officer. The supplier is defined as the last source of any modification to the binder. The Contracting Officer may sample and test the binder at the mix plant at any time before or during mix production. Samples for this verification testing shall be obtained by the Contractor in accordance with ASTM D 140 and in the presence of the Contracting Officer. These samples shall be furnished to the Contracting Officer for the verification testing, which shall be at no cost to the Contractor. Samples of the asphalt cement specified shall be submitted for approval not less than 14 days before start of the test section.

2.3 MIX DESIGN

The Contractor shall develop the mix design. The asphalt mix shall be composed of a mixture of well-graded aggregate, mineral filler if required, and asphalt material. The aggregate fractions shall be sized, handled in separate size groups, and combined in such proportions that the resulting mixture meets the grading requirements of the job mix formula

(JMF). No hot-mix asphalt for payment shall be produced until a JMF has been approved. The hot-mix asphalt shall be designed using procedures contained in AI MS-2 and the criteria shown in Table 3. If the Tensile Strength Ratio (TSR) of the composite mixture, as determined by ASTM D 4867/D 4867M is less than 75, the aggregates shall be rejected or the asphalt mixture treated with an approved anti-stripping agent. The amount of anti-stripping agent added shall be sufficient to produce a TSR of not less than 75. If an antistrip agent is required, it shall be provided by the Contractor at no additional cost. Sufficient materials to produce 90 kg of blended mixture shall be provided to the Contracting Officer for verification of mix design at least 14 days prior to construction of test section.

At the option of the contractor a currently used DOT superpave hot mix may be used in lieu of developing a new hot mix design study as described herein. The superpave volumetric mix shall be designed in accordance with AASHTO MP 2.

2.3.1 JMF Requirements

The job mix formula shall be submitted in writing by the Contractor for approval at least 14 days prior to the start of the test section and shall include as a minimum:

a. Percent passing each sieve size.

b. Percent of asphalt cement.

c. Percent of each aggregate and mineral filler to be used.

d. Asphalt viscosity grade, penetration grade, or performance grade.

e. Number of blows of hammer per side of molded specimen.

f. Laboratory mixing temperature.

g. Lab compaction temperature.

h. Temperature-viscosity relationship of the asphalt cement.

i. Plot of the combined gradation on the 0.45 power gradation chart, stating the nominal maximum size.

j. Graphical plots of stability, flow, air voids, voids in the mineral aggregate, and unit weight versus asphalt content as shown in AI MS-2.

k. Specific gravity and absorption of each aggregate.

l. Percent natural sand.

m. Percent particles with 2 or more fractured faces (in coarse aggregate).

n. Fine aggregate angularity.

o. Percent flat or elongated particles (in coarse aggregate).

p. Tensile Strength Ratio(TSR).

q. Antistrip agent (if required) and amount.

r. List of all modifiers and amount.

s. Percentage and properties (asphalt content, binder properties, and aggregate properties) of reclaimed asphalt pavement (RAP) in accordance with paragraph RECYCLED HOT-MIX ASPHALT, if RAP is used.

Table 3. Marshall Design Criteria

Test Property	75 Blow Mix
Stability, newtons minimum	*8000
Flow, 0.25 mm	8-16
Air voids, percent	3-5
Percent Voids in mineral aggregate (VMA), (minimum)	13.0
TSR, minimum percent	75

* This is a minimum requirement. The average during construction shall be significantly higher than this number to ensure compliance with the specifications.

** Calculate VMA in accordance with AI MS-2, based on ASTM D 2726 bulk specific gravity for the aggregate.

2.3.2 Adjustments to Field JMF

The Laboratory JMF for each mixture shall be in effect until a new formula is approved in writing by the Contracting Officer. Should a change in sources of any materials be made, a new laboratory JMF design shall be performed and a new JMF approved before the new material is used. The Contractor will be allowed to adjust the Laboratory JMF within the limits specified below to optimize mix volumetric properties with the approval of the Contracting Officer. Adjustments to the Laboratory JMF shall be applied to the field (plant) established JMF and limited to those values as shown. Adjustments shall be targeted to produce or nearly produce 4 percent voids total mix (VTM).

TABLE 4. Field (Plant) Established JMF Tolerances

Sieves	Adjustments (plus or minus), percent
12.5 mm	3
4.75 mm	3
2.36 mm	3

0.075 mm	1
Binder Content	0.4

If adjustments are needed that exceed these limits, a new mix design shall be developed. Tolerances given above may permit the aggregate grading to be outside the limits shown in Table 2; while not desirable, this is acceptable.

2.4 RECYCLED HOT MIX ASPHALT

Recycled HMA shall consist of reclaimed asphalt pavement (RAP), coarse aggregate, fine aggregate, mineral filler, and asphalt cement. The RAP shall be of a consistent gradation and asphalt content and properties. When RAP is fed into the plant, the maximum RAP chunk size shall not exceed 50 mm. The recycled HMA mix shall be designed using procedures contained in AI MS-2 and AI MS-22. The job mix shall meet the requirements of paragraph MIX DESIGN. The amount of RAP shall not exceed 30 percent.

2.4.1 RAP Aggregates and Asphalt Cement

The blend of aggregates used in the recycled mix shall meet the requirements of paragraph AGGREGATES. The percentage of asphalt in the RAP shall be established for the mixture design according to ASTM D 2172 using the appropriate dust correction procedure.

2.4.2 RAP Mix

The blend of new asphalt cement and the RAP asphalt binder shall meet the dynamic shear rheometer at high temperature and bending beam at low temperature requirements in paragraph ASPHALT CEMENT BINDER. The virgin asphalt cement shall not be more than two standard asphalt material grades different than that specified in paragraph ASPHALT CEMENT BINDER.

PART 3 EXECUTION

3.1 PREPARATION OF ASPHALT BINDER MATERIAL

The asphalt cement material shall be heated avoiding local overheating and providing a continuous supply of the asphalt material to the mixer at a uniform temperature. The temperature of unmodified asphalts shall be no more than 160 degrees C when added to the aggregates. Modified asphalts shall be no more than 174 degrees C when added to the aggregates.

3.2 PREPARATION OF MINERAL AGGREGATE

The aggregate for the mixture shall be heated and dried prior to mixing. No damage shall occur to the aggregates due to the maximum temperature and rate of heating used. The temperature of the aggregate and mineral filler shall not exceed 175 degrees C when the asphalt cement is added. The temperature shall not be lower than is required to obtain complete coating and uniform distribution on the aggregate particles and to provide a mixture of satisfactory workability.

3.3 PREPARATION OF HOT-MIX ASPHALT MIXTURE

The aggregates and the asphalt cement shall be weighed or metered and introduced into the mixer in the amount specified by the JMF. The combined materials shall be mixed until the aggregate obtains a uniform coating of asphalt binder and is thoroughly distributed throughout the mixture. Wet mixing time shall be the shortest time that will produce a satisfactory mixture, but no less than 25 seconds for batch plants. The wet mixing time for all plants shall be established by the Contractor, based on the procedure for determining the percentage of coated particles described in ASTM D 2489, for each individual plant and for each type of aggregate used. The wet mixing time will be set to at least achieve 95 percent of coated particles. The moisture content of all hot-mix asphalt upon discharge from the plant shall not exceed 0.5 percent by total weight of mixture as measured by ASTM D 1461.

3.4 PREPARATION OF THE UNDERLYING SURFACE

Immediately before placing the hot mix asphalt, the underlying course shall be cleaned of dust and debris. A prime coat and/or tack coat shall be applied in accordance with the contract specifications.

3.6 TESTING LABORATORY

The laboratory used to develop the JMF shall meet the requirements of ASTM D 3666. A certification signed by the manager of the laboratory stating that it meets these requirements or clearly listing all deficiencies shall be submitted to the Contracting Officer prior to the start of construction. The certification shall contain as a minimum:

a. Qualifications of personnel; laboratory manager, supervising technician, and testing technicians.

b. A listing of equipment to be used in developing the job mix.

c. A copy of the laboratory's quality control system.

d. Evidence of participation in the AASHTO Materials Reference Laboratory (AMRL) program.

3.7 TRANSPORTING AND PLACING

3.7.1 Transporting

The hot-mix asphalt shall be transported from the mixing plant to the site in clean, tight vehicles. Deliveries shall be scheduled so that placing and compacting of mixture is uniform with minimum stopping and starting of the paver. Adequate artificial lighting shall be provided for night placements. Hauling over freshly placed material will not be permitted until the material has been compacted as specified, and allowed to cool to 60 degrees C. To deliver mix to the paver, the Contractor shall use a material transfer vehicle which shall be operated to produce continuous forward motion of the paver.

3.7.2 Placing

The mix shall be placed and compacted at a temperature suitable for obtaining density, surface smoothness, and other specified requirements. Upon arrival, the mixture shall be placed to the full width by an asphalt paver; it shall be struck off in a uniform layer of such depth that, when the work is completed, it shall have the required thickness and conform to the grade and contour indicated. The speed of the paver shall be regulated to eliminate pulling and tearing of the asphalt mat. Unless otherwise permitted, placement of the mixture shall begin along the centerline of a crowned section or on the high side of areas with a one-way slope. The mixture shall be placed in consecutive adjacent strips having a minimum width of 3 m. The longitudinal joint in one course shall offset the longitudinal joint in the course immediately below by at least 300 mm; however, the joint in the surface course shall be at the centerline of the pavement. Transverse joints in one course shall be offset by at least 3 m from transverse joints in the previous course. Transverse joints in adjacent lanes shall be offset a minimum of 3 m. On isolated areas where irregularities or unavoidable obstacles make the use of mechanical spreading and finishing equipment impractical, the mixture may be spread and luted by hand tools.

3.8 COMPACTION OF MIXTURE

After placing, the mixture shall be thoroughly and uniformly compacted by rolling. The surface shall be compacted as soon as possible without causing displacement, cracking or shoving. The sequence of rolling operations and the type of rollers used shall be at the discretion of the Contractor. The speed of the roller shall, at all times, be sufficiently slow to avoid displacement of the hot mixture and be effective in compaction. Any displacement occurring as a result of reversing the direction of the roller, or from any other cause, shall be corrected at once. Sufficient rollers shall be furnished to handle the output of the plant. Rolling shall continue until the surface is of uniform texture, true to grade and cross section, and the required field density is obtained. To prevent adhesion of the mixture to the roller, the wheels shall be kept properly moistened but excessive water will not be permitted. In areas not accessible to the roller, the mixture shall be thoroughly compacted with hand tampers. Any mixture that becomes loose and broken, mixed with dirt, contains check-cracking, or is in any way defective shall be removed full depth, replaced with fresh hot mixture and immediately compacted to conform to the surrounding area. This work shall be done at the Contractor's expense. Skin patching will not be allowed.

3.9 JOINTS

The formation of joints shall be made ensuring a continuous bond between the courses and to obtain the required density. All joints shall have the same texture as other sections of the course and meet the requirements for smoothness and grade.

3.9.1 Transverse Joints

The roller shall not pass over the unprotected end of the freshly laid mixture, except when necessary to form a transverse joint. When necessary to form a transverse joint, it shall be made by means of placing a bulkhead or by tapering the course. The tapered edge shall be cut back to its full depth and width on a straight line to expose a vertical face prior to placing material at the joint . The cutback material shall be removed from the project. In both methods, all contact surfaces shall be given a light tack coat of asphalt material before placing any fresh mixture against the joint.

3.9.2 Longitudinal Joints

Longitudinal joints which are irregular, damaged, uncompacted, cold (less than 80 degrees C at the time of placing adjacent lanes), or otherwise defective, shall be cut back a minimum of 50 mm from the edge with a cutting wheel to expose a clean, sound vertical surface for the full depth of the course. All cutback material shall be removed from the project. All contact surfaces shall be given a light tack coat of asphalt material prior to placing any fresh mixture against the joint. The Contractor will be allowed to use an alternate method if it can be demonstrated that density, smoothness, and texture can be met.

3.10 CONTRACTOR QUALITY CONTROL

3.10.1 General Quality Control Requirements

The Contractor shall develop an approved Quality Control Plan. Hot-mix asphalt for payment shall not be produced until the quality control plan has been approved. The plan shall address all elements which affect the quality of the pavement including, but not limited to:

a. Mix Design

b. Aggregate Grading

c. Quality of Materials

d. Stockpile Management

e. Proportioning

f. Mixing and Transportation

g. Mixture Volumetrics

h. Moisture Content of Mixtures

i. Placing and Finishing

j. Joints

k. Compaction

l. Surface Smoothness

3.10.2 Testing Laboratory

The Contractor shall attain the services of a fully equipped, commercially-approved, independent material testing laboratory. The laboratory shall meet the requirements as required in ASTM D 3666. The effective working area of the laboratory shall be a minimum of 14 square meters with a ceiling height of not less than 2.3 m. Lighting shall be adequate to illuminate all working areas. It shall be equipped with heating and air conditioning units to maintain a temperature of 24 degrees C plus or minus 2.3 degrees C. Laboratory facilities shall be kept clean and all equipment shall be maintained in proper working condition. The

Contracting Officer shall be permitted unrestricted access to inspect the Contractor's laboratory facility, to witness quality control activities, and to perform any check testing desired. The Contracting Officer will advise the Contractor in writing of any noted deficiencies concerning the laboratory facility, equipment, supplies, or testing personnel and procedures. When the deficiencies are serious enough to adversely affect test results, the incorporation of the materials into the work shall be suspended immediately and will not be permitted to resume until the deficiencies are corrected.

3.10.3 Quality Control Testing

The Contractor shall perform all quality control tests applicable to these specifications and as set forth in the Quality Control Program. The testing program shall include, but shall not be limited to, tests for the control of asphalt content, aggregate gradation, temperatures, aggregate moisture, moisture in the asphalt mixture, laboratory air voids, stability, flow, in-place density, grade and smoothness. A Quality Control Testing Plan shall be developed as part of the Quality Control Program.

3.10.3.1 Asphalt Content

A minimum of two tests to determine asphalt content will be performed per lot (a lot is defined in paragraph MATERIAL ACCEPTANCE) by one of the following methods: the extraction method in accordance with ASTM D 2172, Method A or B, the ignition method in accordance with the AASHTO TP53or ASTM D 6307, or the nuclear method in accordance with ASTM D 4125, provided the nuclear gauge is calibrated for the specific mix being used. For the extraction method, the weight of ash, as described in ASTM D 2172, shall be determined as part of the first extraction test performed at the beginning of plant production; and as part of every tenth extraction test performed thereafter, for the duration of plant production. The last weight of ash value obtained shall be used in the calculation of the asphalt content for the mixture.

3.10.3.2 Gradation

Aggregate gradations shall be determined a minimum of twice per lot from mechanical analysis of recovered aggregate in accordance with ASTM D 5444. When asphalt content is determined by the nuclear method, aggregate gradation shall be determined from hot bin samples on batch plants, or from the cold feed on drum mix plants. For batch plants, aggregates shall be tested in accordance with ASTM C 136 using actual batch weights to determine the combined aggregate gradation of the mixture.

3.10.3.3 Temperatures

Temperatures shall be checked at least four times per lot, at necessary locations, to determine the temperature at the dryer, the asphalt cement in the storage tank, the asphalt mixture at the plant, and the asphalt mixture at the job site.

3.10.3.4 Aggregate Moisture

The moisture content of aggregate used for production shall be determined a minimum of once per lot in accordance with ASTM C 566.

3.10.3.5 Moisture Content of Mixture

The moisture content of the mixture shall be determined at least once per lot in accordance with ASTM D 1461 or an approved alternate procedure.

3.10.3.6 Laboratory Air Voids, Marshall Stability and Flow

Mixture samples shall be taken at least four times per lot and compacted into specimens, using 75 blows per side with the Marshall hammer as described in ASTM D 1559. After compaction, the laboratory air voids of each specimen shall be determined, as well as the Marshall stability and flow.

3.10.3.7 In-Place Density

The Contractor shall conduct any necessary testing to ensure the specified density is achieved. A nuclear gauge may be used to monitor pavement density in accordance with ASTM D 2950.

3.10.3.8 Grade and Smoothness

The Contractor shall conduct the necessary checks to ensure the grade and smoothness requirements are met in accordance with paragraph MATERIAL ACCEPTANCE.

3.10.3.9 Additional Testing

Any additional testing, which the Contractor deems necessary to control the process, may be performed at the Contractor's option.

3.10.3.10 QC Monitoring

The Contractor shall submit all QC test results to the Contracting Officer on a daily basis as the tests are performed. The Contracting Officer reserves the right to monitor any of the Contractor's quality control testing and to perform duplicate testing as a check to the Contractor's quality control testing.

3.10.4 Sampling

When directed by the Contracting Officer, the Contractor shall sample and test any material which appears inconsistent with similar material being produced, unless such material is voluntarily removed and replaced or deficiencies corrected by the Contractor. All sampling shall be in accordance with standard procedures specified.

3.11 MATERIAL ACCEPTANCE

Testing for acceptability of work will be performed by an independent materials testing laboratory hired by the Contractor. Test results shall be forwarded daily to the Contracting Officer. Acceptance of the plant produced mix and in-place requirements will be on a lot to lot basis. A standard lot for all requirements will be equal to 8 hours of production. Where appropriate, acceptance for individual lots of hot-mix asphalt will be made based on in-place density, laboratory air voids, grade and smoothness in accordance with the following paragraphs. Grade and surface smoothness determinations will be made on the lot as a

whole. Exceptions or adjustments to this will be made in situations where the mix within one lot is placed as part of both the intermediate and surface courses, thus grade and smoothness measurements for the entire lot cannot be made. In order to evaluate laboratory air voids and in-place (field) density, each lot will be divided into four equal sublots.

3.11.1 Lot Acceptance

When a lot of material fails to meet the specification requirements as outlined in the following paragraphs, that lot shall be removed and replaced, or corrected as described below, at no additional cost to the Government.

3.11.2 Sublot Sampling

One random mixture sample for determining laboratory air voids, theoretical maximum density, and for any additional testing the Contracting Officer desires, will be taken from a loaded truck delivering mixture to each sublot, or other appropriate location for each sublot. All samples will be selected randomly, using commonly recognized methods of assuring randomness conforming to ASTM D 3665 and employing tables of random numbers or computer programs. Laboratory air voids will be determined from three laboratory compacted specimens of each sublot sample in accordance with ASTM D 1559. The specimens will be compacted within 2 hours of the time the mixture was loaded into trucks at the asphalt plant. Samples will not be reheated prior to compaction and insulated containers will be used as necessary to maintain the temperature.

3.11.3 Additional Sampling and Testing

The Contracting Officer reserves the right to direct additional samples and tests for any area which appears to deviate from the specification requirements. The cost of any additional testing will be paid for by the Government. Testing in these areas will be in addition to the lot testing, and the requirements for these areas will be the same as those for a lot.

3.11.4 Laboratory Air Voids

Laboratory air voids will be calculated by determining the Marshall density of each lab compacted specimen using ASTM D 2726 and determining the theoretical maximum density of every other sublot sample using ASTM D 2041. Laboratory air void calculations for each sublot will use the latest theoretical maximum density values obtained, either for that sublot or the previous sublot. The mean absolute deviation of the four laboratory air void contents (one from each sublot) from the JMF air void content will be evaluated as follows and acceptance determined from Table 5. All laboratory air void tests will be completed and reported within 24 hours after completion of construction of each lot.

3.11.5 Mean Absolute Deviation

An example of the computation of mean absolute deviation for laboratory air voids is as follows: Assume that the laboratory air voids are determined from 4 random samples of a lot (where 3 specimens were compacted from each sample). The average laboratory air voids for each sublot sample are determined to be 3.5, 3.0, 4.0, and 3.7. Assume that the target air voids from the JMF is 4.0. The mean absolute deviation is then:

Mean Absolute Deviation = (|3.5 - 4.0| + |3.0 - 4.0| + |4.0 - 4.0| + |3.7 - 4.0|/4

= (0.5 + 1.0 + 0.0 + 0.3)/4 = (1.8)/4 = 0.45

The mean absolute deviation for laboratory air voids is determined to be 0.45. It can be seen from Table 7 that the lot is accepted based on laboratory air voids.

Table 5. Acceptance Based on Laboratory Air Voids

Mean Absolute Deviation of Lab Air Voids from JMF	
O.60 or less	Accept
0.61 or above	Reject

3.11.6 In-place Density

3.11.6.1 General Density Requirements

For determining in-place density, one random core will be taken by the Contractor from the mat (interior of the lane) of each sublot, and one random core will be taken from the joint (immediately over joint) of each sublot. Each random core will be full thickness of the layer being placed. When the random core is less than 25 mm thick, it will not be included in the analysis. In this case, another random core will be taken. After air drying to a constant weight, cores obtained from the mat and from the joints will be used for in-place density determination.

3.11.6.2 Mat and Joint Densities

The average in-place mat and joint densities are expressed as a percentage of the average Marshall density for the lot. The Marshall density for each lot will be determined as the average Marshall density of the four random samples (3 specimens compacted per sample). The average in-place mat density and joint density for a lot are determined and compared with Table 6 for acceptance based on in-place density, as described below. Acceptance for both mat density and joint density are determined from Table 6.

Table 6. Acceptance Based on In-place Density

Average Mat Density (4 Cores)		Average Joint Density (4 Cores)
97.9 to 100	Accept	96.4 and above
97.8 and below, or 100.1 and above	Reject	96.3 and below

3.11.7 Grade

The final wearing surface of pavement shall conform to the elevations and cross sections shown and shall vary not more than 15 mm from the plan grade established and approved at site of work. Finished surfaces at juncture with other pavements shall coincide with finished surfaces of abutting pavements. Deviation from the plan elevation will not be permitted in

areas of pavements where closer conformance with planned elevation is required for the proper functioning of drainage and other appurtenant structures involved. The final wearing surface of the pavement will be tested for conformance with specified plan grade requirements. The grade will be determined by running lines of levels at intervals of 7.6 m, or less, longitudinally and transversely, to determine the elevation of the completed pavement surface. Within 5 working days, after the completion of a particular lot incorporating the final wearing surface, the Contracting Officer will inform the Contractor in writing, of the results of the grade-conformance tests. When more than 5 percent of all measurements made within a lot are outside the 15 mm tolerance, or where the grade exceeds the tolerance by more than 50 percent, the Contractor shall remove the surface lift full depth; the Contractor shall then replace the lift with hot-mix asphalt to meet specification requirements, at no additional cost to the Government. Diamond grinding may be used to remove high spots to meet grade requirements. Skin patching for correcting low areas or planing or milling for correcting high areas will not be permitted.

3.11.8 Surface Smoothness

The Contractor shall use the straightedge testing method to test and evaluate surface smoothness of the pavement. All testing shall be performed in the presence of the Contracting Officer. Detailed notes of the results of the testing shall be kept and a copy furnished to the Government immediately after each day's testing. Where drawings show required deviations from a plane surface (crowns, drainage inlets, etc.), the surface shall be finished to meet the approval of the Contracting Officer.

3.11.8.1 Smoothness Requirements

a. Straightedge Testing: The finished surfaces of the pavements shall have no abrupt change of 6 mm or more, and all pavements shall be within the tolerances specified in Table 7 when checked with an approved 4 m straightedge.

Table 7. Straightedge Surface Smoothness--Pavements

Pavement Category	Direction of Testing	Tolerance, mm
All paved areas	Longitudinal	6
	Transverse	6

3.11.8.2 Testing Method

After the final rolling, but not later than 24 hours after placement, the surface of the pavement in each entire lot shall be tested by the Contractor in such a manner as to reveal all surface irregularities exceeding the tolerances specified above. Separate testing of individual sublots is not required. If any pavement areas are ground, these areas shall be retested immediately after grinding. The entire area of the pavement shall be tested in both a longitudinal and a transverse direction on parallel lines. The transverse lines shall be 8 m or less apart, as directed. The longitudinal lines shall be at the centerline of each paving lane for lines less than 6.1 m and at the third points for lanes 6.1 m or greater. Other areas having obvious deviations shall also be tested. Longitudinal testing lines shall be continuous across all joints.

a. Straightedge Testing. The straightedge shall be held in contact with the surface and moved ahead one-half the length of the straightedge for each successive measurement. The

amount of surface irregularity shall be determined by placing the freestanding (unleveled) straightedge on the pavement surface and allowing it to rest upon the two highest spots covered by its length, and measuring the maximum gap between the straightedge and the pavement surface in the area between these two high points.

3.11.8.3 Acceptance for Smoothness

a. Straightedge Testing. Location and deviation from straightedge for all measurements shall be recorded. When between 5.0 and 10.0 percent of all measurements made within a lot exceed the tolerance specified in paragraph Smoothness Requirements above, after any reduction of high spots or removal and replacement, that lot will be rejected and removed and replaced at no additional cost to the Government. Regardless of the above, any small individual area with surface deviation which exceeds the tolerance given above by more than 50 percent, shall be corrected by diamond grinding to meet the specification requirements above or shall be removed and replaced at no additional cost to the Government.

END OF SECTION

This page intentionally blank

SECTION 02748 (A)

BITUMINOUS TACK AND PRIME COATS

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO M 20	(1970; R 1996) Penetration Graded Asphalt Cement
AASHTO M 81	(1992; R 1996) Cut-Back Asphalt (Rapid-Curing Type)
AASHTO M 82	(1975; R 1996) Cut-Back Asphalt (Medium-Curing Type)
AASHTO M 226	(1980; R 1996) Viscosity Graded Asphalt Cement
AASHTO T 40	(1978; R 1996) Sampling Bituminous Materials

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 140	(200) Sampling Bituminous Materials
ASTM D 946	(1982; R 1999) Penetration-Graded Asphalt Cement for Use in Pavement Construction
ASTM D 977	(1998) Emulsified Asphalt
ASTM D 1250	(1980; R 1997el) Petroleum Measurement Tables
ASTM D 2026	(1972; R 1997) Cutback Asphalt (Slow-Curing Type)
ASTM D 2027	(1976; R 1997) Cutback Asphalt (Medium-Curing Type)
ASTM D 2028	(1976; R 1997) Cutback Asphalt (Rapid-Curing Type)
ASTM D 2397	(1998) Cationic Emulsified Asphalt
ASTM D 2995	(1999) Determining Application Rate of Bituminous Distributors
ASTM D 3381	(1992; R 1999) Viscosity-Graded Asphalt Cement for Use in Pavement Construction

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Test Reports

Sampling and Testing

Copies of all test results for bituminous materials, within 24 hours of completion of tests. Certified copies of the manufacturer's test reports indicating compliance with applicable specified requirements, not less than 30 days before the material is required in the work.

1.4 PLANT, EQUIPMENT, MACHINES AND TOOLS

1.4.1 General Requirements

Plant, equipment, machines and tools used in the work shall be subject to approval and shall be maintained in a satisfactory working condition at all times.

1.4.2 Bituminous Distributor

The distributor shall have pneumatic tires of such size and number to prevent rutting, shoving or otherwise damaging the base surface or other layers in the pavement structure. The distributor shall be designed and equipped to spray the bituminous material in a uniform coverage at the specified temperature, at readily determined and controlled rates with an allowable variation from the specified rate of not more than plus or minus 5 percent, and at variable widths. Distributor equipment shall include a separate power unit for the bitumen pump, full-circulation spray bars, tachometer, pressure gauges, volume-measuring devices, adequate heaters for heating of materials to the proper application temperature, a thermometer for reading the temperature of tank contents, and a hand hose attachment suitable for applying bituminous material manually to areas inaccessible to the distributor. The distributor shall be equipped to circulate and agitate the bituminous material during the heating process.

1.4.3 Power Brooms and Power Blowers

Power brooms and power blowers shall be suitable for cleaning the surfaces to which the bituminous coat is to be applied.

1.5 WEATHER LIMITATIONS

Bituminous coat shall be applied only when the surface to receive the bituminous coat is dry. Bituminous coat shall be applied only when the atmospheric temperature in the shade is 10 degrees C or above and when the temperature has not been below 2 degrees C for the 12 hours prior to application.

PART 2 PRODUCTS

2.1 TACK COAT

Emulsified asphalt shall conform to ASTM D 977 or ASTM D 2397, Grade SS-1, SS-1h, CSS-1, or CSS-1h.

2.2 PRIME COAT

Emulsified asphalt shall conform to ASTM D 977 or ASTM D 2397, Grades SS-1, SS-1h, CSS-1, or CSS-1h.

PART 3 EXECUTION

3.1 PREPARATION OF SURFACE

Immediately before applying the bituminous coat, all loose material, dirt, clay, or other objectionable material shall be removed from the surface to be treated. The surface shall be dry and clean at the time of treatment.

3.2 APPLICATION RATE

The exact quantities within the range specified, which may be varied to suit field conditions, will be determined by the Contracting Officer.

3.2.1 Tack Coat

Bituminous material for the tack coat shall be applied in quantities of not less than 0.20 liter nor more than 0.70 liter per square meter of pavement surface.

3.2.2 Prime Coat

Bituminous material for the prime coat shall be applied in quantities of not less than 0.70 liter nor more than 1.80 liters per square meter of pavement surface.

3.3 APPLICATION TEMPERATURE

3.3.1 Viscosity Relationship

Asphalt application temperature shall provide an application viscosity between 10 and 60 seconds, Saybolt Furol, or between 20 and 120 square mm/sec, kinematic. The temperature viscosity relation shall be furnished to the Contracting Officer.

3.3.2 Temperature Ranges

The viscosity requirements shall determine the application temperature to be used. The following is a normal range of application temperatures:

Emulsions

SS-1	20-70 degrees C
SS-1h	20-70 degrees C
CSS-1	20-70 degrees C
CSS-1h	20-70 degrees C

*These temperature ranges exceed the flash point of the material and care should be taken in their heating.

3.4 APPLICATION

3.4.1 General

Following preparation and subsequent inspection of the surface, the bituminous coat shall be applied at the specified rate with uniform distribution over the surface to be treated. All areas and spots missed by the distributor shall be properly treated with the hand spray. Until the succeeding layer of pavement is placed, the surface shall be maintained by protecting the surface against damage and by repairing deficient areas at no additional cost to the Government. If required, clean dry sand shall be spread to effectively blot up any excess bituminous material. No smoking, fires, or flames other than those from the heaters that are a part of the equipment shall be permitted within 8 meters of heating, distributing, and transferring operations of bituminous material other than bituminous emulsions. All traffic, except for paving equipment used in constructing the surfacing, shall be prevented from using the underlying material, whether primed or not, until the surfacing is completed. The bituminous coat shall conform to all requirements as described herein.

3.4.2 Prime Coat

The prime coat will be required if it will be at least seven days before a the surfacing (Asphalt cement hot mix concrete)layer is constructed on the underlying (base course, etc)compacted material. The type of liquid asphalt and application rate will be as specified herein. The Contractor shall protect the underlying from any damage (water, traffic, etc.) until the surfacing is placed. If the Contractor places the surfacing within seven days, the choice of protection measures or actions to be taken is at the Contractor's option. Damage to the underlying material caused by lack of, or inadequate, protection shall be repaired (recompacted or replaced) by approved methods at no additional cost to the Government. If the Contractor options to use the prime coat, it shall be applied as soon as possible after consolidation of the underlying material. To obtain uniform application of the prime coat on the surface treated at the junction of previous and subsequent applications, building paper shall be spread on the surface for a sufficient distance back from the ends of each application to start and stop the prime coat on the paper. Immediately after application, the building paper shall be removed and destroyed.

3.4.3 Tack Coat

Tack coat shall be applied at the locations shown on the drawings.

3.5 CURING PERIOD

Following application of the bituminous material and prior to application of the succeeding layer of pavement, the bituminous coat shall be allowed to cure and to obtain evaporation of any volatiles or moisture. Prime coat shall be allowed to cure without being disturbed for a period of at least 48 hours or longer, as may be necessary to attain penetration into the treated course.

3.6 FIELD QUALITY CONTROL

Samples of the bituminous material used shall be obtained by the Contractor as directed, under the supervision of the Contracting Officer. The sample may be retained and tested by the Government at no cost to the Contractor.

3.7 SAMPLING AND TESTING

Sampling and testing shall be performed by an approved commercial testing laboratory or by facilities furnished by the Contractor. No work requiring testing will be permitted until the facilities have been inspected and approved.

3.7.1 Sampling

The samples of bituminous material, unless otherwise specified, shall be in accordance with ASTM D 140 or AASHTO T 40. Sources from which bituminous materials are to be obtained shall be selected and notification furnished the Contracting Officer within 15 days after the award of the contract.

3.7.2 Calibration Test

The Contractor shall furnish all equipment, materials, and labor necessary to calibrate the bituminous distributor. Calibration shall be made with the approved job material and prior to applying the bituminous coat material to the prepared surface. Calibration of the bituminous distributor shall be in accordance with ASTM D 2995.

3.7.3 Trial Applications

Before providing the complete bituminous coat, three lengths of at least 30 meters for the full width of the distributor bar shall be applied to evaluate the amount of bituminous material that can be satisfactorily applied.

3.7.3.1 Tack Coat Trial Application Rate

Unless otherwise authorized, the trial application rate of bituminous tack coat materials shall be applied in the amount of 0.20 liters per square meter. Other trial applications shall be made using various amounts of material as may be deemed necessary.

3.7.3.2 Prime Coat Trial Application Rate

Unless otherwise authorized, the trial application rate of bituminous materials shall be applied in the amount of 1.10 liters per square meter. Other trial applications shall be made using various amounts of material as may be deemed necessary.

3.7.4 Sampling and Testing During Construction

Quality control sampling and testing shall be performed as required in paragraph FIELD QUALITY CONTROL.

END OF SECTION

SECTION 02753 (A)

CONCRETE PAVEMENT FOR AIRFIELDS

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

ACI INTERNATIONAL (ACI)

ACI 211.1	(1991) Standard Practice for Selecting Proportions for Normal, Heavyweight, and Mass Concrete
ACI 214.3R	(1988) Simplified Version of the Recommended Practice for Evaluation of Strength Test Results of Concrete
ACI 305R	(1991) Hot Weather Concreting

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO M 182	(1991; R 1996) Burlap Cloth Made from Jute or Kenaf

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 53	(1999b) Pipe, Steel, Black and Hot-Dipped, Zinc-Coated Welded and Seamless
ASTM A 184/A 184M	(1996) Fabricated Deformed Steel Bar Mats for Concrete Reinforcement
ASTM A 185	(1997) Steel Welded Wire Fabric, Plain, for Concrete Reinforcement
ASTM A 497	(1997) Steel Welded Wire Fabric, Deformed, for Concrete Reinforcement
ASTM A 615/A 615M	(1996a) Deformed and Plain Billet-Steel Bars for Concrete Reinforcement
ASTM A 616/A 616M	(1996a) Rail-Steel Deformed and Plain Bars for Concrete Reinforcement
ASTM A 617/A 617M	(1996a) Axle-Steel Deformed and Plain Bars for Concrete Reinforcement

ASTM C 29/C 29M	(1997) Bulk Density ("Unit Weight") and Voids in Aggregate
ASTM C 31/C 31M	(1998) Making and Curing Concrete Test Specimens in the Field
ASTM C 33	(1999a) Concrete Aggregates
ASTM C 39	(1996) Compressive Strength of Cylindrical Concrete Specimens
ASTM C 78	(1994) Flexural Strength of Concrete (Using Simple Beam with Third-Point Loading)
ASTM C 94/C 94M	(1999el) Ready-Mixed Concrete
ASTM C 117	(1995) Materials Finer Than 75 micrometer (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C 123	(1998) Lightweight Particles in Aggregate
ASTM C 131	(1996) Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine
ASTM C 136	(1996a) Sieve Analysis of Fine and Coarse Aggregates
ASTM C 142	(1978; R 1997) Clay Lumps and Friable Particles in Aggregates
ASTM C 143	(1998) Slump of Hydraulic Cement Concrete
ASTM C 150	(1999a) Portland Cement
ASTM C 171	(1997a) Sheet Materials for Curing Concrete
ASTM C 172	(1999) Sampling Freshly Mixed Concrete
ASTM C 174/C 174M	(1997) Measuring Thickness of Concrete Elements Using Drilled Concrete Cores
ASTM C 192/C 192M	(1998) Making and Curing Concrete Test Specimens in the Laboratory
ASTM C 231	(1997el) Air Content of Freshly Mixed Concrete by the Pressure Method
ASTM C 260	(1998) Air-Entraining Admixtures for Concrete
ASTM C 295	(1998) Petrographic Examination of Aggregates for Concrete

ASTM C 330	(1999) Lightweight Aggregates for Structural Concrete
ASTM C 470/C 470M	(1998) Molds for Forming Concrete Test Cylinders Vertically
ASTM C 494	(1999) Chemical Admixtures for Concrete
ASTM C 595	(1998) Blended Hydraulic Cements
ASTM C 595M	(1997) Blended Hydraulic Cements (Metric)
ASTM C 618	(1999) Coal Fly Ash and Raw or Calcined Natural Pozzolan for Use as a Mineral Admixture in Concrete
ASTM C 881	(1999) Epoxy-Resin-Base Bonding Systems for Concrete
ASTM C 989	(1999) Ground Granulated Blast-Furnace Slag for Use in Concrete and Mortars
ASTM C 1064/C 1064M	(1999) Temperature of Freshly Mixed Portland Cement Concrete
ASTM C 1077	(1998) Laboratories Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Laboratory Evaluation
ASTM C 1240	(1999) Silica Fume for Use as a Mineral Admixture in Hydraulic-Cement Concrete, Mortar and Grout
ASTM C 1260	(1994) Potential Alkali Reactivity of Aggregates (Mortar Bar Method)
ASTM D 449	(1989; R 1999el) Asphalt Used in Dampproofing and Waterproofing
ASTM D 946	(1999) Penetration-Graded Asphalt Cement for Use in Pavement Construction
ASTM D 1227	(1995) Emulsified Asphalt Used as a Protective Coating for Roofing
ASTM D 1751	(1999) Preformed Expansion Joint Filler for Concrete Paving and Structural Construction (Nonextruding and Resilient Bituminous Types)
ASTM D 1752	(1984; R 1996el) Preformed Sponge Rubber and Cork Expansion Joint Fillers for Concrete Paving and Structural Construction

ASTM D 3665	(1999) Random Sampling of Construction Materials

CALIFORNIA DEPARTMENT OF TRANSPORTATION (CDT)

CDT Test 526	(1978) Operation of California Profilograph and Evaluation of Profiles

CORPS OF ENGINEERS (COE)

COE CRD-C 55	(1992) Test Method for Within-Batch Uniformity of Freshly Mixed Concrete
COE CRD-C 100	(1975) Method of Sampling Concrete Aggregate and Aggregate Sources, and Selection of Material for Testing
COE CRD-C 104	(1980) Method of Calculation of the Fineness Modulus of Aggregate
COE CRD-C 114	(1997) Test Method for Soundness of Aggregates by Freezing and Thawing of Concrete Specimens
COE CRD-C 119	(1991) Standard Test Method for Flat or Elongated Particles in Coarse Aggregate
COE CRD-C 130	(1989) Scratch Hardness of Coarse Aggregates Particles
COE CRD-C 143	(1962) Specifications for Meters for Automatic Indication of Moisture in Fine Aggregate
COE CRD-C 171	(1995) Test Method for Determining Percentage of Crushed Particles in Aggregate
COE CRD-C 300	(1990) Specifications for Membrane-Forming Compounds for Curing Concrete
COE CRD-C 400	(1963) Requirements for Water for Use in Mixing or Curing Concrete
COE CRD-C 521	(1981) Standard Test Method for Frequency and Amplitude of Vibrators for Concrete
COE CRD-C 540	(1971; R 1981) Standard Specification for Nonbituminous Inserts for Contraction Joints in Portland Cement Concrete Airfield Pavements, Sawable Type
COE CRD-C 572	(1974) Corps of Engineers Specifications for Polyvinylchloride Waterstop

DEPARTMENT OF DEFENSE

MIL-DTL-24441/20A	(1999) Paint, Epoxy-Polyamide, Green Primer, Formula 150, Type III

NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY (NIST)

NIST HB 44	(1997) NIST Handbook 44: Specifications, Tolerances, and Other Technical Requirements for Weighing and Measuring Devices

NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY (NIST)

NIST HB 44	(1997) NIST Handbook 44: Specifications, Tolerances, and Other Technical Requirements for Weighing and Measuring Devices

NATIONAL READY-MIXED CONCRETE ASSOCIATION (NRMCA)

NRMCA CPMB 100	(1996) Concrete Plant Standards

1.2 SYSTEM DESCRIPTION

This section is intended to stand alone for construction of concrete (rigid) pavement. However, where the construction covered herein interfaces with other sections, the construction at each interface shall conform to the requirements of both this section and the other section, including tolerances for both.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Product Data

Equipment

a. Details and data on the batching and mixing plant prior to plant assembly including manufacturer's literature showing that the equipment meets all requirements specified herein.

b. A description of the equipment proposed for transporting concrete mixture from the central mixing plant to the paving equipment at least 7 days prior to start of paving unless otherwise specified.

c. At the time the materials are furnished for the mixture proportioning study, a description of the equipment proposed for the placing of the concrete mixture, method of control, and manufacturer's literature on the paver and finisher, together with the manufacturer's written instructions on adjustments and operating

procedures necessary to assure a tight, smooth surface on the concrete pavement, free of tears and other surface imperfections, including excessive paste on the surface. The literature shall show that the equipment meets all details of these specifications.

Proposed Techniques; G, RE

a. A description of the placing and protection methods proposed prior to construction of the test section, if concrete is to be placed in or exposed to hot or cold weather conditions.

b. A detailed plan of the proposed paving pattern showing all planned construction joints. No deviation from the jointing pattern shown on the drawings shall be made without written approval of the Seattle District, Design Branch, Civil/Soils Section.

c. Data on the curing media and methods to be used.

Samples for Mixture Proportioning Studies; G, RE

The results of the Contractor's mixture proportioning studies along with a statement giving the maximum nominal coarse aggregate size and the proportions of all ingredients that will be used in the manufacture of concrete at least 14 days prior to commencing concrete placing operations. Aggregate quantities shall be based on the mass in a saturated surface dry condition. The statement shall be accompanied by test results from an independent commercial testing laboratory, inspected by the Government, and approved in writing, showing that mixture proportioning studies have been made with materials proposed for the project and that the proportions selected will produce concrete of the qualities indicated. No substitutions shall be made in the materials used in the mixture proportions without additional tests to show that the quality of the concrete is satisfactory.

Delivery, Storage, and Handling of Materials

Copies of waybills or delivery tickets for cementitious material during the progress of the work. Before the final payment is allowed, waybills and certified delivery tickets shall be furnished for all cementitious material used in the construction.

Test Reports

Sampling and Testing; G, RE

Certified copies of laboratory test reports, including all test data, for cement, pozzolan, aggregate, admixtures, and curing compound proposed for use on this project. These tests shall be made by an approved commercial laboratory or by a laboratory maintained by the manufacturers of the materials. No material shall be used until notice of acceptance has been given. Materials may be subjected to check testing by the Government from samples obtained at the manufacturer, at transfer points, or at the project site.

1.4 MEASUREMENT AND PAYMENT

1.4.1 Measurements

1.4.1.1 Concrete

The quantity of concrete to be paid for will be the volume of concrete in cubic meters including monolithic curb, where required, placed in the completed and accepted pavement. Concrete will be measured in place in the completed and accepted pavement only within the neat line dimensions shown in the plan and cross section. No deductions will be made for rounded or beveled edges or the space occupied by pavement reinforcement, dowel bars, tie bars, or electrical conduits, nor for any void, or other structure extending into or through the pavement slab, measuring 0.1 cubic meter or less in volume. No other allowance for concrete will be made unless placed in specified locations in accordance with written instructions previously issued by the Contracting Officer.

1.4.1.2 Mixture Proportions By Contractor

The Contractor shall be responsible for the mixture proportions of cementitious materials and chemical admixtures; no separate measurement or payment will be made for any cementitious material, including pozzolan, or for any chemical admixture.

1.4.1.5 Dowels

The quantity of dowels and tie bars used in the work will not be measured for payment but will be considered as a subsidiary obligation of the Contractor, covered under the price per cubic meter for concrete.

1.4.1.6 Joint Materials

The quantity of expansion joint filler, slip joint filler, and inserts for contraction joints will not be measured for payment but will be considered as a subsidiary obligation of the Contractor, covered under the price per cubic meter for concrete. Joint sealing materials are covered in Section 02760 FIELD MOLDED SEALANTS FOR SEALING JOINTS IN RIGID PAVEMENTS or Section 02762 COMPRESSION JOINT SEALS FOR CONCRETE PAVEMENTS.

1.4.2 Payments

1.4.2.1 Concrete

The quantity of concrete measured as specified above will be paid for at the contract unit price when placed in completed and accepted pavements. Payment shall be made at the contract price for cubic meter for the scheduled item, with necessary adjustments as specified in paragraph ACCEPTABILITY OF WORK AND PAYMENT ADJUSTMENTS. Payment will constitute full compensation for furnishing all materials, equipment, plant and tools, and for all labor and other incidentals necessary to complete the concrete pavement, except for other items specified herein for separate payment.

1.5 ACCEPTABILITY OF WORK AND PAYMENT ADJUSTMENTS

Concrete samples shall be taken by the Contractor in the field to determine the slump, air content, and strength of the concrete. Test beams and test cylinders shall be made for determining conformance with the strength requirements of these specifications and, when required, for determining the time at which pavements may be placed into service. Any pavement not meeting the requirement for 'specified strength' shall be removed and replaced at no additional cost to the Government. The air content shall be determined in accordance with ASTM C 231. Slump tests shall be made in accordance with ASTM C 143. Test beams and cylinders shall be molded and cured in accordance with ASTM C 31/C 31Mand as specified below. Steel molds shall be used for molding the beams specimens. Molds for cylinder test specimens shall conform to ASTM C 470/C 470M. The Contractor shall furnish all materials, labor, and facilities required for molding, curing, testing, and protecting test specimens at the site and in the laboratory. Laboratory curing facilities for test specimens shall include furnishing and operating water tanks equipped with temperature-control devices that will automatically maintain the temperature of the water at 23 plus or minus 3 degrees C. The Contractor shall furnish and maintain at the site boxes or other facilities suitable for storing the specimens while in the mold at a temperature of 23 plus or minus 6 degrees C. Tests of the fresh concrete and of the hardened concrete specimens shall be made by and at the expense of the Contractor.

1.5.1 Pavement Lots

Appropriate adjustment in payment for individual lots of concrete pavement will be made in accordance with the following paragraphs. No such adjustment in payment will be made for any material other than concrete. A lot will be that quantity of construction that will be evaluated for compliance with specification requirements. A lot will be equal to ~~one shift, but not exceeding~~ 10 hours of production for any individual paving machine. If more than one paving machine is used at the same time, then each machine will have it's own lots. In order to evaluate thickness, each lot will be divided into four equal sublots. However, the lot size shall not exceed 750 cubic meters of concrete pavement. Grade and surface smoothness (and condition) determinations will be made on the lot as a whole. However, any pavement not meeting the required 'specified strength' shall be removed and replaced at no additional cost to the Government. Strength will be evaluated, but will not be considered for payment adjustment. Edge slump requirements will be applied to each individual slab into which the primary paving lanes are divided by transverse joints, and will not be considered for payment adjustment. Samples for determining aggregate grading for fine aggregate and each size of coarse aggregate shall be taken as the aggregate bins discharge into the weigh hoppers. Results of tests on aggregates shall be used to control aggregate production and concreting operations, as specified in paragraph TESTING AND INSPECTION FOR CONTRACTOR QUALITY CONTROL, but will not be used for payment adjustment. Samples for determining air content and slump and for fabricating strength specimens shall be taken in accordance with ASTM C 172 during or immediately following delivery of the concrete at the paving site and deposition of the concrete immediately in front of the paver or transfer spreader. Results of strength tests shall be used to control concreting operations, but will not be used for payment adjustment. Cores for thickness determination shall be drilled and evaluated as specified. Location of all samples shall be as directed and will be deliberately selected on a truly random basis, not haphazard, using commonly recognized methods of assuring randomness, employing randomizing tables or computer programs, in accordance with ASTM D 3665.

1.5.2 Acceptance of Lots

When a lot of material fails to meet the specification requirements, that lot will be accepted at a reduced price or shall be removed and replaced. The lowest computed percent payment determined for any pavement characteristic (i.e., thickness, grade, and surface smoothness) discussed below shall be the actual percent payment for that lot. The actual percent payment will be applied to the bid price and the quantity of concrete placed in the lot to determine actual payment.

1.5.3 Evaluation

The Contractor shall provide facilities for and, where directed, personnel to assist in obtaining samples for any Government testing, all at no additional cost to the Government. Such testing will in no way relieve the Contractor of any specified testing responsibilities. The Contractor shall provide all sampling and testing required for acceptance and payment adjustment at its expense. Such sampling and testing shall be performed by a commercial testing laboratory inspected by the Government and approved in writing. The laboratory performing the tests shall be on-site and shall conform with ASTM C 1077. The individuals who sample and test concrete or the constituents of concrete as required in this specification shall be certified as American Concrete Institute (ACI) Concrete Field Testing Technicians, Grade I, or shall have otherwise demonstrated to the satisfaction of the Contracting Officer other training providing knowledge and ability equivalent to the ACI minimum requirements for certification. The individuals who perform the inspection of concrete shall be certified as ACI Concrete Construction Inspector, Level II, or have otherwise demonstrated to the satisfaction of the Contracting Officer other training providing knowledge and ability equivalent to the ACI minimum requirements for certification. The Government will inspect the laboratory, equipment, and test procedures prior to start of concreting operations and at least once per year thereafter for conformance with ASTM C 1077.

1.5.4 Additional Sampling and Testing

The Contracting Officer reserves the right to direct additional samples and tests for any area which appears to deviate from the specification requirements. Testing in these areas will be in addition to the sublot or lot testing, and the requirements for these areas will be the same as those for a sublot or lot, but shall be at no additional cost to the Government.

1.5.5 Air Content Tests

Air content of the concrete shall be controlled as specified in paragraph TESTING AND INSPECTION FOR CONTRACTOR QUALITY CONTROL and will not be considered for payment adjustment.

1.5.6 Slump Tests

Slump of the concrete shall be controlled as specified in paragraph TESTING AND INSPECTION FOR CONTRACTOR QUALITY CONTROL and will not be considered for payment adjustment.

1.5.7 Surface Smoothness

The Contractor shall use both of the following methods to test and evaluate surface smoothness of the pavement. All testing shall be performed in the presence of the Contracting Officer's representative. Detailed notes shall be kept of the results of the testing and a copy furnished to the Government immediately after each day's testing. The profilograph method shall be used for all longitudinal and transverse testing, except where the runs would be less than 60 m in length and at the ends where the straightedge shall be used. Where drawings show required deviations from a plane surface (crowns, drainage inlets, etc.), the surface shall be finished to meet the approval of the Contracting Officer.

1.5.7.1 Smoothness Requirements

a. Straightedge Testing: The finished surfaces of the pavements shall have no abrupt change of 3 mm or more, and all pavements shall be within the limits specified in Table 1 when checked with an approved 4 m straightedge.

TABLE 1
STRAIGHTEDGE SURFACE SMOOTHNESS--PAVEMENTS

Pavement Category	Direction of Testing	Limits mm
Aprons and Taxiways	Longitudinal	3
	Transverse	6

b. Profilograph Testing: The finished surfaces of the pavements shall have no abrupt change of 3 mm or more, and all pavement shall have a Profile Index not greater than specified in Table 2 when tested with an approved California-type profilograph. If the extent of the pavement in either direction is less than 60 m, that direction shall be tested by the straightedge method and shall meet requirements specified for such.

TABLE 2
PROFILOGRAPH SURFACE SMOOTHNESS--PAVEMENTS

Pavement Category	Direction of Testing	Maximum Specified Profile Index mm per km
Aprons and Taxiways	Longitudinal	110
	Transverse	(Use Straightedge)

1.5.7.2 Testing Method

After the concrete has hardened sufficiently to permit walking thereon, but not later than 36 hours after placement, the surface of the pavement in each entire lot shall be tested by the Contractor in such a manner as to reveal all surface irregularities exceeding the tolerances specified above. However, transverse profilograph testing of multiple paving lanes shall be performed at the timing directed. Separate testing of individual sublots is not required. If any pavement areas are ground, these areas shall be retested immediately after grinding. The entire area of the pavement shall be tested in both a longitudinal and a transverse direction on parallel lines. The transverse lines shall be 4.5 m or less apart, as directed. The

longitudinal lines shall be at the centerline of each paving lane shown on the drawings, regardless of whether the Contractor is allowed to pave two lanes at a time, and at the 1/8th point in from each side of the lane. Other areas having obvious deviations shall also be tested. Longitudinal testing lines shall be continuous across all joints. Transverse testing lines for pilot lanes shall be carried to construction joint lines and for fill-in lanes shall be carried 600 mm across construction joints, and the readings in this area applied to the fill-in lane. Straightedge testing of the longitudinal edges of slipformed pilot lanes shall also be performed before paving fill-in lanes as specified in paragraph "Edge Slump and Joint Face Deformation".

a. Straightedge Testing: The straightedge shall be held in contact with the surface and moved ahead one-half the length of the straightedge for each successive measurement. The amount of surface irregularity shall be determined by placing the freestanding (unleveled) straightedge on the pavement surface and allowing it to rest upon the two highest spots covered by its length and measuring the maximum gap between the straightedge and the pavement surface, in the area between these two high points.

b. Profilograph Testing: Profilograph testing shall be performed using approved equipment and procedures described in CDT Test 526. The equipment shall utilize electronic recording and automatic computerized reduction of data to indicate "must-grind" bumps and the Profile Index for the pavement. The "blanking band" shall be 5 mm wide and the "bump template" shall span 25 mm with an offset of 10 mm. The profilograph shall be operated by an approved, factory-trained operator on the alignments specified above. A copy of the reduced tapes shall be furnished the Government at the end of each day's testing.

1.5.7.3 Payment Adjustment for Smoothness

a. Straightedge Testing: Location and deviation from straightedge for all measurements shall be recorded. When between 5.0 and 10.0 percent and less than 15.0 percent of all measurements made within a lot exceed the tolerance specified in paragraph "Smoothness Requirements" above, after any reduction of high spots or removal and replacement, the computed percent payment based on surface smoothness will be 95 percent. When more than 10.0 percent and less than 15.0 percent of all measurements exceed the tolerance, the computed percent payment will be 90 percent. When between 15.0 and 20.0 percent of all measurements exceed the tolerance, the computed percent payment will be 75 percent. When 20.0 percent or more of the measurements exceed the tolerance, the lot shall be removed and replaced at no additional cost to the Government. Regardless of the above, any small individual area with surface deviation which exceeds the tolerance given above by more than 50 percent shall be corrected by grinding to meet the specification requirements above or shall be removed and replaced at no additional cost to the Government.

b. Profilograph Testing: Location and data from all profilograph measurements shall be recorded. When the Profile Index of a lot exceeds the tolerance specified in paragraph "Smoothness Requirements" above by 16 mm per km but less than 32 mm per km, after any reduction of high spots or removal and replacement, the computed percent payment based on surface smoothness will be 95 percent. When the Profile Index exceeds the tolerance by 32 mm per km but less than 47

mm per km, the computed percent payment will be 90 percent. When the Profile Index exceeds the tolerance by 47 mm per km but less than 63 mm per km, the computed percent payment will be 75 percent. When the Profile Index exceeds the tolerance by 63 mm per km or more, the lot shall be removed and replaced at no additional cost to the Government. Regardless of the above, any small individual area with surface deviation which exceeds the tolerance given above by more than 79 mm per km or more, shall be corrected by grinding to meet the specification requirements above or shall be removed and replaced at no additional cost to the Government.

c. Bumps ("Must Grind" Areas): Any bumps ("must grind" areas) shown on the profilograph trace which exceed 10 mm in height shall be reduced by grinding in accordance with subparagraph "Areas Defective In Plan Grade Or Smoothness" until they do not exceed 7.5 mm when retested. Such grinding shall be tapered in all directions to provide smooth transitions to areas not requiring grinding. Areas of textured pavement shall be retextured in accordance with the subparagraph listed above. At the Contractor's option, pavement areas including ground areas may be rechecked with the profilograph in order to record a lower Profile Index.

1.5.8 Edge Slump and Joint Face Deformation

The following requirements on testing and evaluation of edge slump and joint face deformation apply only to pavements 250 mm or more in thickness. Use of slip-form paving equipment and procedures that fail to consistently provide edges within the specified tolerances on edge slump and joint face deformation shall be discontinued and the pavements shall be constructed by means of standard paving procedures using fixed forms. Slabs having more than the allowable edge slump shall be removed and replaced as specified in subparagraph "Excessive Edge Slump" before the adjacent lane is placed. Edge slump and joint face deformation will not be applied to payment adjustment.

1.5.8.1 Edge Slump

When slip-form paving is used, not more than 15.0 percent of the total free edge of any slab of the pavement, as originally constructed, shall have an edge slump exceeding 6 mm, and no slab shall have an edge slump exceeding 9 mm as determined in accordance with the measurements as specified in paragraph "Determination of Edge Slump". (The total free edge of the pavement will be considered to be the cumulative total linear measurement of pavement edge originally constructed as non-adjacent to any existing pavement; i.e., 30 m of pilot lane, a paving lane originally constructed as a separate lane, will have 60 m of free edge; 30 m of fill-in lane will have no free edge, etc.,). The area affected by the downward movement of the concrete along the pavement edge shall not exceed 450 mm back from the edge.

1.5.8.2 Joint Face Deformation

In addition to the edge slump limits specified above, the vertical joint face shall have a surface within the maximum limits shown below:

	Offset from Straightedge Applied Longitudinally To Pavement Surface 25 mm Back From Joint Line	Offset from Straightedge Applied Longitudinally To Vertical Face	Offset From Straightedge Applied Top to Bottom Against the Joint Face	Abrupt Offset in Any Direction	Offset of Joint Face From True Vertical
Airfield Pavement	3 mm	6 mm	9 mm	3 mm	8 mm per 100 mm

1.5.8.3 Determination of Edge Slump

Immediately after the concrete has hardened sufficiently to permit walking thereon, the pavement surface shall be tested by the Contractor in the presence of a representative of the Contracting Officer. Testing shall be performed with a straightedge to reveal irregularities exceeding the edge slump tolerance specified above. The edge slump shall be determined at each free edge of each slipformed paving lane constructed. The straightedge shall be placed transverse to the direction of paving and the end of the straightedge located at the edge of the paving lane. Measurements shall be made at 1.5 to 4.5 m spacings, as directed, commencing at the header where paving was started. Initially measurements shall be made at 1.5 m intervals in each lane. When no deficiencies are present, the Contracting Officer may approve an increase in the interval. When any deficiencies exist, the interval will be returned to 1.5 m. In no case shall the interval exceed 4.5 m. In addition to the transverse edge slump determination above, the Contractor, at the same time, shall check the longitudinal surface smoothness of the joint on a continuous line 25 mm back from the joint line using the straightedge advanced one-half its length for each reading. Other tests of the exposed joint face shall be made as directed to ensure that a uniform, true vertical joint face is attained. These tests shall include longitudinal straightedge testing of the vertical face and vertical testing of the face for both smoothness and angle. The measurements shall be made by the Contractor, shall be properly referenced in accordance with paving lane identification and stationing, and a report given to the Contracting Officer within 24 hours after measurement is made. The report shall also identify areas requiring replacement in accordance with paragraph "Excessive Edge Slump" as well as the cumulative percentage of total free edge of pavement constructed to date which has an edge slump exceeding 6 mm.

1.5.8.4 Excessive Edge Slump

When edge slump exceeding the limits specified above is encountered on either side of the paving lane, additional straightedge measurements shall be made, if required, to define the linear limits of the excessive slump. The concrete for the entire width of the paving lane within these limits of excessive edge slump or joint deformation shall be removed and replaced in conformance with paragraph REPAIR, REMOVAL, REPLACEMENT OR SLABS. Partial slabs removed and replaced shall extend across the full width of the pavement lane, parallel to the transverse joints, and both the section of the slab removed and the section remaining in place shall have a minimum length of 3 m to the nearest scheduled transverse joint. If less than 3 m remains, the entire slab shall be removed and replaced. Adding concrete or paste to the edge or otherwise manipulating the plastic concrete after the sliding form has passed, or patching the hardened concrete, shall not be used as a method for correcting excessive edge slump.

1.5.9 Plan Grade

1.5.9.1 Plan Grade Tolerances

The finished surfaces of pavements shall conform, within the tolerances shown below, to the lines, grades, and cross sections shown. The finished surfaces of airfield taxiway and apron pavements shall vary not more than 6 mm above or below the plan grade line or elevation indicated. Plan grade shall be checked on the lot as a whole and when more than 5.0 and less than 10.0 percent of all measurements made within a lot are outside the specified tolerance, the computed percent payment for that lot will be 95 percent. When more than 10.0 percent are outside the specified tolerances, the computed percent payment for the lot will be 75 percent. However, in any areas where the deviation from grade exceeds the specified tolerances by 50 percent or more, the deficient area shall be removed and replaced at no additional cost to the Government. However, the above deviations from the approved grade line and elevation will not be permitted in areas where closer conformance with the planned grade and elevation is required for the proper functioning of appurtenant structures. The finished surfaces of new abutting pavements shall coincide at their juncture.

1.5.9.2 Grade Conformance Tests

Each pavement category shall be checked by the Contractor for conformance with plan grade requirements. For the purpose of making grade conformance tests, the pavements will be subdivided into the same lots used for all other payment adjustment items. Within 5 days after paving of each lot, the finished surface of the pavement area in each lot shall be tested by the Contractor, in the presence of a representative of the Contracting Officer, by running lines of levels at intervals corresponding with every longitudinal and transverse joint to determine the elevation at each joint intersection. The results of this survey shall be recorded and a copy given to the Government at the completion of the survey of each lot.

1.5.10 Flexural Strength

Each lot of pavement will be evaluated for acceptance in accordance with the following procedures. The Contractor shall be responsible for all testing required herein. Testing shall be performed by an approved commercial laboratory. Results of strength tests will not be used for payment adjustment.

1.5.10.1 Sampling and Testing

One composite sample of concrete from each sublot shall be obtained in accordance with ASTM C 172 from one batch or truckload. Test cylinders, 152 x 305 mm shall be fabricated and cured in accordance with ASTM C 31/C 31M; and tested in accordance with ASTM C 39. Two test cylinders per sublot (8 per lot) shall be fabricated and cured for compressive strength, and two tested at 14-day age and two at 28-day age. The remaining four shall be tested at the ages directed. At the same time 2 additional test cylinders per sublot to be used for CQC tests shall be fabricated and cured; and tested as specified in paragraph TESTING AND INSTECTION FOR CONTRACTOR QUALITY CONTROL. Two beams for flexural strength shall be fabricated and cured in accordance with ASTM C 31/C 31M and tested in accordance with ASTM C 78 for every 2000 cubic meters of concrete. These shall be tested at the ages directed.

1.5.10.2 Computations

The following computations shall be performed:

a. Average the eight 14-day compressive strength tests for the lot and also compute the standard deviation(s) for the eight tests.

b. Convert the 14-day average compressive strength for the lot to equivalent 90-day average flexural strength for the lot, using the Correlation Ratio determined during mixture design studies.

c. Report results of strength tests to the Contracting Officer daily. These values will be used for acceptance, but will not be used for payment adjustment.

1.5.11 Thickness

Each lot of pavement will be evaluated for acceptance and payment adjustment in accordance with the following procedure. The Contractor shall be responsible for drilling the cores, measuring the cores in the presence of the Contracting Officer's representative, and for filling the core holes as directed.

1.5.11.1 Drilling, Measuring, and Computations

Two cores, between 75 and 150 mm in diameter, shall be drilled from the pavement, per sublot (8 per lot). The Contractor shall fill the core holes with concrete containing an expanding admixture, as directed. The cores shall be evaluated for thickness of the pavement in accordance with ASTM C 174/C 174M. The pavement thickness from the 8 cores for the lot shall be averaged and the standard deviation for the 8 thickness measurements shall be computed.

1.5.11.2 Evaluation and Payment Adjustment for Thickness

Using the Average Thickness of the lot, the computed percent payment for thickness shall be determined by entering the following table:

Pavements Over 200 mm in Thickness

Deficiency in Thickness Determined by Cores, mm	Computed Percent Payment for Thickness
0 to 6	100
6.5 to 12.5	75
13 to 18.5	50
19 or greater	0

Where 0 percent payment is indicated, the entire lot shall be removed and replaced at no additional cost to the Government. Where either of the two cores from a sublot show a thickness deficiency of 19 mm or greater, two more cores shall be drilled in the sublot and the average thickness of the four cores computed. If this average shows a thickness deficiency of 19 mm or more the entire sublot shall be removed.

1.5.12 Partial Lots

When operational conditions cause a lot to be terminated before the specified four sublots have been completed, the following procedure shall be used to adjust the lot size and number of tests for the lot. Where three sublots have been completed, they shall constitute a lot and acceptance criteria adjusted accordingly. Where one or two sublots have been completed, they shall be incorporated into the next lot or the previous lot, as directed, and the total number of sublots shall be used and acceptance criteria adjusted accordingly.

1.5.13 Areas Defective in Plan Grade or Smoothness

In areas not meeting the specified limits for surface smoothness and plan grade, high areas shall be reduced to attain the required smoothness and grade, except as depth is limited below. High areas shall be reduced either by hand rubbing the freshly finished concrete with a silicon carbide brick and water when the concrete is less than 36 hours old or by grinding the hardened concrete with an approved surface grinding machine after the concrete is 14 days or more old. Rubbing with a silicon carbide brick and water shall be discontinued as soon as contact with the coarse aggregate is made, and all further necessary reduction shall be accomplished by grinding the hardened concrete with a surface-grinding machine after it is 14 days old. The area corrected by grinding the surface of the hardened concrete shall not exceed 5 percent of the area of any integral slab, and shall not exceed 1 percent of the total area of any sublot. The depth of grinding shall not exceed 6 mm. All pavement areas requiring plan grade or surface smoothness corrections in excess of the limits specified above, shall be removed and replaced in conformance with paragraph REPAIR, REMOVAL, REPLACEMENT OF SLABS. In pavement areas given a wire comb or tined texture, areas exceeding 2 square meters that have been corrected by rubbing or grinding shall be retextured by transverse grooving using an approved grooving machine of standard manufacture. The grooves shall be 3 mm deep by 6 mm wide on 50 mm centers and shall be carried into, and tapered to zero depth within the non-corrected surface, or shall match any existing grooves in the adjacent pavement. All areas in which rubbing or grinding has been performed will be subject to the thickness tolerances specified in paragraph Thickness. Any rubbing or grinding performed on individual slabs with excessive deficiencies shall be performed at the Contractor's own decision without entitlement to additional compensation if eventual removal of the slab is required.

1.6 ACCEPTABILITY OF WORK

The materials and the pavement itself will be accepted on the basis of tests made by the Government and by the Contractor's approved commercial laboratory or the supplier's approved laboratory, all as specified herein. The Government may, at its discretion, make check tests to validate the results of the Contractor's testing. If the results of the Government and Contractor tests vary by less than 2.0 percent, of the Government's test results, the results of the Contractor's tests will be used. If the results of the Government and Contractor tests vary by 2.0 percent or more, but less than 4.0 percent, the average of the two will be considered the value to be used. If these vary by 4.0 percent or more, each sampling and testing procedure shall be carefully evaluated and both the Government and the Contractor shall take another series of tests on duplicate samples of material. If these vary by 4.0 percent or more, the results of the tests made by the Government shall be used and the Government will continue check testing of this item on a continuous basis until the two sets of tests agree within less than 4.0 percent on a regular basis. Testing performed by the

Government will in no way at any time relieve the Contractor from the specified testing requirements.

1.7 PRECONSTRUCTION TESTING OF MATERIALS

The Contractor shall not be entitled to any additional payment or extension of time because of delays caused by sampling and testing additional sources, or samples, necessitated by failure of any samples.

1.7.1 Aggregates

Aggregates shall be sampled by the Contractor in the presence of a Government representative. Samples shall be obtained in accordance with COE CRD-C 100 and of the size indicated therein, or larger if specified in paragraph Testing Sequence Deleterious Materials -- Airfields Only and shall be representative of the materials to be used for the project. Testing of samples shall be the responsibility of the Contractor and shall be performed by an approved commercial laboratory. Test results shall be submitted 30 days before commencing paving. No material shall be used unless test results show that it meets all requirements of these specifications.

1.7.2 Chemical Admixtures

The Contractor shall provide satisfactory facilities for ready procurement of adequate test samples. All sampling and testing of an admixture will be by and at the expense of the Government. Tests will be conducted with materials proposed for the project. An air-entraining admixture that has been in storage at the project site for longer than 6 months or that has been subjected to freezing will be retested at the expense of the Contractor when considered appropriate and shall be rejected if test results are not satisfactory.

1.7.3 Curing Compound

The Contractor shall provide satisfactory facilities for ready procurement of adequate test samples. The sampling and testing will be by and at the expense of the Government.

1.7.4 Epoxy-Resin Material

At least 30 days before the material is used, the Contractor shall submit certified copies of test results showing that the specific lots or batches from which the material will be furnished to this project have been tested by the manufacturer and that the material conforms to the requirements of these specifications. When epoxy resin arrives at the job site, the Contractor shall assist the Government to sample the material. The Government will test the sample or will retain it in storage for possible future testing, as considered appropriate.

1.7.5 Cements, Pozzolans, and GGBF Slag

Preconstruction sampling and testing of cement, pozzolan, and GGBF slag shall conform to the requirements specified for sampling and testing during construction except that test results showing that each material meets specification requirements shall be available at least 5 days before start of paving operations.

1.8 TESTING BY CONTRACTOR DURING CONSTRUCTION

1.8.1 Contractor's Testing Requirements

During construction, the Contractor shall be responsible for sampling and testing aggregates, cementitious materials (cement and pozzolan), and concrete to determine compliance with the specifications. All sampling and testing shall be performed by an approved commercial laboratory, or for cementitious materials, the manufacturer's laboratory. Samples of aggregate shall be obtained as the bins discharge into the weigh hopper. Samples of concrete shall be obtained at the point of delivery to the paver. The Government will sample and test concrete and ingredient materials as considered appropriate. The Contractor shall provide facilities and labor as may be necessary for procurement of representative test samples. Testing by the Government will in no way relieve the Contractor of the specified testing requirements.

1.8.2 Cementitious Materials

Cement and pozzolan will be accepted on the basis of manufacturer's certification of compliance, accompanied by mill test reports showing that the material in each shipment meets the requirements of the specification under which it is furnished. No cementitious material shall be used until notice of acceptance has been given by the Contracting Officer. Cementitious material may be subjected to check testing by the Government from samples obtained at the mill, at transfer points, or at the project site.

1.11 QUALIFICATIONS

All Contractor Quality Control personnel assigned to concrete construction shall be American Concrete Institute (ACI) Certified Workmen in one of the following grades (or shall have approved written evidence of having completed similar qualification programs):

Concrete Field Testing Technician, Grade I
Concrete Laboratory Testing Technician, Grade I or II
Concrete Construction Inspector, Level II

The foreman or lead journeyman of the finishing crew shall have similar qualification for ACI Concrete Flatwork Technician/Finisher, or equal. Written documentation shall be furnished for each workman in the above groups.

1.12 TEST SECTION

At least 10 days but not more than 60 days prior to construction of the concrete pavement, a test section shall be constructed as part of the production paving area at an outer edge as indicated on the drawings. If part of the production paving area, the test section will be allowed to remain in place, if meeting all specification requirements and will be paid for as part of the production pavement. There will be no separate payment for the test section or sections and the cost of the materials, and the construction will be considered a subsidiary cost of constructing the project. The Contractor shall notify the Contracting Officer at least 5 days in advance of the date of test section construction. The test section shall consist of one paving lane at least 130 m long and shall be constructed to a thickness of 405 mm. The lane width shall be the same as that required for use in the project. The test section shall contain at least one transverse construction joint. If keyed or doweled longitudinal construction joints

are required in any of the production pavements, they shall be installed full length along one side of the test strip throughout the test section. If both keys and dowels are required, each shall be installed in half of the test section. Two separate days shall be used for construction of the test section. The Contractor shall use the test section to develop and demonstrate to the satisfaction of the Contracting Officer the proposed techniques of mixing, hauling, placing, consolidating, finishing, curing, start-up procedures, testing methods, plant operations, and the preparation of the construction joints. Variations in mixture proportions other than water shall be made if directed. The test section shall be placed as approved by the Government. The Contractor shall vary the water content, as necessary, to arrive at the appropriate content. The mixing plant shall be operated and calibrated prior to start of placing the test section. The Contractor shall use the same equipment, materials, and construction techniques on the test section as will be used in all subsequent work. Base course preparation, concrete production, placing, consolidating, curing, construction of joints, and all testing shall be in accordance with applicable provisions of this specification. The Contractor shall construct the test section meeting all specification requirements and being acceptable to the Contracting Officer in all aspects, including surface texture. Failure to construct an acceptable test section will necessitate construction of additional test sections at no additional cost to the Government. Test sections allowed to be constructed as part of the production paving which do not meet specification requirements shall be removed at the Contractor's expense. If the Contractor proposes to use slipform paving and is unable to construct an acceptable test section, or if the slipform paving equipment and procedures are found to be unable to produce acceptable pavement at any time, the slipform paving equipment shall be removed from the job and the construction completed using stationary side forms and equipment compatible with them. The Contractor shall provide four cores at least 150 mm diameter and 2 beams at least 150 by 800 mm by full depth (or 4 beams at least 150 by 500 mm by full depth) cut from points selected in the test section by the Government, 5 days after completion of the test section. The Contractor shall trim the beams to dimensions directed before delivery for inspection and testing, as considered appropriate. Production paving may be started immediately after the results of 7-day tests of the cores (and the sawed beams) have been approved and after approval of the test section.

1.13 DELIVERY, STORAGE, AND HANDLING OF MATERIALS

1.13.1 Bulk Cementitious Materials

All cementitious material shall be furnished in bulk. The temperature of the cementitious material, as delivered to storage at the site, shall not exceed 65 degrees C.

1.13.1.1 Transportation

When bulk cementitious material is not unloaded from primary carriers directly into weather-tight hoppers at the batching plant, transportation from the railhead, mill, or intermediate storage to the batching plant shall be accomplished in adequately designed weather-tight trucks, conveyors, or other means that will protect the cementitious material from exposure to moisture.

1.13.1.2 Storage Requirements

Immediately upon receipt at the site of the work, cementitious materials shall be stored in a dry and properly ventilated structure. All storage facilities shall be subject to approval and shall allow easy access for inspection and identification. Sufficient cementitious materials

shall be in storage to sustain continuous operation of the concrete mixing plant while the pavement is being placed. To prevent cement from becoming unduly aged after delivery, any cement that has been stored at the site for 60 days or more shall be used before using cement of lesser age.

1.13.1.3 Separation of Materials

Separate facilities shall be provided which will prevent any intermixing during unloading, transporting, storing, and handling of each type of cementitious material.

1.13.2 Aggregate Materials

1.13.2.1 Storage

Aggregate shall be stored at the site of the batching and mixing plant avoiding breakage, segregation, or contamination by foreign materials. Each size of aggregate from each source shall be stored separately in free-draining stockpiles. Fine aggregate and the smallest size coarse aggregate shall remain in free-draining storage for at least 24 hours immediately prior to use. Sufficient aggregate shall be maintained at the site at all times to permit continuous uninterrupted operation of the mixing plant at the time concrete pavement is being placed.

1.13.2.2 Handling

Aggregate shall be handled avoiding segregation or degradation. Vehicles used for stockpiling or moving aggregate shall be kept clean of foreign materials. Tracked equipment shall not be allowed on coarse aggregate stockpiles. Stockpiles shall be built up and worked avoiding segregation in the piles and preventing different sizes of aggregate from being mixed during storage or batching. Aggregate shall not be stored directly on ground unless a sacrificial layer is left undisturbed and unused.

1.13.3 Other Materials

Reinforcing bars and accessories shall be stored above the ground on platforms, skids, or other supports. Other materials shall be stored avoiding contamination and deterioration. Chemical admixtures which have been in storage at the project site for longer than 6 months or which have been subjected to freezing shall not be used unless retested and proven to meet the specified requirements. The Contractor shall ensure that materials can be accurately identified after bundles or containers are opened.

1.14 EQUIPMENT

All plant, equipment, tools, and machines used in the work shall be maintained in satisfactory working conditions at all times.

1.14.1 Batching and Mixing Plant

1.14.1.1 Location of Batching and Mixing Plant

The batching and mixing plant shall be located on project site as indicated on the drawings. There shall be operable telephonic or radio communication between the batching plant and the placing site at all times concreting is taking place.

1.14.1.2 Type and Capacity of Batching and Mixing Plant

The batching and mixing plant shall be a stationary-type plant. The plant shall be designed and operated to produce concrete within the specified tolerances, and shall have a capacity of at least 200 cubic meters. The batching plant shall conform to the requirements of NRMCA CPMB 100 and as specified; however, rating plates attached to batch plant equipment are not required.

1.14.1.3 Equipment Requirements

The batching controls shall be either semiautomatic or automatic. Semiautomatic batching system shall be provided with interlocks. Separate bins or compartments shall be provided for each size group of aggregate and each cementitious material. Aggregates shall be weighed either in separate weigh batchers with individual scales or cumulatively in one weigh batcher on one scale, provided the fine aggregate is weighed first. Aggregate shall not be weighed in the same batcher with cementitious material. If both cement and pozzolan are used, they may be batched cumulatively, provided portland cement is batched first. Water shall not be weighed or measured cumulatively with another ingredient. Water batcher filling and discharging valves shall be so interlocked that the discharge valve cannot be opened before the filling valve is fully closed. An accurate mechanical device for measuring and dispensing each chemical admixture shall be provided. Each dispenser shall be interlocked with the batching cycle and discharged automatically to obtain uniform distribution throughout the batch in the specified mixing period. Different chemical admixtures shall not be combined before introduction in water and cement. The plant shall be arranged to facilitate the inspection of all operations at all times. Suitable facilities shall be provided for obtaining representative samples of aggregates from each bin or compartment.

1.14.1.4 Scales

Adequate facilities shall be provided for the accurate measurement and control of each of the materials entering each batch of concrete. The weighing equipment shall conform to the applicable requirements of NIST HB 44, except that the accuracy shall be within 0.2 percent of scale capacity. The Contractor shall provide standard test weights and any other auxiliary equipment required for checking the operating performance of each scale or other measuring device. Each weighing unit shall include a visible springless dial, which shall indicate the scale load at all stages of the weighing operation or shall include a beam scale with a beam balance indicator that will show the scale in balance at zero load and at any beam setting. The indicator shall have an over and under travel equal to at least 5 percent of the capacity of the beam. Approved electronic digital indicators and load cells may also be used. The weighing equipment shall be arranged to allow the concrete plant operator to conveniently observe the dials or indicators.

1.14.1.5 Batching Tolerances

The following tolerances shall apply.

Materials	Percentage of Required Mass
Cement (and Pozzolan)	plus or minus 1
Aggregate	plus or minus 2
Water	plus or minus 1
Admixture	plus or minus 3

For volumetric batching equipment for water and admixtures, the above numeric tolerances shall apply to the required volume of material being batched. Concentrated admixtures shall be uniformly diluted, if necessary, to provide sufficient volume per batch to ensure that the batchers will consistently operate within the above tolerance.

1.14.1.6 Moisture Control

The plant shall be capable of ready adjustment to compensate for the varying moisture contents of the aggregates and to change the quantities of the materials being batched. An electric moisture meter complying with the provisions of COE CRD-C 143 shall be provided for measuring of moisture in the fine aggregate. The sensing element shall be arranged so that measurement is made near the batcher charging gate of the fine aggregate bin or in the fine aggregate batcher.

1.14.1.7 Recorders

A graphic or digital recorder conforming to the requirements of NRMCA CPMB 100 shall be furnished and kept operational at the batching plant.

1.14.2 Concrete Mixers

Mixers shall be stationary mixers. Truck mixers shall not be used for mixing or transporting paving concrete. Mixers shall be capable of combining the materials into a uniform mixture and of discharging this mixture without segregation. The mixers shall not be charged in excess of the capacity recommended by the manufacturer. The mixers shall be operated at the drum or mixing blade speed designated by the manufacturer. The mixers shall be maintained in satisfactory operating condition, and the mixer drums shall be kept free of hardened concrete. Mixer blades or paddles shall be replaced when worn down more than 10 percent of their depth when compared with the manufacturer's dimension for new blades or paddles.

1.14.2.1 Stationary, Central Plant, Mixers

Stationary mixers shall be drum mixers. Mixers shall be provided with an acceptable device to lock the discharge mechanism until the required mixing time has elapsed.

1.14.2.3 Mixing Time and Uniformity

a. Stationary Mixers: For stationary mixers, before uniformity data are available, the mixing time for each batch after all solid materials are in the mixer, provided that all

of the mixing water is introduced before one-fourth of the mixing time has elapsed, shall be 1 minute for mixers having a capacity of 0.75 cubic meter. For mixers of greater capacity, this minimum time shall be increased 20 seconds for each additional cubic meter or fraction thereof. After results of uniformity tests are available, the mixing time may be reduced to the minimum time required to meet uniformity requirements; but if uniformity requirements are not being met, the mixing time shall be increased as directed. Mixer performance tests at new mixing times shall be performed immediately after any change in mixing time. When regular testing is performed, the concrete shall meet the limits of any five of the six uniformity requirements listed in Table 4, below. When abbreviated testing is performed, the concrete shall meet only those requirements listed for abbreviated testing. The concrete proportions used for uniformity tests shall be as used on the project. Regular testing shall consist of performing all six tests on three batches of concrete. The range for regular testing shall be the average of the ranges of the three batches. Abbreviated testing shall consist of performing the three required tests on a single batch of concrete. The range for abbreviated testing shall be the range for one batch. If more than one mixer is used and all are identical in terms of make, type, capacity, condition, speed of rotation, etc., the results of tests on one of the mixers shall apply to the others, subject to the approval of the Contracting Officer. All mixer performance (uniformity) testing shall be performed by the Contractor in accordance with COE CRD-C 55 and with paragraph titled TESTING AND INSPECTION FOR CONTRACTOR QUALITY CONTROL.

TABLE 4
UNIFORMITY REQUIREMENTS--STATIONARY MIXERS

Parameter	Regular Tests Allowable Maximum Range for Average of 3 Batches	Abbreviated Tests Allowable Maximum Range for 1 Batch
Unit weight of air-free mortar, kg/cubic meter	32	32
Air content, percent	1.0	--
Slump, mm	25	--
Coarse aggregate, percent	6.0	6.0
Compressive strength at 7 days, percent	10.0	10.0
Water content, percent	1.5	--

1.14.3 Transporting Equipment

Concrete shall be transported to the paving site in nonagitating equipment conforming to ASTM C 94/C 94M or in approved agitators. All transporting equipment shall be designed and operated to deliver and discharge the required concrete mixture completely without segregation.

1.14.4 Transfer and Spreading Equipment

Equipment for transferring concrete from the transporting equipment to the paving lane in front of the paver shall be specially manufactured, self-propelled transfer equipment which will accept the concrete outside the paving lane and will transfer and spread it evenly across the paving lane in front of the paver and strike off the surface evenly to a depth which permits the paver to operate efficiently. The traveling surge hopper shall be a specially manufactured, self-propelled transfer-placer which will operate in front of the paver and accept the concrete from the transporting equipment outside the paving lane, store it as necessary, and feed it out evenly across the lane in front of the paver at a depth which permits the paver to operate efficiently. The capacity shall be such that concrete is always available in front of the paver, to prevent the need for stopping the paver. It shall be designed to always discharge the oldest concrete remaining in the hopper before the fresher concrete.

1.14.5 Paver-Finisher

The paver-finisher shall be a heavy-duty, self-propelled machine designed specifically for paving and finishing high quality pavement. The paver-finisher shall weigh at least 3280 kg per m of lane width, and shall be powered by an engine having at least 15,000 W per meter of lane width. The paver-finisher shall spread, consolidate, and shape the plastic concrete to the desired cross section in one pass. The mechanisms for forming the pavement shall be easily adjustable in width and thickness and for required crown. In addition to other spreaders required by paragraph Transfer and Spreading Equipment, the paver-finisher shall be equipped with a full width knock-down auger or paddle mechanism, capable of operating in both directions, which will evenly spread the fresh concrete in front of the screed or extrusion plate. Immersion vibrators shall be gang mounted at the front of the paver on a frame equipped with suitable controls so that all vibrators can be operated at any desired depth within the slab or completely withdrawn from the concrete, as required. The vibrators shall be automatically controlled so that they will be immediately stopped as forward motion of the paver ceases. The spacing of the immersion vibrators across the paving lane shall be as necessary to properly consolidate the concrete, but the clear distance between vibrators shall not exceed 750 mm. Spud vibrators shall operate at a frequency of not less than 135 Hz and an amplitude of not less than 0.75 mm and tube vibrators at a frequency of not less than 80 Hz and an amplitude of not less than 0.75 mm, as determined by COE CRD-C 521. The paver-finisher shall be equipped with a transversely oscillating screed or an extrusion plate to shape, compact, and smooth the surface and shall so finish the surface that no significant amount of hand finishing, except use of cutting straightedges, is required. The screed or extrusion plate shall be constructed to provide adjustment for crown in the pavement. The entire machine shall provide adjustment for variation in lane width or thickness and to prevent more than 200 mm of the screed or extrusion plate extending over previously placed concrete on either end when paving fill-in lanes. Machines that cause displacement of properly installed forms or cause ruts or indentations in the prepared underlying materials and machines that cause frequent delays due to mechanical failures shall be replaced as directed.

1.14.5.1 Paver-Finisher with Fixed Forms

The paver-finisher shall be equipped with wheels designed to keep it aligned with the forms and to spread the load so as to prevent deformation of the forms.

1.14.5.2 Slipform Paver-Finisher

The slipform paver-finisher shall be automatically controlled and crawler mounted with four padded tracks so as to be completely stable under all operating conditions. The paver-finisher shall finish the surface and edges so that no edge slump beyond allowable tolerance occurs. Horizontal alignment shall be electronically referenced to a taut wire guideline. Vertical alignment shall be electronically referenced on both sides of the paver to a taut wire guideline, to an approved laser control system, or, only where permitted by paragraph Slipform Paving, to a ski operating on a completed lane. Suitable moving side forms shall be provided that are adjustable and will produce smooth, even edges, perpendicular to the top surface and meeting specification requirements for alignment and freedom from edge slump.

1.14.5.3 Longitudinal Mechanical Float

A longitudinal mechanical float shall be specially designed and manufactured to smooth and finish the pavement surface without working excess paste to the surface. It shall be rigidly attached to the rear of the paver-finisher or to a separate self-propelled frame spanning the paving lane. The float plate shall be at least 1.5 m long by 200 mm wide and shall automatically be oscillated in the longitudinal direction while slowly moving from edge to edge of the paving lane, with the float plate in contact with the surface at all times.

1.14.5.4 Nonrotating Pipe Float

A pipe float if used, shall be a nonrotating pipe 150 to 250 mm in diameter and sufficiently long to span the full paving width when oriented at an angle of approximately 60 degrees with the centerline. The pipe float shall be mounted on a self-propelled frame that spans the paving lane. No means of applying water to the surface shall be incorporated in the pipe float.

1.14.5.5 Other Types of Finishing Equipment

Clary screeds or other rotating tube floats, or bridge deck finishers, shall not be allowed on the project. Concrete finishing equipment of types other than specified above may be demonstrated on a test section outside the production pavement if approved in writing. If the Contracting Officer's representative decides from evaluation of the test section that the equipment is better than the specified finishing equipment, its use will be permitted as long as it continues to perform better than the specified equipment.

1.14.6 Curing Equipment

Equipment for applying membrane-forming curing compound shall be mounted on a self-propelled frame that spans the paving lane. The reservoir for curing compound shall be constantly mechanically (not air) agitated during operation and shall contain means for completely draining the reservoir. The spraying system shall consist of a mechanically powered pump which will maintain constant pressure during operation, an operable pressure gauge, and either a series of spray nozzles evenly spaced across the lane to give uniformly overlapping coverage or a single spray nozzle which is mounted on a carriage which automatically traverses the lane width at a speed correlated with the forward movement of the overall frame. All spray nozzles shall be protected with wind screens. Any hand-operated sprayers allowed by paragraph Membrane Curing shall be compressed air supplied by a

mechanical air compressor. If the curing machine fails to apply an even coating of compound at the specified rate, it shall immediately be replaced.

1.14.7 Texturing Equipment

Texturing equipment shall be as specified below. Before use, the texturing equipment shall be demonstrated on a test section, and the equipment shall be modified as necessary to produce the texture directed.

1.14.7.1 Fabric Drag

A fabric drag shall consist of a piece of material as long as the lane width securely attached to a separate wheel mounted frame spanning the paving lane or to one of the other similar pieces of equipment. Width of the material shall provide 300 to 450 mm dragging flat on the pavement surface. Length shall be at least equal to the width of the slab plus 600 mm. The material shall be clean, reasonably new burlap, completely saturated with water before attachment to the frame and always resaturated before start of use and kept clean and saturated during use. Burlap shall conform to AASHTO M 182, Class 3 or 4.

1.14.8 Sawing Equipment

Equipment for sawing joints and for other similar sawing of concrete shall be standard diamond-type concrete saws mounted on a wheeled chassis which can be easily guided to follow the required alignment. Blades shall be diamond tipped. If demonstrated to operate properly, abrasive blades may be used. Wheel saws shall be saws with large diameter tungsten carbide tipped blades mounted on a heavy-duty chassis which will produce a saw kerf at least 40 mm. All saws shall be capable of sawing to the full depth required.

1.14.9 Straightedge

The Contractor shall furnish and maintain at the job site, in good condition, one 4 m straightedge for each paving train for testing the hardened portland cement concrete surfaces. These straightedges shall be constructed of aluminum or magnesium alloy and shall have blades of box or box-girder cross section with flat bottom, adequately reinforced to insure rigidity and accuracy. Straightedges shall have handles for operation on the pavement.

1.14.10 Profilograph

The Contractor shall furnish a 7.6 m profilograph for testing the finished pavement surface. The profilograph shall produce a record on tape of the results of testing the pavement surface and shall automatically mark the Profile Index of each section tested as well as indicate and measure each "must grind" point, all in accordance with CDT Test 526 and as required by paragraph Surface Smoothness.

PART 2 PRODUCTS

2.1 CEMENTITIOUS MATERIALS

Cementitious materials shall be portland cement or portland cement in combination with pozzolan and shall conform to appropriate specifications listed below. Temperature of cementitious materials as supplied to the project shall not exceed 65 degrees C.

2.1.1 Portland Cement

Portland cement shall conform to ASTM C 150, Type I or II, low-alkali.

2.1.2 High-Early-Strength Portland Cement

High-early-strength cement shall conform to ASTM C 150, Type III with C_3A limited to 5 percent, low-alkali.

2.1.4 Pozzolan (Fly Ash)

2.1.4.1 Fly Ash

Fly ash shall conform to ASTM C 618, Class F, with the optional requirements in Table 1A, 2, and 2A, and shall have a loss of ignition not exceeding 6 percent. Class F fly ash for use in mitigating alkali-aggregate reactivity shall have a calcium oxide (CaO) content less than 8 percent.

2.2 AGGREGATES

In addition to the grading requirements specified for coarse aggregate and for fine aggregate, the combined aggregate grading shall meet the following requirements.

a. If necessary, a blending aggregate shall be used to meet the required combined grading. This blending aggregate shall be batched separately. The combined grading of all aggregates used, in the proportions selected, shall be computed on the basis of cumulative percent retained on each sieve specified for fine and coarse aggregate.

b. The materials selected and the proportions used shall be such that when the Coarseness Factor (CF) and the Workability Factor (W) are plotted on a diagram as described in d. below, the point thus determined shall fall within the parallelogram described therein.

c. The Coarseness Factor (CF) shall be determined from the following equation:

CF = (cumulative percent retained on the 9.5 mm sieve)(100)/(cumulative percent retained on the 2.36 mm sieve)

The Workability Factor (W) is defined as the cumulative percent passing the 2.36 mm sieve. However, W shall be adjusted, upwards only, by 2.5 percentage points for each 42 kg of cementitious material per cubic meter greater than 335 kg per cubic meter.

d. A diagram shall be plotted using a rectangular scale with W on the Y-axis with units from 20 (bottom) to 45 (top), and with CF on the X-axis with units from 80 (left side) to 30 (right side). On this diagram a parallelogram shall be plotted with corners at the following coordinates (CF-75, W-28), (CF-75, W-40), (CF-45, W-32.5), and (CF-45, W-41). If the point determined by the intersection of the computed CF and W does not fall within the above parallelogram, the grading of each size of aggregate used and the proportions selected shall be changed as necessary.

e. In addition, the individual percent retained on each sieve shall be plotted for the combined aggregate grading, on either rectangular or semi-log graph paper. The graph shall show a relative smooth transition between coarse and fine aggregate and shall have no major valleys or peaks in the area smaller than the 23.6 mm sieve. If this plot does not meet the above criteria, the grading of each size aggregate used and the proportions selected shall be changed as necessary.

2.2.1 Coarse Aggregate

Coarse aggregate shall have a satisfactory service record of at least 5 years successful service in three paving projects or, if a new source is used, shall meet the requirements when tested for resistance to freezing and thawing.

2.2.1.1 Material Composition

Coarse aggregate shall consist of crushed gravel, crushed stone, reclaimed portland cement concrete, or a combination thereof. Reclaimed concrete pavement produced from required removal operations may be used for aggregate, provided it meets all requirements specified herein for aggregates.

2.2.1.2 Quality

Aggregates as delivered to the mixers shall consist of clean, hard, uncoated particles meeting the requirements of ASTM C 33 and other requirements specified herein. Coarse aggregate shall be washed. Washing shall be sufficient to remove dust and other coatings.

2.2.1.3 Particle Shape Characteristics

Particles of the coarse aggregate shall be generally spherical or cubical in shape. The quantity of flat and elongated particles in any size group shall not exceed 20 percent by weight as determined by COE CRD-C 119. A flat particle is defined as one having a ratio of width to thickness greater than 3; an elongated particle is one having a ratio of length to width greater than 3.

2.2.1.4 Size and Grading

The nominal maximum size of the coarse aggregate shall be 37.5 mm, and shall meet the size groups below. When the nominal maximum coarse size is greater than 25 mm, the aggregates shall be furnished in two size groups as follows:

Nominal Maximum Size, mm	Size Group
19	ASTM C 33 No. 67 (4.75 to 19 mm)
37.5	ASTM C 33 No. 4 (19 to 37.5 mm)

The grading of the coarse aggregate within the separated size groups shall conform to the requirements of ASTM C 33, Sizes 67 and 4 as delivered to the mixer.

2.2.1.5 Deleterious Materials - Airfield Pavements

The amount of deleterious material in each sieve size of coarse aggregate shall not exceed the limits shown in Table 5 below, determined in accordance with the test methods shown.

TABLE 5
LIMITS OF DELETERIOUS MATERIALS IN COARSE AGGREGATE
FOR AIRFIELD PAVEMENTS

Materials	Percentage by Mass
Clay lumps and friable particles (ASTM C 142)	0.2
Shale (a) (ASTM C 295)	0.1
Material finer than 0.075 mm (No. 200 sieve) (b) (ASTM C 117)	0.5
Lightweight particles (c) (ASTM C 123)	0.2
Clay ironstone (d) (ASTM C 295)	0.1
Chert and cherty stone (less than 2.40 Mg/cubic meter density SSD (2.40 Sp. Gr.)) (e) (ASTM C 295)	0.1
Claystone, mudstone, and siltstone (f) (ASTM C 295)	0.1
Shaly and argillaceous limestone (g) (ASTM C 295)	0.2
Other soft particles COE CRD-C 130	1.0
Total of all deleterious substances exclusive of material finer than 0.075 mm (No. 200 sieve)	1.0

a. Shale is defined as a fine-grained, thinly laminated or fissile sedimentary rock. It is commonly composed of clay or silt or both. It has been indurated by compaction or by cementation, but not so much as to have become slate.

b. Limit for material finer than 0.075 mm (No. 200 sieve) will be increased to 1.5 percent for crushed aggregates if the fine material consists of crusher dust that is essentially free from clay or shale.

c. The separation medium shall have a density of 2.0 Mg/cubic meter (Sp. Gr. of 2.0). This limit does not apply to coarse aggregate manufactured from blast-furnace slag unless contamination is evident.

d. Clay ironstone is defined as an impure variety of iron carbonate, iron oxide, hydrous iron oxide, or combinations thereof, commonly mixed with clay, silt, or sand. It commonly occurs as dull, earthy particles, homogeneous concretionary masses, or hard-shell particles with soft interiors. Other names commonly used for clay ironstone are "chocolate bars" and limonite concretions.

e. Chert is defined as a rock composed of quartz, chalcedony or opal, or any mixture of these forms of silica. It is variable in color. The texture is so fine that the individual mineral grains are too small to be distinguished by the unaided eye. Its hardness is such that it scratches glass but is not scratched by a knife blade. It may contain impurities such as clay, carbonates, iron oxides, and other minerals. Other names commonly applied to varieties of chert are: flint, jasper, agate, onyx, hornstone, porcellanite, novaculite, sard, carnelian, plasma, bloodstone, touchstone, chrysoprase, heliotrope, and petrified wood. Cherty stone is defined as any type of rock (generally limestone) that contains chert as lenses and nodules, or irregular masses partially or completely replacing the original stone.

f. Claystone, mudstone, or siltstone, is defined as a massive fine-grained sedimentary rock that consists predominantly of indurated clay or silt without laminations or fissility. It may be indurated either by compaction or by cementation.

g. Shaly limestone is defined as limestone in which shale occurs as one or more thin beds or laminae. These laminae may be regular or very irregular and may be spaced from a few inches down to minute fractions of an inch. Argillaceous limestone is defined as a limestone in which clay minerals occur disseminated in the stone in the amount of 10 to 50 percent by weight of the rock; when these make up from 50 to 90 percent, the rock is known as calcareous (or dolomitic) shale (or claystone, mudstone, or siltstone).

2.2.1.6 Testing Sequence Deleterious Materials -- Airfields Only

The size of the sample shall be at least 90 kg for the 19 to 37 mm size and 12 kg for the 4.75 to 19 mm coarse aggregate and 5 kg for the fine aggregate. The Contractor shall provide facilities for the ready procurement of representative test samples. Samples shall be taken and tested by and at the expense of the Contractor, using appropriate Corps of Engineers laboratory and ASTM test methods. Additional tests and analyses of aggregates at various stages in the processing and handling operations may be made by the Government at the discretion of the Contracting Officer. Such Government testing will not relieve the Contractor

of any of its testing responsibilities. The testing procedure on each sample of coarse aggregate for compliance with limits on deleterious materials shall be as follows:

Step 1: Test approximately one-fifth of sample for material finer than the 0.075 mm sieve.

Step 2: Wash off material finer than 0.075 mm sieve from the remainder of the sample and recombine the remainder with material retained on the 0.075 mm sieve from Step 1.

Step 3: Test remaining full sample for clay lumps and friable particles and remove.

Step 4: Test remaining full sample for lightweight particles and remove, and then for chert and/or cherty stone with SSD density of less than 2.40 Mg/cubic meter (Sp. Gr. 2.40) and remove.

Step 5: Test remaining sample for clay-ironstone, shale, claystone, mudstone, siltstone, shaly and/or argillaceous limestone, and remove.

Step 6: Test approximately one-fifth of remaining full sample for other soft particles.

Determination of deleterious materials listed in Steps 4 and 5 shall be performed by an individual specifically trained in petrographic identification. The individual selected to perform the identification of these deleterious materials shall be subject to approval and, at least 10 days before any individual is proposed to commence this type of work, the Contractor shall submit a written resume of the individual's training and experience for approval by the CEWES Laboratory. The Contractor will not be entitled to any extension of time or additional payment due to any delays caused by the testing, evaluation, or personnel requirements.

2.2.1.7 Resistance to Freezing and Thawing

Coarse aggregate not having a satisfactory demonstrable service record shall have a durability factor of 50 or more when subjected to freezing and thawing in concrete in accordance with COE CRD-C 114.

2.2.1.8 Resistance to Abrasion

Coarse aggregate shall not show more than 40 percent loss when subjected to the Los Angeles abrasion test in accordance with ASTM C 131.

2.2.1.9 Alkali-Aggregate Reactivity

Fine and Coarse aggregates to be used in all concrete shall be evaluated and tested by the Contractor for alkali-aggregate reactivity in accordance with ASTM C 1260. Both coarse aggregate size groups shall be tested if from different sources. Test results shall have a measured expansion equal to or less than 0.08 percent at 16 days. Should the test data indicate an expansion greater than 0.08 percent, the aggregate(s) shall be rejected, or additional testing, using a modified version of ASTM C 1260 shall be performed by the Contractor as described below. ASTM C 1260 shall be modified as follows to include the following option:

a. Utilize the Contractor's proposed low alkali portland cement and Class "F" fly ash in combination for the test proportioning. Class "F" fly ash shall contain less than 8 percent

Calcium Oxide (CaO) and shall be used in the range of 25 percent to 35 percent of the total cementitious material by mass. The quantity shall be determined that will meet all the requirements of these specifications and that which will lower the expansion equal to or less than 0.08 percent at 16 days.

If the above option does not lower the expansion equal to or less than 0.08 percent at 16 days, the aggregates(s) shall be rejected and the Contractor shall submit new aggregate sources for retesting. The results of the testing shall be submitted to the Contracting Officer for evaluation and acceptance.

2.2.2 Fine Aggregate

Fine aggregate shall have a service record of at least 5 years satisfactory service in three paving projects or, if a new source is used, shall meet the requirements for resistance to freezing and thawing.

2.2.2.1 Composition

Fine aggregate shall consist of natural sand, manufactured sand, or a combination of the two, and shall be composed of clean, hard, durable particles. ~~Fine aggregate shall consist of the minus 10 mm material from the reclaimed portland cement concrete or a combination of the crushed reclaimed concrete blended with sand. If insufficient fine aggregate is available from the recycling process, the additional material shall be natural sand, manufactured sand or a combination thereof meeting all requirements specified.~~ Irrespective of the source from which it is obtained, all fine aggregate shall be composed of clean, hard, durable particles meeting the requirements of ASTM C 33. Each type of fine aggregate shall be stockpiled and batched separately. Any degree of contamination will be cause for the rejection of the entire stockpile.

2.2.2.2 Particle Shape

Particles of the fine aggregate shall be generally spherical or cubical in shape.

2.2.2.3 Grading

Grading of the fine aggregate, as delivered to the mixer, shall conform to the requirements of ASTM C 33. In addition, the fine aggregate, as delivered to the mixer, shall have a fineness modulus of not less than 2.50 nor more than 3.00. The grading of the fine aggregate also shall be controlled so that the fineness moduli of at least nine of every set of ten consecutive samples of the fine aggregate, as delivered to the mixer, will not vary more than 0.15 from the average fineness moduli of all samples previously taken. The fineness modulus shall be determined by COE CRD-C 104.

2.2.2.4 Deleterious Material

The amount of deleterious material in the fine aggregate shall not exceed the following limits by mass:

Material	Percentage by Mass
Clay lumps and friable particles ASTM C 142	1.0
Material finer than 0.075 mm (No. 200 sieve) ASTM C 117	3.0
Lightweight particles ASTM C 123 using a medium with a density of 2.0 Mg/cubic meter (Sp. Gr. of 2.0))	0.5
Total of all above	3.0

2.2.2.5 Resistance to Freezing and Thawing

Fine aggregate not having a satisfactory demonstrable service record shall have a durability factor of 50 or more when subjected to freezing and thawing in concrete in accordance with COE CRD-C 114.

2.2.2.6 Alkali-Aggregate Reactivity

Fine aggregates shall be tested as required for coarse aggregates.

2.3 CHEMICAL ADMIXTURES

2.3.1 Air-Entraining Admixtures

The air-entraining admixture shall conform to ASTM C 260 and shall consistently entrain the air content in the specified ranges under field conditions. The air-entraining admixture shall be in a solution of suitable concentration for field use.

2.3.2 Accelerator

An accelerator shall be used only when specified in paragraph SPECIFIED CONCRETE STRENGTH AND OTHER PROPERTIES and shall not be used to reduce the amount of cementitious material used. Accelerator shall conform to ASTM C 494, Type C. Calcium chloride and admixtures containing calcium chloride shall not be used.

2.3.3 Retarder

A retarding admixture shall meet the requirements of ASTM C 494, Type B, except that the 6-month and 1-year compressive strength tests are waived. The use of the admixture is at the option of the Contractor, but shall not be used to reduce the amount of cementitious material.

2.3.4 Water-Reducer

A water-reducing admixture shall meet the requirements of ASTM C 494, Type A or D except that the 6-month and 1-year compressive strength tests are waived. The admixture may be added to the concrete mixture only when its use is approved or directed, and only when it has been used in mixture proportioning studies to arrive at approved mixture proportions.

2.4 CURING MATERIALS

2.4.1 Membrane Forming Curing Compound

Membrane forming curing compound shall be a white pigmented compound conforming to COE CRD-C 300.

2.4.2 Burlap

Burlap used for curing shall conform to AASHTO M 182, Class 3 or 4. Materials shall be new or shall be clean materials never used for anything other than curing concrete.

2.5 WATER

Water for mixing and curing shall be fresh, clean, potable, and free of injurious amounts of oil, acid, salt, or alkali, except that non-potable water may be used if it meets the requirements of COE CRD-C 400.

2.6 JOINT MATERIALS

2.6.1 Expansion Joint Material

Expansion joint filler shall be a preformed material conforming to ASTM D 1752 Type I, II, or III. Expansion joint filler shall be 20 mm thick.

2.6.2 Slip Joint Material

Slip joint material shall be 6 mm thick expansion joint filler conforming to ASTM D 1752.

2.7 REINFORCING

All reinforcement shall be free from loose, flaky rust, loose scale, oil, grease, mud, or other coatings that might reduce the bond with concrete. Removal of thin powdery rust and tight rust is not required. However, reinforcing steel which is rusted to the extent that it does not conform to the required dimensions or mechanical properties shall not be used.

2.8 DOWELS

2.8.1 Dowels

Dowels shall be single piece bars fabricated or cut to length at the shop or mill before delivery to the site. Dowels shall be free of loose, flaky rust and loose scale and shall be clean and straight. Dowels may be sheared to length provided that the deformation from true shape caused by shearing does not exceed 1 mm on the diameter of the dowel and does not extend more than 1 mm from the end of the dowel. Dowels shall be plain (non-deformed) steel bars conforming to ASTM A 615/A 615M, Grade 40 or 60; ASTM A 616/A 616M, Grade 50 or 60; or ASTM A 617/A 617M, Grade 40 or 60; or shall be steel pipe conforming to ASTM A 53, extra strong, as indicated. If split dowels are proposed for use, a complete description of the materials and installation procedures shall be submitted for approval at least 15 days before start of construction. Paint for dowels shall conform to MIL-DTL-24441/20A.

2.9 EPOXY RESIN

All epoxy-resin materials shall be two-component materials conforming to the requirements of ASTM C 881, Class as appropriate for each application temperature to be encountered, except that in addition, the materials shall meet the following requirements:

a. Material for use for embedding dowels and anchor bolts shall be Type IV, Grade 3.

b. Material for use as patching materials for complete filling of spalls, wide cracks, and other voids and for use in preparing epoxy resin mortar shall be Type III, Grade as approved.

c. Material for use for injecting cracks shall be Type IV, Grade 1.

d. Material for bonding freshly mixed portland cement concrete or mortar or freshly mixed epoxy resin concrete or mortar to hardened concrete shall be Type V, Grade as approved.

2.10 SPECIFIED CONCRETE STRENGTH AND OTHER PROPERTIES

2.10.1 Specified Flexural Strength

Specified flexural strength, R, for concrete is 4.48 MPa (650 psi) at 28 days, as determined by tests made in accordance with ASTM C 78 of beams fabricated and cured in accordance with ASTM C 192/C 192M or as determined by equivalent flexural strength for acceptance as specified in paragraph, Flexural Strength. Maximum allowable water-cementitious material ratio is 0.45. The water-cementitious material ratio will be the equivalent water-cement ratio as determined by conversion from the weight ratio of water to cement plus pozzolan, silica fume, and ground granulated blast furnace slag by the mass equivalency method described in ACI 211.1. The concrete shall be air-entrained with a total air content of 6 plus or minus 1.5 percentage points, at the point of placement. Air content shall be determined in accordance with ASTM C 231. The maximum allowable slump of the concrete at the point of placement shall be 50 mm for pavement constructed with fixed forms. For slipformed pavement, at the start of the project, the Contractor shall select a maximum allowable slump which will produce in-place pavement meeting the specified tolerances for control of edge slump.

2.10.2 Concrete Temperature

The temperature of the concrete as delivered shall conform to the requirements of paragraphs, Paving in Hot Weather and Paving in Cold Weather. Temperature of concrete shall be determined in accordance with ASTM C 1064/C 1064M.

2.10.3 Concrete Strength for Final Acceptance

The strength of the concrete will be considered acceptable when the average equivalent 28-day Flexural strengths for each lot are above the 'Specified Flexural Strength' as determined by correlation with 14-day compressive strength tests specified in paragraph MIXTURE PROPORTIONS BY CONTRACTOR for 28-day flexural Strength, and no individual set (2 cylinders per sublot) in the lot are 170 kPa or more below the equivalent 'Specified Flexural Strength'. If any lot or sublot, respectively, fails to meet the above criteria, the lot or sublot shall be removed and replaced at no additional cost to the Government. This is in addition to

and does not replace the average strength required for day-to-day CQC operations as specified in paragraph Average Flexural Strength Required for Mixtures.

2.11 MIXTURE PROPORTIONS BY CONTRACTOR

2.11.1 Composition

Concrete shall be composed of cementitious material, water, fine and coarse aggregates, and admixtures. The cementitious material shall be portland cement or only portland cement in combination with pozzolan. Pozzolan, if used with non alkali reactive aggregates, shall consist of not less than 15 percent of the cementitious material by mass and not more than 35 percent. If class F fly ash is required to mitigate potential alkali-aggregate reactivity, the percentage by mass determined from the modified ASTM C 1260 testing shall be used in the mixture proportioning studies. The total cementitious material content shall be at least 310 kg/cubic meter (517 lb./cu. Yd). Admixtures shall consist of air entraining admixture and may also include, as approved, accelerator, retarder, and/or water-reducing admixture. If water-reducer is used, it shall be used only at the dosage determined during mixture proportioning studies. High range water-reducing admixtures and admixtures to produce flowable concrete shall not be used.

2.11.2 Concrete Proportioning Studies, Pavement Concrete

Trial design batches, mixture proportioning studies, and testing requirements shall be the responsibility of the Contractor. Mixture proportioning studies shall be performed by a commercial laboratory, inspected by the Government, and approved in writing. The laboratory performing the mixture proportioning shall conform with ASTM C 1077. Strength requirements during mixture proportioning studies shall be based on flexural strength as determined by test specimens fabricated in accordance with ASTM C 192/C 192M and tested in accordance with ASTM C 78. Samples of all materials used in mixture proportioning studies shall be representative of those proposed for use on the project and shall be accompanied by the manufacturer's or producer's test reports indicating compliance with these specifications. Trial mixtures having proportions, slumps, and air content suitable for the work shall be based on methodology described in ACI 211.1, modified as necessary to accommodate flexural strength.

2.11.2.1 Water-Cement Ratio

At least three different water-cement ratios, which will produce a range of strength encompassing that required on the project, shall be used. The maximum allowable water-cement ratio required in paragraph Maximum Water-Cement Ratio will be the equivalent water-cement ratio as determined by conversion from the mass ratio of water to cement plus pozzolan by the weight equivalency method as described in ACI 211.1. Laboratory trial mixtures shall be proportioned for maximum permitted slump and air content.

2.11.2.2 Trial Mixture Studies

Separate sets of trial mixture studies shall be made for each combination of cementitious materials and each combination of admixtures proposed for use. No combination of either shall be used until proven by such studies, except that, if approved in writing and otherwise permitted by these specifications, an accelerator or a retarder may be used without separate trial mixture study. Separate trial mixture studies shall also be made for concrete for any

placing method proposed which requires special properties. The temperature of concrete in each trial batch shall be reported. Each mixture shall be designed to promote easy and suitable concrete placement, consolidation and finishing, and to prevent segregation and excessive bleeding. Concrete proportioning studies shall be performed using the following procedures:

2.11.2.3 Mixture Proportioning for 28-day Flexural Strength

The following step by step procedure shall be followed:

a. Fabricate all beams and cylinders for each mixture from the same batch or blend of batches. Fabricate and cure all beams and cylinders in accordance with ASTM C 192/C 192M, using 152 x 152 mm beams and 152 x 305 mm cylinders.

b. Test beams in accordance with ASTM C 78, cylinders in accordance with ASTM C 39.

c. Fabricate and cure test beams from each mixture for 3, 7, 14, and 28-day flexural tests; 6 beams to be tested per age.

d. Fabricate and cure test cylinders from each mixture for 3, 7, 14, and 28-day compressive strength tests; 6 cylinders to be tested per age.

e. Using the average strength for each w/c at each age, plot all results from each of the three mixtures on separate graphs for w/c versus:

3-day flexural strength
7-day compressive strength
14-day flexural strength
28-day flexural strength

3-day compressive strength
7-day compressive strength
14-day compressive strength
28-day compressive strength

f. From these graphs select a w/c that will produce a mixture giving a 28-day flexural strength equal to the required strength determined in accordance with paragraph "Average Flexural Strength Required for Mixtures".

g. Using the above selected w/c, select from the graphs the expected 3, 7, 14, 28-day flexural strengths and the expected 3, 7, 14, 28-day compressive strengths for the mixture.

h. From the above expected strengths for the selected mixture determine the following Correlation Ratios:

(1) Ratio of the 14-day compressive strength of the selected mixture to the 28-day flexural strength of the mixture (for acceptance).

(2) Ratio of the 7-day compressive strength of the selected mixture to the 28-day flexural strength of the mixture (for CQC control).

i. If there is a change in materials, additional mixture design studies shall be made using the new materials and new Correlation Ratios shall be determined.

j. No concrete pavement shall be placed until the Contracting Officer has approved the Contractor's mixture proportions.

2.11.3 Contractor Quality Control for Average Flexural Strength

The Contractor's day to day production shall be Controlled (CQC) in accordance with the criteria herein, in the following subparagraphs, and in par. 'Concrete Strength Testing for CQC'. This is entirely different from the acceptance requirements of par. 'Concrete Strength for Final Acceptance', and it is mandatory that both sets of requirements must be met. If at any time, the 'equivalent average 28-day flexural strength', for any lot, as determined by correlation with results of 7-day compressive test specimens, is 410 kPa or more below the required equivalent average 28-day flexural strength', as specified below, the paving operation shall be stopped and the Contractor shall take necessary steps to improve the mixture proportioning, materials, or the batching and mixing to increase the strength. The paving operations shall not recommence until the Contracting Officer has approved the Contractor's Proposed changes in writing.

2.11.3.1 Average CQC Flexural Strength Required for Mixtures

In order to ensure meeting, the strength requirements specified in paragraph SPECIFIED CONCRETE STRENGTH AND OTHER PROPERTIES, during production, the mixture proportions selected during mixture proportioning studies and used during construction shall produce a required average CQC flexural strength exceeding the specified strength, R, by the amount indicated below. This required average CQC flexural strength, Ra, will be used only for CQC operations as specified in paragraph TESTING AND INSPECTION FOR CONTRACTOR QUALITY CONTROL and as specified in the previous paragraph. During production, the required Ra shall be adjusted (increased or decreased), as appropriate and as approved, based on the standard deviation of equivalent 90-day strengths being attained during paving.

a. From Previous Test Records: Where a concrete production facility has previous test records, a standard deviation shall be established in accordance with the applicable provisions of ACI 214.3R. Test records from which a standard deviation is calculated shall represent materials, quality control procedures, and conditions similar to those expected, shall represent concrete produced to meet a specified flexural strength or strengths within 1 MPa of the 28-day flexural strength specified for the proposed work, and shall consist of at least 30 consecutive tests. A strength test shall be the average of the strengths of two specimens made from the same sample of concrete and tested at 28 days. Required average CQC flexural strength, Ra, used as the basis for selection of concrete proportions shall be the value from the equation that follows, using the standard deviation as determined above:

$$Ra = R + 1.34S$$

Where: S = standard deviation
R = specified flexural strength
Ra = required average flexural strength

Where a concrete production facility does not have test records meeting the requirements above but does have a record based on 15 to 29 consecutive tests, a standard deviation shall be established as the product of the calculated standard deviation and a modification factor from the following table:

MODIFICATION FACTOR

NUMBER OF TESTS	FOR STANDARD DEVIATION
15	1.16
20	1.08
25	1.03
30 or more	1.00

b. Without Previous Test Records: When a concrete production facility does not have sufficient field strength test records for calculation of the standard deviation, the required average strength, Ra, shall be determined by adding 15 percent to the specified flexural strength, R.

PART 3 EXECUTION

3.1 PREPARATION FOR PAVING

Before commencing paving, the following shall be performed. Surfaces to receive concrete shall be prepared as specified below. If used, forms shall be in place, cleaned, coated, and adequately supported. Any reinforcing steel needed shall be at the paving site. All transporting and transfer equipment shall be ready for use, clean, and free of hardened concrete and foreign material. Equipment for spreading, consolidating, screeding, finishing, and texturing concrete shall be at the paving site, clean and in proper working order. All equipment and material for curing and for protecting concrete from weather or mechanical damage shall be at the paving site, in proper working condition, and in sufficient amount for the entire placement. When hot, windy conditions during paving appear probable, equipment and material shall be at the paving site to provide windbreaks, shading, fogging, or other action to prevent plastic shrinkage cracking or other damaging drying of the concrete.

3.2 CONDITIONING OF UNDERLYING MATERIAL

3.2.1 General Procedures

The underlying base course material upon which concrete is to be placed shall be clean, damp, and free from debris, waste concrete or cement, frost, ice, and standing or running water. Prior to setting forms or placement of concrete, the underlying material shall be well drained and shall have been satisfactorily graded and uniformly compacted in accordance with the applicable Section of these specifications. The surface of the subgrade or base course shall be tested as to crown, elevation, and density in advance of setting forms or of concrete placement using slip-form techniques. High areas shall be trimmed to proper elevation. Low areas shall be filled and compacted to a condition similar to that of surrounding grade, or filled with concrete monolithically with the pavement. Where low areas

are filled with concrete, the areas shall be marked, as approved, and cores for thickness determinations as required by paragraph, Flexural Strength and Thickness shall not be drilled in those areas. Any underlying material disturbed by construction operations shall be reworked and recompacted to specified density immediately in front of the paver. If a slipform paver is permitted and is used, the same underlying material under the paving lane shall be continued beyond the edge of the lane a sufficient distance and shall be thoroughly compacted and true to grade to provide a suitable trackline for the slipform paver and firm support for the edge of the paving lane. Where an open-graded granular base is required under the concrete, the Contractor shall select paving equipment and procedures which will operate properly on the base course without causing displacement or other damage.

3.2.2 Traffic on Underlying Material

After the underlying material has been prepared for concrete placement, no equipment shall be permitted thereon. Subject to specific approval, crossing of the prepared base course at specified intervals for construction purposes may be permitted, provided rutting or indentations do not occur; however, if traffic has been allowed to use the prepared base course, the surface shall be reworked and reprepared to the satisfaction of the Contracting Officer before concrete is placed.

3.3 WEATHER LIMITATIONS

3.3.1 Placement and Protection During Inclement Weather

The Contractor shall not commence placing operations when heavy rain or other damaging weather conditions appear imminent. At all times when placing concrete, the Contractor shall maintain on-site sufficient waterproof cover and means to rapidly place it over all unhardened concrete or concrete that might be damaged by rain. Placement of concrete shall be suspended whenever rain or other damaging weather commences to damage the surface or texture of the placed unhardened concrete, washes cement out of the concrete, or changes the water content of the surface concrete. All unhardened concrete shall be immediately covered and protected from the rain or other damaging weather. Any pavement damaged by rain or other weather shall be completely removed and replaced at the Contractor's expense as specified in paragraph, Repair, Removal, Replacement of Slabs.

3.3.2 Paving in Hot Weather

When the ambient temperature during paving is expected to exceed 32 degrees C, the concrete shall be properly placed and finished in accordance with procedures previously submitted and as specified herein. The concrete temperature at time of delivery to the forms shall not exceed the temperature shown in the table below when measured in accordance with ASTM C 1064/C 1064M. Cooling of the mixing water or aggregates or placing in the cooler part of the day may be required to obtain an adequate placing temperature. An approved retarder may be used to facilitate placing and finishing. Steel forms and reinforcing shall be cooled as approved prior to concrete placement when steel temperatures are greater than 49 degrees C. Transporting and placing equipment shall be cooled or protected if necessary to maintain proper concrete-placing temperature. Concrete shall be placed continuously and rapidly at a rate of not less than 30 m of paving lane per hour. The finished surfaces of the newly laid pavement shall be kept damp by applying a fog spray (mist) with approved spraying equipment until the pavement is covered by the curing medium. If necessary, wind screens shall be provided to protect the concrete from an evaporation rate in

excess of 1 kg/square meter per hour, as determined by method shown in Figure 2.1.5 of ACI 305R.

Maximum Allowable Concrete Placing Temperature

Relative Humidity, Percent, During Time of Concrete Placement	Maximum Allowable Concrete Temperature in Degrees C
Greater than 60	33
40-60	30
Less than 40	27

3.3.3 Prevention of Plastic Shrinkage Cracking

During hot weather with low humidity, and particularly with appreciable wind, the Contractor shall develop and institute measures to prevent plastic shrinkage cracks from developing. Particular care shall be taken if plastic shrinkage cracking is potentially imminent and especially if it has developed during a previous placement. Periods of high potential for plastic shrinkage cracking can be anticipated by use of Fig. 2.1.5 of ACI 305R. In addition to the protective measures specified in the previous paragraph, the concrete placement shall be further protected by erecting shades and windbreaks and by applying fog sprays of water, sprinkling, ponding, or wet covering. When such water treatment is stopped, curing procedures shall be immediately commenced. Plastic shrinkage cracks that occur shall be filled by injection of epoxy resin as directed, after the concrete hardens. Plastic shrinkage cracks shall never be troweled over or filled with slurry.

3.3.4 Paving in Cold Weather

Special protection measures, as submitted and approved, and as specified herein, shall be used if freezing temperatures are anticipated before the expiration of the specified curing period. The ambient temperature of the air at the placing site and the temperature of surfaces to receive concrete shall be not less 5 degrees C. However, placement may begin when both the ambient temperature and the temperature of the underlying material are at least 2 degrees C and rising. When the ambient temperature is less than 10 degrees C, the temperature of the concrete when placed shall be not less than 10 degrees C nor more than 25 degrees C. Heating of the mixing water or aggregates will be required to regulate the concrete placing temperature. Materials entering the mixer shall be free from ice, snow, or frozen lumps. Salt, chemicals or other materials shall not be incorporated in the concrete to prevent freezing. Upon written approval, chemical admixture conforming to ASTM C 494 Type C or E may be used provided it contains no calcium chloride. Calcium chloride shall not be used at any time. Covering and other means shall be provided for maintaining the concrete at a temperature of at least 10 degrees C for not less than 72 hours after placing, and at a temperature above freezing for the remainder of the curing period. Pavement damaged by freezing shall be completely removed and replaced at the Contractor's expense as specified in paragraph REPAIR, REMOVAL, REPLACEMENT OF SLABS.

3.4 CONCRETE PRODUCTION

Batching, mixing, and transporting equipment shall have a capacity sufficient to maintain a continuous, uniform forward movement of the paver of not less than 0.8 m per minute. Concrete shall be deposited in front of the paver within 45 minutes from the time cement has been charged into the mixing drum, except that if the ambient temperature is above 32

degrees C, the time shall be reduced to 30 minutes. No water shall be added to the concrete after it is batched. Every load of concrete delivered to the paving site shall be accompanied by a batch ticket from the operator of the batching plant. Tickets shall be on approved forms and shall show at least the mass, or volume, of all ingredients in each batch delivered, and the time of day. Tickets shall be delivered to the placing foreman who shall keep them on file and deliver them to the Government weekly.

3.4.1 Batching and Mixing Concrete

The batching and mixing equipment and the operation thereof shall conform to the requirements of paragraph EQUIPMENT and as specified herein. All equipment shall be kept clean and in operable condition at all times. Scale pivots and bearings shall be kept clean and free of rust. Any equipment which fails to perform as specified shall immediately be removed from use until properly repaired and adjusted, or replaced.

3.4.2 Transporting and Transfer - Spreading Operations

The transporting and transfer equipment and the operation thereof shall conform to the requirements of paragraph EQUIPMENT and as specified herein. All equipment shall be kept clean and in operable condition at all times. Non-agitating equipment shall be used only on smooth roads and for haul time less than 15 minutes at all times during the work day. No transporting equipment shall be allowed to operate on the prepared and compacted underlying material in front of the paver-finisher. A traveling surge hopper shall be used to accept the concrete from the transporting equipment, store it as necessary, and feed it evenly across the paving lane at a depth which permits the paver to operate efficiently and at a rate that permits the paver to have a continuous forward movement. Concrete shall be deposited as close as possible to its final position in the paving lane. All equipment shall be operated to discharge and transfer concrete without segregation. In no case shall dumping of concrete in discrete piles be permitted. No transfer or spreading operation which requires the use of front-end loaders, dozers, or similar equipment to distribute the concrete will be permitted. All batching and mixing, transporting, transferring, paving, and finishing shall be properly coordinated and controlled such that the paver-finisher has a continuous forward movement at a reasonably uniform speed from beginning to end of each paving lane, except for inadvertent equipment breakdown. Failure to achieve this shall require the Contractor to halt operations, regroup, and modify operations to achieve this requirement.

3.5 PAVING

3.5.1 General Requirements

The paving and finishing equipment and the operation thereof shall conform to the requirements of paragraph EQUIPMENT and as specified herein. All equipment shall be kept clean and properly operable at all times. Pavement shall be constructed with paving and finishing equipment utilizing rigid fixed forms or by use of slipform paving equipment. Paving and finishing equipment and procedures shall be capable of constructing paving lanes of the required width at a rate of at least 30 m of paving lane per hour on a routine basis. Paving equipment and its operation shall be controlled, and coordinated with all other operations, such that the paver-finisher has a continuous forward movement, at a reasonably uniform speed, from beginning to end of each paving lane, except for inadvertent equipment breakdown. Workmen with foreign material on their footwear or construction equipment that might deposit foreign material shall not be permitted to walk or operate in the plastic concrete.

3.5.2 Consolidation

Concrete shall be consolidated with the specified type of lane-spanning, gang-mounted, mechanical, immersion type vibrating equipment mounted in front of the paver, supplemented, in rare instances as specified, by hand-operated vibrators. Gang-mounted vibrator spuds shall be spaced so as to thoroughly consolidate the entire paving lane, but not more than 750 mm spacing, and with the outside vibrators not more than 300 mm from the edge of the lane. The vibrators shall be inserted into the concrete to a depth that will provide the best full-depth consolidation but not closer to the underlying material than 50 mm. The vibrators or any tamping units in front of the paver shall be automatically controlled so that they shall be stopped immediately as forward motion ceases. Excessive vibration shall not be permitted. If the vibrators cause visible tracking in the paving lane, the paving operation shall be stopped and equipment and operations modified to prevent it. Concrete in small, odd-shaped slabs or in isolated locations inaccessible to the gang-mounted vibration equipment shall be vibrated with an approved hand-operated immersion vibrator. Vibrators shall not be used to transport or spread the concrete. Hand-operated vibrators shall not be operated in the concrete at one location for more than 20 seconds. For each paving train, at least one additional vibrator spud, or sufficient parts for rapid replacement and repair of vibrators shall be maintained at the paving site at all times. Any evidence of inadequate consolidation (honeycomb along the edges, large air pockets, or any other evidence) shall require the immediate stopping of the paving operation and approved adjustment of the equipment or procedures.

3.5.3 Operation

When the paver approaches a header at the end of a paving lane, a sufficient amount of concrete shall be maintained ahead of the paver to provide a roll of concrete which will spill over the header. The amount of extra concrete shall be sufficient to prevent any slurry that is formed and carried along ahead of the paver from being deposited adjacent to the header. The spud vibrators in front of the paver shall be brought as close to the header as possible before they are lifted. Additional consolidation shall be provided adjacent to the headers by hand-manipulated vibrators. When the paver is operated between or adjacent to previously constructed pavement (fill-in lanes), provisions shall be made to prevent damage to the previously constructed pavement. Transversely oscillating screeds and extrusion plates shall overlap the existing pavement the minimum possible, but in no case more than 200 mm. These screeds or extrusion plates shall be electronically controlled from the previously placed pavement so as to prevent them from applying pressure to the existing pavement and to prevent abrasion of the pavement surface. The overlapping area of existing pavement surface shall at all times be kept completely free of any loose or bonded foreign material as the paver-finisher operates across it. When the paver travels on existing pavement, approved provisions shall be made to prevent damage to the existing pavement. Pavers using transversely oscillating screeds shall not be used to form fill-in lanes that have widths less than a full width for which the paver was designed or adjusted.

3.5.4 Required Results

The paver-finisher, and its gang-mounted vibrators, together with its operating procedures shall be adjusted and operated and coordinated with the concrete mixture being used to produce a thoroughly consolidated slab throughout, true to line and grade within specified tolerances. The screed or the extrusion plate shall be properly adjusted to produce a pavement surface true to line and grade. Any necessary adjustment to compensate for

surging behind the screed or for inadequate height of surface after paving shall be carefully made and checked frequently. The paver-finishing operation shall produce a surface finish free of irregularities, tears, voids of any kind, and any other discontinuities. It shall produce only a very minimum of paste at the surface; never more than 2.5 mm cover over the top layer of coarse aggregate. The paver-finisher shall make only one pass across the pavement; multiple passes will not be permitted. The equipment and its operation shall produce a finished surface requiring no hand finishing other than the use of cutting straightedges, except in very infrequent instances. If any equipment or operation fails to produce the above results, the paving shall be stopped, the equipment shall be replaced or properly adjusted, the operation shall be appropriately modified, or the mixture proportions modified, in order to produce the required results before recommencing paving. No water, other than true fog sprays (mist) as specified in paragraph, Prevention of Plastic Shrinkage Cracking, shall be applied to the concrete or the concrete surface during paving and finishing.

3.5.5 Fixed Form Paving

Paving equipment for fixed-form paving and the operation thereof shall conform to the requirements of paragraph EQUIPMENT, all requirements specified above under paragraph PAVING and as specified herein.

3.5.5.1 Forms for Fixed-Form Paving

a. Forms shall be steel, except that wood forms may be used for curves having a radius of 45 m or less, and for fillets. Forms shall be equal in depth to the edge thickness of the slab as shown on the drawings. Forms shall be in one piece for the full depth required, except as permitted below. Under no conditions shall forms be adjusted by filling or excavating under the forms to an elevation other than the bottom of the pavement slab. Where the project requires several different slab thicknesses, forms may be built up with metal or wood to provide an increase in depth of not more than 25 percent. The required form depth may be obtained by securely bolting or welding to the bottom of the form a tubular metal section of the proper thickness or by securely bolting wood planks to the bottom of the form. The tubular metal section or wood planks shall completely cover the underside of the base of the form and shall extend beyond the edge of the base a sufficient distance to provide the necessary stability. The base width of the one-piece form, or built-up form, shall be not less than eight-tenths of the vertical height of the form, except that forms 200 mm or less in vertical height shall have a base width not less than the vertical height of the form. Forms shall not be built-up by adding to the top. The top surface of each form section shall not vary more than 1.5 mm in 4 m from a true line. The face of the form shall not vary more than 5 mm in 4 m from a true plane. Forms with battered top surfaces or distorted faces or bases shall be removed from the project. Where keyway forms are required, they shall be rigidly attached to the main form so no displacement can take place. Metal keyway forms shall be tack-welded to steel forms. Keyway forms shall be so aligned that there is no variation over 6 mm either vertically or horizontally, when tested with a 4 m template after forms are set, including tests across form joints.

b. Steel forms shall be furnished in sections not less than 3 m in length, except that on curves having a radius of 45 m or less, the length of the sections shall be 1.5 m unless the sections are flexible or curved to the proper radius. Each 3 m length of form shall be provided with at least three form braces and pin sockets so spaced

that the form will be rigidly braced throughout its length. Lock joints between form sections shall be free from play or movement. Forms shall be free of warps, bends, or kinks.

c. Wood forms for curves and fillets shall be made of well-seasoned, surfaced plank or plywood, straight, and free from warp or bend. Wood forms shall be adequate in strength and rigidly braced.

d. The forms shall be set on firm material cut true to grade so that each form section when placed will be firmly in contact with the underlying layer for its entire length and base width. Underlying material shall be thoroughly compacted and trimmed to grade before forms are set in place. Setting forms on blocks or on built-up spots of underlying material will be not permitted under any condition. The form sections shall be staked into position and tightly locked together. The length of pins and quantity provided in each section shall be sufficient to hold the form at the correct line and grade. When tested with a straightedge, the top of the installed form shall conform to the requirements specified for the finished surface of the concrete, and the longitudinal axis of the upstanding leg shall not vary more than 6 mm from the straightedge. Conformity to the alignment and grade elevations shown on the drawings shall be checked and necessary corrections shall be made immediately prior to placing the concrete. Forms shall be set well in advance of concrete placement. The forms shall be cleaned and oiled each time before concrete is placed. No concrete shall be placed until setting of forms has been checked and approved by the CQC team.

3.5.5.2 Form Removal

Forms shall remain in place at least 12 hours after the concrete has been placed. When conditions are such that the early strength gain of the concrete is delayed, the forms shall be left in place for a longer time, as directed. Forms shall be removed by procedures that do not injure the concrete. Bars or heavy metal tools shall not be used directly against the concrete in removing the forms. Any concrete found to be defective after form removal shall be repaired promptly, using procedures specified hereinafter or as directed.

3.5.6 Slipform Paving

3.5.6.1 General

Paving equipment for slipform paving and the operation thereof shall conform to the requirement of paragraph EQUIPMENT, all requirements specified above in subparagraphs, General, Consolidation, Operation, and Required Results, and as specified herein. The slipform paver shall shape the concrete to the specified and indicated cross section, meeting all tolerances, in one pass. The slipform paver shall finish the surface and edges so that only a very minimum isolated amount of hand finishing is required. If the paving operation does not meet the above requirements and the specified tolerances, the operation shall be immediately stopped, and the Contractor shall regroup and replace or modify any equipment as necessary, modify paving procedures or modify the concrete mix, in order to resolve the problem. The slipform paver shall be automatically electronically controlled from a taut wire guideline for horizontal alignment and on both sides from a taut wire guideline for vertical alignment, except that electronic control from a ski operating on a previously constructed adjoining lane shall be used where applicable for either or both sides. Automatic, electronic

controls for vertical alignment shall always be used on both sides of the lane. Control from a slope-adjustment control or control operating from the underlying material shall never be used. If approved by the Contracting Officer after a preconstruction demonstration, automatic laser controls may be used in lieu of or to supplement the taut wire guidelines. Side forms on slipform pavers shall be properly adjusted so that the finished edge of the paving lane meets all specified tolerances. Dowels in longitudinal construction joints shall be installed as specified below. The installation of these dowels by dowel inserters attached to the paver or by any other means of inserting the dowels into the plastic concrete shall not be permitted.

3.5.6.2 Guideline for Slipform Paving

Guidelines shall be accurately and securely installed well in advance of concrete placement. Supports shall be provided at necessary intervals to eliminate all sag in the guideline when properly tightened. The guideline shall be high strength wire set with sufficient tension to remove all sag between supports. Supports shall be securely staked to the underlying material or other provisions made to ensure that the supports will not be displaced when the guideline is tightened or when the guideline or supports are accidentally touched by workmen or equipment during construction. The appliances for attaching the guideline to the supports shall be capable of easy adjustment in both the horizontal and vertical directions. When it is necessary to leave gaps in the guideline to permit equipment to use or cross underlying material, provisions shall be made for quickly and accurately replacing the guideline without any delay to the forward progress of the paver. Supports on either side of the gap shall be secured in such a manner as to avoid disturbing the remainder of the guideline when the portion across the gap is positioned and tightened. The guideline across the gap and adjacent to the gap for a distance of 60 m shall be checked for horizontal and vertical alignment after the guideline across the gap is tightened. Vertical and horizontal positioning of the guideline shall be such that the finished pavement shall conform to the alignment and grade elevations shown on the drawings within the specified tolerances for grade and smoothness. The specified tolerances are intended to cover only the normal deviations in the finished pavement that may occur under good supervision and do not apply to setting of the guideline. The guideline shall be set true to line and grade.

3.5.6.3 Laser Controls

If the Contractor proposes to use any type of automatic laser controls, a detailed description of the system shall be submitted and a trial field demonstration shall be performed in the presence of the Contracting Officer at least one week prior to start of paving. Approval of the control system will be based on the results of the demonstration and on continuing satisfactory operation during paving.

3.5.7 Placing Reinforcing Steel

The type and amount of steel reinforcement shall be as shown on the drawings. For pavement thickness of 300 mm or more, the reinforcement steel shall be installed by the strike-off method wherein a layer of concrete is deposited on the underlying material, consolidated, and struck to the indicated elevation of the steel reinforcement. The reinforcement shall be laid upon the prestruck surface, and the remaining concrete shall then be placed and finished in the required manner. When placement of the second lift causes the steel to be displaced horizontally from its original position, provisions shall be made for increasing the thickness of the first lift and depressing the reinforcement into the unhardened concrete to the required elevation. The increase in thickness shall be only as necessary to

permit correct horizontal alignment to be maintained. Any portions of the bottom layer of concrete that have been placed more than 30 minutes without being covered with the top layer shall be removed and replaced with newly mixed concrete without additional cost to the Government. For pavements less than 300 mm thick, the reinforcement shall be positioned on suitable chairs securely fastened to the subgrade prior to concrete placement. Concrete shall be vibrated after the steel has been placed. Regardless of placement procedure, the reinforcing steel shall be free from coatings which could impair bond between the steel and concrete, and laps in the reinforcement shall be as indicated. In lieu of the above, automatic reinforcement depressing attachments may be used to position the reinforcement, either bar mats or welded wire fabric, provided the entire operation is approved by the Contracting Officer. Regardless of the equipment or procedures used for installing reinforcement, the Contractor shall ensure that the entire depth of concrete is adequately consolidated.

3.5.8 Placing Dowels

The method used in installing and holding dowels in position shall ensure that the error in alignment of any dowel from its required alignment after the pavement has been completed will not be greater than 1 mm per 100 mm. Except as otherwise specified below, location of dowels shall be within a horizontal tolerance of plus or minus 15 mm. The Contractor shall furnish an approved template for checking the alignment and position of the dowels. The portion of each dowel intended to move within the concrete or expansion cap shall be painted with one coat of the specified paint. When dry, the painted portion shall be wiped clean and coated with a thin, even film of lubricating oil before the concrete is placed. Pipe used as dowels shall be filled with a stiff sand-asphalt mixture or portland-cement mortar. Dowels in joints shall be omitted when the center of the dowel is located within a horizontal distance from an intersecting joint equal to or less than one-fourth of the slab thickness. Dowels shall be installed as specified in the following subparagraphs.

3.5.8.1 Contraction Joints

Dowels in longitudinal and transverse contraction joints within the paving lane shall be held securely in place, as indicated, by means of rigid metal frames or basket assemblies of an approved type. The assemblies shall consist of a framework of metal bars or wires arranged to provide rigid support for the dowels throughout the paving operation, with a minimum of four continuous bars or wires extending along the joint line. The dowels shall be welded to the assembly or held firmly by mechanical locking arrangements that will prevent them from rising, sliding out, or becoming distorted during paving operations. The basket assemblies shall be held securely in the proper location by means of suitable pins or anchors. At the Contractor's option, in lieu of the above, dowels in contraction joints shall be installed near the front of the paver by insertion into the plastic concrete using approved equipment and procedures. Approval will be based on the results of a preconstruction demonstration which the Contractor shall conduct, showing that the dowels are installed within specified tolerances.

3.5.8.2 Construction Joints-Fixed Form Paving

Installation of dowels shall be by the bonded-in-place method. Installation by removing and replacing in preformed holes will not be permitted. Dowels shall be prepared and placed across joints where indicated, correctly aligned, and securely held in the proper horizontal and vertical position during placing and finishing operations, by means of devices fastened to the forms. The spacing of dowels in construction joints shall be as indicated, except that,

where the planned spacing cannot be maintained because of form length or interference with form braces, closer spacing with additional dowels shall be used.

3.5.8.3 Dowels Installed in Hardened Concrete

Dowels installed in hardened concrete, such as in longitudinal construction joints for slipform paving, in joints between new and existing pavement, and similar locations, shall be installed by bonding the dowels into holes drilled into the hardened concrete. The installation of dowels in longitudinal construction joints by dowel inserters attached to a slipform paver or by any other means of inserting the dowels into the plastic concrete shall not be permitted. However, when paving two lanes together with a longitudinal contraction joint between, any dowels required may be installed in this joint with an approved inserter. Holes approximately 3 mm greater in diameter than the dowels shall be drilled into the hardened concrete with rotary core drills to receive the dowels. In lieu of rotary drills, the contractor may use percussion drills, provided that spalling at the collar of the hole does not occur. Regardless of the type of drill used, the drill shall be held rigidly in exact alignment by means of a stable jig or framework, solidly supported; gang drills meeting this are acceptable. Any damage to the concrete face during drilling shall be repaired as directed; continuing damage shall require modification of the equipment and operation. Dowels shall be bonded in the drilled holes using epoxy resin. Epoxy resin shall be injected at the back of the hole before installing the dowel and extruded to the collar during insertion of the dowel so as to completely fill the void around the dowel. Application by buttering the dowel shall not be permitted. The dowels shall be held in alignment at the collar of the hole, after insertion and before the grout hardens, by means of a suitable metal or plastic collar fitted around the dowel. The vertical alignment of the dowels shall be checked by placing a straightedge on the surface of the pavement over the top of the dowel and measuring the vertical distance between the straightedge and the beginning and ending point of the exposed part of the dowel. The horizontal alignment shall be checked with a framing square. Dowels required to be installed in any joints between new and existing concrete shall be grouted in holes drilled in the existing concrete, all as specified above.

3.6 FINISHING

The finishing machine, or paver-finisher, shall meet all requirements specified in paragraph EQUIPMENT and herein. Finishing operations shall be a continuing part of placing operations starting immediately behind the strike-off of the paver and the machines shall be designed and operated to strike off, screed, and consolidate the concrete. Initial finishing shall be provided by the transverse screed or extrusion plate. The sequence of operations shall be transverse finishing, longitudinal machine floating if used, straightedge finishing, texturing, and then edging of joints. Finishing shall be by the machine method. The hand method shall be used only infrequently and only on isolated areas of odd slab widths or shapes and in the event of a breakdown of the mechanical finishing equipment. When approved, the hand finishing method may also be used for separate, isolated slabs during removal and replacement type repair operations. Supplemental hand finishing for machine finished pavement shall be kept to an absolute minimum. Equipment to be used for supplemental hand finishing shall primarily be 3 to 4 m cutting straightedges; only very sparing use of bull floats shall be allowed. Any machine finishing operation which requires appreciable hand finishing, other than a moderate amount of straightedge finishing, shall be immediately stopped and proper adjustments made or the equipment replaced. Every effort shall be made to prevent bringing excess paste to the surface and any operations which produce more than 2.5 mm paste (mortar, water, laitance, etc.) over the top layer of coarse

aggregate shall be halted immediately and the equipment, mixture, or procedures modified as necessary. Compensation shall be made for surging behind the screeds or extrusion plate and settlement during hardening and care shall be taken to ensure that paving and finishing machines are properly adjusted so that the finished surface of the concrete (not just the cutting edges of the screeds) will be at the required line and grade. Surface checks shall be made regularly and paving operations immediately halted and adjustments made whenever compensation is inadequate. Screed and float adjustments of the machines shall be checked at the start of each day's paving operations and more often if required. Machines that cause frequent delays due to mechanical failure shall be replaced. When machines ride the edge of a previously constructed slab, the edge shall be kept clean and provision shall be made to protect the surface of the slab. Clary screeds, "bridge deck" finishers, or other rotating pipe or tube type equipment will not be permitted. Finishing equipment and tools shall be maintained clean and in an approved condition. At no time shall water be added to the surface of the slab with the finishing equipment or tools, or in any other way, except for fog (mist) sprays specified to prevent plastic shrinkage cracking.

3.6.1 Longitudinal Floating

When the equipment contains a mechanical, longitudinal, oscillating float, the float shall be operated to smooth and finish the pavement immediately behind the transverse screed or extrusion plate. The float shall be operated maintaining contact with the surface at all times. Care shall be taken to prevent working paste to the surface in excess of the amount specified above.

3.6.2 Other Types of Finishing Equipment

Concrete finishing equipment of types other than those specified above may be used on a trial basis, when specifically approved, except that rotating pipe or tubes or bridge deck finishers will not be permitted. Approval will be given after demonstration on a test section prior to start of construction, and provided the Contracting Officer determines that the pavement produced is better than that produced by the specified equipment. The use of equipment that fails to produce finished concrete of the required quality, using concrete proportions and slump as specified, shall be discontinued, and the concrete shall be finished with specified equipment and in the manner specified above. Vibrating screeds or pans shall be used only for isolated slabs where hand finishing is permitted as specified, and only where specifically approved. Slipform paving equipment shall not be operated on fixed forms unless approved in writing prior to use.

3.6.3 Machine Finishing With Fixed Forms

The machine shall be designed to ride the forms and shall be operated to screed and consolidate the concrete. Machines that cause displacement of the forms shall be replaced. The machine shall make only one pass over each area of pavement. If the equipment and procedures do not produce a surface of uniform texture, true to grade, in one pass, the operation shall be immediately stopped and the equipment, mixture, and procedures adjusted as necessary.

3.6.4 Machine Finishing With Slipform Pavers

The slipform paver shall be operated so that only a very minimum of additional finishing work is required to produce pavement surfaces and edges meeting the specified tolerances. Any

equipment or procedure that fails to meet these specified requirements shall immediately be replaced or modified as necessary. A self-propelled nonrotating pipe float may be used if the Contractor desires while the concrete is still plastic, to remove minor irregularities and score marks. The pipe float shall be 150 to 250 mm in diameter and sufficiently long to span the full paving width when oriented at an angle of approximately 60 degrees with the center line. Only one pass of the pipe float shall be allowed. If there is sufficient concrete slurry or fluid paste on the surface that it runs over the edge of the pavement, the paving operation shall be immediately stopped and the equipment, mixture, or operation modified to prevent formation of such slurry. Any slurry which does run down the vertical edges shall be immediately removed by hand, using stiff brushes or scrapers. No slurry, concrete or concrete mortar shall be used to build up along the edges of the pavement to compensate for excessive edge slump, either while the concrete is plastic or after it hardens. Slabs having areas of edge slump in excess of the specified tolerances shall be removed and replaced in accordance with paragraph, REPAIR, REMOVAL, REPLACEMENT OF SLABS; repair operations on such areas will not be permitted.

3.6.5 Surface Correction and Testing

After all other finishing is completed but while the concrete is still plastic, minor irregularities and score marks in the pavement surface shall be eliminated by means of cutting straightedges. Such straightedges shall be 4 m in length and shall be operated from the sides of the pavement and from bridges. A straightedge operated from the side of the pavement shall be equipped with a handle 1 m longer than one-half the width of the pavement. The surface shall then be tested for trueness with a straightedge held in successive positions parallel and at right angles to the center line of the pavement, and the whole area covered as necessary to detect variations. The straightedge shall be advanced along the pavement in successive stages of not more than one-half the length of the straightedge. Depressions shall be immediately filled with freshly mixed concrete, struck off, consolidated, and refinished. Projections above the required elevation shall also be struck off and refinished. The straightedge testing and finishing shall continue until the entire surface of the concrete is free from observable departure from the straightedge and conforms to the surface requirements specified in paragraph ACCEPTABILITY OF WORK AND PAYMENT ADJUSTMENTS. Long-handled, flat bull floats shall be used very sparingly and only as necessary to correct minor, scattered surface defects. If frequent use of bull floats is necessary, the paving operation shall be stopped and the equipment, mixture or procedures adjusted to eliminate the surface defects. Finishing with hand floats and trowels shall be held to the absolute minimum necessary. Extreme care shall be taken to prevent overfinishing joints and edges. The surface finish of the pavement shall be produced essentially by the finishing machine and not by subsequent hand finishing operations. All hand finishing operations shall be subject to approval and shall be modified when directed. No water shall be added to the pavement surface during these operations.

3.6.6 Hand Finishing

Hand finishing operations shall be used only as specified above.

3.6.6.1 Equipment

In addition to approved mechanical internal vibrators for consolidating the concrete, a strike-off and tamping template and a longitudinal float shall be provided for hand finishing. The template shall be at least 300 mm longer than the width of pavement being finished, of an

approved design, and sufficiently rigid to retain its shape, and shall be constructed of metal or other suitable material shod with metal. The longitudinal float shall be at least 3 m long, of approved design, and rigid and substantially braced, and shall maintain a plane surface on the bottom . Grate tampers (jitterbugs) shall not be used.

3.6.6.2 Finishing and Floating

As soon as placed and vibrated, the concrete shall be struck off and screeded to the crown and cross section and to such elevation above grade that when consolidated and finished, the surface of the pavement will be at the required elevation. In addition to previously specified complete coverage with handheld immersion vibrators, the entire surface shall be tamped with the strike-off and tamping template, and the tamping operation continued until the required compaction and reduction of internal and surface voids are accomplished (grate tampers shall not be used). Immediately following the final tamping of the surface, the pavement shall be floated longitudinally from bridges resting on the side forms and spanning but not touching the concrete. If necessary, additional concrete shall be placed and screeded, and the float operated until a satisfactory surface has been produced. The floating operation shall be advanced not more than half the length of the float and then continued over the new and previously floated surfaces. Long-handled, flat bull floats shall be used very sparingly and only as necessary to correct minor, scattered surface defects. If frequent use of bull floats is necessary, the operation shall be stopped and adjusted to eliminate the surface defects. Finishing with hand floats and trowels shall be held to the absolute minimum necessary. Extreme care shall be taken to prevent overfinishing joints and edges. No water shall be added to the pavement during finishing operations.

3.6.7 Texturing

Before the surface sheen has disappeared and before the concrete hardens, the surface of the pavement shall be given a texture as described herein. After curing is complete, all textured surfaces shall be thoroughly power broomed to remove all debris.

3.6.7.1 Fabric Drag Surface Finish

Surface texture shall be applied by dragging the surface of the pavement, in the direction of the concrete placement, with an approved fabric drag. The drag shall be operated with the fabric moist, and the fabric shall be cleaned or changed as required to keep clean. The dragging shall be done so as to produce a uniform finished surface having a fine sandy texture without disfiguring marks.

3.6.7.2 Broom Texturing

Surface texture shall be applied using an approved mechanical stiff bristle broom drag of a type that will uniformly score the surface. The broom shall be operated to score the surface transverse to the pavement centerline. The broom shall be capable of traversing the full width of the pavement in a single pass at a uniform speed and with a uniform pressure. Successive passes of the broom shall be overlapped the minimum necessary to obtain a uniformly textured surface. Brooms shall be washed thoroughly at frequent intervals during use. Worn or damaged brooms shall be removed from the job site. Brooming should be completed before the concrete has hardened to the point where the surface will be unduly torn or roughened, but after hardening has progressed enough so that the mortar will not flow and reduce the sharpness of the scores. Specific requirements for the texturing will be given

on the drawings, but, if not given, the scores shall be uniform in appearance and approximately 1.5 mm in depth but not more than 3 mm in depth. Hand brooming will be permitted only on isolated odd shaped slabs or slabs where hand finishing is permitted. For hand brooming, the brooms shall have handles longer than half the width of slab to be finished. The hand brooms shall be drawn transversely across the surface from the centerline to each edge with slight overlapping strokes.

3.6.8 Edging

After texturing has been completed, the edge of the slabs along the forms, along the edges of slipformed lanes, and at the joints shall be carefully finished with an edging tool to form a smooth rounded surface of 3 mm radius. Tool marks shall be eliminated, and the edges shall be smooth and true to line. No water shall be added to the surface during edging. Extreme care shall be taken to prevent overworking the concrete.

3.6.9 Outlets in Pavement

Recesses for the tie-down anchors, lighting fixtures, and other outlets in the pavement shall be constructed to conform to the details and dimensions shown. The concrete in these areas shall be carefully finished to provide a surface of the same texture as the surrounding area that will be within the requirements for plan grade and surface smoothness.

3.7 CURING

3.7.1 Protection of Concrete

Concrete shall be continuously protected against loss of moisture and rapid temperature changes for at least 7 days from the completion of finishing operations. Unhardened concrete shall be protected from rain and flowing water. All equipment needed for adequate curing and protection of the concrete shall be on hand and ready for use before actual concrete placement begins. Sufficient sheet material to protect unhardened concrete from rain shall be at the paver at all times. Protection shall be provided as necessary to prevent cracking of the pavement due to temperature changes during the curing period. If any selected method of curing does not afford the proper curing and protection against concrete cracking, the damaged pavement shall be removed and replaced, and another method of curing shall be employed as directed. Curing shall be accomplished by one of the following methods.

3.7.2 Membrane Curing

A uniform coating of white-pigmented, membrane-forming, curing compound shall be applied to the entire exposed surface of the concrete as soon as the free water has disappeared from the surface after finishing. If evaporation is high and no moisture is present on the surface even though bleeding has not stopped, fog sprays shall be used to keep the surface moist until setting of the cement occurs and bleeding is complete. Curing compound shall then be immediately applied. Along the formed edge faces, it shall be applied immediately after the forms are removed. Concrete shall not be allowed to dry before the application of the membrane. If any drying has occurred, the surface of the concrete shall be moistened with a fine spray of water, and the curing compound applied as soon as the free water disappears. The curing compound shall be applied to the finished surfaces by means of an approved automatic spraying machine. The spraying machine shall be self-propelled and shall span the newly paved lane. The machine shall have one or more spraying nozzles that can be

controlled and operated to completely and uniformly cover the pavement surface with the required amount of curing compound. The curing compound in the drum used for the spraying operation shall be thoroughly and continuously agitated mechanically throughout the full depth of the drum during the application. Air agitation may be used only to supplement mechanical agitation. Spraying pressure shall be sufficient to produce a fine spray as necessary to cover the surface thoroughly and completely with a uniform film. Spray equipment shall be kept clean and properly maintained and the spray nozzle or nozzles shall have adequate wind shields. The curing compound shall be applied with an overlapping coverage that will give a two-coat application at a coverage of 10 square meters per L, plus or minus 5.0 percent for each coat. A one-coat application may be applied provided a uniform application and coverage of 5 square meters per L, plus or minus 5.0 percent is obtained. The application of curing compound by hand-operated, mechanical powered pressure sprayers will be permitted only on odd widths or shapes of slabs where indicated and on concrete surfaces exposed by the removal of forms. When the application is made by hand-operated sprayers, the second coat shall be applied in a direction approximately at right angles to the direction of the first coat. The compound shall form a uniform, continuous, cohesive film that will not check, crack, or peel and that will be free from pinholes and other discontinuities. If pinholes, abrasions, or other discontinuities exist, an additional coat shall be applied to the affected areas within 30 minutes. Concrete surfaces that are subjected to heavy rainfall within 3 hours after the curing compound has been applied shall be resprayed by the method and at the coverage specified above. Areas where the curing compound is damaged by subsequent construction operations within the curing period shall be immediately resprayed. The surfaces adjacent to joint sawcuts shall be cleaned and resprayed with curing compound immediately after cutting. Approved standby facilities for curing concrete pavement shall be provided at an accessible location at the job site for use in the event of mechanical failure of the spraying equipment or other conditions that might prevent correct application of the membrane-curing compound at the proper time. Concrete surfaces to which membrane-curing compounds have been applied shall be adequately protected during the entire curing period from pedestrian and vehicular traffic, except as required for joint-sawing operations and surface tests, and from any other possible damage to the continuity of the membrane.

3.7.3 Moist Curing

Concrete to be moist-cured shall be maintained continuously wet for the entire curing period, or until curing compound is applied, commencing immediately after finishing. If forms are removed before the end of the curing period, curing shall be carried out as on unformed surfaces, using suitable materials. Surfaces shall be cured by ponding, by continuous sprinkling, by continuously saturated burlap or cotton mats, or by continuously saturated plastic coated burlap. Burlap and mats shall be clean and free from any contamination and shall be completely saturated before being placed on the concrete. The Contractor shall have an approved work system to ensure that moist curing is continuous 24 hours per day and that the entire surface is wet.

3.8 JOINTS

3.8.1 General Requirements for Joints

Joints shall conform to the details indicated and shall be perpendicular to the finished grade of the pavement. All joints shall be straight and continuous from edge to edge or end to end of the pavement with no abrupt offset and no gradual deviation greater than 12 mm. Before

commencing construction, the Contractor shall submit for approval a control plan and equipment to be used for ensuring that all joints are straight from edge to edge of the pavement within the above tolerances. Where any joint fails to meet these tolerances, the slabs adjacent to the joint shall be removed and replaced at no additional cost to the Government. No change from the jointing pattern shown on the drawings shall be made without written approval of the Contracting Officer. Sealing of joints shall be in accordance with Section 02760 (A) FIELD MOLDED SEALANTS FOR SEALING JOINTS IN RIGID PAVEMENTS or Section 02762 (A) COMPRESSION JOINT SEALS FOR CONCRETE PAVEMENTS.

3.8.2 Longitudinal Construction Joints

Longitudinal construction joints between paving lanes shall be located as indicated. Dowels shall be installed in the longitudinal construction joints, or the edges shall be thickened as indicated. Dowels shall be installed in conformance with paragraph, Placing Dowels. After the end of the curing period, longitudinal construction joints shall be sawed to provide a groove at the top for sealant conforming to the details and dimensions indicated.

3.8.3 Transverse Construction Joints

Transverse construction joints shall be installed at the end of each day's placing operations and at any other points within a paving lane when concrete placement is interrupted for 30 minutes or longer. When concrete placement cannot be continued, the transverse construction joint shall be installed at a planned transverse joint, if possible. Transverse construction joints shall be constructed by utilizing headers and the very minimum amount of hand placement and finishing techniques. Pavement shall be constructed with the paver as close to the header as possible, and the paver shall be run out completely past the header. Transverse construction joints installed at a planned transverse joint shall be constructed as shown or, if not shown otherwise, shall be dowelled. Those not at a planned transverse joint shall be constructed with tie bars and shall not be sawed or sealed.

3.8.4 Expansion Joints

Expansion joints shall be formed where indicated, and about any structures and features that project through or into the pavement, using joint filler of the type, thickness, and width indicated, and shall be installed to form a complete, uniform separation between the structure and the pavement. The filler shall be attached to the original concrete placement with adhesive or other fasteners and shall extend the full slab depth. Adjacent sections of filler shall be fitted tightly together, and the filler shall extend across the full width of the paving lane or other complete distance in order to prevent entrance of concrete into the expansion space. Edges of the concrete at the joint face shall be finished with an edger with a radius of 3 mm. The joint filler strips shall be installed 20 mm below the pavement surface with a slightly tapered, dressed-and-oiled wood strip or other approved material temporarily secured to the top of the filler to form a recess to be filled with joint sealant. The wood strip shall be removed soon after the concrete has set and the reservoir temporarily filled with an approved material to protect the reservoir until the joint sealer is installed. Expansion joints shall be constructed with thickened edges for load transfer.

3.8.5 Slip Joints

Slip joints shall be installed where indicated using the specified materials. Preformed joint filler material shall be attached to the face of the original concrete placement with adhesive or other fasteners. Bituminous material shall be applied to cover the entire surface of the face of the original concrete placement to a depth of 6 mm plus or minus 1.5 mm. Only a material which will remain in place on the vertical surface shall be used. In each case a 20 mm deep reservoir for joint sealant shall be constructed at the top of the joint. Edges of the joint face shall be finished with an edger with a radius of 3 mm.

3.8.6 Contraction Joints

Transverse and longitudinal contraction joints shall be of the weakened-plane or dummy type and shall be constructed as indicated. Longitudinal contraction joints shall be constructed by sawing a groove in the hardened concrete with a power-driven saw in conformance with requirements for sawed joints, unless otherwise approved in writing. Transverse contraction joints shall be constructed in conformance with requirements for sawed joints.

3.8.6.1 Sawed Joints

Sawed contraction joints shall be constructed by sawing an initial groove in the concrete with a 3 mm blade to the indicated depth. During sawing of joints, and again 24 hours later, the CQC team shall inspect all exposed lane edges for development of cracks below the saw cut, and shall immediately report results to the Contracting Officer. If the Contracting Officer determines that there are more uncracked joints than desired, the Contractor will be directed to saw succeeding joints 25 percent deeper than originally indicated at no additional cost to the Government. After expiration of the curing period, the upper portion of the groove shall be widened by sawing to the width and depth indicated for the joint sealer. The time of initial sawing shall vary depending on existing and anticipated weather conditions and shall be such as to prevent uncontrolled cracking of the pavement. Sawing of the joints shall commence as soon as the concrete has hardened sufficiently to permit cutting the concrete without chipping, spalling, or tearing. The sawed faces of joints will be inspected for undercutting or washing of the concrete due to the early sawing, and sawing shall be delayed if undercutting is sufficiently deep to cause structural weakness or excessive roughness in the joint. The sawing operation shall be carried on as required during both day and night regardless of weather conditions. The joints shall be sawed at the required spacing consecutively in the sequence of the concrete placement. A chalk line or other suitable guide shall be used to mark the alignment of the joint. Before sawing a joint, the concrete shall be examined closely for cracks, and the joint shall not be sawed if a crack has occurred near the planned joint location. Sawing shall be discontinued when a crack develops ahead of the saw cut. Workmen and inspectors shall wear clean, rubber-soled footwear, and the number of persons walking on the pavement shall be limited to those actually performing the sawing operation. Immediately after the joint is sawed, the saw cut and adjacent concrete surface shall be thoroughly flushed with water until all waste from sawing is removed from the joint. The surface shall be resprayed with curing compound as soon as free water disappears. Necessary precautions shall be taken to insure that the concrete is properly cured at sawed joints, but that no curing compound enters the joints. The top of the joint opening and the joint groove at exposed edges shall be tightly sealed with cord, backer rod, or other approved material before the concrete in the region of the joint is resprayed with curing compound. The method used for sealing the joint groove shall prevent loss of moisture from the joint during the entire specified curing period and shall prevent infiltration of foreign material until removed

immediately before sawing joint sealant reservoir. The sawing equipment shall be adequate in the number of units and the power to complete the sawing at the required rate. An ample supply of saw blades shall be available on the job before concrete placement is started and at all times during sawing. At least one standby sawing unit in good working order shall be available at the jobsite at all times during the sawing operation.

3.8.7 Thickened Edge Joints

Thickened edge joints shall be constructed as indicated on the drawings. Underlying material in the transition area shall be graded as shown and shall meet the requirements for smoothness and compaction specified for all other areas of the underlying material.

3.8.8 Special Joints

"Special joints" (undercut joints) shall be constructed adjacent to existing pavement as indicated. The concrete under the edge of the existing pavement and the concrete below the normal level of the bottom of the new pavement shall be placed as a separate operation in front of the paving train. The concrete shall be worked under the edge of the existing pavement to completely fill the void and shall be thoroughly consolidated by the use of hand-held vibrators. Timing shall be such that this concrete is still workable when the paving train goes across it. In no case shall this concrete be placed as part of the operation of the paving equipment.

3.8.9 Sealing Joints

Joints shall be sealed immediately following curing of the concrete or as soon thereafter as weather conditions permit. Joints shall be sealed as specified in Section 02760 (A) FIELD MOLDED SEALANTS FOR SEALING JOINTS IN RIGID PAVEMENTS where new rigid pavement abuts existing rigid pavement, and 02762 (A) COMPRESSION JOINT SEALS FOR CONCRETE PAVEMENTS for all new rigid pavements.

3.9 REPAIR, REMOVAL, REPLACEMENT OF SLABS

3.9.1 General Criteria

New pavement slabs that are broken or contain cracks shall be removed and replaced or repaired, as specified hereinafter at no cost to the Government. Spalls along joints shall be repaired as specified. Where removal of partial slabs is permitted, as specified, removal and replacement shall be full depth, shall be full width of the paving lane, and the limit of removal shall be normal to the paving lane and not less than 3 m from each original transverse joint (i.e., removal portion shall be at least 3 m longitudinally, and portion to remain in place shall be at least 3 m longitudinally; thus, if original slab length is less than 6 m, the entire slab shall be removed). The Contracting Officer will determine whether cracks extend full depth of the pavement and may require cores to be drilled on the crack to determine depth of cracking. Such cores shall be at least 150 mm diameter, shall be drilled by the Contractor and shall be filled by the Contractor with a well consolidated concrete mixture bonded to the walls of the hole with epoxy resin, using approved procedures. Drilling of cores and refilling holes shall be at no expense to the Government. All epoxy resin used in this work shall conform to paragraph EPOXY RESIN, Type and Grade as specified.

3.9.2 Slabs with Cracks Thru Interior Areas

Interior area is defined as that area more than 600 mm from either adjacent original transverse joint. Slabs with any cracks that extend into the interior area, regardless of direction, shall be treated by one of the following procedures.

3.9.2.1 Cracks That Do Not Extend Full Depth of Slab

These cracks, and similar cracks within the areas 600 mm each side of transverse joints, shall be cleaned and then pressure injected with epoxy resin, Type IV, Grade 1, using procedures as approved. The procedure shall not widen the crack during epoxy resin injection. All epoxy resin injection shall take place in the presence of a representative of the Contracting Officer.

3.9.2.2 Cracks That Extend Full Depth of Slab

Where there is any full depth crack at any place within the interior area, the full slab shall be removed. However, if the cracked area all lies within 3 m of one original transverse joint, only a partial slab need be removed provided all criteria specified above for distance from each original transverse joint is met.

3.9.3 Cracks close to and Parallel to Transverse Joints

All cracks essentially parallel to original transverse joints, extending full depth of the slab, and lying wholly within 600 mm either side of the joint shall be treated as specified hereinafter. Any crack extending more than 600 mm from the transverse joint shall be treated as specified above for Slabs With Cracks Through Interior Areas. Any cracks which do not extend full depth of the slab shall be treated as specified above in subparagraph, Cracks That Do Not Extend Full Depth Of Slab, and the original transverse joint constructed as originally designed.

3.9.3.1 Full Depth Cracks Present, Original Joint Not Opened

When the original transverse joint has not opened, the crack shall be routed and sealed, and the original transverse joint filled with epoxy resin. The crack shall be routed with an easily guided, wheel mounted, vertical shaft, powered rotary router designed so the routing spindle will caster as it moves along the crack, or with a small diameter saw designed for this use. The reservoir for joint sealant in the crack shall be formed by routing to a depth of 19 mm, plus or minus 1.5 mm, and to a width of 16 mm, plus or minus 3 mm. Any equipment or procedure which causes raveling or spalling along the crack shall be modified or replaced to prevent such raveling or spalling. The joint sealant shall be a liquid sealant as specified for rigid pavement joints. Installation of joint seal shall be as specified for sealing joints or as directed. The uncracked transverse joint shall be filled with epoxy resin. If the joint sealant reservoir has been sawed out, the reservoir and as much of the lower saw cut as possible shall be filled with epoxy resin, Type IV, Grade 2, thoroughly tooled into the void using approved procedures. If only the original narrow saw cut has been made, it shall be cleaned and pressure injected with epoxy resin, Type IV, Grade 1, using approved procedures. If filler material (joint insert) has been used to form a weakened plane in the transverse joint, it shall be completely sawed out and the saw cut pressure injected with epoxy resin, Type IV, Grade 1, using approved procedures. Where a parallel crack goes part way across the paving lane and then intersects and follows the original transverse joint which is cracked only for the

remainder of the width, it shall be treated as follows: The area with the separate crack shall be treated as specified above for a parallel crack, and the cracked original joint shall be prepared and sealed as originally designed.

3.9.3.2 Full Depth Cracks, Original Joint Also Cracked

At a transverse joint, if there is any place in the lane width where a parallel crack and a cracked portion of the original joint overlap, a section of the slab containing the crack shall be removed and replaced for the full lane width and at least 3 m long. If this partial slab removal places the limit of removal less than 3 m from the next transverse joint, the entire slab shall be removed. If the parallel crack crosses the transverse joint line, a similar area shall be removed and replaced in both slabs.

3.9.4 Removal and Replacement of Full Slabs

Where it is necessary to remove full slabs, unless there are keys or dowels present, all edges of the slab shall be cut full depth with a concrete saw. All saw cuts shall be perpendicular to the slab surface. If keys, dowels, or tie bars are present along any edges, these edges shall be sawed full depth 150 mm from the edge if only keys are present, or just beyond the end of dowels or tie bars if they are present. These joints shall then be carefully sawed on the joint line to within 25 mm of the depth of the dowel or key. The main slab shall be further divided by sawing full depth, at appropriate locations, and each piece lifted out and removed. Suitable equipment shall be used to provide a truly vertical lift, and approved safe lifting devices used for attachment to the slabs. The narrow strips along keyed or doweled edges shall be carefully broken up and removed using light, hand-held jackhammers, 14 kg or less, or other approved similar equipment. Care shall be taken to prevent damage to the dowels, tie bars, or keys or to concrete to remain in place. The joint face below keys or dowels shall be suitably trimmed so that there is no abrupt offset in any direction greater than 12 mm and no gradual offset greater than 25 mm when tested in a horizontal direction with a straightedge. No mechanical impact breakers, other than the above hand-held equipment shall be used for any removal of slabs. If underbreak between 37 and 100 mm deep occurs at any point along any edge, the area shall be repaired as directed before replacing the removed slab. Procedures directed will be similar to those specified for surface spalls, modified as necessary. If underbreak over 100 mm deep occurs, the entire slab containing the underbreak shall be removed and replaced. Where there are no dowels, tie bars, or keys on an edge, or where they have been damaged, dowels of the size and spacing as specified for other joints in similar pavement shall be installed by epoxy grouting them into holes drilled into the existing concrete using procedures as specified in paragraph, Placing Dowels and Tie Bars. Original damaged dowels or tie bars shall be cut off flush with the joint face. Protruding portions of dowels shall be painted and lightly oiled. All four edges of the new slab shall thus contain dowels or original keys or original tie bars. Placement of concrete shall be as specified for original construction. Prior to placement of new concrete, the underlying material shall be recompacted and shaped as specified in the appropriate section of these specifications, and the surfaces of all four joint faces shall be cleaned of all loose material and contaminants and coated with a double application of membrane forming curing compound as bond breaker. Care shall be taken to prevent any curing compound from contacting dowels or tie bars. The resulting joints around the new slab shall be prepared and sealed as specified for original construction.

3.9.5 Removal and Replacement of Partial Slabs

Where the above criteria permits removal of partial slabs, removal and replacement operations shall be as specified for full slabs, except that the joint between the removed area and the partial slab to remain in place shall consist of a full depth saw cut across the full lane width and perpendicular to the centerline of the paving lane. Replacement operations shall be the same as specified above, except that, at the joint between the removed area and the partial slab to remain, deformed tie bars shall be epoxy resin grouted into holes drilled into the slab to remain in place. Size and spacing of the tie bars shall be as specified for dowels. Drilling of holes and installation of tie bars shall be as specified for dowels in paragraph, Placing Dowels and Tie Bars, except that no portion of the tie bars shall be painted or oiled. No curing compound shall be used on this joint face and, immediately before placing new concrete, the joint surface of the partial slab remaining in place shall be coated with epoxy resin, Type V, Grade 2.

3.9.6 Repairing Spalls Along Joints

Where directed, spalls along joints of new slabs, along edges of adjacent existing concrete, and along parallel cracks shall be repaired by first making a vertical saw cut at least 25 mm outside the spalled area and to a depth of at least 50 mm. Saw cuts shall be straight lines forming rectangular areas. The concrete between the saw cut and the joint, or crack, shall be chipped out to remove all unsound concrete and at least a depth of 12 mm of visually sound concrete. The cavity thus formed shall be thoroughly cleaned with high pressure water jets supplemented with compressed air to remove all loose material. Immediately before filling the cavity, a prime coat shall be applied to the dry cleaned surface of all sides and bottom of the cavity, except any joint face. The prime coat shall be applied in a thin coating and scrubbed into the surface with a stiff-bristle brush. Prime coat for portland cement repairs shall be a neat cement grout and for epoxy resin repairs shall be epoxy resin, Type III, Grade 1. The cavity shall be filled with low slump portland cement concrete or mortar or with epoxy resin concrete or mortar. Portland cement concrete shall be used for larger spalls, those more than 0.009 cubic meter in size after removal operations; portland cement mortar shall be used for spalls between 0.00085 cubic meter and 0.009 cubic meter; and epoxy resin mortar or Type III, Grade 3 epoxy resin for those spalls less than 0.00085 cubic meter in size after removal operations. Portland cement concretes and mortars shall be very low slump mixtures, 12 mm slump or less, proportioned, mixed, placed, consolidated by tamping, and cured, all as directed. Epoxy resin mortars shall be made with Type III, Grade 1, epoxy resin, using proportions and mixing and placing procedures as recommended by the manufacturer and approved by the Contracting Officer. The epoxy resin materials shall be placed in the cavity in layers not over 50 mm thick. The time interval between placement of additional layers shall be such that the temperature of the epoxy resin material does not exceed 60 degrees C at any time during hardening. Mechanical vibrators and hand tampers shall be used to consolidate the concrete or mortar. Any repair material on the surrounding surfaces of the existing concrete shall be removed before it hardens. Where the spalled area abuts a joint, an insert or other bond-breaking medium shall be used to prevent bond at the joint face. A reservoir for the joint sealant shall be sawed to the dimensions required for other joints, or as required to be routed for cracks. The reservoir shall be thoroughly cleaned and then sealed with the sealer specified for the joints. If any spall penetrates half the depth of the slab or more, the entire slab, or 3 m portion thereof, shall be removed and replaced as previously specified. In lieu of sawing, spalls not adjacent to joints, and popouts, both less than 150 mm in maximum dimension, may be prepared by drilling a core 50 mm in diameter greater than the size of the defect, centered over the defect, and 50 mm deep or 12 mm into sound

concrete, whichever is greater. The core hole shall be repaired as specified above for other spalls.

3.10 EXISTING CONCRETE PAVEMENT REMOVAL AND REPAIR

Existing concrete pavement shall be removed as indicated and as specified in Section 02220 DEMOLITION, modified, and expanded as specified herein. Repairs shall be made as indicated and as specified herein. All operations shall be carefully controlled to prevent damage to the concrete pavement and to the underlying material to remain in place. All saw cuts shall be made perpendicular to the slab surface, and forming rectangular areas.

3.10.1 Removal of Existing Pavement Slab

When existing concrete pavement is to be removed and adjacent concrete is to be left in place, the joint between the removal area and adjoining pavement to stay in place shall first be cut full depth with a standard diamond-type concrete saw. Next, a full depth saw cut shall be made parallel to the joint at least 600 mm from the joint. This saw cut shall be made with a wheel saw as specified in paragraph SAWING EQUIPMENT. All pavement to be removed beyond this last saw cut shall be removed using equipment and procedures specified in Section 02220 (A) DEMOLITION and as approved. All pavement between this last saw cut and the joint line shall be removed by carefully pulling pieces and blocks away from the joint face with suitable equipment and then picking them up for removal. In lieu of this method, this strip of concrete may be carefully broken up and removed using hand-held jackhammers, 14 kg or less, or other approved light-duty equipment which will not cause stress to propagate across the joint saw cut and cause distress in the pavement which is to remain in place. In lieu of the above specified removal method, the slab may be sawcut full depth to divide it into several pieces and each piece lifted out and removed. Suitable equipment shall be used to provide a truly vertical lift, and safe lifting devices used for attachment to the slab.

3.10.2 Edge Repair

The edge of existing concrete pavement against which new pavement abuts shall be protected from damage at all times. Areas which are damaged during construction shall be repaired at no cost to the Government; repair of previously existing damage areas will be considered a subsidiary part of concrete pavement construction.

3.10.2.1 Spall Repair

Spalls along joints and along cracks shall be repaired where indicated and where directed. Repair materials and procedures shall be as previously specified in subparagraph, Repairing Spalls Along Joints.

3.10.2.2 Underbreak Repair

All underbreak shall be repaired. First, all delaminated and loose material shall be carefully removed. Next, the underlying material shall be recompacted, without addition of any new material. Finally, the void shall be completely hand-filled with paving concrete mixture, thoroughly consolidated. Care shall be taken to produce an even joint face from top to bottom. Prior to placing concrete, the underlying material shall be thoroughly moistened.

After placement, the exposed surface shall be heavily coated with curing compound. All this shall be done at least 24 hours before placing the new paving concrete against the joint.

3.10.2.3 Underlying Material

The underlying material adjacent to the edge of and under the existing pavement which is to remain in place shall be protected from damage or disturbance during removal operations and until placement of new concrete, and shall be shaped as shown on the drawings or as directed. Sufficient underling material shall be kept in place outside the joint line to completely prevent disturbance of material under the pavement which is to remain in place. Any material under the portion of the concrete pavement to remain in place which is disturbed or loses its compaction shall be carefully removed and replaced with concrete as specified above under Underbreak Repair. The underlying material outside the joint line shall be thoroughly compacted and shall be moist when new concrete is placed.

3.11 PAVEMENT PROTECTION

The Contractor shall protect the pavement against all damage prior to final acceptance of the work by the Government. Aggregates rubble, or other similar construction materials shall not be piled on airfield pavements. Traffic shall be excluded from the new pavement by erecting and maintaining barricades and signs until the concrete is at least 14 days old, or for a longer period if so directed. As a construction expedient in paving intermediate lanes between newly paved pilot lanes, operation of the hauling equipment will be permitted on the new pavement after the pavement has been cured for 7 days and the joints have been sealed or otherwise protected. Also, the subgrade planer, concrete paving and finishing machines, and similar equipment may be permitted to ride upon the edges of previously constructed slabs when the concrete has attained a minimum flexural strength of 2.8 MPa and approved means are furnished to prevent damage to the slab edge. All new and existing pavement carrying construction traffic or equipment shall be continuously kept completely clean, and spillage of concrete or other materials shall be cleaned up immediately upon occurrence. Special care shall be used where Contractor's traffic uses or crosses active airfield pavement. In these areas, if necessary in order to accomplish this, full-time workmen with hand brooms shall be used at anytime there is traffic. Other existing pavements used by the Contractor shall be power broomed at least daily when traffic operates. For fill-in lanes, equipment shall be used that will not damage or spall the edges or joints of the previously constructed pavement.

3.12 TESTING AND INSPECTION FOR CONTRACTOR QUALITY CONTROL

3.12.1 Testing and Inspection by Contractor

The Contractor shall perform the inspection and tests described below, and based upon the results of these inspections and tests, shall take the action required and submit reports as required. When, in the opinion of the Contracting Officer, the paving operation is out of control, concrete placement shall cease. The laboratory performing the tests shall be on-site and shall conform with ASTM C 1077. The individuals who sample and test concrete or the constituents of concrete as required in this specification shall have demonstrated a knowledge and ability to perform the necessary test procedures equivalent to the ACI minimum guidelines for certification of Concrete Field Testing Technicians, Grade I. The individuals who perform the inspection of concrete shall have demonstrated a knowledge and ability equivalent to the ACI minimum guidelines for certification of Concrete Construction Inspector, Level II. The Government will inspect the laboratory, equipment, and test

procedures prior to start of concreting operations and at least once per year thereafter for conformance with ASTM C 1077. This testing shall be performed by the Contractor regardless of any other testing performed by the Government, either for pay adjustment purposes or for any other reason.

3.12.2 Testing and Inspection Requirements

3.12.2.1 Fine Aggregate

a. Grading. At least once during each shift when the concrete plant is operating, there shall be one sieve analysis and fineness modulus determination in accordance with ASTM C 136 and COE CRD-C 104 for the fine aggregate or for each fine aggregate if it is batched in more than one size or classification. The location at which samples are taken may be selected by the Contractor as the most advantageous for control. However, the Contractor is responsible for delivering fine aggregate to the mixer within specification limits.

b. Corrective Action for Fine Aggregate Grading. When the amount passing on any sieve is outside the specification limits, the fine aggregate shall be immediately resampled and retested. If there is another failure on any sieve, the fact shall be immediately reported to the Contracting Officer, paving shall be stopped, and immediate steps taken to correct the grading.

3.12.2.2 Coarse Aggregate

a. Grading. At least once during each shift in which the concrete plant is operating, there shall be a sieve analysis in accordance with ASTM C 136 for each size of coarse aggregate. The location at which samples are taken may be selected by the Contractor as the most advantageous for production control. However, the Contractor shall be responsible for delivering the aggregate to the mixer within specification limits. A test record of samples of aggregate taken at the same locations shall show the results of the current test as well as the average results of the five most recent tests including the current test. The Contractor may adopt approved limits for control coarser than the specification limits for samples taken other than as delivered to the mixer to allow for degradation during handling.

b. Corrective Action for Grading. When the amount passing any sieve is outside the specification limits, the coarse aggregate shall be immediately resampled and retested. If the second sample fails on any sieve, that fact shall be reported to the Contracting Officer, and steps taken to correct the grading. Where two consecutive averages of 5 tests are outside specification limits, the operation shall be considered out of control and shall be reported to the Contracting Officer, paving shall be stopped, and immediate steps shall be taken to correct the grading.

3.12.2.3 Quality of Aggregates

Thirty days prior to the start of concrete placement, the Contractor shall perform all tests specified for aggregate quality, including deleterious materials. In addition, after the start of paving, the Contractor shall perform similar tests for aggregate quality at least once every month, and when the source of aggregate or aggregate quality changes. Testing interval may be increased to three months when the previous two tests indicate the aggregate meets all

quality requirements. Samples tested after the start of concrete placement shall be taken immediately prior to entering the concrete mixer.

3.12.2.4 Scales, Batching and Recording

a. Weighing Accuracy. The accuracy of the scales shall be checked by test weights prior to start of concrete operations and at least once every month for conformance with specified requirements. Such tests shall also be made as directed whenever there are variations in properties of the fresh concrete that could result from batching errors.

b. Batching and Recording Accuracy. Once a week the accuracy of each batching and recording device shall be checked during a weighing operation by noting and recording the required mass, recorded mass, and the actual mass batched. The Contractor shall test and ensure that the devices for dispensing admixtures are operating properly and accurately.

c. Corrective Action. When either the weighing accuracy or batching accuracy does not comply with specification requirements, the plant shall not be operated until necessary adjustments or repairs have been made. Discrepancies in recording accuracies shall be corrected immediately.

3.12.2.5 Batch-Plant Control

The measurement of all constituent materials including cementitious materials, each size of aggregate, water, and admixtures shall be continuously controlled. The aggregate masses and amount of added water shall be adjusted as necessary to compensate for free moisture in the aggregates. The amount of air-entraining agent shall be adjusted to control air content within specified limits. A report shall be prepared indicating type and source of cement used, type and source of pozzolan or slag used, amount and source of admixtures used, aggregate source, the required aggregate and water masses per cubic meter, amount of water as free moisture in each size of aggregate, and the batch aggregate and water masses per cubic meter for each class of concrete batched during each day's plant operation.

3.12.2.6 Concrete Mixture

a. Air Content Testing. Air content tests shall be made when test specimens are fabricated. In addition, at least two other tests for air content shall be made on randomly selected batches of each separate concrete mixture produced during each 8-hour period of paving. Additional tests shall be made when excessive variation in workability is reported by the placing foreman or Government inspector. Tests shall be made in accordance with ASTM C 231. Test results shall be plotted on control charts which are kept current and shall, at all times, be readily available to the Government and shall be submitted weekly. Copies of the current control charts shall be kept in the field by testing crews and results plotted as tests are made. When a single test result reaches either the upper or lower action limit, a second test shall immediately be made. The results of the two tests shall be averaged and this average used as the air content of the batch to plot on both the air content and the control chart for range, and for determining need for any remedial action. The result of each test, or average as noted in the previous sentence, shall be plotted on a separate control chart for each mixture on which an

average line is set at the midpoint of the specified air content range from paragraph SPECIFIED CONCRETE STRENGTH AND OTHER PROPERTIES. An upper warning limit and a lower warning limit line shall be set 1.0 percentage point above and below the average line, respectively. An upper action limit and a lower action limit line shall be set 1.5 percentage points above and below the average line, respectively. The range between each two consecutive tests shall be plotted on a secondary control chart for range where an upper warning limit is set at 2.0 percentage points and an upper action limit is set at 3.0 percentage points. Samples for air content shall be taken at the paving site. The Contractor shall deliver the concrete to the paving site at the stipulated air content. If the Contractor's materials or transportation methods cause air content loss between the mixer and the paving site, correlation samples shall be taken at the paving site as required by the Contracting Officer, and the air content at the mixer controlled as directed.

b. Air Content Corrective Action. Whenever points on the control chart for percent air reach either warning limit, an adjustment shall immediately be made in the amount of air-entraining admixture batched. As soon as practical after each adjustment, another test shall be made to verify the result of the adjustment. Whenever a point on the secondary control chart for range reaches the warning limit, the admixture dispenser shall be recalibrated to insure that it is operating accurately and with good reproducibility. Whenever a point on either control chart (single test or result of two tests made concurrently, as specified above) reaches an action limit line, the air content shall be considered out of control and the paving operation shall immediately be halted until the air content is under control. Additional air content tests shall be made when paving is restarted.

c. Slump Testing. Slump tests shall be made when test specimens are fabricated. In addition, at least four other slump tests shall be made on randomly selected batches in accordance with ASTM C 143 for each separate concrete mixture produced during each 8-hour or less period of concrete production each day. Also, additional tests shall be made when excessive variation in workability is reported by the placing foreman or Government inspector. Test results shall be plotted on control charts which shall at all times be readily available to the Government and shall be submitted weekly. Copies of the current control charts shall be kept in the field by testing crews and results plotted as tests are made. When a single slump test reaches or goes beyond the upper action limit, a second test shall immediately be made. The results of the two tests shall be averaged and this average used as the slump of the batch to plot on both the control chart for slump and the chart for range, and for determining need for any remedial action. An upper warning limit shall be set at 12 mm below the maximum allowable slump on separate control charts for slump used for each type of mixture as specified in paragraph, SPECIFIED CONCRETE STRENGTH AND OTHER PROPERTIES, and an upper action limit line shall be set at the maximum allowable slump, as specified in the same paragraph for fixed form paving or as selected by the Contractor at the start of the project for slipform paving. The range between each consecutive slump test for each type of mixture shall be plotted on a single control chart for range on which an upper action limit is set at 38 mm. Samples for slump shall be taken at the paving site. The Contractor is responsible for delivering the concrete to the paving site at the stipulated slump. If the Contractor's materials or transportation methods cause slump loss between the mixer and the paving site, correlation samples shall

be taken at the paving site as required by the Contracting Officer, and the slump at the mixer controlled as directed.

d. Slump Corrective Action. Whenever points on the control charts for slump reach the upper warning limit, an approved adjustment shall immediately be made in the batch masses of water and fine aggregate. The adjustments are to be made so that the total water content does not exceed that amount allowed by the maximum w/c specified, based on aggregates which are in a saturated surface dry condition. When a slump result (average of two tests made concurrently, as specified above) exceeds the upper action limit, no further concrete shall be delivered to the paving site until proper adjustments have been made. Immediately after each adjustment, another test shall be made to verify the correctness of the adjustment. Whenever two consecutive individual slump tests, made during a period when there was no adjustment of batch masses, produce a point on the control chart for range at or above the upper action limit, the paving operation shall immediately be halted, and the Contractor shall take approved steps to bring the slump under control. Additional slump tests shall be made as directed.

e. Temperature. The temperature of the concrete shall be measured when compressive strength specimens are fabricated. Measurement shall be in accordance with ASTM C 1064/C 1064M. The temperature shall be reported along with the compressive strength data.

3.12.2.7 Concrete Strength Testing for CQC

Contractor Quality Control operations for concrete strength shall consist of the following steps:

a. Take samples for strength tests at the paving site. Fabricate and cure test cylinders in accordance with ASTM C 31/C 31M; test them in accordance with ASTM C 39.

b. Fabricate and cure 2 test cylinders per sublot from the same batch or truckload and at the same time acceptance cylinders are fabricated and test them for compressive strength at 7-day age.

c. Average all 8 compressive tests per lot. Convert this average 7-day compressive strength per lot to equivalent 90-day flexural strength using the Correlation Ratio determined during mixture proportioning studies.

d. Compare the equivalent 28-day flexural strength from the conversion to the Average Flexural Strength Required for Mixtures from paragraph of same title.

e. If the equivalent average 28-day strength for the lot is below the Average Flexural Strength Required for Mixtures by 138 kPa flexural strength or more, at any time, adjust the mixture to increase the strength, as approved.

f. If the equivalent average 28-day strength is above the Average Flexural Strength Required for Mixtures by 138 kPa flexural strength or more for 2 consecutive days, the Contractor will be permitted to adjust the mixture to decrease the strength, as approved.

g. The Contractor's CQC testing agency shall maintain up-to-date control charts for strength, showing the 7-day CQC compressive strength, the 14-day compressive strength (from acceptance tests) and the 28-day equivalent flexural strength of each of these for each lot.

3.12.2.8 Inspection Before Placing

Underlying materials, construction joint faces, forms, reinforcing, dowels, and embedded items shall be inspected by the Contractor in sufficient time prior to each paving operation in order to certify to the Contracting Officer that they are ready to receive concrete. The results of each inspection shall be reported in writing.

3.12.2.9 Paving

a. Paving Inspection. The placing foreman shall supervise all placing and paving operations, shall determine that the correct quality of concrete is placed in each location as shown and that finishing is performed as specified; shall be responsible for measuring and recording concrete temperatures and ambient temperature hourly during placing operations, weather conditions, time of placement, volume of concrete placed, and method of paving and any problems encountered.

b. Placing and Paving Corrective Action. The paving foreman shall not permit batching and paving to begin until it has been verified that an adequate number of vibrators in working order and with competent operators are available. Paving shall not be continued if piles of concrete exist or if the concrete is inadequately consolidated or if surface finish is not satisfactory. If any batch of concrete fails to meet the temperature requirements, immediate steps shall be taken to improve temperature controls.

3.12.2.10 Vibrators

a. Vibrator Testing and Use. The frequency and amplitude of each vibrator shall be determined in accordance with COE CRD-C 521 prior to initial use and at least once a month when paving is in progress. Additional tests shall be made as directed when a vibrator does not appear to be adequately consolidating the concrete. The frequency shall be determined while the vibrator is operating in concrete with the tachometer being held against the upper end of the vibrator head while almost submerged and just before the vibrator is withdrawn from the concrete. The amplitude shall be determined with the head vibrating in air. Two measurements shall be taken, one near the tip and another near the upper end of the vibrator head, and these results averaged. The make, model, type, and size of the vibrator and frequency and amplitude results shall be reported in writing.
b. Vibrator Corrective Action. Any vibrator not meeting the requirements of subparagraphs, Paver-Finisher and Consolidation, shall be immediately removed from service and repaired or replaced.

3.12.2.11 Curing Inspection

a. Moist Curing Inspections. At least twice each shift, and not less than four times per day (never more than 7 hours apart) on both work and non-work days, an

inspection shall be made of all areas subject to moist curing. The surface moisture condition shall be noted and recorded.

b. Moist Curing Corrective Action. When any inspection finds an area of inadequate curing, immediate corrective action shall be taken, and the required curing period for the area shall be extended by 1 day.

c. Membrane Curing Inspection. No curing compound shall be applied until the Contractor has verified that the compound is properly mixed and ready for spraying. At the end of each day's operation, the quantity of compound used shall be determined by measurement of the container and the area of concrete surface covered; the Contractor shall then compute the rate of coverage in square meters per L and shall also note whether or not coverage is uniform. All this shall be reported daily.

d. Membrane Curing Corrective Action. When the coverage rate of the curing compound is less than that specified or when the coverage is not uniform, the entire surface shall be sprayed again.

e. Sheet Curing Inspection. At least once each shift and once per day on non-work days, an inspection shall be made of all areas being cured using impervious sheets. The condition of the covering and the tightness of the laps and tapes shall be noted and recorded.

f. Sheet Curing Corrective Action. When a daily inspection report lists any tears, holes, or laps or joints that are not completely closed, the tears and holes shall promptly be repaired or the sheets replaced, the joints closed, and the required curing period for those areas shall be extended by 1 day.

3.12.2.12 Cold-Weather Protection

At least once each shift and once per day on non-work days, an inspection shall be made of all areas subject to cold-weather protection. Any deficiencies shall be noted, corrected, and reported.

3.12.2.13 Mixer Uniformity

a. Stationary Mixers. Prior to the start of concrete placing and once every 4 months when concrete is being placed, or once for every 38,000 cubic meters of concrete placed, whichever results in the longest time interval, uniformity of concrete mixing shall be determined in accordance with COE CRD-C 55. The original test shall be a Regular Test. After the mixing operation has been tested and approved, subsequent tests shall be Abbreviated Tests.

b. Truck Mixers. Prior to the start of concrete placing and at least once every 4 months when concrete is being placed, uniformity of concrete mixing shall be determined in accordance with ASTM C 94/C 94M. The truck mixers shall be selected randomly for testing. When satisfactory performance is found in one truck mixer, the performance of mixers of substantially the same design and condition of the blades may be regarded as satisfactory.

c. Mixer Uniformity Corrective Action. When a mixer fails to meet mixer uniformity requirements, either the mixing time shall be increased, batching sequence changed, batch size reduced, or adjustments shall be made to the mixer until compliance is achieved. After adjustments have been made, another uniformity test shall be made.

3.12.2.14 Reports

All results of tests or inspections conducted shall be reported informally as they are completed and in writing daily. A weekly report shall be prepared for the updating of control charts covering the entire period from the start of the construction season through the current week. During periods of cold-weather protection, reports of pertinent temperatures shall be made daily. These requirements do not relieve the Contractor of the obligation to report certain failures immediately as required in preceding paragraphs. Such reports of failures and the action taken shall be confirmed in writing in the routine reports. The Contracting Officer has the right to examine all contractor quality control records.

END OF SECTION

SECTION 02760 (A)

FIELD MOLDED SEALANTS FOR SEALING JOINTS IN RIGID PAVEMENTS

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in this text by the basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 509	(1994) Elastomeric Cellular Preformed Gasket and Sealing Material
ASTM D 789	(1998) Determination of Relative Viscosity and Moisture Content of Polyamide (PA)
ASTM D 5893	(1996) Cold Applied, Single Component Chemically Curing Silicon Joint Sealant for Portland Cement Concrete Pavement

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Product Data

Manufacturer's Recommendations; G, RE.

Where installation procedures, or any part thereof, are required to be in accordance with the manufacturer's recommendations, printed copies of these recommendations, 30 days prior to use on the project. Installation of the material will not be allowed until the recommendations are received. Failure to furnish these recommendations can be cause for rejection of the material.

Construction Equipment List.

List of proposed equipment to be used in performance of construction work including descriptive data, 30 days prior to use on the project.

Samples

Materials; G, RE.

This page intentionally blank

Samples of the materials (sealant, primer if required, and backup material), in sufficient quantity for testing and approval 30 days prior to the beginning of work. No material will be allowed to be used until it has been approved.

1.3 TEST REQUIREMENTS

The joint sealant and backup or separating material shall be tested for conformance with the referenced applicable material specification. Testing of the materials shall be performed in an approved independent laboratory and certified copies of the test reports shall be submitted and approved 30 days prior to the use of the materials at the job site. Samples will be retained by the Government for possible future testing should the materials appear defective during or after application. Conformance with the requirements of the laboratory tests specified will not constitute final acceptance of the materials. Final acceptance will be based on the performance of the in-place materials.

1.4 EQUIPMENT

Machines, tools, and equipment used in the performance of the work required by this section shall be approved before the work is started and shall be maintained in satisfactory condition at all times.

1.4.1 Joint Cleaning Equipment

1.4.1.1 Concrete Saw

A self-propelled power saw with water-cooled diamond or abrasive saw blades will be provided for cutting joints to the depths and widths specified or for refacing joints or cleaning sawed joints where sandblasting does not provide a clean joint.

1.4.1.2 Sandblasting Equipment

Sandblasting equipment shall include an air compressor, hose, and long-wearing venturi-type nozzle of proper size, shape and opening. The maximum nozzle opening should not exceed 6.4 mm (1/4 inch). The air compressor shall be portable and shall be capable of furnishing not less than 71 liters per second (150 cubic feet per minute) and maintaining a line pressure of not less than 621 kPa (90 psi) at the nozzle while in use. Compressor capability under job conditions must be demonstrated before approval. The compressor shall be equipped with traps that will maintain the compressed air free of oil and water. The nozzle shall have an adjustable guide that will hold the nozzle aligned with the joint approximately 1 inch above the pavement surface. The height, angle of inclination and the size of the nozzle shall be adjusted as necessary to secure satisfactory results.

1.4.1.3 Waterblasting Equipment

Waterblasting equipment shall include a trailer-mounted water tank, pumps, high-pressure hose, wand with safety release cutoff control, nozzle, and auxiliary water resupply equipment. The water tank and auxiliary resupply equipment shall be of sufficient capacity to permit continuous operations. The nozzle shall have an adjustable guide that will hold the nozzle aligned with the joint approximately 1 inch above the pavement surface. The height, angle of inclination and the size of the nozzle shall be adjustable as necessary to obtain satisfactory

results. A pressure gauge mounted at the pump shall show at all times the pressure in pounds per square inch at which the equipment is operating.

1.4.1.4 Hand Tools

Hand tools may be used, when approved, for removing defective sealant from a crack and repairing or cleaning the crack faces.

1.4.2 Sealing Equipment

1.4.2.1 Cold-Applied, Single-Component Sealing Equipment

The equipment for installing ASTM D 5893 single component joint sealants shall consist of an extrusion pump, air compressor, following plate, hoses, and nozzle for transferring the sealant from the storage container into the joint opening. The dimension of the nozzle shall be such that the tip of the nozzle will extend into the joint to allow sealing from the bottom of the joint to the top. The initially approved equipment shall be maintained in good working condition, serviced in accordance with the supplier's instructions, and shall not be altered in any way without obtaining prior approval. Small hand-held air-powered equipment (i.e., caulking guns) may be used for small applications.

1.5 TRIAL JOINT SEALANT INSTALLATION

Prior to the cleaning and sealing of the joints for the entire project, a test section of at least 60 m long shall be prepared using the specified materials and approved equipment, so as to demonstrate the proposed joint preparation and sealing of all types of joints in the project. Following the completion of the test section and before any other joint is sealed, the test section shall be inspected to determine that the materials and installation meet the requirements specified. If it is determined that the materials or installation do not meet the requirements, the materials shall be removed, and the joints shall be recleaned and resealed at no cost to the Government. When the test section meets the requirements, it may be incorporated into the permanent work and paid for at the contract unit price per linear foot for sealing items scheduled. All other joints shall be prepared and sealed in the manner approved for sealing the test section.

1.6 DELIVERY AND STORAGE

Materials delivered to the job site shall be inspected for defects, unloaded, and stored with a minimum of handling to avoid damage. Storage facilities shall be provided by the Contractor at the job site for maintaining materials at the temperatures and conditions recommended by the manufacturer.

1.7 ENVIRONMENTAL CONDITIONS

The ambient air temperature and the pavement temperature within the joint wall shall be a minimum of 10 degrees C and rising at the time of application of the materials. Sealant shall not be applied if moisture is observed in the joint.

PART 2 PRODUCTS

2.1 SEALANTS

Materials for sealing joints between new and existing rigid pavements indicated on the drawings shall be ASTM D 5893.

2.2 PRIMERS

Primers, when their use is recommended by the manufacturer of the sealant, shall be as recommended by the manufacturer of the sealant.

2.3 BACKUP MATERIALS

The backup material shall be a compressible, nonshrinking, nonstaining, nonabsorbing material and shall be nonreactive with the joint sealant. The material shall have a melting point at least 3 degrees C greater than the pouring temperature of the sealant being used when tested in accordance with ASTM D 789. The material shall have a water absorption of not more than 5 percent of the sample weight when tested in accordance with ASTM C 509. The backup material shall be 25 plus or minus 5 percent larger in diameter than the nominal width of the crack.

2.4 BOND BREAKING TAPES

The bond breaking tape or separating material shall be a flexible, nonshrinkable, nonabsorbing, nonstaining, and nonreacting adhesive-backed tape. The material shall have a melting point at least 3 degrees C greater than the pouring temperature of the sealant being used when tested in accordance with ASTM D 789. The bond breaker tape shall be approximately 3 mm wider than the nominal width of the joint and shall not bond to the joint sealant.

PART 3 EXECUTION

3.1 PREPARATION OF JOINTS

Immediately before the installation of the sealant, the joints shall be thoroughly cleaned to remove all laitance, curing compound, filler, protrusions of hardened concrete, and old sealant from the sides and upper edges of the joint space to be sealed.

3.1.1 Existing Sealant Removal

The in-place sealant shall be cut loose from both joint faces and to the depth shown on the drawings, using the concrete saw as specified in paragraph EQUIPMENT. Depth shall be sufficient to accommodate any separating or backup material that is required to maintain the depth of new sealant to be installed. Prior to further cleaning operations, all loose old sealant remaining in the joint opening shall be removed by blowing with compressed air. Hand tools may be required to remove sealant from random cracks. Chipping, spalling, or otherwise damaging the concrete will not be allowed.

3.1.2 Sawing

3.1.2.1 Facing of Joints

Facing of joints shall be accomplished using a concrete saw as specified in paragraph EQUIPMENT to saw through sawed and filler-type joints to loosen and remove material until the joint is clean and open to the full specified width and depth. The blade shall be stiffened with a sufficient number of suitable dummy (used) blades or washers. Immediately following the sawing operation, the joint opening shall be thoroughly cleaned using a water jet to remove all saw cuttings and debris.

3.1.2.2 Refacing of Random Cracks

Sawing of the cracks shall be accomplished using a power-driven concrete saw as specified in paragraph EQUIPMENT. The saw blade shall be 152 mm (6 inch) or less in diameter to enable the saw to follow the trace of the crack. The blade shall be stiffened as necessary with suitable dummy (or used) blades or washers. Immediately following the sawing operation, the crack opening shall be thoroughly cleaned using a water jet to remove all saw cuttings and debris.

3.1.3 Sandblasting

The newly exposed concrete joint faces and the pavement surfaces extending a minimum of 13 mm from the joint edges shall be sandblasted and/or waterblasted clean. A multiple-pass technique shall be used until the surfaces are free of dust, dirt, curing compound, filler, old sealant residue, or any foreign debris that might prevent the bonding of the sealant to the concrete. After final cleaning and immediately prior to sealing, the joints shall be blown out with compressed air and left completely free of debris and water.

3.1.4 Back-Up Material

When the joint opening is of a greater depth than indicated for the sealant depth, the lower portion of the joint opening shall be plugged or sealed off using a back-up material to prevent the entrance of the sealant below the specified depth. Care shall be taken to ensure that the backup material is placed at the specified depth and is not stretched or twisted during installation.

3.1.5 Bond Breaking Tape

Where inserts or filler materials contain bitumen, or the depth of the joint opening does not allow for the use of a backup material, a bond breaker separating tape will be inserted to prevent incompatibility with the filler materials and three-sided adhesion of the sealant. The tape shall be securely bonded to the bottom of the joint opening so it will not float up into the new sealant.

3.1.6 Rate of Progress of Joint Preparation

The stages of joint preparation which include sandblasting, air pressure cleaning and placing of the back-up material shall be limited to only that lineal footage that can be sealed during the same day.

3.2 PREPARATION OF SEALANT

3.2.1 Single-Component, Cold-Applied Sealants

The ASTM D 5893 sealant and containers shall be inspected prior to use. Any materials that contain water, hard caking of any separated constituents, nonreversible jell, or materials that are otherwise unsatisfactory shall be rejected. Settlement of constituents in a soft mass that can be readily and uniformly remixed in the field with simple tools will not be cause for rejection.

3.3 INSTALLATION OF SEALANT

3.3.1 Time of Application

Joints shall be sealed immediately following final cleaning of the joint walls and following the placement of the separating or backup material. Open joints that cannot be sealed under the conditions specified, or when rain interrupts sealing operations shall be recleaned and allowed to dry prior to installing the sealant.

3.3.2 Sealing Joints

Immediately preceding, but not more than 15 m ahead of the joint sealing operations, a final cleaning with compressed air shall be performed. The joints shall be filled from the bottom up to 3 mm plus or minus 1.5 mm below the pavement surface. Excess or spilled sealant shall be removed from the pavement by approved methods and shall be discarded. The sealant shall be installed in such a manner as to prevent the formation of voids and entrapped air. In no case shall gravity methods or pouring pots be used to install the sealant material. Traffic shall not be permitted over newly sealed pavement until authorized by the Contracting Officer. When a primer is recommended by the manufacturer, it shall be applied evenly to the joint faces in accordance with the manufacturer's instructions. Joints shall be checked frequently to ensure that the newly installed sealant is cured to a tack-free condition within the time specified.

3.4 INSPECTION

3.4.1 Joint Cleaning

Joints shall be inspected during the cleaning process to correct improper equipment and cleaning techniques that damage the concrete pavement in any manner. Cleaned joints shall be approved prior to installation of the separating or back-up material and joint sealant.

3.4.2 Joint Sealant Application Equipment

The application equipment shall be inspected to ensure conformance to temperature requirements and proper installation. Evidences of bubbling, improper installation, failure to cure or set shall be cause to suspend operations until causes of the deficiencies are determined and corrected.

3.4.3 Joint Sealant

The joint sealant shall be inspected for proper rate of cure and set, bonding to the joint walls, cohesive separation within the sealant, reversion to liquid, entrapped air and voids. Sealants exhibiting any of these deficiencies at any time prior to the final acceptance of the project shall be removed from the joint, wasted, and replaced as specified herein at no additional cost to the Government.

3.5 CLEAN-UP

Upon completion of the project, all unused materials shall be removed from the site and the pavement shall be left in a clean condition.

END OF SECTION

SECTION 02762 A

COMPRESSION JOINT SEALS FOR CONCRETE PAVEMENTS

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in this text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 2628	(1991; R 1998) Preformed Polychloroprene Elastomeric Joint Seals for Concrete Pavements
ASTM D 2835	(1989; R 1998) Lubricant for Installation of Preformed Compression Seals in Concrete Pavements

CORPS OF ENGINEERS (COE)

COE CRD-C 548	(1988) Jet-Fuel and Heat Resistant Preformed Polychloroprene Elastomeric Joint Seals for Rigid Pavements

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Product Data

Equipment

List of proposed equipment to be used in the performance of construction work, including descriptive data, 30 days prior to use on the project.

Manufacturer's Instructions; G, RE

Where installation procedures are required in accordance with the manufacturer's recommendations, printed copies of manufacturers' instructions, 30 days prior to use on the project.

Samples

Compression Seals; G, RE

Regardless of testing responsibility, 1.2 meter long samples of the materials, 30 days prior to use on the project. Printed directions from the manufacturer on recommended installation criteria shall be furnished with the samples plus the manufacturer's certification that the selected seal is recommended for the installation on this project.

Test Reports

Test Requirements; G, RE

Certified copies of test results, 30 days prior to use of material on the project.

1.4 TEST REQUIREMENTS

Each lot of compression joint seal and lubricant/adhesive shall be sampled, identified, and tested for conformance with the applicable material specification. A lot of compression seal shall consist of 1 day's production or 6,000 meters for each cross section, whichever is less. A lot of lubricant/adhesive shall consist of 1 day's production. Testing of the compression joint seal and lubricant/adhesive material shall be the responsibility of the Contractor and shall be performed in an approved independent laboratory, and certified copies of the test reports shall be submitted for approval 30 days prior to the use of the materials at the jobsite. Samples of each lot of material shall also be submitted and will be retained by the Government for possible future testing should the materials appear defective during or after application. The Contractor shall furnish additional samples of materials, in sufficient quantity to be tested, upon request. Final acceptance will be based on conformance to the specified test requirements and the performance of the in-place materials.

1.5 EQUIPMENT

Machines, tools, and equipment used in the performance of the work required by this section shall be approved before the work is started and shall be maintained in satisfactory condition at all times.

1.5.1 Joint Cleaning Equipment

1.5.1.1 Concrete Saw

A self-propelled power saw with water-cooled diamond saw blades shall be provided for cutting joints to the depths and widths specified and for removing filler, existing old joint seal, or other material embedded in the joints or adhered to the joint faces.

1.5.1.2 Sandblasting Equipment

Sandblasting equipment shall include an air compressor, hose, and a long-wearing venturi-type nozzle of proper size, shape, and opening. The maximum nozzle opening should not exceed 6 mm. The air compressor shall be portable and shall be capable of furnishing not less than 4200 liters per minute and maintaining a line pressure of not less than 620 kPa at the nozzle while in use. The compressor shall be equipped with traps that will maintain the compressed air free of oil and water. The nozzle shall have an adjustable guide that will hold the nozzle aligned with the joint about 25 mm above the pavement surface and will direct the

blast to clean the joint walls. The height, angle of inclination, and the size of the nozzle shall be adjusted as necessary to ensure satisfactory results.

1.5.1.3 Waterblasting Equipment

Waterblasting equipment shall include a trailer-mounted water tank, pumps, high-pressure hose, a wand with safety release cutoff controls, nozzle, and auxiliary water resupply equipment. The water tank and auxiliary water resupply equipment shall be of sufficient capacity to permit continuous operations. The pumps, hoses, wand, and nozzle shall be of sufficient capacity to permit the cleaning of both walls of the joint and the pavement surface for a width of at least 12 mm on either side of the joint. A pressure gauge mounted at the pump shall show at all times the pressure in kPa psi at which the equipment is operating.

1.5.2 Sealing Equipment

Equipment used to install the compression seal shall place the compression seal to the prescribed depths within the specified tolerances without cutting, nicking, twisting, or otherwise damaging the seal. The equipment shall be capable of placing the seal with not more than two percent longitudinal stretch or compression of the seal during installation. The machine shall be an automatic self-propelled joint seal application equipment and engine powered. The machine shall include a reservoir for the lubricant/adhesive, a device for conveying the lubricant/adhesive in the proper quantities to the sides of the compression seal or the sidewalls of the joints, a reel capable of holding one full spool of compression seal, and a power-driven apparatus for feeding the joint seal through a compression device and inserting the seal into the joint. The equipment shall also include a guide to maintain the proper course along the joint being sealed. The machine shall at all times be operated by an experienced operator.

1.6 TRIAL JOINT SEAL AND LUBRICANT/ADHESIVE INSTALLATION

Prior to the cleaning and sealing of the joints for the entire project, a test section at least 69 meters long shall be prepared at a designated location in the project pavement, using the specified materials and the approved equipment to demonstrate the proposed joint preparation and sealing of all types of joints in the project. Following the completion of the trial length and before any other joint is sealed, the trial joints will be inspected by the Government to determine that the materials and installation meet the requirements specified. If materials or installation do not meet requirements, the materials shall be removed, and the joints shall be recleaned and resealed at no cost to the Government. No other joints shall be sealed until the test installation has been approved. If the trial section is approved, it may be incorporated into the permanent work. Other joints shall be sealed in the manner approved for sealing the trial joint.

1.7 DELIVERY AND STORAGE

Materials delivered to the jobsite shall be inspected for defects, unloaded, and stored with a minimum of handling to avoid damage. Storage facilities shall protect materials from weather and shall maintain materials at temperatures recommended by the manufacturer.

1.8 ENVIRONMENTAL CONDITIONS

The ambient temperature and the pavement temperature within the joint wall shall be at least 16 degrees C and rising at the time of installation of the materials. Sealant installation will not be allowed if moisture or foreign material is observed in the joint.

PART 2 PRODUCTS

2.1 COMPRESSION SEALS

Compression joint seal materials shall be a vulcanized elastomeric compound using polychloroprene as the only base polymer. The material and manufactured seal shall conform to ASTM D 2628 and COE CRD-C 548 where jet fuel and/or heat blast resistance is required. The joint seal shall be a labyrinth type seal. The uncompressed depth of the face of the compression seal (that is to be bonded to the joint wall) shall be greater than the uncompressed width of the seal. The actual width of the uncompressed seal for construction and contraction joints shall be 21 mm, and for expansion joints shall be 32 mm. The tolerance on the seal shall be plus 3 mm or minus 1.5 mm.

2.2 LUBRICANT/ADHESIVE

Lubricant/adhesive used for the compression elastomeric joint seal shall be a one-component compound conforming to ASTM D 2835.

PART 3 EXECUTION

3.1 PREPARATION OF JOINTS

Immediately before installation of the compression joint seal, the joints shall be thoroughly cleaned to remove laitance, filler, existing sealer, foreign material and protrusions of hardened concrete from the sides and upper edges of the joint space to be sealed. Cleaning shall be by sandblasting or waterblasting and shall extend along pavement surfaces at least 12 mm on either side of the joint. After final cleaning and immediately prior to sealing, the joints shall be blown out with compressed air and left completely free of debris and water. The Contractor shall demonstrate that the selected cleaning operation meets the cleanliness requirements. Any irregularity in the joint face which would prevent uniform contact between the joint seal and the joint face shall be corrected prior to the installation of the joint seal.

3.1.1 Sawing

Joints shall be cleaned and opened to the specified width and depth by sawing. Immediately following the sawing operation, the joint faces and opening shall be thoroughly cleaned using a water jet to remove saw cuttings or debris remaining on the faces or in the joint opening. Compression seal shall be installed within 3 calendar days of the time the joint cavity is sawed. Depth of the joint cavity shall be per manufacturer's instructions. The saw cut for the joint seal cavity shall be centered over the joint line. The nominal width of the sawed joint seal cavity shall be as follows; the actual width shall be within a tolerance of plus or minus 1.5 mm:

a. If a nominal 20.6 mm wide compression seal is furnished, the nominal width of the saw cut shall be 14.3 mm when the pavement temperature at the time of sawing is

between -4 and +60 degrees C. If the pavement temperature at the time of sawing is above this range, the nominal width of the saw cut shall be decreased 1.5 mm. If the pavement temperature at the time of sawing is below this range, the nominal width of the saw cut shall be increased 1.5 mm.

b. The pavement temperature shall be measured in the presence of the Contracting Officer. Measurement shall be made each day before commencing sawing and at any other time during the day when the temperature appears to be varying from the allowable sawing range.

3.1.2 Sandblast Cleaning

A multiple pass sandblasting technique shall be used until the surfaces are free of dust, dirt, curing compound, or any residue that might prevent ready insertion or uniform contact of the seal and bonding of the lubricant/adhesive to the concrete.

3.1.3 Waterblast Cleaning

A multiple pass waterblast technique shall be used until the surfaces are free of dust, dirt, curing compound, or any residue that might prevent ready insertion or uniform contact of the seal and bonding of the lubricant/adhesive to the concrete.

3.1.4 Rate of Progress

Sandblasting or waterblasting of joint faces shall be limited to the length of joint that can be sealed during the same workday.

3.2 INSTALLATION OF THE COMPRESSION SEAL

3.2.1 Time of Installation

Joints shall be sealed immediately within 3 calendar days of sawing the joint seal cavity and following concrete cure and the final cleaning of the joint walls. Open joints ready for sealing that cannot be sealed under the specified conditions shall be provided with an approved temporary seal to prevent infiltration of foreign material. When rain interrupts the sealing operations, the joints shall be washed, air pressure cleaned, and allowed to dry prior to installing the lubricant/adhesive and compression seal.

3.2.2 Sequence of Installation

Longitudinal joints shall be sealed first, followed by transverse joints. Seals in longitudinal joints shall be installed so that all transverse joint seals will be intact from edge to edge of the pavement. Intersections shall be made monolithic by use of joint seal adhesive and care in fitting the intersection parts together. Extender pieces of seal shall not be used at intersections. Any seal falling short at the intersection shall be removed and replaced with new seal at no additional cost to the Government. Seals that are required to change direction by more than 20 degrees, may require a poured sealant at the intersection. Poured sealant shall be per compression seal manufacturer's instructions.

3.3 SEALING OF JOINTS

The sides of the joint seal or the sides of the joint shall be covered with a coating of lubricant/adhesive and the seal installed as specified. Butt joints and seal intersections shall be coated with liberal applications of lubricant/ adhesive. Lubricant/adhesive spilled on the pavement shall be removed immediately to prevent setting on the pavement. The in-place joint seal shall be in an upright position and free from twisting, distortion, and cuts. Adjustments shall be made to the installation equipment and procedure, if the stretch exceeds 1 percent. Any seal exceeding 2 percent stretch shall be removed and replaced. The joint seal shall be placed at a uniform depth within the tolerances specified. In-place joint seal which fails to meet the specified requirements shall be removed and replaced with new joint seal at no cost to the Government. The compression joint seal shall be placed to a depth of 6 mm, plus or minus 3 mm, below the pavement surface except when the joint is beveled or has a radius at the surface, or unless otherwise directed. For beveled joints or joints with a radius at the surface, the compression joint seal shall be installed at a depth of 3 mm, plus or minus 3 mm, below the bottom of the edge of the bevel or radius. No part of the seal shall be allowed to project above the surface of the pavement or above the edge of the bevel or radius. The seal shall be installed in the longest practicable lengths in longitudinal joints and shall be cut at the joint intersections to provide continuous installation of the seal in the transverse joints. The lubricant/adhesive in the longitudinal joints shall be allowed to set for 1 hour prior to cutting at the joint intersections to reduce the possibility of shrinkage. For all transverse joints, the minimum length of the compression joint seal shall be the pavement width from edge to edge.

3.4 CLEAN-UP

Upon completion of the project, all unused materials shall be removed from the site, any lubricant/adhesive on the pavement surface shall be removed, and the pavement shall be left in clean condition.

3.5 QUALITY CONTROL PROVISIONS

3.5.1 Application Equipment

The application equipment shall be inspected to assure uniform application of lubricant/adhesive to the sides of the compression joint seal or the walls of the joint. If any equipment causes cutting, twisting, nicking, excessive stretching or compressing of the seal, or improper application of the lubricant/adhesive, the operation shall be suspended until causes of the deficiencies are determined and corrected.

3.5.2 Procedures

3.5.2.1 Quality Control Inspection

Quality control provisions shall be provided during the joint cleaning process to prevent or correct improper equipment and cleaning techniques that damage the concrete in any manner. Cleaned joints shall be approved by the Government prior to installation of the lubricant/adhesive and compression joint seal.

3.5.2.2 Conformance to Stretching and compression Limitations

Conformance to stretching and compression limitations shall be determined. The top surface of the compression seal shall be marked at 305 mm intervals in a manner clear and durable

to enable length determinations of the seal. After installation, the distance between the marks shall be measured on the seal. If the stretching or compression exceeds 2 percent, the seal shall be removed and replaced with new joint at no additional cost to the Government. The seal shall be removed up to the last correct measurement. The seal shall be inspected a minimum of once per 30 meters of seal for compliance to the shrinkage or compression requirements. Measurements shall also be made at the same interval to determine conformance with depth and width of installation requirements. Compression seal that is not in conformance with specification requirements shall be removed and replaced with new joint seal at no additional cost to the Government.

3.5.2.3 Pavement Temperature

The pavement temperature shall be determined by placing a thermometer in the initial saw cut for the joint and the reading shall be recorded. The thermometer shall remain in the joint for an adequate time to provide a control reading.

3.5.3 Product

The joint sealing system (compression seal and lubricant/adhesive) shall be inspected for proper rate of cure and bonding to the concrete, cuts, twists, nicks and other deficiencies. Seals exhibiting any defects, at any time prior to final acceptance of the project, shall be removed from the joint, wasted, and replaced in a satisfactory manner.

END OF SECTION

This page intentionally blank

SECTION 02763 (A)

PAVEMENT MARKINGS

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO M 247	(1981; R 1996) Glass Beads Used in Traffic Paint

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 792	(1998) Density and Specific Gravity (Relative Density) of Plastics by Displacement
ASTM D 4280	(1996) Extended Life Type, Nonplowable, Prismatic, Raised, Retroreflective Pavement Markers
ASTM D 4505	(1996) Preformed Plastic Pavement Marking Tape for Extended Service Life
ASTM E 28	(1999) Softening Point of Resins by Ring and Ball Apparatus

FEDERAL SPECIFICATIONS (FS)

FS TT-B-1325	(Rev C; Notice 1; Canc. Notice 2) Beads (Glass Spheres) Retro-Reflective (Metric)
FS TT-P-1952	(Rev D; Canc. Notice 1) Paint, Traffic and Airfield Marking, Waterborne (Metric)

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Product Data

Equipment; G, RE

Lists of proposed equipment, including descriptive data, and notifications of proposed Contractor actions as specified in this section. List of removal equipment shall include descriptive data indicating area of coverage per pass, pressure adjustment range, tank and flow capacities, and safety precautions required for the equipment operation.

Composition Requirements

Manufacturer's current printed product description and Material Safety Data Sheets (MSDS) for each type paint/color proposed for use.

Qualifications

Document certifying that personnel are qualified for equipment operation and handling of chemicals.

Test Reports

Sampling and Testing; G, RE

Certified copies of the test reports, prior to the use of the materials at the jobsite. Testing shall be performed in an approved independent laboratory.

Certificates

Volatile Organic Compound (VOC); G, RE

Certificate stating that the proposed pavement marking paint meets the VOC regulations of the local Air Pollution Control District having jurisdiction over the geographical area in which the project is located.

1.4 DELIVERY AND STORAGE

All materials shall be delivered and stored in sealed containers that plainly show the designated name, formula or specification number, batch number, color, date of manufacture, manufacturer's name, and directions, all of which shall be plainly legible at time of use.

1.5 EQUIPMENT

All machines, tools and equipment used in the performance of the work shall be approved and maintained in satisfactory operating condition. Equipment operating on roads and runways shall display low speed traffic markings and traffic warning lights.

1.5.1 Paint Application Equipment

The equipment to apply paint to pavements shall be a self-propelled or mobile-drawn pneumatic spraying machine with suitable arrangements of atomizing nozzles and controls to obtain the specified results. The machine shall have a speed during application not less than 8 kilometers per hour (5 mph), and shall be capable of applying the stripe widths indicated, at the paint coverage rate specified in paragraph APPLICATION, and of even uniform thickness with clear-cut edges. The equipment used to apply the paint binder to airfield pavements

shall be a self-propelled or mobile-drawn pneumatic spraying machine with an arrangement of atomizing nozzles capable of applying a line width at any one time in multiples of 150 mm (6 inches), from 150 mm (6 inches) to 900 mm (36 inches). The paint applicator shall have paint reservoirs or tanks of sufficient capacity and suitable gauges to apply paint in accordance with requirements specified. Tanks shall be equipped with suitable air-driven mechanical agitators. The spray mechanism shall be equipped with quick-action valves conveniently located, and shall include necessary pressure regulators and gauges in full view and reach of the operator. Paint strainers shall be installed in paint supply lines to ensure freedom from residue and foreign matter that may cause malfunction of the spray guns. The paint applicator shall be readily adaptable for attachment of an air-actuated dispenser for the reflective media approved for use. Pneumatic spray guns shall be provided for hand application of paint in areas where the mobile paint applicator cannot be used.

1.5.3 Reflective Media Dispenser

The dispenser for applying the reflective media shall be attached to the paint dispenser and shall operate automatically and simultaneously with the applicator through the same control mechanism. The dispenser shall be capable of adjustment and designed to provide uniform flow of reflective media over the full length and width of the stripe at the rate of coverage specified in paragraph APPLICATION, at all operating speeds of the applicator to which it is attached.

1.5.5 Surface Preparation Equipment

1.5.5.1 Sandblasting Equipment

Sandblasting equipment shall include an air compressor, hoses, and nozzles of proper size and capacity as required for cleaning surfaces to be painted. The compressor shall be capable of furnishing not less than 70.8 liters per sec (150 cfm) of air at a pressure of not less than 620 kPa (90 psi) at each nozzle used, and shall be equipped with traps that will maintain the compressed air free of oil and water.

1.5.5.2 Waterblast Equipment

The water pressure shall be specified at 17.9 MPa (2600 psi) at 60 degrees C (140 degrees F) in order to adequately clean the surfaces to be marked.

1.5.6 Marking Removal Equipment

Equipment shall be mounted on rubber tires and shall be capable of removing markings from the pavement without damaging the pavement surface or joint sealant. Waterblasting equipment shall be capable of producing an adjustable, pressurized stream of water. Sandblasting equipment shall include an air compressor, hoses, and nozzles. The compressor shall be equipped with traps to maintain the air free of oil and water.

1.5.6.1 Shotblasting Equipment

Shotblasting equipment shall be capable of producing an adjustable depth of removal of marking and pavement. Each unit shall be self-cleaning and self-contained, shall be able to confine dust and debris from the operation, and shall be capable of recycling the abrasive for reuse.

1.5.6.2 Chemical Equipment

Chemical equipment shall be capable of application and removal of chemicals from the pavement surface, and shall leave only non-toxic biodegradable residue.

1.5.7 Traffic Controls

Suitable warning signs shall be placed near the beginning of the worksite and well ahead of the worksite for alerting approaching traffic from both directions. Small markers shall be placed along newly painted lines or freshly placed raised markers to control traffic and prevent damage to newly painted surfaces or displacement of raised pavement markers. Painting equipment shall be marked with large warning signs indicating slow-moving painting equipment in operation.

1.7 MAINTENANCE OF TRAFFIC

1.7.1 Airfield

The performance of work in the controlled zones of airfields shall be coordinated with the Contracting Officer and with the Flight Operations Officer. Verbal communications shall be maintained with the control tower before and during work in the controlled zones of the airfield. The control tower shall be advised when the work is completed. A radio for this purpose shall be provided by the Contractor and approved by the Contracting Officer.

1.7.2 Roads, Streets, and Parking Areas

When traffic must be rerouted or controlled to accomplish the work, the necessary warning signs, flag persons, and related equipment for the safe passage of vehicles shall be provided.

1.8 WEATHER LIMITATIONS FOR REMOVAL

Pavement surface shall be free of snow, ice, or slush. Surface temperature shall be at least 5 degrees C and rising at the beginning of operations, except those involving shot or sand blasting. Operation shall cease during thunderstorms. Operation shall cease during rainfall, except for waterblasting and removal of previously applied chemicals. Waterblasting shall cease where surface water accumulation alters the effectiveness of material removal.

1.9 BLACKED-OUT PAVEMENT MARKINGS

Existing and temporary pavement markings designated to be "blacked-out" shall be as indicated on the contract drawings. Markings to be "blacked-out" shall be cleaned and prepared as indicated in paragraph SURFACE PREPARATION, or as recommended by the manufacturer.

PART 2 PRODUCTS

2.1 PAINT

The paint shall be water-based, homogeneous, easily stirred to smooth consistency, and shall show no hard settlement or other objectionable characteristics during a storage period of 6 months. Paints for airfields, roads, and streets shall conform to FS TT-P-1952, color as

indicated. Pavement marking paints shall comply with applicable state and local laws enacted to ensure compliance with Federal Clean Air Standards. Paint materials shall conform to the restrictions of the local Air Pollution Control District.

2.5 REFLECTIVE MEDIA

Reflective media for airfields shall conform to FS TT-B-1325, Type I, Gradation A. Reflective media for roads and streets shall conform to FS TT-B-1325, Type I, Gradation A or AASHTO M 247, Type I.

2.6 SAMPLING AND TESTING

Materials proposed for use shall be stored on the project site in sealed and labeled containers, or segregated at source of supply, sufficiently in advance of needs to allow 60 days for testing. Upon notification by the Contractor that the material is at the site or source of supply, a sample shall be taken by random selection from sealed containers by the Contractor in the presence of a representative of the Contracting Officer. Samples shall be clearly identified by designated name, specification number, batch number, manufacturer's formulation number, project contract number, intended use, and quantity involved. Testing shall be performed in an approved independent laboratory. If materials are approved based on reports furnished by the Contractor, samples will be retained by the Government for possible future testing should the material appear defective during or after application.

PART 3 EXECUTION

3.1 SURFACE PREPARATION

Surfaces to be marked shall be thoroughly cleaned before application of the pavement marking material. Dust, dirt, and other granular surface deposits shall be removed by sweeping, blowing with compressed air, rinsing with water or a combination of these methods as required. Rubber deposits, surface laitance, existing paint markings, and other coatings adhering to the pavement shall be completely removed with scrapers, wire brushes, sandblasting, approved chemicals, or mechanical abrasion as directed. Areas of old pavement affected with oil or grease shall be scrubbed with several applications of trisodium phosphate solution or other approved detergent or degreaser, and rinsed thoroughly after each application. After cleaning, oil-soaked areas shall be sealed with cut shellac to prevent bleeding through the new paint. Pavement surfaces shall be allowed to dry, when water is used for cleaning, prior to striping or marking. Surfaces shall be recleaned, when work has been stopped due to rain. All new pavement surfaces shall be at least 7 days old before applying paint. However, pavement markings may be applied earlier due to Base operation requirements. Specific approval will be required from the Contracting Officer, based on the pavement marking manufacturer’s installation recommendations.

3.1.1 Pretreatment for Early Painting

Where early painting is required on rigid pavements, a pretreatment with an aqueous solution containing 3 percent phosphoric acid and 2 percent zinc chloride shall be applied to prepared pavement areas prior to painting.

3.1.2 Cleaning Existing Pavement Markings

In general, markings shall not be placed over existing pavement marking patterns. Existing pavement markings, which are in good condition but interfere or conflict with the newly applied marking patterns, shall be removed. Deteriorated or obscured markings that are not misleading or confusing or interfere with the adhesion of the new marking material do not require removal. Whenever grinding, scraping, sandblasting or other operations are performed the work must be conducted in such a manner that the finished pavement surface is not damaged or left in a pattern that is misleading or confusing. When these operations are completed the pavement surface shall be blown off with compressed air to remove residue and debris resulting from the cleaning work unless otherwise indicated.

3.1.3 Cleaning Concrete Curing Compounds

Cleaning operations on new Portland cement concrete pavements shall not begin before a minimum of 7 days after the placement of concrete, or as recommended by the manufacturer and specifically approved by the Contracting Officer. All new concrete pavements shall be cleaned by either sandblasting or water blasting. The extent of the blasting work shall be to clean and prepare the concrete surface as follows:

a. There is no visible evidence of curing compound on the peaks of the textured concrete surface.

b. There are no heavy puddled deposits of curing compound in the valleys of the textured concrete surface.

c. All remaining curing compound is intact; all loose and flaking material is removed.

d. The peaks of the textured pavement surface are rounded in profile and free of sharp edges and irregularities.

e. The surface to be marked is dry.

3.2 APPLICATION

a. All pavement markings and patterns shall be placed as shown on the plans, except as specified in 3.2.b below.

b. If The extension of the aircraft parking apron onto Taxiway A, including concrete curing period, is not accomplished within the construction period stated in Section 01005(AR), paragraph 1.5.1, the Contractor shall develop a temporary pavement marking plan which will allow aircraft to bypass the southern border of Phase 2 construction, along Taxiway A. The temporary pavement markings shall be used to offset the Taxiway A centerline to approximately 300 mm south of the southern most longitudinal pavement joint on Taxiway A, and allow for construction bypass along the taxiway and access to Taxiway H. The Contractor shall include "blacking out" of existing pavement markings and re-establishment of these markings upon Phase 2 completion. The Contractor shall submit the temporary pavement marking plan, for approval by the Contracting Officer, a minimum of 14 days prior to application.

3.2.1 Paint

Paint shall be applied to clean, dry surfaces, and only when air and pavement temperatures are above 5 degrees C and less than 35 degrees C. Paint temperature shall be maintained within these same limits. Paint shall be applied pneumatically with approved equipment at rate of coverage specified. The Contractor shall provide guide lines and templates as necessary to control paint application. Special precautions shall be taken in marking numbers, letters, and symbols. Edges of markings shall be sharply outlined.

3.2.1.1 Rate of Application

a. Reflective Markings: Pigmented binder shall be applied evenly to the pavement area to be coated at a rate of 2.9 plus or minus 0.5 square meter per liter. Glass spheres shall be applied uniformly to the wet paint on airfield pavement at a rate of 1.0 plus or minus 0.06 kilograms of glass spheres per liter of paint.

b. Nonreflective Markings: Paint shall be applied evenly to the pavement surface to be coated at a rate of 2.9 plus or minus 0.5 square meter per liter.

3.2.1.2 Drying

The maximum drying time requirements of the paint specifications will be strictly enforced to prevent undue softening of bitumen, and pickup, displacement, or discoloration by tires of traffic. If there is a delay in drying of the markings, painting operations shall be discontinued until cause of the slow drying is determined and corrected.

3.2.5 Reflective Media

Application of reflective media shall immediately follow application of pigmented binder. Drop-on application of glass spheres shall be accomplished to insure that reflective media is evenly distributed at the specified rate of coverage. Should there be malfunction of either paint applicator or reflective media dispenser, operations shall be discontinued immediately until deficiency is corrected.

3.3 MARKING REMOVAL

Pavement markings shall be removed in the areas shown on the drawings. Removal of marking shall be as complete as possible without damage to the surface. The removal process shall not expose aggregate. After the markings are removed, the cleaned pavement surfaces shall exhibit adequate texture for remarking as specified in paragraph SURFACE PREPARATION. Contractor shall demonstrate removal of pavement marking in an area designated by the Contracting Officer. The demonstration area will become the standard for the remainder of the work.

3.3.1 Equipment Operation

Equipment shall be controlled and operated to remove markings from the pavement surface, prevent dilution or removal of binder from underlying pavement, and prevent emission of blue smoke from asphalt or tar surfaces.

3.3.2 Cleanup and Waste Disposal

The worksite shall be kept clean of debris and waste from the removal operations. Cleanup shall immediately follow removal operations in areas subject to air traffic. Debris shall be disposed of at approved sites.

END OF SECTION

SECTION 02964 (A)

COLD MILLING OF BITUMINOUS PAVEMENTS

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 136 (1996a) Sieve Analysis of Fine and Coarse Aggregates

1.2 EQUIPMENT, TOOLS, AND MACHINES

Equipment, tools, and machines used in the performance of the work shall be maintained in a satisfactory working condition.

1.2.1 Cold-Milling Machine

The cold-milling machine shall be a self-propelled machine capable of milling the pavement to a specified depth and smoothness. Pavement milling machine shall be capable of establishing grade control; shall have means of controlling transverse slope; and shall have effective means of controlling dust produced during the pavement milling operation. The machine shall have the ability to remove the millings or cuttings from the pavement and load them into a truck. The milling machine shall not cause damage to any part of the pavement structure that is not to be removed.

1.2.2 Cleaning Equipment

Cleaning equipment shall be suitable for removing and cleaning loose material from the pavement surface.

1.3 WEATHER LIMITATIONS

Milling shall not be performed when there is accumulation of snow or ice on the pavement surface.

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION

3.1 PREPARATION OF SURFACE

The pavement surface shall be cleaned of excessive dirt, clay, or other foreign material immediately prior to milling the pavement.

3.2 MILLING OPERATION

Sufficient passes shall be made so that the designated area is milled to the grades and cross sections indicated. The milling shall proceed with care and in depth increments that will not damage the pavement below the designated finished grade. Items damaged during milling, such as manholes, valve boxes, utility lines, pavement that is torn, cracked, gouged, broken, or undercut, shall be repaired or replaced as directed. Removed material shall have a minimum of 95 percent by weight passing a 50 mm sieve when tested in accordance with ASTM C 136.

3.3 REMOVAL OF MILLED MATERIAL

Material that is removed shall be delivered to the indicated disposal area as specified, and stockpiled in such a manner to prevent segregation or contamination, as approved.

END OF SECTION

THE FOLLOWING TECHNICAL SPECIFICATIONS APPLY TO
REPAIR RUNWAY ONLY:

Section No.	Section Title
	DIVISION 2 - SITEWORK
	Repair Runway
02220 R	Demolition
02300 R	Earthwork
02316 R	Excavation, Trenching, and Backfilling for Utilities Systems
02510 R	Water Distribution
02531 R	Sanitary Sewers
02722 R	Graded-Crushed Aggregate Base Course
02748 R	Bituminous Tack and Prime Coats
02749 R	Hot Mix Asphalt (HMA) for Airfields
02753 R	Concrete Pavement for Airfields and Other Heavy-Duty Pavements
02760 R	Field Molded Sealants for Sealing Joints in Rigid Pavement
02762 R	Compression Joint Seals for Concrete Pavements
02763 R	Pavement Markings
02900 R	Landscape Work
02964 R	Cold Milling of Bituminous Pavement
02975 R	Sealing of Cracks in Bituminous Pavements
02981 R	Grooving for Airfield Pavements
02999 R	Installation of Ultra-High-Molecular Weight Polyethylene (UHMW) Panels Under Aircraft Arresting System Cables

This page was intentionally left blank for duplex printing.

SECTION 02220 (R)

DEMOLITION

1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(1996) U.S. Army Corps of Engineers Safety and Health Requirements Manual

1.2 GENERAL REQUIREMENTS

The work includes demolition, salvage of identified items and materials, and removal of resulting rubbish and debris. Rubbish and debris shall be removed from Government property daily, unless otherwise directed, to avoid accumulation at the demolition site. Materials that cannot be removed daily shall be stored in areas specified by the Contracting Officer. In the interest of occupational safety and health, the work shall be performed in accordance with EM 385-1-1, Section 23, Demolition, and other applicable Sections. In the interest of conservation, salvage shall be pursued to the maximum extent possible (in accordance with Section ~~01572 CONSTRUCTION AND DEMOLITION WASTE MANAGEMENT~~ 01061 (AR) ENVIRONMENTAL PROTECTION, if applicable); salvaged items and materials shall be disposed of as specified.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Product Data

Work Plan; G

The procedures proposed for the accomplishment of the work. The procedures shall provide for safe conduct of the work, including procedures and methods to provide necessary supports, lateral bracing and shoring when required, careful removal and disposition of materials specified to be salvaged, protection of property which is to remain undisturbed, coordination with other work in progress, and timely disconnection of utility services. The procedures shall include a detailed description of the methods and equipment to be used for each operation, and the sequence of operations in accordance with EM 385-1-1.

1.4 DUST CONTROL

The amount of dust resulting from demolition shall be controlled to prevent the spread of dust to occupied portions of the construction site and to avoid creation of a nuisance in the surrounding area. Use of water will not be permitted when it will result in, or create, hazardous or objectionable conditions such as ice, flooding and pollution.

1.5 PROTECTION

1.5.1 Protection of Personnel

During the demolition work the Contractor shall continuously evaluate the condition of the structure being demolished and take immediate action to protect all personnel working in and around the demolition site. No area, section, or component of floors, roofs, walls, columns, pilasters, or other structural element will be allowed to be left standing without sufficient bracing, shoring, or lateral support to prevent collapse or failure while workmen remove debris or perform other work in the immediate area.

1.5.2 Protection of Existing Property

Before beginning any demolition work, the Contractor shall survey the site and examine the drawings and specifications to determine the extent of the work. The Contractor shall take necessary precautions to avoid damage to existing items to remain in place, to be reused, or to remain the property of the Government; any damaged items shall be repaired or replaced as approved by the Contracting Officer. The Contractor shall coordinate the work of this section with all other work and shall construct and maintain shoring, bracing, and supports as required. The Contractor shall ensure that structural elements are not overloaded and shall be responsible for increasing structural supports or adding new supports as may be required as a result of any cutting, removal, or demolition work performed under this contract.

1.5.3 Environmental Protection

The work shall comply with the requirements of Section 01355 ENVIRONMENTAL PROTECTION.

1.6 BURNING

The use of burning at the project site for the disposal of refuse and debris will not be permitted.

1.7 USE OF EXPLOSIVES

Use of explosives will not be permitted.

2 PRODUCTS (NOT APPLICABLE)

3 EXECUTION

3.1 UTILITIES

Existing utilities shall be removed as indicated. When utility lines are encountered that are not indicated on the drawings, the Contracting Officer shall be notified prior to further work in that area.

3.2 DISPOSITION OF MATERIAL

Title to material and equipment to be demolished, except Government salvage and historical items, is vested in the Contractor when the material or equipment to be demolished is removed from Government property. The Government will not be responsible for the condition, loss or damage to such property after notice to proceed.

3.2.1 Salvageable Items and Material

Contractor shall salvage items and material to the maximum extent possible.

3.2.1.1 Material Salvaged for the Contractor

Material salvaged for the Contractor shall be stored as approved by the Contracting Officer and shall be removed from Government property before completion of the contract. Material salvaged for the Contractor shall not be sold on the site.

3.2.1.2 Items Salvaged for the Government

Salvaged items to remain the property of the Government shall be as noted. Items damaged during removal or storage shall be repaired or replaced to match existing items. Asphalt pavement millings and crushed concrete meeting the materials requirements for the specified use will be incorporated in the work as specified. Excess material shall be stockpiled at the locations shown in the drawings.

3.2.2 Unsalvageable Material

Concrete, masonry, and other noncombustible material shall be disposed of in the disposal area located as shown on the plans. The fill in the disposal area shall be placed as directed by the Contracting Officer and after disposal is completed, the disposal area shall be uniformly graded to drain. Combustible material shall be disposed of off the site.

3.3 CRUSHING DEMOLISHED CONCRETE

3.3.1 Requirement

Concrete demolished in this project shall be crushed. Crushed concrete meeting the specified requirements shall be recycled as base course for use in this project. Unused crushed concrete shall be turned over to the Government at the Crushed Concrete Stockpile location shown on the drawings. See Section 02722(R) GRADED-CRUSHED AGGREGATE BASE COURSE.

3.3.2 Procedure

3.3.2.1 Sequence

Concrete will be demolished as specified in this section and hauled to a designated site for crushing. Material shall be temporarily stockpiled and reused as base course, as suitable. Any excess material shall be hauled and stockpiled in the "crushed concrete stockpile" designated in the plans, after all base course is constructed.

3.3.2.2 Method

Crushing will be by machine specifically designed for crushing rocks or concrete.

3.3.2.3 Particle Size

Largest particle size of the finished project will be 1.5 inches. Material recycled for base course shall be graded to meet the requirements of Specification 02722~~A~~ (R), "Graded-Crushed Aggregate Base Course".

3.3.2.4 Removal of Metal and Other Foreign Matter

Remove all metal and other foreign matter from the crushed concrete before use or stockpiling.

3.3.2.5 Location

Crushing and temporary storage of demolished and crushed concrete will be allowed at the designated "batch plant/staging area" shown on the project drawings, unless an alternate location is approved by the Contracting Officer.

3.4 CLEAN UP

Debris shall be removed and transported in a manner that prevents spillage on streets or adjacent areas. Local regulations regarding hauling and disposal shall apply.

3.5 PAVEMENTS

Existing pavements designated for removal shall be saw cut and removed in accordance with the details shown on the drawings and to the limits and depths indicated on the drawings.

END OF SECTION

SECTION 02300 (R)

EARTHWORK

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO T 180	(1997) Moisture-Density Relations of Soils Using a 4.54-kg (10-lb) Rammer and an 457 mm (18-in) Drop
AASHTO T 224	(1996) Correction for Coarse Particles in the Soil Compaction Test

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 136	(1996a) Sieve Analysis of Fine and Coarse Aggregates
ASTM D 422	(1963; R 1998) Particle-Size Analysis of Soils
ASTM D 1140	(1997) Amount of Material in Soils Finer than the No. 200 (75-micrometer) Sieve
ASTM D 1556	(1990; R 1996el) Density and Unit Weight of Soil in Place by the Sand-Cone Method
ASTM D 1557	(1991; R 1998) Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/cu. ft. (2,700 kN-m/cu. m.))
ASTM D 2167	(1994) Density and Unit Weight of Soil in Place by the Rubber Balloon Method
ASTM D 2487	(1998) Classification of Soils for Engineering Purposes (Unified Soil Classification System)
ASTM D 2922	(1996el) Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth)
ASTM D 2937	(1994) Density of Soil in Place by the Drive-Cylinder Method
ASTM D 3017	(1988; R 1996el) Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth)

ASTM D 4318	(1998) Liquid Limit, Plastic Limit, and Plasticity Index of Soils

1.4 DEFINITIONS

1.4.1 Satisfactory Materials

Satisfactory materials shall comprise any materials classified by ASTM D 2487 as GW, GP, SW, SP. Satisfactory materials for grading shall be comprised of stones less than 3 inches, except for fill material for pavements and railroads which shall be comprised of stones less than 3 inches in any dimension.

1.4.2 Unsatisfactory Materials

Materials which do not comply with the requirements for satisfactory materials are unsatisfactory. Unsatisfactory materials also include man-made fills; trash; refuse; backfills from previous construction; and material classified as satisfactory which contains root and other organic matter or frozen material. The Contracting Officer shall be notified of any contaminated materials.

1.4.3 Cohesionless and Cohesive Materials

Cohesionless materials include materials classified in ASTM D 2487 as GW, GP, SW, and SP. Cohesive materials include materials classified as GC, SC, ML, CL, MH, and CH. Materials classified as GM and SM will be identified as cohesionless only when the fines are nonplastic. Testing required for classifying materials shall be in accordance with ASTM D 4318, ASTM C 136, ASTM D 422, and ASTM D 1140.

1.4.4 Degree of Compaction

Degree of compaction required, except as noted in the second sentence, is expressed as a percentage of the maximum density obtained by the test procedure presented in ASTM D 1557abbreviated as a percent of laboratory maximum density. Since ASTM D 1557 applies only to soils that have 30 percent or less by weight of their particles retained on the 3/4 inch sieve, the degree of compaction for material having more than 30 percent by weight of their particles retained on the 3/4 inch sieve shall be expressed as a percentage of the maximum density in accordance with AASHTO T 180 Method D and corrected with AASHTO T 224. To maintain the same percentage of coarse material, the "remove and replace" procedure as described in the NOTE 8 in Paragraph 7.2 of AASHTO T 180 shall be used.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 (AR) SUBMITTAL PROCEDURES:

Product Data

Earthwork; G.

Procedure and location for disposal of unused satisfactory material.

Notification of encountering rock in the project. Advance notice on the opening of excavation. Advance notice on shoulder construction for rigid pavements.

Test Reports

Testing; G.

Within 24 hours of conclusion of physical tests, two copies of test results, including calibration curves and results of calibration tests.

Certificates

Testing; G.

Qualifications of the commercial testing laboratory or Contractor's testing facilities.

1.6 SUBSURFACE DATA

Subsurface soil boring logs are attached at the end of this section. The subsoil investigation report may be examined by contacting the Contracting Officer. These data represent the best subsurface information available; however, variations may exist in the subsurface between boring locations.

1.7 CLASSIFICATION OF EXCAVATION

No consideration will be given to the nature of the materials, and all excavation will be designated as unclassified excavation.

1.8 BLASTING

Blasting will not be permitted.

1.9 UTILIZATION OF EXCAVATED MATERIALS

Unsatisfactory materials removed from excavations shall be disposed of in designated waste disposal or spoil areas. Satisfactory material removed from excavations shall be used, insofar as practicable, in the construction of fills, embankments, subgrades, shoulders, bedding (as backfill), and for similar purposes. No satisfactory excavated material shall be wasted without specific written authorization. Satisfactory material authorized to be wasted shall be disposed of in designated areas approved for surplus material storage or designated waste areas as directed. Newly designated waste areas on Government-controlled land shall be cleared and grubbed before disposal of waste material thereon. Coarse rock from excavations shall be stockpiled and used for constructing slopes or embankments adjacent to streams, or sides and bottoms of channels and for protecting against erosion. No excavated material shall be disposed of to obstruct the flow of any stream, endanger a partly finished structure, impair the efficiency or appearance of any structure, or be detrimental to the completed work in any way.

1.10 PAVEMENT BORING LOGS

Included in the Contract Documents are the pavement boring logs identified in the Project Drawings. These logs are included at the end of this specification for the Contractor's information.

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION

3.1 GENERAL EXCAVATION

The Contractor shall perform excavation of every type of material encountered within the limits of the project to the lines, grades, and elevations indicated and as specified. Grading shall be in conformity with the typical sections shown and the tolerances specified in paragraph FINISHING. Satisfactory excavated materials shall be transported to and placed in fill or embankment within the limits of the work. Unsatisfactory materials encountered within the limits of the work shall be excavated below grade and replaced with satisfactory materials as directed. Such excavated material and the satisfactory material ordered as replacement shall be included in excavation. Surplus satisfactory excavated material not required for fill or embankment shall be disposed of in areas approved for surplus material storage or designated waste areas. Unsatisfactory excavated material shall be disposed of in designated waste or spoil areas. During construction, excavation and fill shall be performed in a manner and sequence that will provide proper drainage at all times. Material required for fill or embankment in excess of that produced by excavation within the grading limits shall be excavated from other approved areas selected by the Contractor as specified.

3.1.1 Ditches, Gutters, and Channel Changes

Excavation of ditches, gutters, and channel changes shall be accomplished by cutting accurately to the cross sections, grades, and elevations shown. Ditches and gutters shall not be excavated below grades shown. Excessive open ditch or gutter excavation shall be backfilled with satisfactory, thoroughly compacted, material or with suitable stone or cobble to grades shown. Material excavated shall be disposed of as shown or as directed, except that in no case shall material be deposited less than 4 feet from the edge of a ditch. The Contractor shall maintain excavations free from detrimental quantities of leaves, brush, sticks, trash, and other debris until final acceptance of the work.

3.1.2 Drainage Structures

Excavations shall be made to the lines, grades, and elevations shown, or as directed. Trenches and foundation pits shall be of sufficient size to permit the placement and removal of forms for the full length and width of structure footings and foundations as shown. Rock or other hard foundation material shall be cleaned of loose debris and cut to a firm, level, stepped, or serrated surface. Loose disintegrated rock and thin strata shall be removed. When concrete or masonry is to be placed in an excavated area, the bottom of the excavation shall not be disturbed. Excavation to the final grade level shall not be made until just before the concrete or masonry is to be placed.

3.3 OPENING AND DRAINAGE OF EXCAVATION

The Contractor shall notify the Contracting Officer sufficiently in advance of the opening of any excavation or borrow pit to permit elevations and measurements of the undisturbed ground surface to be taken. Except as otherwise permitted, excavation areas shall be excavated providing adequate drainage. Overburden and other spoil material shall be transported to designated spoil areas or otherwise disposed of as directed. The Contractor shall ensure that excavation of any area, or dumping of spoil material results in minimum detrimental effects on natural environmental conditions.

3.4 GRADING AREAS

Where indicated, work will be divided into grading areas within which satisfactory excavated material shall be placed in embankments, fills, and required backfills. The Contractor shall not haul satisfactory material excavated in one grading area to another grading area except when so directed in writing.

3.5 BACKFILL

Backfill adjacent to any and all types of structures shall be placed and compacted to at least 90 percent laboratory maximum density for cohesive materials or 95 percent laboratory maximum density for cohesionless materials to prevent wedging action or eccentric loading upon or against the structure. Ground surface on which backfill is to be placed shall be prepared as specified in paragraph PREPARATION OF GROUND SURFACE FOR EMBANKMENTS. Compaction requirements for backfill materials shall also conform to the applicable portions of paragraphs PREPARATION OF GROUND SURFACE FOR EMBANKMENTS, EMBANKMENTS, and SUBGRADE PREPARATION. Compaction shall be accomplished by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment.

3.6 SUBGRADE PREPARATION

3.6.1 Construction

Subgrade shall be shaped to line, grade, and cross section, and compacted as specified. This operation shall include plowing, disking, and any moistening or aerating required to obtain specified compaction. Soft or otherwise unsatisfactory material shall be removed and replaced with satisfactory excavated material or other approved material as directed. Rock encountered in the cut section shall be excavated to a depth of 6 inches below finished grade for the subgrade. Low areas resulting from removal of unsatisfactory material or excavation of rock shall be brought up to required grade with satisfactory materials, and the entire subgrade shall be shaped to line, grade, and cross section and compacted as specified. After rolling, the surface of the subgrade for airfields shall not show deviations greater than 12 inches when tested with a 12 foot straightedge applied both parallel and at right angles to the centerline of the area. The elevation of the finish subgrade shall not vary more than 0.05 foot from the established grade and cross section.

3.6.2 Compaction

Compaction shall be accomplished by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment. Except for paved areas

and railroads, each layer of the embankment shall be compacted to at least 95 percent of laboratory maximum density.

3.6.2.2 Subgrade for Pavements

Subgrade for pavements shall be compacted to at least 100 percentage laboratory maximum density for a depth of six inches belowthe top of the subgrade. When more than one soil classification is present in the subgrade, the top six inches of subgrade shall be scarified, windrowed, thoroughly blended, reshaped, and compacted.

3.6.2.3 Subgrade for Shoulders

Subgrade for shoulders shall be compacted to at least 100 percentage laboratory maximum density for the full depth of the shoulder.

3.7 SHOULDER CONSTRUCTION

Shoulders shall be constructed of satisfactory excavated material or as otherwise shown or specified. Shoulders shall be constructed as soon as possible after adjacent paving is complete, but in the case of rigid pavements, shoulders shall not be constructed until permission of the Contracting Officer has been obtained. The entire shoulder area shall be compacted to at least the percentage of maximum density as specified in paragraph SUBGRADE PREPARATION above, for specific ranges of depth below the surface of the shoulder. Compaction shall be accomplished by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment. Shoulder construction shall be done in proper sequence in such a manner that adjacent ditches will be drained effectively and that no damage of any kind is done to the adjacent completed pavement. The completed shoulders shall be true to alignment and grade and shaped to drain in conformity with the cross section shown.

3.8 FINISHING

The surface of excavations, embankments, and subgrades shall be finished to a smooth and compact surface in accordance with the lines, grades, and cross sections or elevations shown. The degree of finish for graded areas shall be within 0.1 foot of the grades and elevations indicated except that the degree of finish for subgrades shall be specified in paragraph SUBGRADE PREPARATION. Gutters and ditches shall be finished in a manner that will result in effective drainage. The surface of areas to be turfed shall be finished to a smoothness suitable for the application of turfing materials.

3.9 TESTING

Testing shall be performed by an approved commercial testing laboratory or by the Contractor subject to approval. If the Contractor elects to establish testing facilities, no work requiring testing will be permitted until the Contractor's facilities have been inspected and approved by the Contracting Officer. Field in-place density shall be determined in accordance with ASTM D 2922. When ASTM D 2922 is used, the calibration curves shall be checked and adjusted using only the sand cone method as described in ASTM D 1556. ASTM D 2922results in a wet unit weight of soil and when using this method ASTM D 3017 shall be used to determine the moisture content of the soil. The calibration curves furnished with the moisture gauges shall also be checked along with density calibration checks as described in ASTM D 3017;

the calibration checks of both the density and moisture gauges shall be made at the beginning of a job on each different type of material encountered and at intervals as directed by the Contracting Officer. When test results indicate, as determined by the Contracting Officer, that compaction is not as specified, the material shall be removed, replaced and recompacted to meet specification requirements. Tests on recompacted areas shall be performed to determine conformance with specification requirements. Inspections and test results shall be certified by a registered professional civil engineer. These certifications shall state that the tests and observations were performed by or under the direct supervision of the engineer and that the results are representative of the materials or conditions being certified by the tests. The following number of tests, if performed at the appropriate time, will be the minimum acceptable for each type operation.

3.9.1 Fill and Backfill Material Gradation

One test per 500 cubic yards stockpiled or in-place source material. Gradation of fill and backfill material shall be determined in accordance with ASTM C 136.

3.9.2 In-Place Densities

a. One test per 2,000 square yards or fraction thereof, of each lift of fill or backfill areas compacted by other than hand-operated machines.

b. One test per 2000 square yards or fraction thereof, of subgrage and each lift of embankment or backfill for airfields.

3.9.3 Check Tests on In-Place Densities

If ASTM D 2922 is used, in-place densities shall be checked by ASTM D 1556 as follows:

a. One check test per lift for each 20,000 square yards or fraction thereof, of subgrade and embankment or backfill for airfields.

3.9.4 Moisture Contents

In the stockpile, excavation, or borrow areas, a minimum of two tests per day per type of material or source of material being placed during stable weather conditions shall be performed. During unstable weather, tests shall be made as dictated by local conditions and approved by the Contracting Officer.

3.9.5 Optimum Moisture and Laboratory Maximum Density

Tests shall be made for each type material or source of material to determine the optimum moisture and laboratory maximum density values. One representative test per 5000 cubic yards of fill and backfill, or when any change in material occurs which may affect the optimum moisture content or laboratory maximum density.

3.9.6 Tolerance Tests for Subgrades

Continuous checks on the degree of finish specified in paragraph SUBGRADE PREPARATION shall be made during construction of the subgrades.

3.10 SUBGRADE AND EMBANKMENT PROTECTION

During construction, embankments and excavations shall be kept shaped and drained. Ditches and drains along subgrade shall be maintained to drain effectively at all times. The finished subgrade shall not be disturbed by traffic or other operation and shall be protected and maintained by the Contractor in a satisfactory condition until ballast, subbase, base, or pavement is placed. The storage or stockpiling of materials on the finished subgrade will not be permitted. No subbase, base course, ballast, or pavement shall be laid until the subgrade has been checked and approved, and in no case shall subbase, base, surfacing, pavement, or ballast be placed on a muddy, spongy, or frozen subgrade.



File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB



File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB



File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB

Boring No. B-5 Subsurface Soil Description	Depth (in feet)	USCS Class	Symbol	Sample interval	SPT (blows /ft)	REMARKS
Asphalt Concrete - 1/2" Dense Grade some voids.		AC				
Asphalt Concrete - 3/4" Dense Grade, high void ratio, brittle		AC				
Concrete - not bored	1					
	2					
	3					
	4					
	5					

File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB

EXPLORATORY BORING LOGS

STRATA
GEOTECHNICAL ENGINEERING & MATERIALS TESTING



File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB

Boring No. B-7 Subsurface Soil Description	Depth (in feet)	USCS Class	Symbol	Sample Interval	SPT (blows /ft)	REMARKS
Asphalt Concrete - 1/4" Dense Grade, coarse aggregate segragation at bottom of lift, moderately high void ratio.		AC				
Asphalt Concrete - 1" Dense Grade, extremely high void ratio, hard brittle.		AC				
Gravel with Sand - grey-brown, medium dense, moist.	1	GP/SP			9	
	2				38	
	3					
Boring Terminated at 3.5 ft.	4					
	5					

File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB



File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB



File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB



File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB



File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB

Boring No. B-12 Subsurface Soil Description	Depth (in feet)	USCS Class	Symbol	Sample interval	SPT (blows /ft)	REMARKS
Asphalt Concrete - 1/2" Dense Grade low void ratio.		AC				
Asphalt Concrete - 3/4" Dense Grade, high void ratio, hard, brittle		AC				
Concrete - not bored	1 2 3 4 5					

File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB



File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB



File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB



File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB

Boring No. B-16 Subsurface Soil Description	Depth (in feet)	USCS Class	Symbol	Sample interval	SPT (blows /ft)	REMARKS
Asphalt Concrete - 1/2" Dense Grade, low void ratio.		AC				Entire length of core drilled along a reflective crack, possibly originated from the middle
Asphalt Concrete - 3/4" Dense Grade, very high void ratio, hard, brittle.		AC				
Asphalt Concrete - 1" Dense Grade, aggregate rounded to sub-rounded high void ratio, hard, brittle.		AC				
Gravel with Sand - grey-brown, loose to medium dense, moist.	1 2	GP/SP			10	
Silt with sand - brown, moist, medium dense.	3	ML			10	
Boring Terminated at 3.8 ft.	4 5					

File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB

Boring No. B-17 Subsurface Soil Description	Depth (in feet)	USCS Class	Symbol	Sample Interval	SPT (blows /ft)	REMARKS
Asphalt Concrete - 1/2" Dense Grade, low void ratio.		AC				
Asphalt Concrete - 3/4" Dense Grade, high void ratio, hard, brittle.		AC				
Asphalt Concrete - 1" Dense Grade, high void ratio, hard, brittle.		AC				
CONCRETE - Not bored or sampled	1					
	2					
	3					
	4					
	5					

File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB



File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB

Boring No. B-19 Subsurface Soil Description	Depth (in feet)	USCS Class	Symbol	Sample interval	SPT (blows /ft)	REMARKS
Asphalt Concrete - 1/2" Dense Grade, low void ratio.		AC				
Asphalt Concrete - 3/4" Dense Grade, moderate void ratio.		AC				
Asphalt Concrete - 1" Dense Grade, aggregate rounded to sub-rounded high void ratio, hard, brittle.		AC				
Gravel with Sand - grey-brown, medium dense, moist.	1	GP/SP			17	
Silt - brown, moist, very medium dense.	2					
	3	ML			23	Insitu Dry Density =106.0pcf Insitu Moisture = 12.5pcf LL=NV, PI=NP
Boring Terminated at 3.8 ft.	4					
	5					

File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB



File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB



File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB

Boring No. B-22 Subsurface Soil Description	Depth (in feet)	USCS Class	Symbol	Sample interval	SPT (blows /ft)	REMARKS
Asphalt Concrete - 1/2" Dense Grade, low void ratio.		AC				
Asphalt Concrete - 3/4" Dense Grade, moderate void ratio, hard, brittle.		AC				
CONCRETE - Not bored or sampled	1					
	2					
	3					
	4					
	5					

File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB



File: TOOO01-B01086A	Driller: Haz-Tech, Inc., Boise, ID
Location: Mountain Home AFB, ID	Date Drilled: August 17, 2001
Surface Elevation: Existing Grade	Boring Diameter: 4.5" HSA
Depth to Groundwater: N/A	Logged By: RDB

END OF SECTION

SECTION 02316 (R)

EXCAVATION, TRENCHING, AND BACKFILLING FOR UTILITIES SYSTEMS

1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 1556	(1990; R 1996) Density and Unit Weight of Soil in Place by the Sand-Cone Method
ASTM D 1557	(1998) Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/cu. ft. (2,700 kN-m/cu. m.))
ASTM D 2167	(1994) Density and Unit Weight of Soil in Place by the Rubber Balloon Method
ASTM D 2487	(1998) Classification of Soils for Engineering Purposes (Unified Soil Classification System)
ASTM D 2922	(1996) Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth)
ASTM D 3017	(1988; R1996el) Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth)

1.2 DEGREE OF COMPACTION

Degree of compaction shall be expressed as a percentage of the maximum density obtained by the test procedure presented in ASTM D 1557.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 (AR) SUBMITTAL PROCEDURES:

Test Reports

Field Density Tests; ~~0~~G
Testing of Backfill Materials; ~~0~~G

Copies of all laboratory and field test reports within 24 hours of the completion of the test.

2 PRODUCTS

2.1 MATERIALS

2.1.1 Satisfactory Materials

Satisfactory materials shall comprise any materials classified by ASTM D 2487 as GW, GP, SW, SP. Satisfactory materials for grading shall be comprised of stones less than 8 inches, except for fill material for pavements and railroads which shall be comprised of stones less than 3 inches in any dimension.

2.1.2 Unsatisfactory Materials

Materials which do not comply with the requirements for satisfactory materials are unsatisfactory. Unsatisfactory materials also include man-made fills, trash, refuse, or backfills from previous construction. Unsatisfactory material also includes material classified as satisfactory which contains root and other organic matter, frozen material, and stones larger than 3 inches. The Contracting Officer shall be notified of any contaminated materials.

2.1.3 Cohesionless and Cohesive Materials

Cohesionless materials shall include materials classified in ASTM D 2487 as GW, GP, SW, and SP. Cohesive materials shall include materials classified as GC, SC, ML, CL, MH, and CH. Materials classified as GM and SM shall be identified as cohesionless only when the fines are nonplastic.

2.1.4 Unyielding Material

Unyielding material shall consist of rock and gravelly soils with stones greater than 3 inches in any dimension or as defined by the pipe manufacturer, whichever is smaller.

2.1.5 Unstable Material

Unstable material shall consist of materials too wet to properly support the utility pipe, conduit, or appurtenant structure.

2.1.6 Select Granular Material

Select granular material shall consist of well-graded sand, gravel, crushed gravel, crushed stone or crushed slag composed of hard, tough and durable particles, and shall contain not more than 10 percent by weight of material passing a No. 200 mesh sieve and no less than 95 percent by weight passing the 1 inch sieve. The maximum allowable aggregate size shall be 3 inches or the maximum size recommended by the pipe manufacturer, whichever is smaller.

2.1.7 Initial Backfill Material

Initial backfill shall consist of select granular material or satisfactory materials free from rocks 3 inches or larger in any dimension or free from rocks of such size as recommended by the pipe manufacturer, whichever is smaller.

2.2 PLASTIC MARKING TAPE

Plastic marking tape shall be acid and alkali-resistant polyethylene film, 6 inches wide with minimum thickness of 0.004 inch. Tape shall have a minimum strength of 1750 psi lengthwise and 1500 psi crosswise. The tape shall be manufactured with integral wires, foil backing or other means to enable detection by a metal detector when the tape is buried up to 3 feet deep. The tape shall be of a type specifically manufactured for marking and locating underground utilities. The metallic core of the tape shall be encased in a protective jacket or provided with other means to protect it from corrosion. Tape color shall be as specified in TABLE 1 and shall bear a continuous printed inscription describing the specific utility.

TABLE 1. Tape Color

Red:	Electric
Yellow:	Gas, Oil, Dangerous Materials
Orange:	Telephone, Telegraph, Television, Police, and Fire Communications
Blue:	Water Systems
Green:	Sewer Systems

3 EXECUTION

3.1 EXCAVATION

Excavation shall be performed to the lines and grades indicated. Rock excavation shall include removal and disposition of material defined as rock in paragraph MATERIALS. Earth excavation shall include removal and disposal of material not classified as rock excavation. During excavation, material satisfactory for backfilling shall be stockpiled in an orderly manner at a distance from the banks of the trench equal to 1/2 the depth of the excavation, but in no instance closer than 2 feet. Excavated material not required or not satisfactory for backfill shall be removed from the site. Disposal shall be carried out by the Contractor to a location on base specified by the CO. Grading shall be done as may be necessary to prevent surface water from flowing into the excavation, and any water accumulating shall be removed to maintain the stability of the bottom and sides of the excavation. Unauthorized overexcavation shall be backfilled in accordance with paragraph BACKFILLING AND COMPACTION at no additional cost to the Government.

3.1.1 Trench Excavation Requirements

The trench shall be excavated as recommended by the manufacturer of the pipe to be installed. Trench walls below the top of the pipe shall be sloped, or made vertical, and of such width as recommended in the manufacturer's installation manual. Where no manufacturer's installation manual is available, trench walls shall be made vertical. Trench walls more than 5 feet high shall be shored, cut back to a stable slope, or provided with equivalent means of protection for employees who may be exposed to moving ground or cave

in. Trench walls which are cut back shall be excavated to at least the angle of repose of the soil. Special attention shall be given to slopes which may be adversely affected by weather or moisture content. The trench width below the top of pipe shall not exceed 24 inches plus pipe outside diameter (O.D.) for pipes of less than 24 inches inside diameter and shall not exceed 36 inches plus pipe outside diameter for sizes larger than 24 inches inside diameter. Where recommended trench widths are exceeded, redesign, stronger pipe, or special installation procedures shall be utilized by the Contractor. The cost of redesign, stronger pipe, or special installation procedures shall be borne by the Contractor without any additional cost to the Government.

3.1.1.1 Bottom Preparation

The bottoms of trenches shall be accurately graded to provide uniform bearing and support for the bottom quadrant of each section of the pipe. Bell holes shall be excavated to the necessary size at each joint or coupling to eliminate point bearing. Stones of 3 inches or greater in any dimension, or as recommended by the pipe manufacturer, whichever is smaller, shall be removed to avoid point bearing.

3.1.1.2 Removal of Unyielding Material

Where overdepth is not indicated and unyielding material is encountered in the bottom of the trench, such material shall be removed 12 inches below the required grade and replaced with suitable materials as provided in paragraph BACKFILLING AND COMPACTION.

3.1.1.3 Removal of Unstable Material

Where unstable material is encountered in the bottom of the trench, such material shall be removed to the depth directed and replaced to the proper grade with select granular material as provided in paragraph BACKFILLING AND COMPACTION. When removal of unstable material is required due to the Contractor's fault or neglect in performing the work, the resulting material shall be excavated and replaced by the Contractor without additional cost to the Government.

3.1.1.4 Excavation for Appurtenances

Excavation for manholes, catch-basins, inlets, or similar structures shall be sufficient to leave at least 12 inches clear between the outer structure surfaces and the face of the excavation or support members Rock shall be cleaned of loose debris and cut to a firm surface either level, stepped, or serrated, as shown or as directed. Loose disintegrated rock and thin strata shall be removed. Removal of unstable material shall be as specified above. When concrete or masonry is to be placed in an excavated area, special care shall be taken not to disturb the bottom of the excavation. Excavation to the final grade level shall not be made until just before the concrete or masonry is to be placed.

3.1.2 Stockpiles

Stockpiles of satisfactory, unsatisfactory, and wasted materials shall be placed and graded as specified. Stockpiles shall be kept in a neat and well drained condition, giving due consideration to drainage at all times. The ground surface at stockpile locations shall be cleared, grubbed, and sealed by rubber-tired equipment, excavated satisfactory and unsatisfactory materials shall be separately stockpiled. Stockpiles of satisfactory materials

shall be protected from contamination which may destroy the quality and fitness of the stockpiled material. If the Contractor fails to protect the stockpiles, and any material becomes unsatisfactory, such material shall be removed and replaced with satisfactory material from approved sources at no additional cost to the Government. Locations of stockpiles of satisfactory materials shall be as shown on plans.

3.2 BACKFILLING AND COMPACTION

Backfill material shall consist of satisfactory material, select granular material, or initial backfill material as required. Backfill shall be placed in layers not exceeding 6 inches loose thickness for compaction by hand operated machine compactors, and 8 inches loose thickness for other than hand operated machines, unless otherwise specified. Each layer shall be compacted to at least 95 percent maximum density for cohesionless soils and 90 percent maximum density for cohesive soils, unless otherwise specified.

3.2.1 Trench Backfill

Trenches shall be backfilled to the grade shown. The trench shall be backfilled to 2 feet above the top of pipe prior to performing the required pressure tests. The joints and couplings shall be left uncovered during the pressure test.

3.2.1.1 Replacement of Unyielding Material

Unyielding material removed from the bottom of the trench shall be replaced with select granular material or initial backfill material.

3.2.1.2 Replacement of Unstable Material

Unstable material removed from the bottom of the trench or excavation shall be replaced with select granular material placed in layers not exceeding 6 inches loose thickness.

3.2.1.3 Bedding and Initial Backfill

Bedding shall be of the type and thickness shown. Initial backfill material shall be placed and compacted with approved tampers to a height of at least one foot above the utility pipe or conduit. The backfill shall be brought up evenly on both sides of the pipe for the full length of the pipe. Care shall be taken to ensure thorough compaction of the fill under the haunches of the pipe.

3.2.1.4 Final Backfill

The remainder of the trench, except for special materials for roadways, railroads and airfields, shall be filled with satisfactory material. Backfill material shall be placed and compacted as follows:

a. Roadways, Railroads, and Airfields: Backfill shall be placed up to the elevation at which the requirements in Section 02300 EARTHWORK control. Water flooding or jetting methods of compaction will not be permitted.

b. Sidewalks, Turfed or Seeded Areas and Miscellaneous Areas: Backfill shall be deposited in layers of a maximum of 12 inch loose thickness, and compacted to 85

percent maximum density for cohesive soils and 90 percent maximum density for cohesionless soils. Compaction by water flooding or jetting will not be permitted. This requirement shall also apply to all other areas not specifically designated above.

3.3 SPECIAL REQUIREMENTS

Special requirements for both excavation and backfill relating to the specific utilities are as follows:

3.3.1 Water Lines

Trenches shall be of a depth to provide a minimum cover of 2 1/2 feet except under runway where the minimum cover shall be 4 feet from the existing ground surface, or from the indicated finished grade, whichever is lower, to the top of the pipe.

3.3.2 Plastic Marking Tape

Warning tapes shall be installed directly above the pipe, at a depth of 12 inches below finished grade or bottom of pavement section unless otherwise shown.

3.4 TESTING

Testing shall be the responsibility of the Contractor and shall be performed at no additional cost to the Government.

3.4.1 Testing Facilities

Tests shall be performed by an approved commercial testing laboratory or may be tested by facilities furnished by the Contractor. No work requiring testing will be permitted until the facilities have been inspected and approved by the Contracting Officer.

3.4.2 Testing of Backfill Materials

Classification of backfill materials shall be determined in accordance with ASTM D 2487 and the moisture-density relations of soils shall be determined in accordance with ASTM D 1557. A minimum of one soil classification and one moisture-density relation test shall be performed on each different type of material used for bedding and backfill.

3.4.3 Field Density Tests

Tests shall be performed in sufficient numbers to ensure that the specified density is being obtained. A minimum of one field density test per lift of backfill for every 150 feet of installation, with a minimum of two tests per trench, shall be performed. One moisture density relationship shall be determined for every 1500 cubic yards of material used. Field in-place density shall be determined in accordance with ASTM D 1556 ASTM D 2167 ASTM D 2922. When ASTM D 2922 is used, the calibration curves shall be checked and adjusted using the sand cone method as described in paragraph Calibration of the ASTM publication. ASTM D 2922 results in a wet unit weight of soil and when using this method, ASTM D 3017 shall be used to determine the moisture content of the soil. The calibration curves furnished with the moisture gauges shall be checked along with density calibration checks as described in

ASTM D 3017. The calibration checks of both the density and moisture gauges shall be made at the beginning of a job, on each different type of material encountered, at intervals as directed by the Contracting Officer. Copies of calibration curves, results of calibration tests, and field and laboratory density tests shall be furnished to the Contracting Officer. Trenches improperly compacted shall be reopened to the depth directed, then refilled and compacted to the density specified at no additional cost to the Government.

3.4.4 Displacement of Sewers

After other required tests have been performed and the trench backfill compacted to 3/4 of the distance from the top of pipe to existing grade except under the runway where the trench backfill shall be compacted to subgrade level, the pipe shall be inspected to determine whether significant displacement has occurred. This inspection shall be conducted in the presence of the Contracting Officer. Pipe sizes larger than 36 inches shall be entered and examined, while smaller diameter pipe shall be inspected by shining a light or laser between manholes or manhole locations, or by the use of television cameras passed through the pipe. If, in the judgment of the Contracting Officer, the interior of the pipe shows poor alignment or any other defects that would cause improper functioning of the system, the defects shall be remedied as directed at no additional cost to the Government.

END OF SECTION

This page intentionally blank

SECTION 02510 (R)

WATER DISTRIBUTION

1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN SOCIETY OF SANITARY ENGINEERING (ASSE)

ASME/ANSI B16.1	(1989) Cast Iron Pipe Flanges and Flanged Fittings
ANSI/ASME B16.3	(1992) Malleable Iron Threaded Fittings
ANSI/ASME B16.4	(1992) Gray Iron Threaded Fittings
ASME/ANSI B18.2.2	(1987; R 1993) Square and Hex Nuts (Inch Series)

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 47M	(1990) Ferritic Malleable Iron Castings (Metric)
ASTM A 47	(1990) Ferritic Malleable Iron Castings
ASTM A 48	(1994; Rev. A) Gray Iron Castings
ASTM A 307	(1994) Carbon Steel Bolts and Studs, 60,000 psi Tensile Strength
ASTM A 536	(1984; R 1993) Ductile Iron Castings
ASTM A 563	(1994) Carbon and Alloy Steel Nuts
ASTM C 94	(1997) Ready-Mixed Concrete
ASTM C 150	(1997; Rev. A) Portland Cement
ASTM D 2241	(1994) Poly(Vinyl Chloride) (PVC) Pressure-Rated Pipe (SDR Series)
ASTM D 2774	(1994) Underground Installation of Thermoplastic Pressure Piping
ASTM D 3139	(1995) Joints for Plastic Pressure Pipes Using Flexible Elastomeric Seals
ASTM F 477	(1995) Elastomeric Seals (Gaskets) for Joining Plastic Pipe

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA C110/A21.10	(1993) Ductile-Iron and Gray-Iron Fittings, 3 in. Through 48 in. (75 mm Through 1200 mm), for Water and Other Liquids
AWWA C111/A21.11	(1990; Erratum 1991) Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings
AWWA C153/A21.53	(1994) Ductile-Iron Compact Fittings, 3 in. Through 24 in. (76 mm Through 610 mm) and 54 in. Through 64 in. (1,000 mm Through 1,600 mm), for Water Service
AWWA C500	(1993) Metal-Seated Gate Valves for Water Supply Service
AWWA C508	(1993) Swing-Check Valves for Waterworks Service, 2 in. (50 mm) Through 24 in. (600 mm) NPS
AWWA C509	(1994) Resilient-Seated Gate Valves for Water and Sewerage Systems
AWWA C606	(1987) Grooved and Shouldered Joints
AWWA C651	(1992) Disinfecting Water Mains
AWWA C800	(1989) Underground Service Line Valves and Fittings
AWWA C900	(1989; Addendum 1992) Polyvinyl Chloride (PVC) Pressure Pipe, 4 in. Through 12 in., for Water Distribution
AWWA M23	(1980) PVC Pipe - Design and Installation

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 24	(1995) Installation of Private Fire Service Mains and Their Appurtenances

UNI-BELL PVC PIPE ASSOCIATION (UBPPA)

UBPPA UNI-B-3	(1988) Installation of Polyvinyl Chloride (PVC) Pressure Pipe
UBPPA UNI-B-8	(1986) Direct Tapping of Polyvinyl Chloride (PVC) Pressure Water Pipe

UNDERWRITERS LABORATORIES (UL)

UL 262	(1994) Gate Valves for Fire-Protection Service

UL 312	(1993; R 1994) Check Valves for Fire-Protection Service
UL 789	(1993; R 1994) Indicator Posts for Fire-Protection Service

1.2 SUBMITTALS

Submit the following in accordance with Section 01330, "Submittal Procedures."

Product Data

Piping Materials

Water distribution main piping, fittings, joints, valves, and coupling

Water service line piping, fittings, joints, valves, and coupling

Submit manufacturer's standard drawings or catalog cuts, except submit both drawings and cuts for push-on and rubber-gasketed bell-and-spigot joints. Include information concerning gaskets with submittal for joints and couplings.

Certificates

Water distribution main piping, fittings, joints, valves, and coupling

Water service line piping, fittings, joints, valves, and coupling

Certificates shall attest that tests set forth in each applicable referenced publication have been performed, whether specified in that publication to be mandatory or otherwise and that production control tests have been performed at the intervals or frequency specified in the publication. Other tests shall have been performed within 3 years of the date of submittal of certificates on the same type, class, grade, and size of material as is being provided for the project.

Manufacturer's Instructions

Installation procedures for water piping

1.3 DELIVERY, STORAGE, AND HANDLING

1.3.1 Delivery and Storage

Inspect materials delivered to site for damage. Unload and store with minimum handling. Store materials on site in enclosures or under protective covering. Store plastic piping, jointing materials and rubber gaskets under cover out of direct sunlight. Do not store materials directly on the ground. Keep inside of pipes, fittings, free of dirt and debris.

1.3.2 Handling

Handle pipe, fittings, valves, hydrants, and other accessories in a manner to ensure delivery to the trench in sound undamaged condition. Take special care to avoid injury to coatings and linings on pipe and fittings; make satisfactory repairs if coatings or linings are damaged. Carry, do not drag pipe to the trench. Store plastic piping, jointing materials and rubber gaskets that are not to be installed immediately, under cover out of direct sunlight.

2 PRODUCTS

2.1 WATER DISTRIBUTION MAIN MATERIALS

2.1.1 Piping Materials

2.1.1.1 Polyvinyl Chloride (PVC) Plastic Piping

a. Pipe and Fittings: Pipe, AWWA C900, shall be plain end or gasket bell end, Pressure Class [150 (DR 18)] with cast-iron-pipe-equivalent OD. Fittings shall be gray iron or ductile iron, AWWA C110/A21.10 or AWWA C153/A21.53, and have cement-mortar lining, AWWA C104/A21.4, standard thickness. Fittings with push-on joint ends shall conform to the same requirements as fittings with mechanical-joint ends, except that bell design shall be modified, as approved, for push-on joint suitable for use with PVC plastic pipe specified in this paragraph.

b. Joints and Jointing Material: Joints for pipe shall be push-on joints, ASTM D 3139. Joints between pipe and metal fittings, valves, and other accessories shall be push-on joints ASTM D 3139, or compression-type joints/mechanical joints, ASTM D 3139 and AWWA C111/A21.11. Provide each joint connection with an elastomeric gasket suitable for the bell or coupling with which it is to be used. Gaskets for push-on joints for pipe, ASTM F 477. Gaskets for push-on joints and compression-type joints/mechanical joints for joint connections between pipe and metal fittings, valves, and other accessories, AWWA C111/A21.11, respectively, for push-on joints and mechanical joints. Mechanically coupled joints using a sleeve-type mechanical coupling, as specified in paragraph entitled "Sleeve-Type Mechanical Couplings," may be used as an optional jointing method in lieu of push-on joints on plain-end PVC plastic pipe, subject to the limitations specified for mechanically coupled joints using a sleeve-type mechanical coupling and to the use of internal stiffeners as specified for compression-type joints in ASTM D 3139.

3 EXECUTION

3.1 INSTALLATION OF PIPELINES

3.1.1 General Requirements for Installation of Pipelines

These requirements shall apply to all pipeline installation except where specific exception is made in the "Special Requirements..." paragraphs.

3.1.1.1 Location of Water Lines

Where the location of the water line is not clearly defined by dimensions on the drawings, do not lay water line closer horizontally than 10 feet from any sewer line. Do not lay water lines in the same trench with gas lines fuel lines or electric wiring.

a. Water Piping Installation Parallel With Sewer Piping

(1) Normal Conditions: Lay water piping at least 10 feet horizontally from a sewer or sewer manhole whenever possible. Measure the distance edge-to-edge.

(2) Unusual Conditions: When local conditions prevent a horizontal separation of 10 feet, the water piping may be laid closer to a sewer or sewer manhole provided that:

(a) The bottom (invert) of the water piping shall be at least 18 inches above the top (crown) of the sewer piping.

(b) Where this vertical separation cannot be obtained, the sewer piping shall be constructed of AWWA-approved water pipe and pressure tested in place without leakage prior to backfilling.

(c) The sewer manhole shall be of watertight construction and tested in place.

b. Installation of Water Piping Crossing Sewer Piping

(1) Normal Conditions: Water piping crossing above sewer piping shall be laid to provide a separation of at least 18 inches between the bottom of the water piping and the top of the sewer piping.

(2) Unusual Conditions: When local conditions prevent a vertical separation described above, use the following construction:

(a) Sewer piping passing over or under water piping shall be constructed of AWWA-approved ductile iron water piping, pressure tested in place without leakage prior to backfilling.

(b) Water piping passing under sewer piping shall, in addition, be protected by providing a vertical separation of at least 18 inches between the bottom of the sewer piping and the top of the water piping; adequate structural support for the sewer piping to prevent excessive deflection of the joints and the settling on and breaking of the water piping; and that the length, minimum 20 feet, of the water piping be centered at the point of the crossing so that joints shall be equidistant and as far as possible from the sewer piping.

c. Sewer Piping or Sewer Manholes: No water piping shall pass through or come in contact with any part of a sewer manhole.

3.1.1.2 Earthwork

Perform earthwork operations in accordance with Section 02316A Excavation, Trenching, and Backfilling for Utilities Systems.

3.1.1.3 Pipe Laying and Jointing

Remove fins and burrs from pipe and fittings. Before placing in position, clean pipe, fittings, valves, and accessories, and maintain in a clean condition. Provide proper facilities for lowering sections of pipe into trenches. Do not under any circumstances drop or dump pipe, fittings, valves, or any other water line material into trenches. Cut pipe accurately to length established at the site and work into place without springing or forcing. Replace by one of the proper length any pipe or fitting that does not allow sufficient space for proper installation of jointing material. Blocking or wedging between bells and spigots will not be permitted. Lay bell-and-spigot pipe with the bell end pointing in the direction of laying. Grade the pipeline in straight lines; avoid the formation of dips and low points. Support pipe at proper elevation and grade. Secure firm, uniform support. Wood support blocking will not be permitted. Lay pipe so that the full length of each section of pipe and each fitting will rest solidly on the pipe bedding; excavate recesses to accommodate bells, joints, and couplings. Provide anchors and supports where indicated and where necessary for fastening work into place. Make proper provision for expansion and contraction of pipelines. Keep trenches free of water until joints have been properly made. At the end of each work day, close open ends of pipe temporarily with wood blocks or bulkheads. Do not lay pipe when conditions of trench or weather prevent installation. Depth of cover over top of pipe shall not be less than 2 1/2 feet except under runway where depth with cover shall not be less than 4 feet.

3.1.1.4 Connections to Existing Water Lines

Make connections to existing water lines after approval is obtained from Contract Officer and with a minimum interruption of service on the existing line.

3.1.2 Special Requirements for Installation of Water Mains

3.1.2.1 Installation of PVC Plastic Water Main Pipe

Installation of PVC Plastic Water Main Pipe and Associated Fittings: Unless otherwise specified, install pipe and fittings in accordance with paragraph entitled "General Requirements for Installation of Pipelines"; with the requirements of UBPPA UNI-B-3 for laying of pipe, joining PVC pipe to fittings and accessories, and setting of hydrants, valves, and fittings; and with the recommendations for pipe joint assembly and appurtenance installation in AWWA M23, Chapter 7, "Installation."

a. Jointing: Make push-on joints with the elastomeric gaskets specified for this type joint, using either elastomeric-gasket bell-end pipe or elastomeric-gasket couplings. For pipe-to-pipe push-on joint connections, use only pipe with push-on joint ends having factory-made bevel; for push-on joint connections to metal fittings, valves, and other accessories, cut spigot end of pipe off square and re-bevel pipe end to a bevel approximately the same as that on ductile-iron pipe used for the same type of joint. Use an approved lubricant recommended by the pipe manufacturer for push-on joints. Assemble push-on joints for pipe-to-pipe joint connections in accordance with the requirements of UBPPA UNI-B-3 for laying the pipe and the

recommendations in AWWA M23, Chapter 7, "Installation," for pipe joint assembly. Assemble push-on joints for connection to fittings, valves, and other accessories in accordance with the requirements of UBPPA UNI-B-3 for joining PVC pipe to fittings and accessories and with the applicable requirements of AWWA C600 for joint assembly. Make compression-type joints/mechanical joints with the gaskets, glands, bolts, nuts, and internal stiffeners previously specified for this type joint; assemble in accordance with the requirements of UBPPA UNI-B-3 for joining PVC pipe to fittings and accessories, with the applicable requirements of AWWA C600 for joint assembly, and with the recommendations of Appendix A to AWWA C111/A21.11. Cut off spigot end of pipe for compression-type joint/mechanical-joint connections and do not re-bevel. Assemble joints made with sleeve-type mechanical couplings in accordance with the recommendations of the coupling manufacturer using internal stiffeners as previously specified for compression-type joints.

b. Pipe Anchorage: Provide concrete thrust blocks (reaction backing) for pipe anchorage. Thrust blocks shall be in accordance with the requirements of UBPPA UNI-B-3 for reaction or thrust blocking and plugging of dead ends, except that size and positioning of thrust blocks shall be as indicated. Use concrete, ASTM C 94, having a minimum compressive strength of 2,500 psi at 28 days; or use concrete of a mix not leaner than one part cement, 2 1/2 parts sand, and 5 parts gravel, having the same minimum compressive strength.

3.1.2.2 Roads, Railroads and Airfields

Water pipe shall be encased in a sleeve of rigid conduit, as shown on the drawings, for the lengths shown. ~~Where sleeves are required, the pipe sleeve shall be as specified for storm drains in Section 02630 STORM DRAINAGE SYSTEM.~~ A minimum clearance of at least 2 inches between the inner wall of the sleeve and the maximum outside diameter of the sleeved pipe and joints shall be provided. Sand bedding shall be provided for the water pipe through the sleeve. Sleeves of ferrous material shall be provided with the corrosion protection as required for the conditions encountered at the site of installation.

3.1.3 Disinfection

Disinfect new water piping and existing water piping affected by Contractor's operations in accordance with AWWA C651. Fill piping systems with solution containing minimum of 50 parts per million of available chlorine and allow solution to stand for minimum of 24 hours. Flush solution from the systems with domestic water until maximum residual chlorine content is within the range of 0.2 and 0.5 parts per million, or the residual chlorine content of domestic water supply. Obtain at least two consecutive satisfactory bacteriological samples from new water piping, analyze by a certified laboratory, and submit the results prior to the new water piping being placed into service. Disinfection of systems supplying nonpotable water is not required.

3.2 FIELD QUALITY CONTROL

3.2.1 Field Tests and Inspections

The Contracting Officer will conduct field inspections and witness field tests specified in this section. The Contractor shall perform field tests, and provide labor, equipment, and

incidentals required for testing except that water and electric power needed for field tests will be furnished as indicated on plans. The Contractor shall produce evidence, when required, that any item of work has been constructed in accordance with the drawings and specifications.

3.2.2 Testing Procedure

Test water mains and water service lines in accordance with the applicable specified standard, except for the special testing requirements given in paragraph entitled "Special Testing Requirements." Test PVC plastic water mains in accordance with the requirements of UBPPA UNI-B-3 for pressure and leakage tests. The amount of leakage on pipelines made of PVC plastic water main pipe shall not exceed the amounts given in UBPPA UNI-B-3, except that at joints made with sleeve-type mechanical couplings, no leakage will be allowed.

3.2.3 Special Testing Requirements

For pressure test, use a hydrostatic pressure 50 psi greater than the maximum working pressure of the system, except that for those portions of the system having pipe size larger than 2 inches in diameter, hydrostatic test pressure shall be not less than 200 psi. Hold this pressure for not less than 2 hours. Prior to the pressure test, fill that portion of the pipeline being tested with water for a soaking period of not less than 24 hours. For leakage test, use a hydrostatic pressure not less than the maximum working pressure of the system. Leakage test may be performed at the same time and at the same test pressure as the pressure test.

END OF SECTION

SECTION 02531 (R)

SANITARY SEWERS

1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 14	(1999) Concrete Sewer, Storm Drain, and Culvert Pipe
ASTM C 33	(1999ael) Concrete Aggregates
ASTM C 76	(2000) Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe
ASTM C 76M	(2000) Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe (Metric)
ASTM C 94/C 94M	(2000) Ready-Mixed Concrete
ASTM C 150	(1999a) Portland Cement
ASTM C 260	(2000) Air-Entraining Admixtures for Concrete
ASTM C 270	(2000) Mortar for Unit Masonry
ASTM C 443	(1998) Joints for Circular Concrete Sewer and Culvert Pipe, Using Rubber Gaskets
ASTM C 478	(1997) Precast Reinforced Concrete Manhole Sections
ASTM C 828	(1998) Low-Pressure Air Test of Vitrified Clay Pipe Lines
ASTM C 924	(1998) Concrete Pipe Sewer Lines by Low-Pressure Air Test Method
ASTM C 924M	Concrete Pipe Sewer Lines by Low Pressure Air Test Method (Metric)
ASTM C 972	(2000) Compression-Recovery of Tape Sealant
ASTM D 412	(1998a) Vulcanized Rubber and Thermoplastic Rubbers and Thermoplastic Elastomers - Tension

ASTM D 624	(2000) Tear Strength of Conventional Vulcanized Rubber and Thermoplastic Elastomers

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 49	(1994) Hazardous Chemicals Data
NFPA 325-1	(1994) Fire Hazard Properties of Flammable Liquids, Gases, and Volatile Solids
NFPA 704	(1996) Identification of the Fire Hazards of Materials for Emergency Response

UNI-BELL PVC PIPE ASSOCIATION (UBPPA)

UBPPA UNI-B-6	(1990) Recommended Practice for the Low-Pressure Air Testing of Installed Sewer Pipe
UBPPA UNI-B-9	(1990; Addenda 1994) Recommended Performance Specification for Polyvinyl Chloride (PVC) Profile Wall Gravity Sewer Pipe and Fittings Based on Controlled Inside Diameter (Nominal Pipe Sizes 4-48 inch)

1.2 GENERAL REQUIREMENTS

The Contractor shall replace damaged material and redo unacceptable work at no additional cost to the Government. Excavation and backfilling is specified in Section 02316 EXCAVATION, TRENCHING, AND BACKFILLING FOR UTILITIES SYSTEMS. Backfilling shall be accomplished after inspection by the Contracting Officer. The Contractor shall have a copy of the manufacturer's instructions available at the construction site at all times and shall follow these instructions unless directed otherwise by the Contracting Officer.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Certificates

Portland Cement; G

Certificates of compliance stating the type of cement used in manufacture of concrete pipe, fittings and precast manholes.

Joints; G

Certificates of compliance stating that the fittings or gaskets used for waste drains or lines designated on the plans as 24" RCP Sanitary Sewer Lines are oil resistant.

2 PRODUCTS

2.1 PIPE

Pipe shall conform to the respective specifications and other requirements specified below.

2.2 REQUIREMENTS FOR FITTINGS

Fittings shall be compatible with the pipe supplied and shall have a strength not less than that of the pipe. Fittings shall conform to the respective specifications and other requirements specified below.

2.3 JOINTS

Joints installation shall comply with the manufacturer's instructions. Fittings and gaskets utilized for waste drains or industrial waste lines shall be certified by the manufacturer as oil resistant.

2.4 FRAMES AND COVERS

Frames and covers shall be cast iron, ductile iron or reinforced concrete. Cast iron frames and covers shall be as indicated or shall be of type suitable for the application, circular with vent holes. The frames and covers shall have a combined weight of not less than 400 pounds. Reinforced concrete frames and covers shall be as indicated or shall conform to ASTM C 478 or ASTM C 478M. The word "Sewer" shall be stamped or cast into covers so that it is plainly visible.

2.5 CEMENT MORTAR

Cement mortar shall conform to ASTM C 270, Type M with Type II cement.

2.5.1 Portland Cement

Portland cement shall conform to ASTM C 150, Type V for concrete used in concrete pipe, concrete pipe fittings, and manholes and type optional with the Contractor for cement used in concrete cradle, concrete encasement, and thrust blocking. Air-entraining admixture conforming to ASTM C 260 shall be used with Type V cement. Where aggregates are alkali reactive, as determined by Appendix XI of ASTM C 33, a cement containing less than 0.60 percent alkalies shall be used.

2.5.2 Portland Cement Concrete

Portland cement concrete shall conform to ASTM C 94/C 94M, compressive strength of 4000 psi at 28 days, except for concrete cradle and encasement or concrete blocks for manholes. Concrete used for cradle and encasement shall have a compressive strength of 2500 psiminimum at 28 days. Concrete in place shall be protected from freezing and moisture loss for 7 days.

2.6 STRUCTURES

2.6.1 Precast Reinforced Concrete Manhole Sections

Precast reinforced concrete manhole sections shall conform to ASTM C 478, except that portland cement shall be as specified herein. Joints shall be cement mortar, an approved mastic, rubber gaskets, a combination of these types; or the use of external preformed rubber joint seals and extruded rolls of rubber with mastic adhesive on one side.

3 EXECUTION

3.1 INSTALLATION

3.1.1 Adjacent Facilities

3.1.1.1 Water Lines

Where the location of the sewer is not clearly defined by dimensions on the drawings, the sewer shall not be closer horizontally than 10 feet to a water-supply main or service line, except that where the bottom of the water pipe will be at least 12 inches above the top of the sewer pipe, the horizontal spacing may be a minimum of 6 feet Where gravity-flow sewers cross above water lines, the sewer pipe for a distance of 10 feet on each side of the crossing shall be fully encased in concrete or shall be acceptable pressure pipe with no joint closer horizontally than 3 feet to the crossing. The thickness of the concrete encasement including that at the pipe joints shall be not less than 4 inches

3.1.2 Pipe Laying

a. Pipe shall be protected during handling against impact shocks and free fall; the pipe interior shall be free of extraneous material.

b. Pipe laying shall proceed upgrade with the spigot ends of bell-and-spigot pipe and tongue ends of tongue-and-groove pipe pointing in the direction of the flow. Each pipe shall be laid accurately to the line and grade shown on the drawings. Pipe shall be laid and centered so that the sewer has a uniform invert. As the work progresses, the interior of the sewer shall be cleared of all superfluous materials.

c. Before making pipe joints, all surfaces of the portions of the pipe to be joined shall be clean and dry. Lubricants, primers, and adhesives shall be used as recommended by the pipe manufacturer. The joints shall then be placed, fitted, joined, and adjusted to obtain the degree of water tightness required.

3.1.2.1 Trenches

Trenches shall be kept free of water and as dry as possible during bedding, laying, and jointing and for as long a period as required. When work is not in progress, open ends of pipe and fittings shall be satisfactorily closed so that no trench water or other material will enter the pipe or fittings.

3.1.2.2 Backfill

As soon as possible after the joint is made, sufficient backfill material shall be placed along the pipe to prevent pipe movement off line or grade.

3.1.2.3 Width of Trench

If the maximum width of the trench at the top of the pipe, as specified in Section 02316 EXCAVATION, TRENCHING, AND BACKFILLING FOR UTILITIES SYSTEMS, is exceeded for any reason other than by direction, the Contractor shall install, at no additional cost to the Government, concrete cradling, pipe encasement, or other bedding required to support the added load of the backfill.

3.1.2.4 Jointing

Joints between different pipe materials shall be made as specified, using approved jointing materials.

3.1.2.5 Handling and Storage

Pipe, fittings and joint material shall be handled and stored in accordance with the manufacturer's recommendations. Storage facilities for plastic pipe, fittings, joint materials and solvents shall be classified and marked in accordance with NFPA 704, with classification as indicated in NFPA 49 and NFPA 325-1.

3.1.3 Leakage Tests

Lines shall be tested for leakage by low pressure air testing~~, infiltration tests or exfiltration tests, as appropriate~~. Low pressure air testing for concrete pipes shall be as prescribed in ASTM C 828. ~~Prior to infiltration or exfiltration tests, the trench shall be backfilled up to at least the lower half of the pipe. If required, sufficient additional backfill shall be placed to prevent pipe movement during testing, leaving the joints uncovered to permit inspection. Visible leaks encountered shall be corrected regardless of leakage test results. When the water table is 2 feet or more above the top of the pipe at the upper end of the pipeline section to be tested, infiltration shall be measured using a suitable weir or other device acceptable to the Contracting Officer. When the Contracting Officer determines that infiltration cannot be properly tested, an exfiltration test shall be made by filling the line to be tested with water so that a head of at least 2 feet is provided above both the water table and the top of the pipe at the upper end of the pipeline to be tested. The filled line shall be allowed to stand until the pipe has reached its maximum absorption, but not less than 4 hours. After absorption, the head shall be re-established. The amount of water required to maintain this water level during a 2-hour test period shall be measured. Leakage as measured by either the infiltration test or exfiltration test shall not exceed 25 gal per inch diameter per mile of pipeline per day.~~ The Contractor shall test only the new sewer pipe. No leakage testing is to be conducted on existing pipe. The Contractor must not rely on existing manholes for access to seal the pipe for testing. Instead, the new pipe shall be sealed for testing prior to making the connection between the new and the existing. When leakage exceeds the maximum amount specified, satisfactory correction shall be made and retesting accomplished. Testing, correction, and retesting shall be made at no additional cost to the Government.

Closed Circuit Television (CCTV) Inspection (and Attached)

1. Acceptance criteria:

   a. No visible standing water in pipeline caused by grade defects.
   b. No pipeline structural defects observed.
   c. No pipeline installation defects observed.
   d. No infiltration observed.

2. CCTV sewer line inspection to be performed by firms which are suitably equipped, experienced, qualified and staffed for sewer line CCTV inspection. If requested, provide a calibration tape showing various water depths for the size of pipe being videoed. Calibration tape must be onsite during CCTV process.

3. Perform CCTV inspection after backfill and prior to surface repair. Uncover and reinstall sections of the pipe found to have defects in workmanship (including standing water caused by grade defects) as directed by the Owner. After repair re-CCTV the repaired section. Do not reinstall damaged or rejected pipe.

4. Notify Engineer at least 48 hours prior to CCTV inspection to allow for Engineer, at Engineer's discretion, to witness.

5. Clean lines prior to CCTV inspection using hydro cleaner, flushing balls or other suitable means acceptable to Engineer.

6. Immediately prior to CCTV inspection, pour sufficient water/dye mixture in upstream manhole to produce visible flow in downstream manhole(s).

7. Provide CCTV sewer kube ubsoectuib eqyuonebt ubckydubg a cikir canera ststenm 1/2" VHS taping system, camera propulsion equipment and van to allow witness of CCTV by Inspector.

8. Use super high grade, color, 1/2" VHS tapes. The tapes shall include the following video and audio information:

   a. Video:
      1) Project Number & Name
      2) Date of TV Inspection
      3) Upstream and downstream manhole numbers
      4) Current distance along line segment

   b. Audio:
      1) Date of TV Inspection
      2) Verbal confirmation of upstream and downstream manhole numbers and/or locations
      3) Verbal description of pipe, size, type, and pipe joint length
      4) Verbal description of location of each service connection

   c. Tape identification Tag:
      1) Manhole to Manhole Designation

9. If no defects observed submit tapes and logs to Engineer for review and acceptance.

3.2 GENERAL REQUIREMENTS

Manholes shall be constructed of precast concrete manhole sections. The invert channels shall be smooth and semicircular in shape conforming to the inside of the adjacent sewer section. Changes in direction of flow shall be made with a smooth curve of as large a radius as the size of the manhole will permit. Changes in size and grade of the channels shall be made gradually and evenly. The invert channels shall be formed directly in the concrete of the manhole base, or shall be built up with brick and mortar, or shall be half tile laid in concrete, or shall be constructed by laying full section sewer pipe through the manhole and breaking out the top half after the surrounding concrete has hardened. Pipe connections shall be made to manhole using water stops, standard O-ring joints, special manhole coupling, or shall be made in accordance with the manufacturer's recommendation. The Contractor's proposed method of connection, list of materials selected, and specials required, shall be approved prior to installation. The floor of the manhole outside the channels shall be smooth and shall slope toward the channels not less than 1 inch per foot nor more than 2 inches per foot. Free drop inside the manholes shall not exceed 18 inches, measured from the invert of the inlet pipe to the top of the floor of the manhole outside the channels; drop manholes shall be constructed whenever the free drop would otherwise be greater than 1 foot 6 inches.

3.2.1 Jointing, Plastering and Sealing

Mortar joints shall be completely filled and shall be smooth and free from surplus mortar on the inside of the manhole. Mortar and mastic joints between precast rings shall be full-bedded in jointing compound and shall be smoothed to a uniform surface on both the interior and exterior of the manhole. Installation of rubber gasket joints between precast rings shall be in accordance with the recommendations of the manufacturer. Precast rings may also be sealed by the use of extruded rolls of rubber with mastic adhesive on one side.

3.2.2 Setting of Frames and Covers

Unless otherwise indicated, tops of frames and covers shall be set flush with finished grade in paved areas or 2 inches higher than finished grade in unpaved areas. Frame and cover assemblies shall be sealed to manhole sections using external preformed rubber joint seals that meet the requirements of ASTM D 412 and ASTM D 624, or other methods specified in paragraph Jointing, Plastering and Sealing, unless otherwise specified.

3.2.3 External Preformed Rubber Joint Seals

External preformed rubber joint seals and extruded rolls of rubber with mastic adhesive shall meet the requirements of ASTM D 412 and ASTM C 972 to ensure conformance with paragraph Leakage Tests. The seal shall be multi-section with neoprene rubber top section and all lower sections made of Ethylene Propylene Di Monomer (EPDM) rubber with a minimum thickness of 60 mils Each unit shall consist of a top and a bottom section and shall have mastic on the bottom of the bottom section and mastic on the top and bottom of the top section. The mastic shall be non-hardening butyl rubber sealant and shall seal to the cone/top slab of the manhole/catch basin and over the lip of the casting. One unit shall seal a casting and up to six, 2inch adjusting rings. The bottom section shall be 12 inches in height. A 6 inch high top section will cover up to two, 2 inchadjusting rings. A 12 inch high bottom

section will cover up to six, 2 inch adjusting rings. Extension sections shall cover up to two more adjusting rings. Each extension shall overlap the bottom section by 2 inch and shall be overlapped by the top section by 2 inch

3.3 CONNECTING TO EXISTING MANHOLES

Pipe connections to existing manholes shall be made so that finish work will conform as nearly as practicable to the applicable requirements specified for new manholes, including all necessary concrete work, cutting, and shaping. The connection shall be centered on the manhole. Holes for the new pipe shall be of sufficient diameter to allow packing cement mortar around the entire periphery of the pipe but no larger than 1.5 times the diameter of the pipe. Cutting the manhole shall be done in a manner that will cause the least damage to the walls.

3.4 BUILDING CONNECTIONS

Building connections shall include the lines to and connection with the building waste drainage piping at a point approximately 5 feet outside the building, unless otherwise indicated. Where building drain piping is not installed, the Contractor shall terminate the building connections approximately 5 feet from the site of the building at a point and in a manner designated.

3.5 CLEANOUTS AND OTHER APPURTENANCES

Cleanouts and other appurtenances shall be installed where shown on the drawings or as directed by the Contracting Officer, and shall conform to the detail of the drawings.

END OF SECTION

SECTION 02722 (R)

GRADED-CRUSHED AGGREGATE BASE COURSE

1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO T 180	(1997) Moisture-Density Relations of Soils Using a 4.54-kg (10-lb) Rammer and an 457 mm (18-in) Drop
AASHTO T 224	(1996) Correction for Coarse Particles in the Soil Compaction Test

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 29/C 29M	(1997) Bulk Density ("Unit Weight") and Voids in Aggregates
ASTM C 88	(1999a) Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate
ASTM C 117	(1995) Materials Finer Than 75 micrometer (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C 127	(1988; R 1993el) Specific Gravity and Absorption of Course Aggregate
ASTM C 128	(1997) Specific Gravity and Absorption of Fine Aggregate
ASTM C 131	(1996) Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine
ASTM C 136	(1996a) Sieve Analysis of Fine and Coarse Aggregates
ASTM D 75	(1987; R 1997) Sampling Aggregates
ASTM D 422	(1963; R 1998) Particle-Size Analysis of Soils
ASTM D 1556	(2000) Density and Unit Weight of Soil in Place by the Sand-Cone Method

ASTM D 1557	(1991; R 1998) Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/cu. ft. (2,700 kN-m/cu.m.))
ASTM D 2167	(1994) Density and Unit Weight of Soil in Place by the Rubber Balloon Method
ASTM D 2487	(2000) Classification of Soils for Engineering Purposes (Unified Soil Classification System)
ASTM D 2922	(1996el) Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth)
ASTM D 3017	(1988; R 1996el) Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth)
ASTM D 4318	(2000) Liquid Limit, Plastic Limit, and Plasticity Index of Soils
ASTM E 11	(1995) Wire-Cloth Sieves for Testing Purposes

1.2 DEFINITIONS

For the purposes of this specification, the following definitions apply.

1.2.1 Graded-crushed Aggregate Base Course

Graded-crushed aggregate (GCA) base course is well graded, crushed, durable aggregate uniformly moistened and mechanically stabilized by compaction. GCA is similar to ABC, but it has more stringent requirements and it produces a base course with higher strength and stability.

1.2.2 Degree of Compaction

Degree of compaction shall be expressed as a percentage of the maximum density obtained by the test procedure presented in AASHTO T 180, Method D and corrected with AASHTO T 224.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Product Data

Plant, Equipment, and Tools; G

List of proposed equipment to be used in performance of construction work, including descriptive data.

Test Reports

Sampling and testing; G
Field Density Tests; G

Calibration curves and related test results prior to using the device or equipment being calibrated. Copies of field test results within 24 hours after the tests are performed. Certified copies of test results for approval not less than 30 days before material is required for the work.

1.4 SAMPLING AND TESTING

Sampling and testing shall be the responsibility of the Contractor. Sampling and testing shall be performed by a testing laboratory approved in accordance with Section 01451 CONTRACTOR QUALITY CONTROL. Work requiring testing will not be permitted until the testing laboratory has been inspected and approved. The materials shall be tested to establish compliance with the specified requirements; testing shall be performed at the specified frequency. The Contracting Officer may specify the time and location of the tests. Copies of test results shall be furnished to the Contracting Officer within 24 hours of completion of the tests.

1.4.1 Sampling

Samples for laboratory testing shall be taken in conformance with ASTM D 75. When deemed necessary, the sampling will be observed by the Contracting Officer.

1.4.2 Tests

The following tests shall be performed in conformance with the applicable standards listed.

1.4.2.1 Sieve Analysis

Sieve analysis shall be made in conformance with ASTM C 117 and ASTM C 136. Sieves shall conform to ASTM E 11. Particle-size analysis of the soils shall also be completed in conformance with ASTM D 422.

1.4.2.2 Liquid Limit and Plasticity Index

Liquid limit and plasticity index shall be determined in accordance with ASTM D 4318.

1.4.2.3 Moisture-Density Determinations

The maximum density and optimum moisture content shall be determined in accordance with AASHTO T 180, Method D and corrected with AASHTO T 224. To maintain the same percentage of coarse material, the "remove and replace" procedure as described in the NOTE 8 in Paragraph 7.2 of AASHTO T 180 shall be used.

1.4.2.4 Field Density Tests

Density shall be field measured in accordance with ASTM D 2922. For the method presented in ASTM D 2922 the calibration curves shall be checked and adjusted if necessary using only the sand cone method as described in paragraph Calibration, of the ASTM publication. Tests performed in accordance with ASTM D 2922 result in a wet unit weight of soil and when using this method, ASTM D 3017 shall be used to determine the moisture content of the soil. The calibration curves furnished with the moisture gauges shall also be checked along with density calibration checks as described in ASTM D 3017. The calibration checks of both the density and moisture gauges shall be made by the prepared containers of material method, as described in paragraph Calibration of ASTM D 2922, on each different type of material being tested at the beginning of a job and at intervals as directed.

1.4.2.5 Wear Test

Wear tests shall be made on GCA course material in conformance with ASTM C 131.

1.4.2.6 Soundness

Soundness tests shall be made on GCA in accordance with ASTM C 88.

1.4.3 Testing Frequency

1.4.3.1 Initial Tests

One of each of the following tests shall be performed on the proposed material prior to commencing construction to demonstrate that the proposed material meets all specified requirements when furnished. If materials from more than one source are going to be utilized, this testing shall be completed for each source.

a. Sieve Analysis including No. 635 size material.

b. Liquid limit and plasticity index.

c. Moisture-density relationship.

d. Wear.

e. Soundness.

1.4.3.2 In Place Tests

Each of the following tests shall be performed on samples taken from the placed and compacted GCA. Samples shall be taken and tested at the rates indicated.

a. Density tests shall be performed on every lift of material placed and at a frequency of one set of tests for every 1000 square yards, or portion thereof, of completed area.

b. Sieve Analysis including No. 635 size material shall be performed for every 500 cubic yards, or portion thereof, of material placed.

c. Liquid limit and plasticity index tests shall be performed at the same frequency as the sieve analysis.

1.4.4 Approval of Material

The source of the material shall be selected 30 days prior to the time the material will be required in the work. Tentative approval of material will be based on initial test results. Final approval of the materials will be based on sieve analysis, liquid limit, and plasticity index tests performed on samples taken from the completed and fully compacted GCA.

1.5 WEATHER LIMITATIONS

Construction shall be done when the atmospheric temperature is above 35 degrees F. When the temperature falls below 35 degrees F the Contractor shall protect all completed areas by approved methods against detrimental effects of freezing. Completed areas damaged by freezing, rainfall, or other weather conditions shall be corrected to meet specified requirements.

1.6 PLANT, EQUIPMENT, AND TOOLS

All plant, equipment, and tools used in the performance of the work will be subject to approval before the work is started and shall be maintained in satisfactory working condition at all times. The equipment shall be adequate and shall have the capability of producing the required compaction, meeting grade controls, thickness control, and smoothness requirements as set forth herein.

2 PRODUCTS

2.1 AGGREGATES

The GCA shall consist of clean, sound, durable particles of crushed stone, crushed gravel, crushed recycled concrete, angular sand, or other approved material. GCA shall be free of silt and clay as defined by ASTM D 2487, organic matter, and other objectionable materials or coatings. The portion retained on the No. 4 sieve shall be known as coarse aggregate; that portion passing the No. 4 sieve shall be known as fine aggregate.

2.1.1 Coarse Aggregate

Coarse aggregates shall be angular particles of uniform density. When the coarse aggregate is supplied from more than one source, aggregate from each source shall meet the specified requirements and shall be stockpiled separately.

a. Crushed Gravel: Crushed gravel shall be manufactured by crushing gravels, and shall meet all the requirements specified below.

b. Crushed Stone: Crushed stone shall consist of freshly mined quarry rock, and shall meet all the requirements specified below.

c. Crushed Recycled Concrete: Crushed recycled concrete shall consist of previously hardened portland cement concrete or other concrete containing pozzolanic binder material. The recycled material shall be free of all reinforcing steel, bituminous concrete surfacing, and

any other foreign material and shall be crushed and processed to meet the required gradations for coarse aggregate. Crushed recycled concrete shall meet all other applicable requirements specified below.

2.1.1.1 Graded-Crushed Aggregate Base Course

GCA coarse aggregate shall not show more than 40 percent loss when subjected to the Los Angeles abrasion test in accordance with ASTM C 131. GCA coarse aggregate shall not exhibit a loss greater than 40 percent weighted average, at five cycles, when tested for soundness in magnesium sulfate in accordance with ASTM C 88. The amount of flat and elongated particles shall not exceed 20 percent for the fraction retained on the 1/2 inch sieve nor 20 percent for the fraction passing the 1/2 inch sieve. A flat particle is one having a ratio of width to thickness greater than 3; an elongated particle is one having a ratio of length to width greater than 3. In the portion retained on each sieve specified, the crushed aggregate shall contain at least 90 percent by weight of crushed pieces having two or more freshly fractured faces with the area of each face being at least equal to 75 percent of the smallest midsectional area of the piece. When two fractures are contiguous, the angle between planes of the fractures must be at least 30 degrees in order to count as two fractured faces. Crushed gravel shall be manufactured from gravel particles 90 percent of which by weight are retained on the maximum size sieve listed in TABLE 1.

2.1.2 Fine Aggregate

Fine aggregates shall be angular particles of uniform density. When the fine aggregate is supplied from more than one source, aggregate from each source shall meet the specified requirements.

2.1.2.1 Graded-Crushed Aggregate Base Course

GCA fine aggregate shall consist of angular particles produced by crushing stone, recycled concrete, or gravel that meets the requirements for wear and soundness specified for GCA coarse aggregate. Fine aggregate shall be produced by crushing only particles larger than No. 4 sieve in size. The fine aggregate shall contain at least 90 percent by weight of particles having two or more freshly fractured faces in the portion passing the No. 4 sieve and retained on the No. 10 sieve, and in the portion passing the No. 10 sieve and retained on the No. 40 sieve.

2.1.3 Gradation Requirements

The specified gradation requirements shall apply to the completed base course. The aggregates shall have a maximum size of 1-1/2inches and shall be continuously well graded within the limits specified in TABLE 1. Sieves shall conform to ASTM E 11.

TABLE 1. GRADATION OF AGGREGATES

Percentage by Weight Passing Square-Mesh Sieve

Sieve Designation	Percentage Passing
2 inch	----
1-1/2 inch	100
1 inch	60-100
1/2 inch	30-65
No. 4	20-50
No. 10	15-40
No. 40	5-25
No. 200	0-8

NOTE 1: Particles having diameters less than 0.0008 inch shall not be in excess of 3 percent by weight of the total sample tested.

NOTE 2: The values are based on aggregates of uniform specific gravity. If materials from different sources are used for the coarse and fine aggregates, they shall be tested in accordance with ASTM C 127 and ASTM C 128 to determine their specific gravities. If the specific gravities vary by more than 10 percent, the percentages passing the various sieves shall be corrected as directed by the Contracting Officer.

2.1.4 Liquid Limit and Plasticity Index

Liquid limit and plasticity index requirements shall apply to the completed course and shall also apply to any component that is blended to meet the required gradation. The portion of any component or of the completed course passing the No. 40 sieve shall be either nonplastic or have a liquid limit not greater than 25 and a plasticity index not greater than 5.

2.1.5 Recycled Concrete

The demolished concrete shall be recycled by the Contractor as GCA. Concrete shall be crushed and must meet specification for GCA. Other materials may be added to the crushed concrete to meet specifications, if needed. Any unused crushed concrete shall become the property of the Government and will be stockpiled as shown on the drawings. See Section 02220A DEMOLITION.

3 EXECUTION

3.1 GENERAL REQUIREMENTS

When the GCA is constructed in more than one layer, the previously constructed layer shall be cleaned of loose and foreign matter by sweeping with power sweepers or power brooms, except that hand brooms may be used in areas where power cleaning is not practicable. Adequate drainage shall be provided during the entire period of construction to prevent water from collecting or standing on the working area. Line and grade stakes shall be provided as necessary for control. Grade stakes shall be in lines parallel to the centerline of the area under construction and suitably spaced for string lining.

3.2 STOCKPILING MATERIAL

Prior to stockpiling of material, storage sites shall be cleared and leveled by the Contractor. All materials, including approved material available from excavation and grading, shall be stockpiled in the manner and at the locations designated. Aggregates shall be stockpiled on the cleared and leveled areas designated by the Contracting Officer to prevent segregation. Materials obtained from different sources shall be stockpiled separately.

3.3 PREPARATION OF UNDERLYING COURSE

Prior to constructing the GCA, the underlying course or subgrade shall be cleaned of all foreign substances. At the time of construction of the GCA, the underlying course shall contain no frozen material. The surface of the underlying course or subgrade shall meet specified compaction and surface tolerances. The underlying course shall conform to Section 02300 (R) EARTHWORK. Ruts or soft yielding spots in the underlying courses, areas having inadequate compaction, and deviations of the surface from the requirements set forth herein shall be corrected by loosening and removing soft or unsatisfactory material and by adding approved material, reshaping to line and grade, and recompacting to specified density requirements. For cohesionless underlying courses containing sands or gravels, as defined in ASTM D 2487, the surface shall be stabilized prior to placement of the GCA. Stabilization shall be accomplished by mixing GCA into the underlying course and compacting by approved methods. The stabilized material shall be considered as part of the underlying course and shall meet all requirements of the underlying course. The finished underlying course shall not be disturbed by traffic or other operations and shall be maintained by the Contractor in a satisfactory condition until the GCA is placed.

3.4 INSTALLATION

3.4.1 Mixing the Materials

The coarse and fine aggregates shall be mixed in a stationary plant, or in a traveling plant or bucket loader on an approved paved working area. The Contractor shall make adjustments in mixing procedures or in equipment as directed to obtain true grades, to minimize segregation or degradation, to obtain the required water content, and to insure a satisfactory GCA meeting all requirements of this specification.

3.4.2 Placing

The mixed material shall be placed on the prepared subgrade or subbase in layers of uniform thickness with an approved spreader. When a compacted layer 6 inches or less in thickness is required, the material shall be placed in a single layer. When a compacted layer in excess of 6 inches is required, the material shall be placed in layers of equal thickness. No layer shall exceed 6 inches or less than 3 inches when compacted. The layers shall be so placed that when compacted they will be true to the grades or levels required with the least possible surface disturbance. Where the GCA is placed in more than one layer, the previously constructed layers shall be cleaned of loose and foreign matter by sweeping with power sweepers, power brooms, or hand brooms, as directed. Such adjustments in placing procedures or equipment shall be made as may be directed to obtain true grades, to minimize segregation and degradation, to adjust the water content, and to insure an acceptable GCA.

3.4.3 Grade Control

The finished and completed GCA shall conform to the lines, grades, and cross sections shown. Underlying material(s) shall be excavated and prepared at sufficient depth for the required GCA thickness so that the finished GCA with the subsequent surface course will meet the designated grades.

3.4.4 Edges of Base Course

The GCA shall be placed so that the completed section will be a minimum of 1 feet wider, on all sides, than the next layer that will be placed above it. Additionally, approved fill material shall be placed along the outer edges of GCA in sufficient quantities to compact to the thickness of the course being constructed, or to the thickness of each layer in a multiple layer course, allowing in each operation at least a 2 foot width of this material to be rolled and compacted simultaneously with rolling and compacting of each layer of GCA. If this base course material is to be placed adjacent to another pavement section, then the layers for both of these sections shall be placed and compacted along this edge at the same time.

3.4.5 Compaction

Each layer of the GCA shall be compacted as specified with approved compaction equipment. Water content shall be maintained during the compaction procedure to within plus or minus 1-1/2 percent of the optimum water content determined from laboratory tests as specified in paragraph SAMPLING AND TESTING. Rolling shall begin at the outside edge of the surface and proceed to the center, overlapping on successive trips at least one-half the width of the roller. Alternate trips of the roller shall be slightly different lengths. Speed of the roller shall be such that displacement of the aggregate does not occur. In all places not accessible to the rollers, the mixture shall be compacted with hand-operated power tampers. Compaction shall continue until each layer has a degree of compaction that is at least 100 percent of laboratory maximum density through the full depth of the layer. The Contractor shall make such adjustments in compacting or finishing procedures as may be directed to obtain true grades, to minimize segregation and degradation, to reduce or increase water content, and to ensure a satisfactory GCA. Any materials that are found to be unsatisfactory shall be removed and replaced with satisfactory material or reworked, as directed, to meet the requirements of this specification.

3.4.6 Thickness

Compacted thickness of the aggregate course shall be as indicated. No individual layer shall exceed 6 inches nor be less than3 inches in compacted thickness. The total compacted thickness of the GCA course shall be within 1/2 inch of the thickness indicated. Where the measured thickness is more than 1/2 inch deficient, such areas shall be corrected by scarifying, adding new material of proper gradation, reblading, and recompacting as directed. Where the measured thickness is more than 1/2 inch thicker than indicated, the course shall be considered as conforming to the specified thickness requirements. Average job thickness shall be the average of all thickness measurements taken for the job, but shall be within 1/4 inch of the thickness indicated. The total thickness of the GCA course shall be measured at intervals in such a manner as to ensure one measurement for each 500 square yards of base course. Measurements shall be made in 3 inch diameter test holes penetrating the base course or by survey before and after placement.

3.4.7 Finishing

The surface of the top layer of GCA shall be finished after final compaction by cutting any overbuild to grade and rolling with a steel-wheeled roller. Thin layers of material shall not be added to the top layer of base course to meet grade. If the elevation of the top layer of GCA is1/2 inch or more below grade, then the top layer should be scarified to a depth of at least3 inches and new material shall be blended in and compacted to bring to grade. Adjustments to rolling and finishing procedures shall be made as directed to minimize segregation and degradation, obtain grades, maintain moisture content, and insure an acceptable base course. Should the surface become rough, corrugated, uneven in texture, or traffic marked prior to completion, the unsatisfactory portion shall be scarified, reworked and recompacted or it shall be replaced as directed.

3.4.8 Smoothness

The surface of the top layer shall show no deviations in excess of 3/8 inch when tested with a 12-foot straightedge. Measurements shall be taken in successive positions parallel to the centerline of the area to be paved. Measurements shall also be taken perpendicular to the centerline at 50 foot intervals. Deviations exceeding this amount shall be corrected by removing material and replacing with new material, or by reworking existing material and compacting it to meet these specifications.

3.5 TRAFFIC

Traffic shall not be allowed on the completed GCA course. . Heavy equipment shall not be permitted except when necessary to construction, and then the area shall be protected against marring or damage to the completed work.

3.6 MAINTENANCE

The GCA shall be maintained in a satisfactory condition until the full pavement section is completed and accepted. Maintenance shall include immediate repairs to any defects and shall be repeated as often as necessary to keep the area intact. Any GCA that is not paved over prior to the onset of winter, shall be retested to verify that it still complies with the requirements of this specification. Any area of GCA that is damaged shall be reworked or replaced as necessary to comply with this specification.

3.7 DISPOSAL OF UNSATISFACTORY MATERIALS

Any unsuitable materials that must be removed shall be disposed of in waste disposal areas indicated. No additional payments will be made for materials that must be replaced.

END OF SECTION

SECTION 02748 (R)

BITUMINOUS TACK AND PRIME COATS

1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO M 20	(1970; R 1996) Penetration Graded Asphalt Cement
AASHTO M 81	(1992; R 1996) Cut-Back Asphalt (Rapid-Curing Type)
AASHTO M 82	(1975; R 1996) Cut-Back Asphalt (Medium-Curing Type)
AASHTO M 226	(1980; R 1996) Viscosity Graded Asphalt Cement
AASHTO T 40	(1978; R 1996) Sampling Bituminous Materials

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 140	(200) Sampling Bituminous Materials
ASTM D 946	(1982; R 1999) Penetration-Graded Asphalt Cement for Use in Pavement Construction
ASTM D 977	(1998) Emulsified Asphalt
ASTM D 1250	(1980; R 1997el) Petroleum Measurement Tables
ASTM D 2026	(1972; R 1997) Cutback Asphalt (Slow-Curing Type)
ASTM D 2027	(1976; R 1997) Cutback Asphalt (Medium-Curing Type)
ASTM D 2028	(1976; R 1997) Cutback Asphalt (Rapid-Curing Type)
ASTM D 2397	(1998) Cationic Emulsified Asphalt
ASTM D 2995	(1999) Determining Application Rate of Bituminous Distributors
ASTM D 3381	(1992; R 1999) Viscosity-Graded Asphalt Cement for Use in Pavement Construction

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Product Data

Waybills and Delivery Tickets

Waybills and delivery tickets, during progress of the work.

Test Reports

Sampling and Testing

Copies of all test results for bituminous materials, within 24 hours of completion of tests. Certified copies of the manufacturer's test reports indicating compliance with applicable specified requirements, not less than 14 days before the material is required in the work.

1.3 PLANT, EQUIPMENT, MACHINES AND TOOLS

1.3.1 General Requirements

Plant, equipment, machines and tools used in the work shall be subject to approval and shall be maintained in a satisfactory working condition at all times.

1.3.2 Bituminous Distributor

The distributor shall have pneumatic tires of such size and number to prevent rutting, shoving or otherwise damaging the base surface or other layers in the pavement structure. The distributor shall be designed and equipped to spray the bituminous material in a uniform coverage at the specified temperature, at readily determined and controlled rates with an allowable variation from the specified rate of not more than plus or minus 5 percent, and at variable widths. Distributor equipment shall include a separate power unit for the bitumen pump, full-circulation spray bars, tachometer, pressure gauges, volume-measuring devices, adequate heaters for heating of materials to the proper application temperature, a thermometer for reading the temperature of tank contents, and a hand hose attachment suitable for applying bituminous material manually to areas inaccessible to the distributor. The distributor shall be equipped to circulate and agitate the bituminous material during the heating process.

1.3.3 Power Brooms and Power Blowers

Power brooms and power blowers shall be suitable for cleaning the surfaces to which the bituminous coat is to be applied.

1.4 WEATHER LIMITATIONS

Bituminous coat shall be applied only when the surface to receive the bituminous coat is dry. Bituminous coat shall be applied only when the atmospheric temperature in the shade is 50 degrees F or above and when the temperature has not been below 35 degrees F for the 12 hours prior to application.

2 PRODUCTS

2.1 TACK COAT

The bituminous material used for tack coat shall be emulsified asphalt, Grade SS-1h or CSS-1h. Emulsified asphalt shall conform to ASTM D 977 or ASTM D 2397.

2.2 PRIME COAT

Prime coat not required for this project.

3. PART 3 EXECUTION

2.3 PREPARATION OF SURFACE

Immediately before applying the bituminous coat, all loose material, dirt, clay, or other objectionable material shall be removed from the surface to be treated. The surface shall be dry and clean at the time of treatment.

2.4 APPLICATION RATE

The exact quantities within the range specified, which may be varied to suit field conditions, will be determined by the Contracting Officer.

2.4.1 Tack Coat For New Pavement On Milled Surface Or Other Existing Pavement Or Structures

Bituminous material for the tack coat shall be applied in quantities of not less than 0.10 gallon nor more than 0.30 gallon per square yard of pavement surface.

2.4.2 Tack Coat For Second Lift Pavement Constructed on New Pavement

Bituminous material for the tack coat shall be applied in quantities of not less than 0.05 gallon nor more than 0.15 gallon per square yard of pavement surface.

2.5 APPLICATION TEMPERATURE

2.5.1 Viscosity Relationship

Asphalt application temperature shall provide an application viscosity between 10 and 60 seconds, Saybolt Furol, or between 20 and 120 centistokes kinematic. The temperature viscosity relation shall be furnished to the Contracting Officer.

2.5.2 Temperature Ranges

The viscosity requirements shall determine the application temperature to be used. The following is a normal range of application temperatures:

Emulsions	Temperature Range
SS-1h	70-160 degrees F
CSS-1h	70-160 degrees F

2.6 APPLICATION

2.6.1 General

Following preparation and subsequent inspection of the surface, the bituminous coat shall be applied at the specified rate with uniform distribution over the surface to be treated. All areas and spots missed by the distributor shall be properly treated with the hand spray. Until the succeeding layer of pavement is placed, the surface shall be maintained by protecting the surface against damage and by repairing deficient areas at no additional cost to the Government. If required, clean dry sand shall be spread to effectively blot up any excess bituminous material. No smoking, fires, or flames other than those from the heaters that are a part of the equipment shall be permitted within 25 feet of heating, distributing, and transferring operations of bituminous material other than bituminous emulsions. All traffic, except for paving equipment used in constructing the surfacing, shall be prevented from using the underlying material, whether primed or not, until the surfacing is completed. The bituminous coat shall conform to all requirements as described herein.

2.6.2 Tack Coat

Tack coat shall be applied at the locations shown on the drawings, and at all interfaces between new and existing asphalt pavement, including but not limited to milled asphalt pavement surfaces, new or existing concrete pavement or structures, and all saw cut edges, including pavement patches.

2.7 CURING PERIOD

Following application of the bituminous material and prior to application of the succeeding layer of pavement, the bituminous coat shall be allowed to cure and to obtain evaporation of any volatiles or moisture.

2.8 FIELD QUALITY CONTROL

Samples of the bituminous material used shall be obtained by the Contractor as directed, under the supervision of the Contracting Officer. The sample may be retained and tested by the Government at no cost to the Contractor.

2.9 SAMPLING AND TESTING

Sampling and testing shall be performed by an approved commercial testing laboratory or by facilities furnished by the Contractor. No work requiring testing will be permitted until the facilities have been inspected and approved.

2.9.1 Sampling

The samples of bituminous material, unless otherwise specified, shall be in accordance with ASTM D 140 or AASHTO T 40. Sources from which bituminous materials are to be obtained shall be selected and notification furnished the Contracting Officer within 15 days after the award of the contract.

2.9.2 Calibration Test

The Contractor shall furnish all equipment, materials, and labor necessary to calibrate the bituminous distributor. Calibration shall be made with the approved job material and prior to applying the bituminous coat material to the prepared surface. Calibration of the bituminous distributor shall be in accordance with ASTM D 2995.

2.9.3 Trial Applications

Before providing the complete bituminous coat, three lengths of at least 100 feet for the full width of the distributor bar shall be applied to evaluate the amount of bituminous material that can be satisfactorily applied.

2.9.3.1 Tack Coat Trial Application Rate

Unless otherwise authorized, the trial application rate of bituminous tack coat materials shall be applied in the amount of 0.05 gallons per square yard. Other trial applications shall be made using various amounts of material as may be deemed necessary.

2.9.4 Sampling and Testing During Construction

Quality control sampling and testing shall be performed as required in paragraph FIELD QUALITY CONTROL.

END OF SECTION

This page intentionally blank

SECTION 02749 (R)

HOT-MIX ASPHALT (HMA) FOR AIRFIELDS

1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO MP	(1997)Performance Graded Asphalt Binder
AASHTO TP53	(1995) Determining Asphalt Content of Hot Mix Asphalt by the Ignition Method

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 29/C 29M	(1997) Bulk Density (Unit Weight) and Voids in Aggregates
ASTM C 88	(1998) Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate
ASTM C 117	(1995) Materials Finer than 75 micrometer (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C 127	(2001) Specific Gravity and Absorbtion of Fine Aggregate
ASTM C 128	(1997) Specific Gravity and Absorbtion of Course Aggregate
ASTM C 131	(1996) Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine
ASTM C 136	(1996a) Sieve Analysis of Fine and Coarse Aggregates
ASTM C 183	(1997) Sampling Hydraulic Cement
ASTM C 566	(1997) Total Evaporable Moisture Content of Aggregate by Drying
ASTM C 1252	(1998) Uncompacted Void Content of Fine Aggregate (as Influenced by Particle Shape, Surface Texture, and Grading)

ASTM D 75	(1997) Sampling Aggregates
ASTM D 140	(1993) Sampling Bituminous Materials
ASTM D 242	(1995) Mineral Filler for Bituminous Paving Mixtures
ASTM D 946	(1982; R 1993) Penetration-Graded Asphalt Cement for Use in Pavement Construction
ASTM D 995	(1995b) Mixing Plants for Hot-Mixed, Hot-Laid Bituminous Paving Mixtures
ASTM D 1461	(1985) Moisture or Volatile Distillates in Bituminous Paving Mixtures
ASTM D 1559	(1989) Resistance to Plastic Flow of Bituminous Mixtures Using Marshall Apparatus
ASTM D 2041	(1995) Theoretical Maximum Specific Gravity and Density of Bituminous Paving Mixtures
ASTM D 2172	(1995) Quantitative Extraction of Bitumen from Bituminous Paving Mixtures
ASTM D 2419	(1995) Sand Equivalent Value of Soils and Fine Aggregate
ASTM D 2489	(1984; R 1994) Degree of Particle Coating of Bituminous-Aggregate Mixtures
ASTM D 2726	(1996a) Bulk Specific Gravity and Density of Non-Absorptive Compacted Bituminous Mixture
ASTM D 2950	(1997) Density of Bituminous Concrete in Place by Nuclear Method
ASTM D 3203	(1994) Percent Air Voids in Compacted Dense and Open Bituminous Paving Mixtures
ASTM D 3381	(1992) Viscosity-Graded Asphalt Cement for Use in Pavement Construction
ASTM D 3665	(1994) Random Sampling of Construction Materials
ASTM D 3666	(1996a) Minimum Requirements for Agencies Testing and Inspecting Bituminous Paving Materials
ASTM D 4125	(1994) Asphalt Content of Bituminous Mixtures by the Nuclear Method

ASTM D 4318	(2000) Liquid Limit, Plastic Limit and Plasticity Index of Soils
ASTM D 4791	(1995) Flat Particles, Elongated Particles, or Flat and Elongated Particles in Coarse Aggregate
ASTM D 4867/D 4867M	(1996) Effect of Moisture on Asphalt Concrete Paving Mixtures
ASTM D 5444	(1994) Mechanical Size Analysis of Extracted Aggregate
ASTM D 6307	(1999) Asphalt Content of Hot Mix Asphalt by Ignition Method

ASPHALT INSTITUTE (AI)

AI MS-2	(1994) Mix Design Methods for Asphalt Concrete and Other Hot-Mix Types

AMERICAN ASSOCIATION OF STATE HIGHWAY TRANSPORTATION OFFICIALS

AASHTO MP-1	Performance Graded Asphalt Binder

STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION (CDT)

CDT Test 526	(1978) Operation of California Profilograph and Evaluation of Profiles

U.S. ARMY CORPS OF ENGINEERS (USACE)

COE CRD-C 171	(1995) Test Method for Determining Percentage of Crushed Particles in Aggregate

1.2 DESCRIPTION OF WORK

The work shall consist of pavement courses composed of mineral aggregate and asphalt material heated and mixed in a central mixing plant and placed on a prepared course. HMA designed and constructed in accordance with this section shall conform to the lines, grades, thicknesses, and typical cross sections shown on the drawings. Each course shall be constructed to the depth, section, or elevation required by the drawings and shall be rolled, finished, and approved before the placement of the next course.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 (AR) SUBMITTAL PROCEDURES:

Product Data

Mix Design; G

Proposed JMF.

Contractor Quality Control; G

Quality control plan.

Samples

Asphalt Cement Binder; G

5 gallon sample for mix design verification.

Aggregates; G

Sufficient materials to produce 200 lb of blended mixture for mix design verification.

Test Reports

Aggregates; G
QC Monitoring; G

Aggregate and QC test results.

Certificates

Asphalt Cement Binder; G

Copies of certified test data.

Testing Laboratory; G

Certification of compliance.

1.4 METHOD OF MEASUREMENT

The amount paid for will be the number of ~~2,000 pound~~ tons of hot-mix asphalt mixture used in the accepted work. Hot-mix asphalt mixture shall be weighed after mixing, and no separate payment will be made for weight of asphalt cement material incorporated herein.

1.5 BASIS OF PAYMENT

Quantities of overlays, runway centerline repair and bituminous pavement patching, except for crack repair, determined as specified above, will be paid for at respective contract unit prices or at reduced prices adjusted in accordance with paragraph MATERIAL ACCEPTANCE AND PERCENT PAYMENT. Payment shall constitute full compensation for furnishing all materials, equipment, plant, and tools; and for all labor and other incidentals necessary to complete work required by this section of the specification.

1.6 ASPHALT MIXING PLANT

The asphalt mixing plant shall be located on the project site as indicated on the drawings. There shall be operable telephone or radio communication between the plant and the placing site at all times paving is taking place.

Plants used for the preparation of hot-mix asphalt shall conform to the requirements of ASTM D 995 with the following changes:

a. Truck Scales. The asphalt mixture shall be weighed on approved scales furnished by the Contractor, or on certified public scales at the Contractor's expense. Scales shall be inspected and sealed at least annually by an approved calibration laboratory.

b. Testing Facilities. The Contractor shall provide laboratory facilities at the plant for the use in the Contractor's quality control testing.

c. Inspection of Plant. The Contracting Officer shall have access at all times, to all areas of the plant for checking adequacy of equipment; inspecting operation of the plant; verifying weights, proportions, and material properties; checking the temperatures maintained in the preparation of the mixtures and for taking samples. The Contractor shall provide assistance to the Contracting Officer as requested to procure any desired samples.

d. Storage Bins. The asphalt mixture may be stored in non-insulated storage bins for a period of time not exceeding 3 hours. The asphalt mixture may be stored in insulated storage bins for a period of time not exceeding 8 hours. The mix drawn from bins shall meet the same requirements as mix loaded directly into trucks.

1.7 HAULING EQUIPMENT

Trucks used for hauling hot-mix asphalt shall have tight, clean, and smooth metal beds. To prevent the mixture from adhering to them, the truck beds shall be lightly coated with a minimum amount of paraffin oil, lime solution, or other approved material. Petroleum based products shall not be used as a release agent. Each truck shall have a suitable cover to protect the mixture from adverse weather. When necessary to ensure that the mixture will be delivered to the site at the specified temperature, truck beds shall be insulated or heated and covers (tarps) shall be securely fastened.

1.8 ASPHALT PAVERS

Asphalt pavers shall be self-propelled, with an activated screed, heated as necessary, and shall be capable of spreading and finishing courses of hot-mix asphalt which will meet the specified thickness, smoothness, and grade. The paver shall have sufficient power to propel itself and the hauling equipment without adversely affecting the finished surface.

1.8.1 Receiving Hopper

The paver shall have a receiving hopper of sufficient capacity to permit a uniform spreading operation. The hopper shall be equipped with a distribution system to place the mixture uniformly in front of the screed without segregation. The screed shall effectively produce a

finished surface of the required evenness and texture without tearing, shoving, or gouging the mixture.

1.8.2 Automatic Grade Controls

The paver shall be equipped with a control system capable of automatically maintaining the specified screed elevation. The control system shall be automatically actuated through a system of mechanical sensors or sensor-directed mechanisms or devices that will maintain the paver screed at a predetermined transverse slope and at the proper elevation to obtain the required surface. The transverse slope controller shall be capable of maintaining the screed at the desired slope within plus or minus 0.1 percent. A transverse slope controller shall not be used to control grade. The controls shall be capable of working in conjunction with any of the following attachments:

a. Ski-type device of not less than 30 feet in length.

b. Taut stringline set to grade.

c. Short ski or shoe for joint matching.

d. Laser control.

1.9 ROLLERS

Rollers shall be in good condition and shall be operated at slow speeds to avoid displacement of the asphalt mixture. The number, type, and weight of rollers shall be sufficient to compact the mixture to the required density while it is still in a workable condition. Equipment which causes excessive crushing of the aggregate shall not be used.

1.10 WEATHER LIMITATIONS

The hot-mix asphalt shall not be placed upon a wet surface or when the surface temperature of the underlying course is less than specified in Table 1. The temperature requirements may be waived by the Contracting Officer, if requested; however, all other requirements, including compaction, shall be met.

Table 1. Surface Temperature Limitations of Underlying Course

Mat Thickness, inches	Degrees F
3 or greater	40
Less than 3	45

2 PRODUCTS

2.1 AGGREGATES

Aggregates shall consist of crushed stone, crushed gravel, crushed slag, screenings, natural sand and mineral filler, as required. The portion of material retained on the No. 4 sieve is coarse aggregate. The portion of material passing the No. 4 sieve and retained on the No. 200 sieve is fine aggregate. The portion passing the No. 200 sieve is defined as mineral filler.

All aggregate test results and samples shall be submitted to the Contracting Officer at least 14 days prior to start of construction.

2.1.1 Coarse Aggregate

Coarse aggregate shall consist of sound, tough, durable particles, free from films of material that would prevent thorough coating and bonding with the asphalt material and free from organic matter and other deleterious substances. The coarse aggregate particles shall meet the following requirements:

a. The percentage of loss shall not be greater than 40 percent after 500 revolutions when tested in accordance with ASTM C 131.

b. The percentage of loss shall not be greater than 12 percent after five cycles when tested in accordance with ASTM C 88 using magnesium sulfate.

c. At least 75 percent by weight of coarse aggregate shall have at least two or more fractured faces when tested in accordance with COE CRD-C 171. Fractured faces shall be produced by crushing.

d. The particle shape shall be essentially cubical and the aggregate shall not contain more than 20 percent, by weight, of flat and elongated particles (3:1 ratio of maximum to minimum) when tested in accordance with ASTM D 4791.

e. Slag shall be air-cooled, blast furnace slag, and shall have a compacted weight of not less than 75 lb/cu ft when tested in accordance with ASTM C 29/C 29M.

2.1.2 Fine Aggregate

Fine aggregate shall consist of clean, sound, tough, durable particles. The aggregate particles shall be free from coatings of clay, silt, or any objectionable material and shall contain no clay balls. The fine aggregate particles shall meet the following requirements:

a. The quantity of natural sand (noncrushed material) added to the aggregate blend shall not exceed 15 percent by weight of total aggregate.

b. The individual fine aggregate sources shall have a sand equivalent value greater than 45 when tested in accordance with ASTM D 2419.

c. The fine aggregate portion of the blended aggregate shall have an uncompacted void content greater than 45.0 percent when tested in accordance with ASTM C 1252 Method A.

2.1.3 Mineral Filler

Mineral filler shall be nonplastic material meeting the requirements of ASTM D 242.

2.1.4 Aggregate Gradation

The combined aggregate gradation shall conform to gradations specified in Table 2, when tested in accordance with ASTM C 136 and ASTM C 117, and shall not vary from the low limit

on one sieve to the high limit on the adjacent sieve or vice versa, but grade uniformly from coarse to fine.

Table 2
Aggregate Gradation

Sieve Size, inch	Percent Passing by Mass
1	---
3/4	100
1/2	76-98
3/8	69-89
No. 4	53-73
No. 8	38-60
No. 16	26-48
No. 30	18-38
No. 50	11-27
No. 100	6-18
No. 200	3-6

2.2 ASPHALT CEMENT BINDER

Asphalt cement binder shall conform to AASHTO MP1 Performance Grade (PG) 70-28 and shall be polymer modified. Test data indicating grade certification shall be provided by the supplier at the time of delivery of each load to the mix plant. Copies of these certifications shall be submitted to the Contracting Officer. The supplier is defined as the last source of any modification to the binder. The Contracting Officer may sample and test the binder at the mix plant at any time before or during mix production. Samples for this verification testing shall be obtained by the Contractor in accordance with ASTM D 140 and in the presence of the Contracting Officer. These samples shall be furnished to the Contracting Officer for the verification testing, which shall be at no cost to the Contractor. Samples of the asphalt cement specified shall be submitted for approval not less than 14 days before start of the test section.

2.3 MIX DESIGN

The Contractor shall develop the mix design. The asphalt mix shall be composed of a mixture of well-graded aggregate, mineral filler if required, and asphalt material. The aggregate fractions shall be sized, handled in separate size groups, and combined in such proportions that the resulting mixture meets the grading requirements of the job mix formula (JMF). No hot-mix asphalt for payment shall be produced until a JMF has been approved. The hot-mix asphalt shall be designed using procedures contained in AI MS-2 and the criteria shown in Table 3. If the Tensile Strength Ratio (TSR) of the composite mixture, as determined by ASTM D 4867/D 4867M is less than 75, the aggregates shall be rejected or the asphalt mixture treated with an approved anti-stripping agent. The amount of anti-stripping agent added shall be sufficient to produce a TSR of not less than 75. If an antistrip agent is required, it shall be provided by the Contractor at no additional cost. Sufficient materials to produce 200 pounds of blended mixture shall be provided to the Contracting Officer for verification of mix design at least 14 days prior to construction of test section.

2.3.1 JMF Requirements

The job mix formula shall be submitted in writing by the Contractor for approval at least 14 days prior to the start of the test section and shall include as a minimum:

a. Percent passing each sieve size.

b. Percent of asphalt cement.

c. Percent of each aggregate and mineral filler to be used.

d. Asphalt viscosity grade, penetration grade, or performance grade.

e. Number of blows of hammer per side of molded specimen.

f. Laboratory mixing temperature.

g. Lab compaction temperature.

h. Temperature-viscosity relationship of the asphalt cement.

i. Plot of the combined gradation on the 0.45 power gradation chart, stating the nominal maximum size.

j. Graphical plots of stability, flow, air voids, voids in the mineral aggregate, and unit weight versus asphalt content as shown in AI MS-2.

k. Specific gravity and absorption of each aggregate.

l. Percent natural sand.

m. Percent particles with two or more fractured faces (in coarse aggregate).

n. Fine aggregate angularity.

o. Percent flat or elongated particles (in coarse aggregate).

p. Tensile Strength Ratio.

q. Antistrip agent (if required) and amount.

r. List of all modifiers and amount.

Table 3. Marshall Design Criteria

Test Property	75 Blow Mix
Stability, pounds minimum	*1800
Flow, 0.01 inch	8-16
Air voids, percent	3-5
Percent Voids in mineral aggregate (minimum)**	14.0
TSR, minimum percent	75

* This is a minimum requirement. The average during construction shall be significantly higher than this number to ensure compliance with the specifications.

** Calculate VMA in accordance with AI MS-2, based on ASTM D 2726 bulk specific gravity for the aggregate.

2.3.2 Adjustments to JMF

The JMF for each mixture shall be in effect until a new formula is approved in writing by the Contracting Officer. Should a change in sources of any materials be made, a new mix design shall be performed and a new JMF approved before the new material is used. The Contractor will be allowed to adjust the JMF within the limits specified below to optimize mix volumetric properties. Adjustments to the JMF shall be limited to plus or minus 3 percent on the 1/2 inch, No. 4, and No. 8 sieves; plus or minus 1.0 percent on the No. 200 sieve; and plus or minus 0.40 percent binder content. If adjustments are needed that exceed these limits, a new mix design shall be developed. Tolerances given above may permit the aggregate grading to be outside the limits shown in Table 2; this is acceptable.

3 EXECUTION

3.1 PREPARATION OF ASPHALT BINDER MATERIAL

The asphalt cement material shall be heated avoiding local overheating and providing a continuous supply of the asphalt material to the mixer at a uniform temperature. The temperature of unmodified asphalts shall be no more than 325 degrees F when added to the aggregates. Modified asphalts shall be no more than 350 degrees F when added to the aggregates.

3.2 PREPARATION OF MINERAL AGGREGATE

The aggregate for the mixture shall be heated and dried prior to mixing. No damage shall occur to the aggregates due to the maximum temperature and rate of heating used. The temperature of the aggregate and mineral filler shall not exceed 350 degrees F when the asphalt cement is added. The temperature shall not be lower than is required to obtain complete coating and uniform distribution on the aggregate particles and to provide a mixture of satisfactory workability.

3.3 PREPARATION OF HOT-MIX ASPHALT MIXTURE

The aggregates and the asphalt cement shall be weighed or metered and introduced into the mixer in the amount specified by the JMF. The combined materials shall be mixed until the aggregate obtains a uniform coating of asphalt binder and is thoroughly distributed throughout the mixture. Wet mixing time shall be the shortest time that will produce a satisfactory mixture, but no less than 25 seconds for batch plants. The wet mixing time for all plants shall be established by the Contractor, based on the procedure for determining the percentage of coated particles described in ASTM D 2489, for each individual plant and for each type of aggregate used. The wet mixing time will be set to at least achieve 95 percent of coated particles. The moisture content of all hot-mix asphalt upon discharge from the plant shall not exceed 0.5 percent by total weight of mixture as measured by ASTM D 1461.

3.4 PREPARATION OF THE UNDERLYING SURFACE

Immediately before placing the hot mix asphalt, the underlying course shall be cleaned of dust and debris. A tack coat shall be applied in accordance with the contract specifications.

3.5 TEST SECTION

Prior to full production, the Contractor shall place a test section for each JMF used. The contractor shall construct a test section 250-500 feet long and two paver passes wide placed in two lanes, with a longitudinal cold joint. The test section shall be of the same depth as the course which it represents. The underlying grade or pavement structure upon which the test section is to be constructed shall be the same as the remainder of the course represented by the test section. The equipment used in construction of the test section shall be the same equipment to be used on the remainder of the course represented by the test section. The test section shall be placed as part of the project pavement as approved by the Contracting Officer.

3.5.1 Sampling and Testing for Test Section

One random sample shall be taken at the plant, triplicate specimens compacted, and tested for stability, flow, and laboratory air voids. A portion of the same sample shall be tested for aggregate gradation and asphalt content. Four randomly selected cores shall be taken from the finished pavement mat, and four from the longitudinal joint, and tested for density. Random sampling shall be in accordance with procedures contained in ASTM D 3665. The test results shall be within the tolerances shown in Table 4 for work to continue. If all test results meet the specified requirements, the test section shall remain as part of the project pavement. If test results exceed the tolerances shown, the test section shall be removed and replaced at no cost to the Government and another test section shall be constructed.

Table 4. Test Section Requirements for Material and Mixture Properties

Property	Specification Limit
Aggregate Gradation-Percent Passing (Individual Test Result)	
No. 4 and larger	JMF plus or minus 8
No. 8, No. 16, No. 30, and No. 50	JMF plus or minus 6
No. 100 and No. 200	JMF plus or minus 2.0
Asphalt Content, Percent (Individual Test Result)	JMF plus or minus 0.5
Laboratory Air Voids, Percent (Average of 3 specimens)	JMF plus or minus 1.0
VMA, Percent (Average of 3 specimens)	14 minimum
Stability, pounds (Average of 3 specimens)	1800 minimum
Flow, 0.01 inches (Average of 3 specimens)	8 - 16
Mat Density, Percent of Marshall (Average of 4 Random Cores)	97.0 - 100.5
Joint Density, Percent of Marshall (Average of 4 Random Cores)	95.5 - 100.5

3.5.2 Additional Test Sections

If the initial test section should prove to be unacceptable, the necessary adjustments to the JMF, plant operation, placing procedures, and/or rolling procedures shall be made. A second test section shall then be placed. Additional test sections, as required, shall be constructed and evaluated for conformance to the specifications. Full production shall not begin until an acceptable section has been constructed and accepted.

3.6 TESTING LABORATORY

The laboratory used to develop the JMF and for Contractor quality control testing shall meet the requirements of ASTM D 3666. A certification signed by the manager of the laboratory stating that it meets these requirements or clearly listing all deficiencies shall be submitted to the Contracting Officer prior to the start of construction. The certification shall contain as a minimum:

a. Qualifications of personnel; laboratory manager, supervising technician, and testing technicians.

b. A listing of equipment to be used in developing the job mix.

c. A copy of the laboratory's quality control system.

d. Evidence of participation in the AASHTO Materials Reference Laboratory (AMRL) program.

3.7 TRANSPORTING AND PLACING

3.7.1 Transporting

The hot-mix asphalt shall be transported from the mixing plant to the site in clean, tight vehicles. Deliveries shall be scheduled so that placing and compacting of mixture is uniform with minimum stopping and starting of the paver. Adequate artificial lighting shall be provided for night placements. Hauling over freshly placed material will not be permitted until the material has been compacted as specified, and allowed to cool to 140 degrees F. To deliver mix to the paver, the Contractor shall use a material transfer vehicle which shall be operated to produce continuous forward motion of the paver.

3.7.2 Placing

The mix shall be placed and compacted at a temperature suitable for obtaining density, surface smoothness, and other specified requirements. Upon arrival, the mixture shall be placed to the full width by an asphalt paver; it shall be struck off in a uniform layer of such depth that, when the work is completed, it shall have the required thickness and conform to the grade and contour indicated. The speed of the paver shall be regulated to eliminate pulling and tearing of the asphalt mat. Unless otherwise permitted, placement of the mixture shall begin along the centerline of a crowned section or on the high side of areas with a one-way slope. The mixture shall be placed in consecutive adjacent strips having a minimum width of 10 feet. The longitudinal joint in one course shall offset the longitudinal joint in the course immediately below by at least 1 foot however, the joint in the surface course shall be at the centerline of the pavement. Transverse joints in one course shall be offset by at least 10 feet from transverse joints in the previous course. Transverse joints in adjacent lanes shall be offset a minimum of 10 feet. On isolated areas where irregularities or unavoidable obstacles make the use of mechanical spreading and finishing equipment impractical, the mixture may be spread and luted by hand tools.

3.8 COMPACTION OF MIXTURE

After placing, the mixture shall be thoroughly and uniformly compacted by rolling. The surface shall be compacted as soon as possible without causing displacement, cracking or shoving. The sequence of rolling operations and the type of rollers used shall be at the discretion of the Contractor, with the exception that the Contractor shall not apply more than three passes with a vibratory roller in the vibrating mode. The speed of the roller shall, at all times, be sufficiently slow to avoid displacement of the hot mixture and be effective in compaction. Any displacement occurring as a result of reversing the direction of the roller, or from any other cause, shall be corrected at once. Sufficient rollers shall be furnished to handle the output of the plant. Rolling shall continue until the surface is of uniform texture, true to grade and cross section, and the required field density is obtained. To prevent adhesion of the mixture to the roller, the wheels shall be kept properly moistened but excessive water will not be permitted. In areas not accessible to the roller, the mixture shall be thoroughly compacted with hand tampers. Any mixture that becomes loose and broken, mixed with dirt, contains check-cracking, or is in any way defective shall be removed full depth, replaced with fresh hot mixture and immediately compacted to conform to the

surrounding area. This work shall be done at the Contractor's expense. Skin patching will not be allowed.

3.9 JOINTS

The formation of joints shall be made ensuring a continuous bond between the courses and to obtain the required density. All joints shall have the same texture as other sections of the course and meet the requirements for smoothness and grade.

3.9.1 Transverse Joints

The roller shall not pass over the unprotected end of the freshly laid mixture, except when necessary to form a transverse joint. When necessary to form a transverse joint, it shall be made by means of placing a bulkhead or by tapering the course. The tapered edge shall be cut back to its full depth and width on a straight line to expose a vertical face prior to placing the adjacent lane. The cutback material shall be removed from the project. In both methods, all contact surfaces shall be given a light tack coat of asphalt material before placing any fresh mixture against the joint.

3.9.2 Longitudinal Joints

Longitudinal joints which are irregular, damaged, uncompacted, cold (less than 175 degrees F at the time of placing the adjacent lane), or otherwise defective, shall be cut back a minimum of 2 inches from the edge with a cutting wheel to expose a clean, sound vertical surface for the full depth of the course. All cutback material shall be removed from the project. All contact surfaces shall be given a light tack coat of asphalt material prior to placing any fresh mixture against the joint. The Contractor will be allowed to use an alternate method if it can be demonstrated that density, smoothness, and texture can be met.

3.10 CONTRACTOR QUALITY CONTROL

3.10.1 General Quality Control Requirements

The Contractor shall develop an approved Quality Control Plan. Hot-mix asphalt for payment shall not be produced until the quality control plan has been approved. The plan shall address all elements that affect the quality of the pavement including, but not limited to:

a. Mix Design

b. Aggregate Grading

c. Quality of Materials

d. Stockpile Management

e. Proportioning

f. Mixing and Transportation

g. Mixture Volumetrics

h. Moisture Content of Mixtures

i. Placing and Finishing

j. Joints

k. Compaction

l. Surface Smoothness

3.10.2 Testing Laboratory

The Contractor shall provide a fully equipped asphalt laboratory located at the plant or job site. The effective working area of the laboratory shall be a minimum of 150 square feet with a ceiling height of not less than 7.5 feet. Lighting shall be adequate to illuminate all working areas. It shall be equipped with heating and air conditioning units to maintain a temperature of 75 degrees f plus or minus 5 degrees F. Laboratory facilities shall be kept clean and all equipment shall be maintained in proper working condition. The Contracting Officer shall be permitted unrestricted access to inspect the Contractor's laboratory facility, to witness quality control activities, and to perform any check testing desired. The Contracting Officer will advise the Contractor in writing of any noted deficiencies concerning the laboratory facility, equipment, supplies, or testing personnel and procedures. When the deficiencies are serious enough to adversely affect test results, the incorporation of the materials into the work shall be suspended immediately and will not be permitted to resume until the deficiencies are corrected.

3.10.3 Quality Control Testing

The Contractor shall perform all quality control tests applicable to these specifications and as set forth in the Quality Control Program. The testing program shall include, but shall not be limited to, tests for the control of asphalt content, aggregate gradation, temperatures, aggregate moisture, moisture in the asphalt mixture, laboratory air voids, stability, flow, in-place density, grade and smoothness. A Quality Control Testing Plan shall be developed as part of the Quality Control Program.

3.10.3.1 Asphalt Content

A minimum of two tests to determine asphalt content will be performed per lot (a lot is defined in paragraph MATERIAL ACCEPTANCE AND PERCENT PAYMENT) by one of the following methods: extraction method in accordance with ASTM D 2172, Method A or B, the ignition method in accordance with the AASHTO TP53, ASTM D 6307, or the nuclear method in accordance with ASTM D 4125, provided the nuclear gauge is calibrated for the specific mix being used. For the extraction method, the weight of ash, as described in ASTM D 2172, shall be determined as part of the first extraction test performed at the beginning of plant production; and as part of every tenth extraction test performed thereafter, for the duration of plant production. The last weight of ash value obtained shall be used in the calculation of the asphalt content for the mixture.

3.10.3.2 Gradation

Aggregate gradations shall be determined a minimum of twice per lot from mechanical analysis of recovered aggregate in accordance with ASTM D 5444. When asphalt content is determined by the nuclear method, aggregate gradation shall be determined from hot bin samples on batch plants, or from the cold feed on drum mix plants. For batch plants, aggregates shall be tested in accordance with ASTM C 136 using actual batch weights to determine the combined aggregate gradation of the mixture.

3.10.3.3 Temperatures

Temperatures shall be checked at least four times per lot, at necessary locations, to determine the temperature at the dryer, the asphalt cement in the storage tank, the asphalt mixture at the plant, and the asphalt mixture at the job site.

3.10.3.4 Aggregate Moisture

The moisture content of aggregate used for production shall be determined a minimum of once per lot in accordance with ASTM C 566.

3.10.3.5 Moisture Content of Mixture

The moisture content of the mixture shall be determined at least once per lot in accordance with ASTM D 1461 or an approved alternate procedure.

3.10.3.6 Laboratory Air Voids, Marshall Stability and Flow

Mixture samples shall be taken at least four times per lot and compacted into specimens, using 75 blows per side with the Marshall hammer as described in ASTM D 1559. After compaction, the laboratory air voids of each specimen shall be determined, as well as the Marshall stability and flow.

3.10.3.7 In-Place Density

The Contractor shall conduct any necessary testing to ensure the specified density is achieved. A nuclear gauge may be used to monitor pavement density in accordance with ASTM D 2950.

3.10.3.8 Grade and Smoothness

The Contractor shall conduct the necessary checks to ensure the grade and smoothness requirements are met in accordance with paragraph MATERIAL ACCEPTANCE AND PERCENT PAYMENT.

3.10.3.9 Additional Testing

Any additional testing, which the Contractor deems necessary to control the process, may be performed at the Contractor's option.

3.10.3.10 QC Monitoring

The Contractor shall submit all QC test results to the Contracting Officer on a daily basis as the tests are performed. The Contracting Officer reserves the right to monitor any of the Contractor's quality control testing and to perform duplicate testing as a check to the Contractor's quality control testing.

3.10.4 Sampling

When directed by the Contracting Officer, the Contractor shall sample and test any material that appears inconsistent with similar material being produced, unless such material is voluntarily removed and replaced or deficiencies corrected by the Contractor. All sampling shall be in accordance with standard procedures specified.

3.10.5 Control Charts

For process control, the Contractor shall establish and maintain linear control charts on both individual samples and the running average of the last four samples for the parameters listed in Table 5, as a minimum. These control charts shall be posted as directed by the Contracting Officer and shall be kept current at all times. The control charts shall identify the project number, the test parameter being plotted, the individual sample numbers, the Action and Suspension Limits listed in Table 5 applicable to the test parameter being plotted, and the Contractor's test results. Target values from the JMF shall also be shown on the control charts as indicators of central tendency for the cumulative percent passing, asphalt content, and laboratory air voids parameters. When the test results exceed either applicable Action Limit, the Contractor shall take immediate steps to bring the process back in control. When the test results exceed either applicable Suspension Limit, the Contractor shall halt production until the problem is solved. The Contractor shall use the control charts as part of the process control system for identifying trends so that potential problems can be corrected before they occur. Decisions concerning mix modifications shall be made based on analysis of the results provided in the control charts. The Quality Control Plan shall indicate the appropriate action which shall be taken to bring the process into control when certain parameters exceed their Action Limits.

Table 5. Action and Suspension Limits for the Parameters to be Plotted on Individual and Running Average Control Charts

	Individual Samples		Running Average of Last Four Samples	
Parameter to be Plotted	Action Limit	Suspension Limit	Action Limit	Suspension Limit
No. 4 sieve, Cumulative % Passing, deviation from JMF target; plus or minus values	6	8	4	5
No. 30 sieve, Cumulative % Passing, deviation from JMF target; plus or minus values	4	6	3	4
No. 200 sieve, Cumulative % Passing, deviation from JMF target; plus or minus values	1.4	2.0	1.1	1.5
Stability, pounds (minimum)	1800	1700	1900	1800
Flow, 0.01 inches	8 min. 16 max.	7 min. 17 max.	9 min. 15 max.	8 min. 16 max.
Asphalt content, % deviation from JMF target; plus or minus value	0.4	0.5	0.2	0.3
Laboratory Air Voids, % deviation from JMF target value	No specific action and suspension limits set since this parameter is used to determine percent payment			
In-place Mat Density, % of Marshall density	No specific action and suspension limits set since this parameter is used to determine percent payment			
In-place Joint Density, % of Marshall density	No specific action and suspension limits set since this parameter is used to determine percent payment			

3.11 MATERIAL ACCEPTANCE AND PERCENT PAYMENT

The Government's quality assurance (QA) program for this project, specified below, will be separate and distinct from the Contractor's quality control (QC) program specified above. Testing for acceptability of work will be performed by the Government or by an independent laboratory hired by the Government, except for smoothness testing which shall be performed by the Contractor. Acceptance of the plant produced mix and in-place requirements will be on a lot to lot basis. A standard lot for all requirements will be equal to 2000 ~~2000 pound~~ tons. Where appropriate, adjustment in payment for individual lots of hot-mix asphalt will be made based on in-place density, laboratory air voids, grade and smoothness in accordance with the following paragraphs. Grade and surface smoothness determinations will be made on the lot as a whole. Exceptions or adjustments to this will be made in situations where the mix within one lot is placed as part of both the intermediate and surface courses, thus grade

and smoothness measurements for the entire lot cannot be made. In order to evaluate laboratory air voids and in-place (field) density, each lot will be divided into four equal sublots.

3.11.1 Percent Payment

When a lot of material fails to meet the specification requirements for 100 percent pay as outlined in the following paragraphs, that lot shall be removed and replaced, or accepted at a reduced price which will be computed by multiplying the unit price by the lot's pay factor. The lot pay factor is determined by taking the lowest computed pay factor based on either laboratory air voids, in-place density, grade or smoothness (each discussed below). Pay factors based on different criteria (i.e., laboratory air voids and in-place density) of the same lot will not be multiplied together to get a lower lot pay factor. At the end of the project, an average of all lot pay factors will be calculated. If this average lot pay factor exceeds 95.0 percent, then the percent payment for the entire project will be 100 percent of the unit bid price. If the average lot pay factor is less than 95.0 percent, then each lot will be paid for at the unit price multiplied by the lot's pay factor. For any lots which are less than 2000 2000 pound tons, a weighted lot pay factor will be used to calculate the average lot pay factor.

3.11.2 Sublot Sampling

One random mixture sample for determining laboratory air voids, theoretical maximum density, and for any additional testing the Contracting Officer desires, will be taken from a loaded truck delivering mixture to each sublot, or other appropriate location for each sublot. All samples will be selected randomly, using commonly recognized methods of assuring randomness conforming to ASTM D 3665 and employing tables of random numbers or computer programs. Laboratory air voids will be determined from three laboratory compacted specimens of each sublot sample in accordance with ASTM D 1559. The specimens will be compacted within 2 hours of the time the mixture was loaded into trucks at the asphalt plant. Samples will not be reheated prior to compaction and insulated containers will be used as necessary to maintain the temperature.

3.11.3 Additional Sampling and Testing

The Contracting Officer reserves the right to direct additional samples and tests for any area which appears to deviate from the specification requirements. The cost of any additional testing will be paid for by the Government. Testing in these areas will be in addition to the lot testing, and the requirements for these areas will be the same as those for a lot.

3.11.4 Laboratory Air Voids

Laboratory air voids will be calculated in accordance with ASTM D 3203 by determining the Marshall density of each lab compacted specimen using ASTM D 2726 and determining the theoretical maximum density of every other sublot sample using ASTM D 2041. Laboratory air void calculations for each sublot will use the latest theoretical maximum density values obtained, either for that sublot or the previous sublot. The mean absolute deviation of the four laboratory air void contents (one from each sublot) from the JMF air void content will be evaluated and a pay factor determined from Table 6. All laboratory air void tests will be completed and reported within 24 hours after completion of construction of each lot.

Table 6. Pay Factor Based on Laboratory Air Voids

Mean Absolute Deviation of Lab Air Voids from JMF	Pay Factor, %
0.60 or less	100
0.61 - 0.80	98
0.81 - 1.00	95
1.01 - 1.20	90
Above 1.20	reject (0)

3.11.5 Mean Absolute Deviation

An example of the computation of mean absolute deviation for laboratory air voids is as follows: Assume that the laboratory air voids are determined from 4 random samples of a lot (where 3 specimens were compacted from each sample). The average laboratory air voids for each sublot sample are determined to be 3.5, 3.0, 4.0, and 3.7. Assume that the target air voids from the JMF is 4.0. The mean absolute deviation is then:

Mean Absolute Deviation = (|3.5 - 4.0| + |3.0 - 4.0| + |4.0 - 4.0| + |3.7 - 4.0|)/4

= (0.5 + 1.0 + 0.0 + 0.3)/4 = (1.8)/4 = 0.45

The mean absolute deviation for laboratory air voids is determined to be 0.45. It can be seen from Table 6 that the lot's pay factor based on laboratory air voids, is 100 percent.

3.11.6 In-place Density

3.11.6.1 General Density Requirements

For determining in-place density, one random core will be taken by the from the mat (interior of the lane) of each sublot, and one random core will be taken from the joint (immediately over joint) of each sublot. Each random core will be full thickness of the layer being placed. When the random core is less than 1 inch thick, it will not be included in the analysis. In this case, another random core will be taken. After air drying to a constant weight, cores obtained from the mat and from the joints will be used for in-place density determination.

3.11.6.2 Mat and Joint Densities

The average in-place mat and joint densities are expressed as a percentage of the average Marshall density for the lot. The Marshall density for each lot will be determined as the average Marshall density of the four random samples (3 specimens compacted per sample). The average in-place mat density and joint density for a lot are determined and compared with Table 8 to calculate a single pay factor per lot based on in-place density, as described below. First, a pay factor for both mat density and joint density are determined from Table 7. The area associated with the joint is then determined and will be considered to be 10 feet wide times the length of completed longitudinal construction joint in the lot. This area will not exceed the total lot size. The length of joint to be considered will be that length where a new lane has been placed against an adjacent lane of hot-mix asphalt pavement, either an adjacent freshly paved lane or one paved at any time previously. The area associated with the joint is expressed as a percentage of the total lot area. A weighted pay factor for the joint is determined based on this percentage (see example below). The pay factor for mat density

and the weighted pay factor for joint density is compared and the lowest selected. This selected pay factor is the pay factor based on density for the lot. When the Marshall density on both sides of a longitudinal joint is different, the average of these two densities will be used as the Marshall density needed to calculate the percent joint density. All density results for a lot will be completed and reported within 24 hours after the construction of that lot.

Table 7. Pay Factor Based on In-place Density

Average Mat Density (4 Cores)	Pay Factor, %	Average Joint Density (4 Cores)
98.0 - 100	100.0	Above 96.5
97.9	100.0	96.4
97.8 or 100.1	99.9	96.3
97.7	99.8	96.2
97.6 or 100.2	99.6	96.1
97.5	99.4	96.0
97.4 or 100.3	99.1	95.9
97.3	98.7	95.8
97.2 or 100.4	98.3	95.7
97.1	97.8	95.6
97.0 or 100.5	97.3	95.5
96.9	96.3	95.4
96.8 or 100.6	94.1	95.3
96.7	92.2	95.2
96.6 or 100.7	90.3	95.1
96.5	87.9	95.0
96.4 or 100.8	85.7	94.9
96.3	83.3	94.8
96.2 or 100.9	80.6	94.7
96.1	78.0	94.6
96.0 or 101.0	75.0	94.5
below 96.0, above 101.0	0.0 (reject)	below 94.5

3.11.6.3 Pay Factor Based on In-place Density

An example of the computation of a pay factor (in I-P units only) based on in-place density, is as follows: Assume the following test results for field density made on the lot: (1) Average mat density = 97.2 percent (of lab density). (2) Average joint density = 95.5 percent (of lab density). (3) Total area of lot = 30,000 square feet. (4) Length of completed longitudinal construction joint = 2000 feet.

a. Step 1: Determine pay factor based on mat density and on joint density, using Table 7:

Mat density of 97.2 percent = 98.3 pay factor.

Joint density of 95.5 percent = 97.3 pay factor.

b. Step 2: Determine ratio of joint area (length of longitudinal joint x 10 ft) to mat area (total paved area in the lot): Multiply the length of completed longitudinal construction joint by the specified 10 ft. width and divide by the mat area (total paved area in the lot).

(2000 ft. x 10 ft.)/30000 sq.ft. = 0.6667 ratio of joint area to mat area (ratio).

c. Step 3: Weighted pay factor (wpf) for joint is determined as indicated below:

wpf = joint pay factor + (100 - joint pay factor) (1 - ratio) wpf = 97.3 + (100-97.3) (1-.6667) = 98.2%

d. Step 4: Compare weighted pay factor for joint density to pay factor for mat density and select the smaller:

Pay factor for mat density: 98.3%. Weighted pay factor for joint density: 98.2%

Select the smaller of the two values as pay factor based on density: 98.2%

3.11.7 Grade

The final wearing surface of pavement shall conform to the elevations and cross sections shown and shall vary not more than 0.03 foot for runways or 0.05 foot for taxiways and aprons from the plan grade established and approved at site of work. Finished surfaces at juncture with other pavements shall coincide with finished surfaces of abutting pavements. Deviation from the plan elevation will not be permitted in areas of pavements where closer conformance with planned elevation is required for the proper functioning of drainage and other appurtenant structures involved. The final wearing surface of the pavement will be tested for conformance with specified plan grade requirements. The grade will be determined by running lines of levels at intervals of 50 feet or less, longitudinally and transversely, to determine the elevation of the completed pavement surface. Within 5 working days, after the completion of a particular lot incorporating the final wearing surface, the Contracting Officer will inform the Contractor in writing, of the results of the grade-conformance tests. When more than 15 percent of all measurements made within a lot are outside the 0.03 foot tolerance, the pay factor based on grade for that lot will be 95 percent. In areas where the grade exceeds the tolerance by more than 50 percent, the Contractor shall remove the surface lift full depth; the Contractor shall then replace the lift with hot-mix asphalt to meet specification requirements, at no additional cost to the Government. Diamond grinding may be used to remove high spots to meet grade requirements. Skin patching for correcting low areas or planing or milling for correcting high areas will not be permitted.

3.11.8 Surface Smoothness

The Contractor shall use both of the following methods to test and evaluate surface smoothness of the pavement. All testing shall be performed in the presence of the Contracting Officer. Detailed notes of the results of the testing shall be kept and a copy furnished to the Contracting Officer immediately after each day's testing. The profilograph method shall be used for all longitudinal and transverse testing, except where the runs would be less than 200 feet in length and the ends where the straightedge shall be used. Where drawings show required deviations from a plane surface (crowns, drainage inlets, etc.), the surface shall be finished to meet the approval of the Contracting Officer.

3.11.8.1 Smoothness Requirements

a. Straightedge Testing: The finished surfaces of the pavements shall have no abrupt change of 1/8 inch or more, and all pavements shall be within the tolerances specified in Table 8 when checked with an approved 12 foot straightedge.

Table 8. Straightedge Surface Smoothness--Pavements

Pavement Category	Direction of Testing	Tolerance, inches
Runways and taxiways	Longitudinal	1/8
	Transverse	1/4
All other airfields and helicopter paved areas	Longitudinal	1/4
	Transverse	1/4

b. Profilograph Testing: The finished surfaces of the pavements shall have no abrupt change of 1/8 inch or more, and all pavement shall have a Profile Index not greater than specified in Table 9 when tested with an approved California-type profilograph. If the extent of the pavement in either direction is less than 200 feet that direction shall be tested by the straightedge method and shall meet requirements specified above.

Table 9. Profilograph Surface Smoothness--Pavements

Pavement Category	Direction of Testing	Maximum Specified Profile Index (inch/mile)
Runways	Longitudinal	7
	Transverse	9
Taxiways	Longitudinal	9
	Transverse	(Use Straightedge)
All Other Airfield & Helicopter Paved Areas	Longitudinal	9
	Transverse	9

3.11.8.2 Testing Method

After the final rolling, but not later than 24 hours after placement, the surface of the pavement in each entire lot shall be tested by the Contractor in such a manner as to reveal all surface irregularities exceeding the tolerances specified above. Separate testing of individual sublots is not required. If any pavement areas are ground, these areas shall be retested immediately after grinding. The entire area of the pavement shall be tested in both a longitudinal and a transverse direction on parallel lines. The transverse lines shall be 15 feet or less apart, as directed. The longitudinal lines shall be at the centerline of each paving lane for lanes less than 20 feet and at the third points for lanes 20 feet or greater. Other areas having obvious deviations shall also be tested. Longitudinal testing lines shall be continuous across all joints.

a. Straightedge Testing. The straightedge shall be held in contact with the surface and moved ahead one-half the length of the straightedge for each successive measurement. The amount of surface irregularity shall be determined by placing the freestanding (unleveled) straightedge on the pavement surface and allowing it to rest upon the two highest spots covered by its length, and measuring the maximum gap between the straightedge and the pavement surface in the area between these two high points.

b. Profilograph Testing. Profilograph testing shall be performed using approved equipment and procedures described in CDT Test 526. The equipment shall utilize electronic recording and automatic computerized reduction of data to indicate "must-grind" bumps and

the Profile Index for the pavement. The "blanking band" shall be 0.2 inches wide and the "bump template" shall span 1 inch with an offset of 0.4 inch. The profilograph shall be operated by an approved, factory-trained operator on the alignments specified above. A copy of the reduced tapes shall be furnished the Contracting Officer at the end of each day's testing.

3.11.8.3 Payment Adjustment for Smoothness

a. Straightedge Testing. Location and deviation from straightedge for all measurements shall be recorded. When between 5.0 and 10.0 percent of all measurements made within a lot exceed the tolerance specified in paragraph Smoothness Requirements above, after any reduction of high spots or removal and replacement, the computed pay factor for that lot based on surface smoothness, will be 95 percent. When more than 10.0 percent of all measurements exceed the tolerance, the computed pay factor will be 90 percent. When between 15.0 and 20.0 percent of all measurements exceed the tolerance, the computed pay factor will be 75 percent. When 20.0 percent or more of the measurements exceed the tolerance, the lot shall be removed and replaced at no additional cost to the Government. Regardless of the above, any small individual area with surface deviation which exceeds the tolerance given above by more than 50 percent, shall be corrected by diamond grinding to meet the specification requirements above or shall be removed and replaced at no additional cost to the Government.

b. Profilograph Testing. Location and data from all profilograph measurements shall be recorded. When the Profile Index of a lot exceeds the tolerance specified in paragraph Smoothness Requirements above by 1.0 inch/mile, but less than 2.0 inches/mile after any reduction of high spots or removal and replacement, the computed pay factor for that lot based on surface smoothness will be 95 percent. When the Profile Index exceeds the tolerance by 2.0 inches/mile, but less than 3.0 inches/mile, the computed pay factor will be 90 percent. When the Profile Index exceeds the tolerance by 3.0 inches/mile, but less than 4.0 inches/mile, the computed pay factor will be 75 percent. When the Profile Index exceeds the tolerance by 4.0 inches/mile or more, the lot shall be removed and replaced at no additional cost to the Government. Regardless of the above, any small individual area with surface deviation which exceeds the tolerance given above by more than 5.0 inches/mile or more, shall be corrected by grinding to meet the specification requirements above or shall be removed and replaced at no additional cost to the Government.

c. Bumps ("Must Grind" Areas). Any bumps ("must grind" areas) shown on the profilograph trace which exceed 0.4 inch in height shall be reduced by diamond grinding until they do not exceed 0.3 inch when retested. Such grinding shall be tapered in all directions to provide smooth transitions to areas not requiring grinding. The following will not be permitted: (1) skin patching for correcting low areas, (2) planing or milling for correcting high areas. At the Contractor's option, pavement areas, including ground areas, may be rechecked with the profilograph in order to record a lower Profile Index.

END OF SECTION

SECTION 02753 (R)

CONCRETE PAVEMENT FOR AIRFIELDS AND OTHER HEAVY-DUTY PAVEMENTS

1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

ACI INTERNATIONAL (ACI)

ACI 211.1	(1991) Standard Practice for Selecting Proportions for Normal, Heavyweight, and Mass Concrete
ACI 214.3R	(1988) Simplified Version of the Recommended Practice for Evaluation of Strength Test Results of Concrete
ACI 305R	(1991) Hot Weather Concreting

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO M 182	(1991; R 1996) Burlap Cloth Made from Jute or Kenaf

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 53	(1999b) Pipe, Steel, Black and Hot-Dipped, Zinc-Coated Welded and Seamless
ASTM A 184/A 184M	(1996) Fabricated Deformed Steel Bar Mats for Concrete Reinforcement
ASTM A 185	(1997) Steel Welded Wire Fabric, Plain, for Concrete Reinforcement
ASTM A 497	(1997) Steel Welded Wire Fabric, Deformed, for Concrete Reinforcement
ASTM A 615/A 615M	(1996a) Deformed and Plain Billet-Steel Bars for Concrete Reinforcement
ASTM A 616/A 616M	(1996a) Rail-Steel Deformed and Plain Bars for Concrete Reinforcement
ASTM A 617/A 617M	(1996a) Axle-Steel Deformed and Plain Bars for Concrete Reinforcement

ASTM C 29/C 29M	(1997)Bulk Density ("Unit Weight") and Voids in Aggregate
ASTM C 31/C 31M	(1998) Making and Curing Concrete Test Specimens in the Field
ASTM C 33	(1999a) Concrete Aggregates
ASTM C 39	(1996) Compressive Strength of Cylindrical Concrete Specimens
ASTM C 78	(1994) Flexural Strength of Concrete (Using Simple Beam with Third-Point Loading)
ASTM C 94/C 94M	(1999el) Ready-Mixed Concrete
ASTM C 117	(1995) Materials Finer Than 75 micrometer (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C 123	(1998) Lightweight Particles in Aggregate
ASTM C 131	(1996) Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine
ASTM C 136	(1996a) Sieve Analysis of Fine and Coarse Aggregates
ASTM C 142	(1978; R 1997) Clay Lumps and Friable Particles in Aggregates
ASTM C 143	(1998) Slump of Hydraulic Cement Concrete
ASTM C 150	(1999a) Portland Cement
ASTM C 171	(1997a) Sheet Materials for Curing Concrete
ASTM C 172	(1999) Sampling Freshly Mixed Concrete
ASTM C 174/C 174M	(1997) Measuring Thickness of Concrete Elements Using Drilled Concrete Cores
ASTM C 192/C 192M	(1998) Making and Curing Concrete Test Specimens in the Laboratory
ASTM C 231	(1997el) Air Content of Freshly Mixed Concrete by the Pressure Method
ASTM C 260	(1998) Air-Entraining Admixtures for Concrete
ASTM C 295	(1998) Petrographic Examination of Aggregates for Concrete

ASTM C 330	(1999) Lightweight Aggregates for Structural Concrete
ASTM C 470/C 470M	(1998) Molds for Forming Concrete Test Cylinders Vertically
ASTM C 494	(1999) Chemical Admixtures for Concrete
ASTM C 595	(1998) Blended Hydraulic Cements
ASTM C 595M	(1997) Blended Hydraulic Cements (Metric)
ASTM C 618	(1999) Coal Fly Ash and Raw or Calcined Natural Pozzolan for Use as a Mineral Admixture in Concrete
ASTM C 881	(1999) Epoxy-Resin-Base Bonding Systems for Concrete
ASTM C 989	(19999) Ground Granulated Blast-Furnace Slag for Use in Concrete and Mortars
ASTM C 1064/C 1064M	(1999) Temperature of Freshly Mixed Portland Cement Concrete
ASTM C 1077	(1998) Laboratories Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Laboratory Evaluation
ASTM C 1240	(1999) Silica Fume for Use as a Mineral Admixture in Hydraulic-Cement Concrete, Mortar and Grout
ASTM D 449	(1989; R 1999el) Asphalt Used in Dampproofing and Waterproofing
ASTM D 946	(1999) Penetration-Graded Asphalt Cement for Use in Pavement Construction
ASTM D 1227	(1995) Emulsified Asphalt Used as a Protective Coating for Roofing
ASTM D 1751	(1999) Preformed Expansion Joint Filler for Concrete Paving and Structural Construction (Nonextruding and Resilient Bituminous Types)
ASTM D 1752	(1984; R 1996el) Preformed Sponge Rubber and Cork Expansion Joint Fillers for Concrete Paving and Structural Construction
ASTM D 3665	(1999) Random Sampling of Construction Materials
ASTM C 1260	(1994) Potential Alkali Reactivity of Aggregates (Mortar Bar Method)

STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION (CDT)

CDT Test 526	(1978) Operation of California Profilograph and Evaluation of Profiles

U.S. ARMY CORPS OF ENGINEERS (USACE)

COE CRD-C 55	(1992) Test Method for Within-Batch Uniformity of Freshly Mixed Concrete
COE CRD-C 100	(1975) Method of Sampling Concrete Aggregate and Aggregate Sources, and Selection of Material for Testing
COE CRD-C 104	(1980) Method of Calculation of the Fineness Modulus of Aggregate
COE CRD-C 114	(1997) Test Method for Soundness of Aggregates by Freezing and Thawing of Concrete Specimens
COE CRD-C 119	(1991) Standard Test Method for Flat or Elongated Particles in Coarse Aggregate
COE CRD-C 130	(1989) Scratch Hardness of Coarse Aggregates Particles
COE CRD-C 143	(1962) Specifications for Meters for Automatic Indication of Moisture in Fine Aggregate
COE CRD-C 171	(1995) Test Method for Determining Percentage of Crushed Particles in Aggregate
COE CRD-C 300	(1990) Specifications for Membrane-Forming Compounds for Curing Concrete
COE CRD-C 400	(1963) Requirements for Water for Use in Mixing or Curing Concrete
COE CRD-C 521	(1981) Standard Test Method for Frequency and Amplitude of Vibrators for Concrete
COE CRD-C 540	(1971; R 1981) Standard Specification for Nonbituminous Inserts for Contraction Joints in Portland Cement Concrete Airfield Pavements, Sawable Type
COE CRD-C 572	(1974) Corps of Engineers Specifications for Polyvinylchloride Waterstop

NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY (NIST)

NIST HB 44	(1997) NIST Handbook 44: Specifications, Tolerances, and Other Technical Requirements for Weighing and Measuring Devices

NATIONAL READY-MIXED CONCRETE ASSOCIATION (NRMCA)

NRMCA CPMB 100	(1996) Concrete Plant Standards

MILITARY STANDARDS (DEPARTMENT OF DEFENSE)

MIL-DTL-24441/20A	(1999) Paint, Epoxy-Polyamide, Green Primer, Formula 150, Type III

1.2 SYSTEM DESCRIPTION

This section is intended to stand alone for construction of concrete (rigid) pavement. However, where the construction covered herein interfaces with other sections, the construction at each interface shall conform to the requirements of both this section and the other section, including tolerances for both.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Product Data

Equipment; G

a. Details and data on the batching and mixing plant prior to plant assembly including manufacturer's literature showing that the equipment meets all requirements specified herein.

b. A description of the equipment proposed for transporting concrete mixture from the central mixing plant to the paving equipment at least 7 days prior to start of paving unless otherwise specified.

c. At the time the materials are furnished for the mixture proportioning study, a description of the equipment proposed for the placing of the concrete mixture, method of control, and manufacturer's literature on the paver and finisher, together with the manufacturer's written instructions on adjustments and operating procedures necessary to assure a tight, smooth surface on the concrete pavement, free of tears and other surface imperfections, including excessive paste on the surface. The literature shall show that the equipment meets all details of these specifications.

Proposed Techniques; G

a. A description of the placing and protection methods proposed prior to construction of the test section, if concrete is to be placed in or exposed to hot or cold weather conditions.

b. A detailed plan of the proposed paving pattern showing all planned construction joints. No deviation from the jointing pattern shown on the drawings shall be made without written approval of the Contracting Officer.

c. Data on the curing media and methods to be used.

Construction Joint Plan: G

Airfield PCC Joint Plan(s) for Taxiway Alpha and, or Taxiway Echo Optional work must be submitted. If either one, or both taxiway options are awarded under the contract a joint plan must be submitted for approval by the Contracting Officer. The joint plan should indicate slabs for both the new work and the existing to remain with joint types both existing and new clearly identified. Each joint type shall be identified on the joint plan and established by identification of existing joint types during demolition of the taxiway PCC and matching existing joint types in the new construction

Samples for Mixture Proportioning Studies; G

The results of the Contractor's mixture proportioning studies along with a statement giving the maximum nominal coarse aggregate size and the proportions of all ingredients that will be used in the manufacture of concrete at least 14 days prior to commencing concrete placing operations. Aggregate quantities shall be based on the mass in a saturated surface dry condition. The statement shall be accompanied by test results from an independent commercial testing laboratory, inspected by the Government, and approved in writing, showing that mixture proportioning studies have been made with materials proposed for the project and that the proportions selected will produce concrete of the qualities indicated. No substitutions shall be made in the materials used in the mixture proportions without additional tests to show that the quality of the concrete is satisfactory.

Delivery, Storage, and Handling of Materials; G

Copies of waybills or delivery tickets for cementitious material during the progress of the work. Before the final payment is allowed, waybills and certified delivery tickets shall be furnished for all cementitious material used in the construction.

Test Reports

Sampling and Testing; G

Certified copies of laboratory test reports, including all test data, for cement, pozzolan, aggregate, admixtures, and curing compound proposed for use on this project. These tests shall be made by an approved commercial laboratory or by a laboratory maintained by the manufacturers of the materials. No material shall be

used until notice of acceptance has been given. Materials may be subjected to check testing by the Government from samples obtained at the manufacturer, at transfer points, or at the project site.

1.4 MEASUREMENT AND PAYMENT

1.4.1 Measurements

1.4.1.1 Concrete

The quantity of concrete to be paid for will be the volume of concrete in cubic yards placed in the completed and accepted pavement. Concrete will be measured in place in the completed and accepted pavement only within the neat line dimensions shown in the plan and cross section. No deductions will be made for rounded or beveled edges or the space occupied by pavement reinforcement, dowel bars, tie bars, or electrical conduits, nor for any void, or other structure extending into or through the pavement slab, measuring 3 cubic feet or less in volume. No other allowance for concrete will be made unless placed in specified locations in accordance with written instructions previously issued by the Contracting Officer.

1.4.1.2 Mixture Proportions By Contractor

The Contractor shall be responsible for the mixture proportions of cementitious materials and chemical admixtures; no separate measurement or payment will be made for any cementitious material, including pozzolan, or for any chemical admixture.

1.4.1.3 Steel Reinforcement

The quantity of fabricated steel bar mats or welded steel wire fabric for reinforcement used in the work will not be measured for payment but will be considered as a subsidiary obligation of the Contractor, covered under the price per yard for concrete.

1.4.1.4 Dowels and Tie Bars

The quantity of dowels and tie bars used in the work will not be measured for payment but will be considered as a subsidiary obligation of the Contractor, covered under the price per yard for concrete.

1.4.1.5 Joint Materials

The quantity of expansion joint filler, slip joint filler, and inserts for contraction joints will not be measured for payment but will be considered as a subsidiary obligation of the Contractor, covered under the price per yard for concrete. Joint sealing materials are covered in Section 02760 (R) FIELD MOLDED SEALANTS FOR SEALING JOINTS IN RIGID PAVEMENTS and Section 02762 (R) COMPRESSION JOINT SEALS FOR CONCRETE PAVEMENTS.

1.4.2 Payments

1.4.2.1 Concrete

The quantity of concrete measured as specified above will be paid for at the contract unit price when placed in completed and accepted pavements. Payment shall be made at the

contract price for the scheduled item, with necessary adjustments as specified in paragraph ACCEPTABILITY OF WORK AND PAYMENT ADJUSTMENTS. Payment will constitute full compensation for furnishing all materials, equipment, plant and tools, and for all labor and other incidentals necessary to complete the concrete pavement, except for other items specified herein for separate payment.

1.5 ACCEPTABILITY OF WORK AND PAYMENT ADJUSTMENTS

Concrete samples shall be taken by the Contractor in the field to determine the slump, air content, and strength of the concrete. Test beams and test cylinders shall be made for determining conformance with the strength requirements of these specifications and, when required, for determining the time at which pavements may be placed into service. Any pavement not meeting the requirement for 'specified strength' shall be removed and replaced at no additional cost to the Government. The air content shall be determined in accordance with ASTM C 231. Slump tests shall be made in accordance with ASTM C 143. Test beams and cylinders shall be molded and cured in accordance with ASTM C 31/C 31M and as specified below. Steel molds shall be used for molding the beams specimens. Molds for cylinder test specimens shall conform to ASTM C 470/C 470M. The Contractor shall furnish all materials, labor, and facilities required for molding, curing, testing, and protecting test specimens at the site and in the laboratory. Laboratory curing facilities for test specimens shall include furnishing and operating water tanks equipped with temperature-control devices that will automatically maintain the temperature of the water at 73 plus or minus 5 degrees F. The Contractor shall furnish and maintain at the site boxes or other facilities suitable for storing the specimens while in the mold at a temperature of 73 plus or minus 10 degrees F. Tests of the fresh concrete and of the hardened concrete specimens shall be made by and at the expense of the Contractor.

1.5.1 Pavement Lots

Appropriate adjustment in payment for individual lots of concrete pavement will be made in accordance with the following paragraphs. No such adjustment in payment will be made for any material described in this section other than concrete. A lot will be that quantity of construction that will be evaluated for compliance with specification requirements. A lot will be equal to 10 hours production for any individual paving machine. If more than one paving machine is used at the same time, then each machine will have it’s own lots.. In order to evaluate thickness, each lot will be divided into four equal sublots. However, the lot size shall not exceed 1000 cubic yards of concrete pavement. Grade and surface smoothness (and condition) determinations will be made on the lot as a whole. However, any pavement not meeting the required 'specified strength' shall be removed and replaced at no additional cost to the Government. Strength will be evaluated, but will not be considered for payment adjustment. Edge slump requirements will be applied to each individual slab into which the primary paving lanes are divided by transverse joints, and will not be considered for payment adjustment. Samples for determining aggregate grading for fine aggregate and each size of coarse aggregate shall be taken as the aggregate bins discharge into the weigh hoppers. Results of tests on aggregates shall be used to control aggregate production and concreting operations, as specified in paragraph TESTING AND INSPECTION FOR CONTRACTOR QUALITY CONTROL, but will not be used for payment adjustment. Samples for determining air content and slump and for fabricating strength specimens shall be taken in accordance with ASTM C 172 during or immediately following delivery of the concrete at the paving site and deposition of the concrete immediately in front of the paver or transfer spreader. Results of strength tests shall be used to control concreting operations, but will not be used for

payment adjustment. Cores for thickness determination shall be drilled and evaluated as specified. Location of all samples shall be as directed and will be deliberately selected on a truly random basis, not haphazard, using commonly recognized methods of assuring randomness, employing randomizing tables or computer programs, in accordance with ASTM D 3665.

1.5.2 Acceptance of Lots

When a lot of material fails to meet the specification requirements, that lot will be accepted at a reduced price or shall be removed and replaced. The lowest computed percent payment determined for any pavement characteristic (i.e., thickness, grade, and surface smoothness) discussed below shall be the actual percent payment for that lot. The actual percent payment will be applied to the bid price and the quantity of concrete placed in the lot to determine actual payment.

1.5.3 Evaluation

The Contractor shall provide facilities for and, where directed, personnel to assist in obtaining samples for any Government testing, all at no additional cost to the Government. Such testing will in no way relieve the Contractor of any specified testing responsibilities. The Contractor shall provide all sampling and testing required for acceptance and payment adjustment at its expense. Such sampling and testing shall be performed by a commercial testing laboratory inspected by the Government and approved in writing. The laboratory performing the tests shall be on-site and shall conform with ASTM C 1077. The individuals who sample and test concrete or the constituents of concrete as required in this specification shall be certified as American Concrete Institute (ACI) Concrete Field Testing Technicians, Grade I, or shall have otherwise demonstrated to the satisfaction of the Contracting Officer other training providing knowledge and ability equivalent to the ACI minimum requirements for certification. The individuals who perform the inspection of concrete shall be certified as ACI Concrete Construction Inspector, Level II, or have otherwise demonstrated to the satisfaction of the Contracting Officer other training providing knowledge and ability equivalent to the ACI minimum requirements for certification. The Government will inspect the laboratory, equipment, and test procedures prior to start of concreting operations and at least once per year thereafter for conformance with ASTM C 1077.

1.5.4 Additional Sampling and Testing

The Contracting Officer reserves the right to direct additional samples and tests for any area which appears to deviate from the specification requirements. Testing in these areas will be in addition to the sublot or lot testing, and the requirements for these areas will be the same as those for a sublot or lot, but shall be at no additional cost to the Government.

1.5.5 Air Content Tests

Air content of the concrete shall be controlled as specified in paragraph TESTING AND INSPECTION FOR CONTRACTOR QUALITY CONTROL and will not be considered for payment adjustment.

1.5.6 Slump Tests

Slump of the concrete shall be controlled as specified in paragraph TESTING AND INSPECTION FOR CONTRACTOR QUALITY CONTROL and will not be considered for payment adjustment.

1.5.7 Surface Smoothness

The Contractor shall use both of the following methods to test and evaluate surface smoothness of the pavement. All testing shall be performed in the presence of the Contracting Officer's representative. Detailed notes shall be kept of the results of the testing and a copy furnished to the Government immediately after each day's testing. The profilograph method shall be used for all longitudinal and transverse testing, except where the runs would be less than 200 feet in length and at the ends where the straightedge shall be used. Where drawings show required deviations from a plane surface (crowns, drainage inlets, etc.), the surface shall be finished to meet the approval of the Contracting Officer.

1.5.7.1 Smoothness Requirements

a. Straightedge Testing: The finished surfaces of the pavements shall have no abrupt change of 1/8 inch or more, and all pavements shall be within the limits specified in Table 1 when checked with an approved 12 foot straightedge.

TABLE 1

STRAIGHTEDGE SURFACE SMOOTHNESS--PAVEMENTS

Pavement Category	Direction of Testing	Limits Inches
Runways and Taxiways	Longitudinal	1/8
	Transverse	1/4

b. Profilograph Testing: The finished surfaces of the pavements shall have no abrupt change of 1/8 inch or more, and all pavement shall have a Profile Index not greater than specified in Table 2 when tested with an approved California-type profilograph. If the extent of the pavement in either direction is less than 200 feet, that direction shall be tested by the straightedge method and shall meet requirements specified for such.

TABLE 2

PROFILOGRAPH SURFACE SMOOTHNESS—PAVEMENTS

Pavement Category	Direction of Testing	Maximum Specified Profile Index Inch per mile
Runways	Longitudinal	7
	Transverse	9
Taxiways	Longitudinal	9
	Transverse	(Use Straightedge)

1.5.7.2 Testing Method

After the concrete has hardened sufficiently to permit walking thereon, but not later than 36 hours after placement, the surface of the pavement in each entire lot shall be tested by the Contractor in such a manner as to reveal all surface irregularities exceeding the tolerances specified above. However, transverse profilograph testing of multiple paving lanes shall be performed at the timing directed. Separate testing of individual sublots is not required. If any pavement areas are ground, these areas shall be retested immediately after grinding. The entire area of the pavement shall be tested in both a longitudinal and a transverse direction on parallel lines. The transverse lines shall be 15 feet or less apart, as directed. The longitudinal lines shall be at the centerline of each paving lane shown on the drawings, regardless of whether the Contractor is allowed to pave two lanes at a time, and at the 1/8th point in from each side of the lane. Other areas having obvious deviations shall also be tested. Longitudinal testing lines shall be continuous across all joints. Transverse testing lines for pilot lanes shall be carried to construction joint lines and for fill-in lanes shall be carried 24 inches across construction joints, and the readings in this area applied to the fill-in lane. Straightedge testing of the longitudinal edges of slipformed pilot lanes shall also be performed before paving fill-in lanes as specified in paragraph "Edge Slump and Joint Face Deformation".

a. Straightedge Testing: The straightedge shall be held in contact with the surface and moved ahead one-half the length of the straightedge for each successive measurement. The amount of surface irregularity shall be determined by placing the freestanding (unleveled) straightedge on the pavement surface and allowing it to rest upon the two highest spots covered by its length and measuring the maximum gap between the straightedge and the pavement surface, in the area between these two high points.

b. Profilograph Testing: Profilograph testing shall be performed using approved equipment and procedures described in CDT Test 526. The equipment shall utilize electronic recording and automatic computerized reduction of data to indicate "must-grind" bumps and the Profile Index for the pavement. The "blanking band" shall be 0.2 inches wide and the "bump template" shall span 1 inch with an offset of 0.4 inch. The profilograph shall be operated by an approved, factory-trained operator on the alignments specified above. A copy of the reduced tapes shall be furnished the Government at the end of each day's testing.

1.5.7.3 Payment Adjustment for Smoothness

a. Straightedge Testing: Location and deviation from straightedge for all measurements shall be recorded. When between 5.0 and 10.0 percent and less than 15.0 percent of all measurements made within a lot exceed the tolerance specified in paragraph "Smoothness Requirements" above, after any reduction of high spots or removal and replacement, the computed percent payment based on surface smoothness will be 95 percent. When more than 10.0 percent and less than 15.0 percent of all measurements exceed the tolerance, the computed percent payment will be 90 percent. When between 15.0 and 20.0 percent of all measurements exceed the tolerance, the computed percent payment will be 75 percent. When 20.0 percent or more of the measurements exceed the tolerance, the lot shall be removed and replaced at no additional cost to the Government. Regardless of the above, any small individual area with surface deviation which exceeds the tolerance given

above by more than 50 percent shall be corrected by grinding to meet the specification requirements above or shall be removed and replaced at no additional cost to the Government.

b. Profilograph Testing: Location and data from all profilograph measurements shall be recorded. When the Profile Index of a lot exceeds the tolerance specified in paragraph "Smoothness Requirements" above by 1.0 inch per mile but less than 2.0 inches per mile after any reduction of high spots or removal and replacement, the computed percent payment based on surface smoothness will be 95 percent. When the Profile Index exceeds the tolerance by 2.0 inches per mile but les 3.0 inches per mile the computed percent payment will be 90 percent. When the Profile Index exceeds the tolerance by 3.0 inches per mile but less than 4.0 inches per mile the computed percent payment will be 75 percent. When the Profile Index exceeds the tolerance by 4.0 inches per mile or more, the lot shall be removed and replaced at no additional cost to the Government. Regardless of the above, any small individual area with surface deviation which exceeds the tolerance given above by more than 5.0 inches per mile or more, shall be corrected by grinding to meet the specification requirements above or shall be removed and replaced at no additional cost to the Government.

c. Bumps ("Must Grind" Areas): Any bumps ("must grind" areas) shown on the profilograph trace which exceed 0.4 inch in height shall be reduced by grinding in accordance with subparagraph "Areas Defective In Plan Grade Or Smoothness" until they do not exceed 0.3 inch when retested. Such grinding shall be tapered in all directions to provide smooth transitions to areas not requiring grinding. Areas of textured pavement shall be retextured in accordance with the subparagraph listed above. At the Contractor's option, pavement areas including ground areas may be rechecked with the profilograph in order to record a lower Profile Index.

1.5.8 Edge Slump and Joint Face Deformation

The following requirements on testing and evaluation of edge slump and joint face deformation apply only to pavements 10 inches or more in thickness. Use of slip-form paving equipment and procedures that fail to consistently provide edges within the specified tolerances on edge slump and joint face deformation shall be discontinued and the pavements shall be constructed by means of standard paving procedures using fixed forms. Slabs having more than the allowable edge slump shall be removed and replaced as specified in subparagraph "Excessive Edge Slump" before the adjacent lane is placed. Edge slump and joint face deformation will not be applied to payment adjustment.

1.5.8.1 Edge Slump

When slip-form paving is used, not more than 15.0 percent of the total free edge of any slab of the pavement, as originally constructed, shall have an edge slump exceeding 1/4 inch and no slab shall have an edge slump exceeding 3/8 inch as determined in accordance with the measurements as specified in paragraph "Determination of Edge Slump". (The total free edge of the pavement will be considered to be the cumulative total linear measurement of pavement edge originally constructed as non-adjacent to any existing pavement; i.e., 100 feet of pilot lane, a paving lane originally constructed as a separate lane, will have 200 feet of free edge; 100 feet of fill-in lane will have no free edge, etc.,). The area affected by the downward

movement of the concrete along the pavement edge shall not exceed 18 inches back from the edge.

1.5.8.2 Joint Face Deformation

In addition to the edge slump limits specified above, the vertical joint face shall have a surface within the maximum limits shown below:

Offset from Straightedge Applied Longitudinally To Pavement Surface 1 Inch Back From Joint Line	Offset From Straightedge Applied Longitudinally to Vertical Face	Offset From Straightedge Applied Top to Bottom Against the Joint Face	Abrupt Offset in Any Direction	Offset of Joint Face From True Vertical
1/8 inch	1/4 inch	3/8 inch	1/8 inch	1 inch per 12 inches

(All values are for Airfield Pavement.)

1.5.8.3 Determination of Edge Slump

Immediately after the concrete has hardened sufficiently to permit walking thereon, the pavement surface shall be tested by the Contractor in the presence of a representative of the Contracting Officer. Testing shall be performed with a straightedge to reveal irregularities exceeding the edge slump tolerance specified above. The edge slump shall be determined at each free edge of each slipformed paving lane constructed. The straightedge shall be placed transverse to the direction of paving and the end of the straightedge located at the edge of the paving lane. Measurements shall be made at 5 to 15 foot spacings, as directed, commencing at the header where paving was started. Initially measurements shall be made at 5 foot intervals in each lane. When no deficiencies are present, the Contracting Officer may approve an increase in the interval. When any deficiencies exist, the interval will be returned to 5 feet In no case shall the interval exceed 15 feet In addition to the transverse edge slump determination above, the Contractor, at the same time, shall check the longitudinal surface smoothness of the joint on a continuous line 1 inch back from the joint line using the straightedge advanced one-half its length for each reading. Other tests of the exposed joint face shall be made as directed to ensure that a uniform, true vertical joint face is attained. These tests shall include longitudinal straightedge testing of the vertical face and vertical testing of the face for both smoothness and angle. The measurements shall be made by the Contractor, shall be properly referenced in accordance with paving lane identification and stationing, and a report given to the Contracting Officer within 24 hours after measurement is made. The report shall also identify areas requiring replacement in accordance with paragraph "Excessive Edge Slump" as well as the cumulative percentage of total free edge of pavement constructed to date which has an edge slump exceeding 1/4 inch

1.5.8.4 Excessive Edge Slump

When edge slump exceeding the limits specified above is encountered on either side of the paving lane, additional straightedge measurements shall be made, if required, to define the linear limits of the excessive slump. The concrete for the entire width of the paving lane

within these limits of excessive edge slump or joint deformation shall be removed and replaced in conformance with paragraph REPAIR, REMOVAL, REPLACEMENT OR SLABS. Partial slabs removed and replaced shall extend across the full width of the pavement lane, parallel to the transverse joints, and both the section of the slab removed and the section remaining in place shall have a minimum length of 10 feet to the nearest scheduled transverse joint. If less than 10 feet remains, the entire slab shall be removed and replaced. Adding concrete or paste to the edge or otherwise manipulating the plastic concrete after the sliding form has passed, or patching the hardened concrete, shall not be used as a method for correcting excessive edge slump.

1.5.9 Plan Grade

1.5.9.1 Plan Grade Tolerances

The finished surfaces of pavements shall conform, within the tolerances shown below, to the lines, grades, and cross sections shown. The finished surfaces of airfield runway, taxiway, and apron pavements shall vary not more than 1/2 inch above or below the plan grade line or elevation indicated. The surfaces of other pavements shall vary not more than 3/4 inch Plan grade shall be checked on the lot as a whole and when more than 5.0 and less than 10.0 percent of all measurements made within a lot are outside the specified tolerance, the computed percent payment for that lot will be 95 percent. When more than 10.0 percent are outside the specified tolerances, the computed percent payment for the lot will be 75 percent. However, in any areas where the deviation from grade exceeds the specified tolerances by 50 percent or more, the deficient area shall be removed and replaced at no additional cost to the Government. However, the above deviations from the approved grade line and elevation will not be permitted in areas where closer conformance with the planned grade and elevation is required for the proper functioning of appurtenant structures. The finished surfaces of new abutting pavements shall coincide at their juncture.

1.5.9.2 Grade Conformance Tests

Each pavement category shall be checked by the Contractor for conformance with plan grade requirements. For the purpose of making grade conformance tests, the pavements will be subdivided into the same lots used for all other payment adjustment items. Within 5 days after paving of each lot, the finished surface of the pavement area in each lot shall be tested by the Contractor, in the presence of a representative of the Contracting Officer, by running lines of levels at intervals corresponding with every longitudinal and transverse joint to determine the elevation at each joint intersection. The results of this survey shall be recorded and a copy given to the Government at the completion of the survey of each lot.

1.5.10 Flexural Strength

Each lot of pavement will be evaluated for acceptance in accordance with the following procedures. The Contractor shall be responsible for all testing required herein. Testing shall be performed by an approved commercial laboratory. Results of strength tests will not be used for payment adjustment.

1.5.10.1 Sampling and Testing

One composite sample of concrete from each sublot shall be obtained in accordance with ASTM C 172 from one batch or truckload. Test cylinders, 6 x 12 in. shall be fabricated and

cured in accordance with ASTM C 31/C 31M; and tested in accordance with ASTM C 39. Two test cylinders per sublot (8 per lot) shall be fabricated and cured for compressive strength, and two tested at 14-day age and two at 28-day age. The remaining four shall be tested at the ages directed. At the same time 2 additional test cylinders per sublot to be used for CQC tests shall be fabricated and cured; and tested as specified in paragraph TESTING AND INSPECTION FOR CONTRACTOR QUALITY CONTROL. Two beams for flexural strength shall be fabricated and cured in accordance with ASTM C 31/C 31M and tested in accordance with ASTM C 78 for every 2500 cubic yards of concrete. These shall be tested at the ages directed.

1.5.10.2 Computations

The following computations shall be performed:

a. Average the eight 14-day compressive strength tests for the lot and also compute the standard deviation(s) for the eight tests.

b. Convert the 14-day average compressive strength for the lot to equivalent 28-day average flexural strength for the lot, using the Correlation Ratio determined during mixture design studies.

c. Report results of strength tests to the Contracting Officer daily. These values will be used for acceptance, but will not be used for payment adjustment.

1.5.11 Thickness

Each lot of pavement will be evaluated for acceptance and payment adjustment in accordance with the following procedure. The Contractor shall be responsible for drilling the cores, measuring the cores in the presence of the Contracting Officer's representative, and for filling the core holes as directed.

1.5.11.1 Drilling, Measuring, and Computations

Two cores, between 3 and 6 in. in diameter, shall be drilled from the pavement, per sublot (8 per lot). The Contractor shall fill the core holes with concrete containing an expanding admixture, as directed. The cores shall be evaluated for thickness of the pavement in accordance with ASTM C 174/C 174M. The pavement thickness from the 8 cores for the lot shall be averaged and the standard deviation for the 8 thickness measurements shall be computed.

1.5.11.2 Evaluation and Payment Adjustment for Thickness

Using the Average Thickness of the lot, the computed percent payment for thickness shall be determined by entering the following table:

Deficiency in Thickness Determined by Cores Inches	Computed Percent Payment for Thickness
0.00 to 0.24	100
0.25 to 0.49	75
0.50 to 0.74	50
0.75 or greater	0

Where 0 percent payment is indicated, the entire lot shall be removed and replaced at no additional cost to the Government. Where either of the two cores from a sublot show a thickness deficiency of 0.75 inch or greater, two more cores shall be drilled in the sublot and the average thickness of the four cores computed. If this average shows a thickness deficiency of 0.75 inch or more the entire sublot shall be removed.

1.5.12 Partial Lots

When operational conditions cause a lot to be terminated before the specified four sublots have been completed, the following procedure shall be used to adjust the lot size and number of tests for the lot. Where three sublots have been completed, they shall constitute a lot and acceptance criteria adjusted accordingly. Where one or two sublots have been completed, they shall be incorporated into the next lot or the previous lot, as directed, and the total number of sublots shall be used and acceptance criteria adjusted accordingly.

1.5.13 Areas Defective in Plan Grade or Smoothness

In areas not meeting the specified limits for surface smoothness and plan grade, high areas shall be reduced to attain the required smoothness and grade, except as depth is limited below. High areas shall be reduced either by hand rubbing the freshly finished concrete with a silicon carbide brick and water when the concrete is less than 36 hours old or by grinding the hardened concrete with an approved surface grinding machine after the concrete is 14 days or more old. Rubbing with a silicon carbide brick and water shall be discontinued as soon as contact with the coarse aggregate is made, and all further necessary reduction shall be accomplished by grinding the hardened concrete with a surface-grinding machine after it is 14 days old. The area corrected by grinding the surface of the hardened concrete shall not exceed 5 percent of the area of any integral slab, and shall not exceed 1 percent of the total area of any sublot. The depth of grinding shall not exceed 1/4 inch. All pavement areas requiring plan grade or surface smoothness corrections in excess of the limits specified above, shall be removed and replaced in conformance with paragraph REPAIR, REMOVAL, REPLACEMENT OF SLABS. All areas in which rubbing or grinding has been performed will be subject to the thickness tolerances specified in paragraph Thickness. Any rubbing or grinding performed on individual slabs with excessive deficiencies shall be performed at the Contractor's own decision without entitlement to additional compensation if eventual removal of the slab is required.

1.6 ACCEPTABILITY OF WORK

The materials and the pavement itself will be accepted on the basis of tests made by the Government and by the Contractor's approved commercial laboratory or the supplier's approved laboratory, all as specified herein. The Government may, at its discretion, make check tests to validate the results of the Contractor's testing. If the results of the Government and Contractor tests vary by less than 2.0 percent, of the Government's test results, the results of the Contractor's tests will be used. If the results of the Government and Contractor tests vary by 2.0 percent or more, but less than 4.0 percent, the average of the two will be considered the value to be used. If these vary by 4.0 percent or more, each sampling and testing procedure shall be carefully evaluated and both the Government and the Contractor shall take another series of tests on duplicate samples of material. If these vary by 4.0 percent or more, the results of the tests made by the Government shall be used and the Government will continue check testing of this item on a continuous basis until the two sets of tests agree within less than 4.0 percent on a regular basis. Testing performed by the

Government will in no way at any time relieve the Contractor from the specified testing requirements.

1.7 PRECONSTRUCTION TESTING OF MATERIALS

The Contractor shall not be entitled to any additional payment or extension of time because of delays caused by sampling and testing additional sources, or samples, necessitated by failure of any samples.

1.7.1 Aggregates

Aggregates shall be sampled by the Contractor in the presence of a Government representative. Samples shall be obtained in accordance with COE CRD-C 100 and of the size indicated therein, or larger if specified in paragraph Testing Sequence Deleterious Materials -- Airfields Only and shall be representative of the materials to be used for the project. Testing of samples shall be the responsibility of the Contractor and shall be performed by an approved commercial laboratory. Test results shall be submitted 14 days before commencing paving. No material shall be used unless test results show that it meets all requirements of these specifications.

1.7.2 Chemical Admixtures

The Contractor shall provide satisfactory facilities for ready procurement of adequate test samples. All sampling and testing of an admixture will be by and at the expense of the Government. Tests will be conducted with materials proposed for the project. An air-entraining admixture that has been in storage at the project site for longer than 6 months or that has been subjected to freezing will be retested at the expense of the Contractor when considered appropriate and shall be rejected if test results are not satisfactory.

1.7.3 Curing Compound

The Contractor shall provide satisfactory facilities for ready procurement of adequate test samples. The sampling and testing will be by and at the expense of the Government.

1.7.4 Epoxy-Resin Material

At least 30 days before the material is used, the Contractor shall submit certified copies of test results showing that the specific lots or batches from which the material will be furnished to this project have been tested by the manufacturer and that the material conforms to the requirements of these specifications. When epoxy resin arrives at the job site, the Contractor shall assist the Government to sample the material. The Government will test the sample or will retain it in storage for possible future testing, as considered appropriate.

1.7.5 Cements, Pozzolans, and GGBF Slag

Preconstruction sampling and testing of cement, pozzolan, and GGBF slag shall conform to the requirements specified for sampling and testing during construction except that test results showing that each material meets specification requirements shall be available at least 5 days before start of paving operations.

1.8 TESTING BY CONTRACTOR DURING CONSTRUCTION

1.8.1 Contractor's Testing Requirements

During construction, the Contractor shall be responsible for sampling and testing aggregates, cementitious materials (cement and pozzolan), and concrete to determine compliance with the specifications. All sampling and testing shall be performed by an approved commercial laboratory, or for cementitious materials, the manufacturer's laboratory. Samples of aggregate shall be obtained as the bins discharge into the weigh hopper. Samples of concrete shall be obtained at the point of delivery to the paver. The Government will sample and test concrete and ingredient materials as considered appropriate. The Contractor shall provide facilities and labor as may be necessary for procurement of representative test samples. Testing by the Government will in no way relieve the Contractor of the specified testing requirements.

1.8.2 Cementitious Materials

Cement and pozzolan will be accepted on the basis of manufacturer's certification of compliance, accompanied by mill test reports showing that the material in each shipment meets the requirements of the specification under which it is furnished. No cementitious material shall be used until notice of acceptance has been given by the Contracting Officer. Cementitious material may be subjected to check testing by the Government from samples obtained at the mill, at transfer points, or at the project site.

1.9 TESTING BY GOVERNMENT DURING CONSTRUCTION

1.9.1 Mill Tests for Cementitious Materials

Cement and pozzolan will be accepted on the basis of manufacturer's certification of compliance accompanied by mill test reports showing that the material in each shipment used meets the requirements of the specification under which it is furnished. No cementitious material shall be used until notice of acceptance has been given by the Contracting Officer. Cementitious material may be subjected to check testing by the Government on samples obtained at the mill, at transfer points, or at the project site.

1.10 QUALIFICATIONS

All Contractor Quality Control personnel assigned to concrete construction shall be American Concrete Institute (ACI) Certified Workmen in one of the following grades (or shall have approved written evidence of having completed similar qualification programs):

Concrete Field Testing Technician, Grade I
Concrete Laboratory Testing Technician, Grade I or II
Concrete Construction Inspector, Level II
The foreman or lead journeyman of the finishing crew shall have similar qualification for ACI Concrete Flatwork Technician/Finisher, or equal. Written documentation shall be furnished for each workman in the above groups.

1.11 TEST SECTION

At least 10 days but not more than 60 days prior to construction of the concrete pavement, a test section shall be constructed as part of the production paving area at an outer edge as indicated on the drawings. If part of the production paving area, the test section will be allowed to remain in place, if meeting all specification requirements and will be paid for as part of the production pavement. There will be no separate payment for the test section or sections and the cost of the materials, and the construction will be considered a subsidiary cost of constructing the project. The Contractor shall notify the Contracting Officer at least 5 days in advance of the date of test section construction. The test section shall consist of one paving lane at least 400 feet long and shall be constructed to the thickness shown on the plans. The lane width shall be the same as that required for use in the project. The test section shall contain at least one transverse construction joint. If keyed or doweled longitudinal construction joints are required in any of the production pavements, they shall be installed full length along one side of the test strip throughout the test section. The Contractor shall use the test section to develop and demonstrate to the satisfaction of the Contracting Officer the proposed techniques of mixing, hauling, placing, consolidating, finishing, curing, start-up procedures, testing methods, plant operations, and the preparation of the construction joints. Variations in mixture proportions other than water shall be made if directed. The test section shall be placed as approved by the Government. The Contractor shall vary the water content, as necessary, to arrive at the appropriate content. The mixing plant shall be operated and calibrated prior to start of placing the test section. The Contractor shall use the same equipment, materials, and construction techniques on the test section as will be used in all subsequent work. Base course preparation, concrete production, placing, consolidating, curing, construction of joints, and all testing shall be in accordance with applicable provisions of this specification. The Contractor shall construct the test section meeting all specification requirements and being acceptable to the Contracting Officer in all aspects, including surface texture. Failure to construct an acceptable test section will necessitate construction of additional test sections at no additional cost to the Government. Test sections allowed to be constructed as part of the production paving which do not meet specification requirements shall be removed at the Contractor's expense. If the Contractor proposes to use slipform paving and is unable to construct an acceptable test section, or if the slipform paving equipment and procedures are found to be unable to produce acceptable pavement at any time, the slipform paving equipment shall be removed from the job and the construction completed using stationary side forms and equipment compatible with them. The Contractor shall provide four cores at least 6 inch diameter and 2 beams at least 6 by 32 inches by full depth (or 4 beams at least 6 by 20 inches by full depth) cut from points selected in the test section by the Government, 5 days after completion of the test section. The Contractor shall trim the beams to dimensions directed before delivery for inspection and testing, as considered appropriate. Production paving may be started immediately after the results of 7-day tests of the cores (and the sawed beams) have been approved and after approval of the test section.

1.12 DELIVERY, STORAGE, AND HANDLING OF MATERIALS

1.12.1 Bulk Cementitious Materials

All cementitious material shall be furnished in bulk. The temperature of the cementitious material, as delivered to storage at the site, shall not exceed 150 degrees F.

1.12.1.1 Transportation

When bulk cementitious material is not unloaded from primary carriers directly into weather-tight hoppers at the batching plant, transportation from the railhead, mill, or intermediate storage to the batching plant shall be accomplished in adequately designed weather-tight trucks, conveyors, or other means that will protect the cementitious material from exposure to moisture.

1.12.1.2 Storage Requirements

Immediately upon receipt at the site of the work, cementitious materials shall be stored in a dry and properly ventilated structure. All storage facilities shall be subject to approval and shall allow easy access for inspection and identification. Sufficient cementitious materials shall be in storage to sustain continuous operation of the concrete mixing plant while the pavement is being placed. To prevent cement from becoming unduly aged after delivery, any cement that has been stored at the site for 60 days or more shall be used before using cement of lesser age.

1.12.1.3 Separation of Materials

Separate facilities shall be provided which will prevent any intermixing during unloading, transporting, storing, and handling of each type of cementitious material.

1.12.2 Aggregate Materials

1.12.2.1 Storage

Aggregate shall be stored at the site of the batching and mixing plant avoiding breakage, segregation, or contamination by foreign materials. Each size of aggregate from each source shall be stored separately in free-draining stockpiles. Fine aggregate and the smallest size coarse aggregate shall remain in free-draining storage for at least 24 hours immediately prior to use. Sufficient aggregate shall be maintained at the site at all times to permit continuous uninterrupted operation of the mixing plant at the time concrete pavement is being placed.

1.12.2.2 Handling

Aggregate shall be handled avoiding segregation or degradation. Vehicles used for stockpiling or moving aggregate shall be kept clean of foreign materials. Tracked equipment shall not be allowed on coarse aggregate stockpiles. Stockpiles shall be built up and worked avoiding segregation in the piles and preventing different sizes of aggregate from being mixed during storage or batching. Aggregate shall not be stored directly on ground unless a sacrificial layer is left undisturbed and unused.

1.12.3 Other Materials

Reinforcing bars and accessories shall be stored above the ground on platforms, skids, or other supports. Other materials shall be stored avoiding contamination and deterioration. Chemical admixtures which have been in storage at the project site for longer than 6 months or which have been subjected to freezing shall not be used unless retested and proven to meet the specified requirements. The Contractor shall ensure that materials can be accurately identified after bundles or containers are opened.

1.13 EQUIPMENT

All plant, equipment, tools, and machines used in the work shall be maintained in satisfactory working conditions at all times.

1.13.1 Batching and Mixing Plant

1.13.1.1 Location of Batching and Mixing Plant

The batching and mixing plant shall be located on project site as indicated on the drawings or off Government premises no more than 15 minutes haul time from the placing site. There shall be operable telephonic or radio communication between the batching plant and the placing site at all times concreting is taking place.

1.13.1.2 Type and Capacity of Batching and Mixing Plant

The batching and mixing plant shall be a stationary-type plant. The plant shall be designed and operated to produce concrete within the specified tolerances, and shall have a capacity of at least 250 cu. yd. per hour. The batching plant shall conform to the requirements of NRMCA CPMB 100 and as specified; however, rating plates attached to batch plant equipment are not required.

1.13.1.3 Equipment Requirements

The batching controls shall be either semiautomatic or automatic. Semiautomatic batching system shall be provided with interlocks. Separate bins or compartments shall be provided for each size group of aggregate and each cementitious material. Aggregates shall be weighed either in separate weigh batchers with individual scales or cumulatively in one weigh batcher on one scale, provided the fine aggregate is weighed first. Aggregate shall not be weighed in the same batcher with cementitious material. If both cement and pozzolan are used, they may be batched cumulatively, provided portland cement is batched first. Water shall not be weighed or measured cumulatively with another ingredient. Water batcher filling and discharging valves shall be so interlocked that the discharge valve cannot be opened before the filling valve is fully closed. An accurate mechanical device for measuring and dispensing each chemical admixture shall be provided. Each dispenser shall be interlocked with the batching cycle and discharged automatically to obtain uniform distribution throughout the batch in the specified mixing period. Different chemical admixtures shall not be combined before introduction in water and cement. The plant shall be arranged to facilitate the inspection of all operations at all times. Suitable facilities shall be provided for obtaining representative samples of aggregates from each bin or compartment.

1.13.1.4 Scales

Adequate facilities shall be provided for the accurate measurement and control of each of the materials entering each batch of concrete. The weighing equipment shall conform to the applicable requirements of NIST HB 44, except that the accuracy shall be within 0.2 percent of scale capacity. The Contractor shall provide standard test weights and any other auxiliary equipment required for checking the operating performance of each scale or other measuring device. Each weighing unit shall include a visible springless dial, which shall indicate the scale load at all stages of the weighing operation or shall include a beam scale with a beam balance indicator that will show the scale in balance at zero load and at any beam setting.

The indicator shall have an over and under travel equal to at least 5 percent of the capacity of the beam. Approved electronic digital indicators and load cells may also be used. The weighing equipment shall be arranged to allow the concrete plant operator to conveniently observe the dials or indicators.

1.13.1.5 Batching Tolerances

The following tolerances shall apply.

Materials	Percentage of Required Mass
Cement (and Pozzolan)	plus or minus 1
Aggregate	plus or minus 2
Water	plus or minus 1
Admixture	plus or minus 3

For volumetric batching equipment for water and admixtures, the above numeric tolerances shall apply to the required volume of material being batched. Concentrated admixtures shall be uniformly diluted, if necessary, to provide sufficient volume per batch to ensure that the batchers will consistently operate within the above tolerance.

1.13.1.6 Moisture Control

The plant shall be capable of ready adjustment to compensate for the varying moisture contents of the aggregates and to change the quantities of the materials being batched. An electric moisture meter complying with the provisions of COE CRD-C 143 shall be provided for measuring of moisture in the fine aggregate. The sensing element shall be arranged so that measurement is made near the batcher charging gate of the fine aggregate bin or in the fine aggregate batcher.

1.13.1.7 Recorders

A graphic or digital recorder conforming to the requirements of NRMCA CPMB 100 shall be furnished and kept operational at the batching plant.

1.13.2 Concrete Mixers

Mixers shall be stationary mixers. Truck mixers shall not be used for mixing or transporting paving concrete if slip-form paving is used. Mixers shall be capable of combining the materials into a uniform mixture and of discharging this mixture without segregation. The mixers shall not be charged in excess of the capacity recommended by the manufacturer. The mixers shall be operated at the drum or mixing blade speed designated by the manufacturer. The mixers shall be maintained in satisfactory operating condition, and the mixer drums shall be kept free of hardened concrete. Mixer blades or paddles shall be replaced when worn down more than 10 percent of their depth when compared with the manufacturer's dimension for new blades or paddles.

1.13.2.1 Stationary, Central Plant, Mixers

Stationary mixers shall be drum mixers or pug mills. Mixers shall be provided with an acceptable device to lock the discharge mechanism until the required mixing time has elapsed.

1.13.2.2 Truck Mixers

The only truck mixers used for mixing or transporting paving concrete shall be those designed with extra large blading and rear opening specifically for low-slump paving concrete. Truck mixers, the mixing of concrete therein, and concrete uniformity and testing thereof shall conform to the requirements of ASTM C 94/C 94M. A truck mixer may be used either for complete mixing (transit-mixed) or to finish the partial mixing done in a stationary mixer (shrink-mixed). Each truck shall be equipped with two counters which will show the number of revolutions at mixing speed and the number of revolutions at agitating speed. Concrete completely mixed in a truck mixer shall be mixed 70 to 100 revolutions at the designated mixing speed after all ingredients, including mixing water, have been charged into the drum. Concrete first partially mixed in a concrete plant mixer (shrink-mixed) a minimum time, as required to combine the ingredients, shall then be completely mixed in a truck mixer. The number of revolutions between 70 to 100 for truck-mixed concrete and the number of revolutions for shrink-mixed concrete shall be determined by uniformity tests as specified in ASTM C 94/C 94M and in requirements for mixer performance stated in paragraph TESTING AND INSPECTION FOR CONTRACTOR QUALITY CONTROL. If requirements for the uniformity of concrete are not met with 100 revolutions of mixing after all ingredients including water are in the truck mixer drum, the mixer shall not be used until the condition is corrected. Additional revolutions beyond the number determined to produce the required uniformity shall be at the designated agitating speed. Water shall not be added after the initial introduction of mixing water except, when on arrival at the job site, the slump is less than specified and the water-cement ratio is less than that given as a maximum in the approved mixture. Additional water may be added to bring the slump within the specified range provided the approved water-cement ratio is not exceeded. Water shall be injected into the head of the mixer (end opposite the discharge opening) drum under pressure, and the drum or blades shall be turned a minimum of 30 additional revolutions at mixing speed. Water shall not be added to the batch at any later time.

1.13.2.3 Mixing Time and Uniformity

a. Stationary Mixers: For stationary mixers, before uniformity data are available, the mixing time for each batch after all solid materials are in the mixer, provided that all of the mixing water is introduced before one-fourth of the mixing time has elapsed, shall be 1 minute for mixers having a capacity of 1 cubic yard. For mixers of greater capacity, this minimum time shall be increased 20 seconds for each additional 1.33 cubic yard or fraction thereof. After results of uniformity tests are available, the mixing time may be reduced to the minimum time required to meet uniformity requirements; but if uniformity requirements are not being met, the mixing time shall be increased as directed. Mixer performance tests at new mixing times shall be performed immediately after any change in mixing time. When regular testing is performed, the concrete shall meet the limits of any five of the six uniformity requirements listed in Table 4, below. When abbreviated testing is performed, the concrete shall meet only those requirements listed for abbreviated testing. The concrete proportions used for uniformity tests shall be as used on the

project. Regular testing shall consist of performing all six tests on three batches of concrete. The range for regular testing shall be the average of the ranges of the three batches. Abbreviated testing shall consist of performing the three required tests on a single batch of concrete. The range for abbreviated testing shall be the range for one batch. If more than one mixer is used and all are identical in terms of make, type, capacity, condition, speed of rotation, etc., the results of tests on one of the mixers shall apply to the others, subject to the approval of the Contracting Officer. All mixer performance (uniformity) testing shall be performed by the Contractor in accordance with COE CRD-C 55 and with paragraph titled TESTING AND INSPECTION FOR CONTRACTOR QUALITY CONTROL.

TABLE 4

UNIFORMITY REQUIREMENTS--STATIONARY MIXERS

Parameter	Regular Tests Allowable Maximum Range for Average of 3 Batches	Abbreviated Tests Allowable Maximum Range for 1 Batch
Unit weight of air-free mortar, lb/cubic ft	2.0	2.0
Air content, percent	1.0	--
Slump, inches	1.0 ~~25~~	--
Coarse aggregate, percent	6.0	6.0
Compressive strength at 7 days, percent	10.0	10.0
Water content, percent	1.5	--

b. Truck Mixers: Mixer performance (uniformity) tests for truck mixers shall be made by the Contractor in accordance with ASTM C 94/C 94M.

1.13.3 Transporting Equipment

Concrete shall be transported to the paving site in nonagitating equipment conforming to ASTM C 94/C 94M [in approved truck mixers designed with extra large blading and rear opening specifically for low slump concrete] or in approved agitators. All transporting equipment shall be designed and operated to deliver and discharge the required concrete mixture completely without segregation.

1.13.4 Transfer and Spreading Equipment

Equipment for transferring concrete from the transporting equipment to the paving lane in front of the paver shall be specially manufactured, self-propelled transfer equipment which will accept the concrete outside the paving lane and will transfer and spread it evenly across the paving lane in front of the paver and strike off the surface evenly to a depth which permits the paver to operate efficiently. The travelling surge hopper, if used shall be a specially

manufactured, self-propelled transfer-placer which will operate in front of the paver and accept the concrete from the transporting equipment outside the paving lane, store it as necessary, and feed it out evenly across the lane in front of the paver at a depth which permits the paver to operate efficiently. The capacity shall be such that concrete is always available in front of the paver, to prevent the need for stopping the paver. It shall be designed to always discharge the oldest concrete remaining in the hopper before the fresher concrete.

1.13.5 Paver-Finisher

The paver-finisher shall be a heavy-duty, self-propelled machine designed specifically for paving and finishing high quality pavement. The paver-finisher shall weigh at least 2200 lb. per foot of lane width, and shall be powered by an engine having at least 6.0 horsepower per foot of lane width. The paver-finisher shall spread, consolidate, and shape the plastic concrete to the desired cross section in one pass. The mechanisms for forming the pavement shall be easily adjustable in width and thickness and for required crown. In addition to other spreaders required by paragraph Transfer and Spreading Equipment, the paver-finisher shall be equipped with a full width knock-down auger or paddle mechanism, capable of operating in both directions, which will evenly spread the fresh concrete in front of the screed or extrusion plate. Immersion vibrators shall be gang mounted at the front of the paver on a frame equipped with suitable controls so that all vibrators can be operated at any desired depth within the slab or completely withdrawn from the concrete, as required. The vibrators shall be automatically controlled so that they will be immediately stopped as forward motion of the paver ceases. The spacing of the immersion vibrators across the paving lane shall be as necessary to properly consolidate the concrete, but the clear distance between vibrators shall not exceed 30 inches Spud vibrators shall operate at a frequency of not less than 8000 impulses per minuteand an amplitude of not less than 0.03 inch and tube vibrators at a frequency of not less than 5000 impulses per minute and an amplitude of not less than 0.03 inch as determined by COE CRD-C 521. The paver-finisher shall be equipped with a transversely oscillating screed or an extrusion plate to shape, compact, and smooth the surface and shall so finish the surface that no significant amount of hand finishing, except use of cutting straightedges, is required. The screed or extrusion plate shall be constructed to provide adjustment for crown in the pavement. The entire machine shall provide adjustment for variation in lane width or thickness and to prevent more than 8 inches of the screed or extrusion plate extending over previously placed concrete on either end when paving fill-in lanes. Machines that cause displacement of properly installed forms or cause ruts or indentations in the prepared underlying materials and machines that cause frequent delays due to mechanical failures shall be replaced as directed.

1.13.5.1 Paver-Finisher with Fixed Forms

The paver-finisher shall be equipped with wheels designed to keep it aligned with the forms and to spread the load so as to prevent deformation of the forms.

1.13.5.2 Slipform Paver-Finisher

The slipform paver-finisher shall be automatically controlled and crawler mounted with four padded tracks so as to be completely stable under all operating conditions. The paver-finisher shall finish the surface and edges so that no edge slump beyond allowable tolerance occurs. Horizontal alignment shall be electronically referenced to a taut wire guideline. Vertical alignment shall be electronically referenced on both sides of the paver to a taut wire guideline, to an approved laser control system, or, only where permitted by paragraph

Slipform Paving, to a ski operating on a completed lane. Suitable moving side forms shall be provided that are adjustable and will produce smooth, even edges, perpendicular to the top surface and meeting specification requirements for alignment and freedom from edge slump.

1.13.5.3 Longitudinal Mechanical Float

A longitudinal mechanical float shall be specially designed and manufactured to smooth and finish the pavement surface without working excess paste to the surface. It shall be rigidly attached to the rear of the paver-finisher or to a separate self-propelled frame spanning the paving lane. The float plate shall be at least 5 feet long by 8 inches wide and shall automatically be oscillated in the longitudinal direction while slowly moving from edge to edge of the paving lane, with the float plate in contact with the surface at all times.

1.13.5.4 Nonrotating Pipe Float

A pipe float if used, shall be a nonrotating pipe 6 to 10 inches in diameter and sufficiently long to span the full paving width when oriented at an angle of approximately 60 degrees with the centerline. The pipe float shall be mounted on a self-propelled frame that spans the paving lane. No means of applying water to the surface shall be incorporated in the pipe float.

1.13.5.5 Other Types of Finishing Equipment

Clary screeds or other rotating tube floats, or bridge deck finishers, shall not be allowed on the project. Concrete finishing equipment of types other than specified above may be demonstrated on a test section outside the production pavement if approved in writing. If the Contracting Officer's representative decides from evaluation of the test section that the equipment is better than the specified finishing equipment, its use will be permitted as long as it continues to perform better than the specified equipment.

1.13.6 Curing Equipment

Equipment for applying membrane-forming curing compound shall be mounted on a self-propelled frame that spans the paving lane. The reservoir for curing compound shall be constantly mechanically (not air) agitated during operation and shall contain means for completely draining the reservoir. The spraying system shall consist of a mechanically powered pump which will maintain constant pressure during operation, an operable pressure gauge, and either a series of spray nozzles evenly spaced across the lane to give uniformly overlapping coverage or a single spray nozzle which is mounted on a carriage which automatically traverses the lane width at a speed correlated with the forward movement of the overall frame. All spray nozzles shall be protected with wind screens. Any hand-operated sprayers allowed by paragraph Membrane Curing shall be compressed air supplied by a mechanical air compressor. If the curing machine fails to apply an even coating of compound at the specified rate, it shall immediately be replaced.

1.13.7 Texturing Equipment

Texturing equipment shall be as specified below. Before use, the texturing equipment shall be demonstrated on a test section, and the equipment shall be modified as necessary to produce the texture directed.

1.13.7.1 Fabric Drag

A fabric drag shall consist of a piece of material as long as the lane width securely attached to a separate wheel mounted frame spanning the paving lane or to one of the other similar pieces of equipment. Width of the material shall provide 12 to 18 inches dragging flat on the pavement surface. Length shall be at least equal to the width of the slab plus 24 inches. The material shall be clean, reasonably new burlap, completely saturated with water before attachment to the frame and always resaturated before start of use and kept clean and saturated during use. Burlap shall conform to AASHTO M 182, Class 3 or 4.

1.13.8 Sawing Equipment

Equipment for sawing joints and for other similar sawing of concrete shall be standard diamond-type concrete saws mounted on a wheeled chassis which can be easily guided to follow the required alignment. Blades shall be diamond tipped. If demonstrated to operate properly, abrasive blades may be used. Wheel saws shall be saws with large diameter tungsten carbide tipped blades mounted on a heavy-duty chassis which will produce a saw kerf at least 1 1/2 inch wide. All saws shall be capable of sawing to the full depth required.

1.13.9 Straightedge

The Contractor shall furnish and maintain at the job site, in good condition, one 12-foot straightedge for each paving train for testing the hardened portland cement concrete surfaces. These straightedges shall be constructed of aluminum or magnesium alloy and shall have blades of box or box-girder cross section with flat bottom, adequately reinforced to insure rigidity and accuracy. Straightedges shall have handles for operation on the pavement without bending over to pick up the straightedge.

1.13.10 Profilograph

The Contractor shall furnish a 25-foot profilograph for testing the finished pavement surface. The profilograph shall produce a record on tape of the results of testing the pavement surface and shall automatically mark the Profile Index of each section tested as well as indicate and measure each "must grind" point, all in accordance with CDT Test 526 and as required by paragraph Surface Smoothness.

2 PRODUCTS

2.1 CEMENTITIOUS MATERIALS

Cementitious materials shall be portland cement, or portland-cement in combination with pozzolan or ground granulated blast furnace slag and shall conform to appropriate specifications listed below. Temperature of cementitious materials as supplied to the project shall not exceed 150 degrees F.

2.1.1 Portland Cement

Portland cement shall conform to ASTM C 150, Type I or II low-alkali.

2.1.2 Pozzolan (Fly Ash and Silica Fume)

2.1.3 Fly Ash

Fly ash shall conform to ASTM C 618, Class F or C with the optional requirements in Table 1A, 2 and 2A and shall have a loss of ignition not exceeding 6 percent. Class F fly ash for use in mitigating alkali-aggregate reactivity shall have a Calcium Oxide (CaO) content of less than 8 percent.

2.2 AGGREGATES

In addition to the grading requirements specified for coarse aggregate and for fine aggregate, the combined aggregate grading shall meet the following requirements.

a. If necessary, a blending aggregate shall be used to meet the required combined grading. This blending aggregate shall be batched separately. The combined grading of all aggregates used, in the proportions selected, shall be computed on the basis of cumulative percent retained on each sieve specified for fine and coarse aggregate.

b. The materials selected and the proportions used shall be such that when the Coarseness Factor (CF) and the Workability Factor (W) are plotted on a diagram as described in d. below, the point thus determined shall fall within the parallelogram described therein.

c. The Coarseness Factor (CF) shall be determined from the following equation:

CF = (cumulative percent retained on the 3/8 in. sieve)(100)/(cumulative percent retained on the No. 8 sieve)

The Workability Factor (W) is defined as the cumulative percent passing the No. 8 sieve. However, W shall be adjusted, upwards only, by 2.5 percentage points for each 94 pounds of cementitious material per cubic yard greater than 64 pounds per cubic yard

d. A diagram shall be plotted using a rectangular scale with W on the Y-axis with units from 20 (bottom) to 45 (top), and with CF on the X-axis with units from 80 (left side) to 30 (right side). On this diagram a parallelogram shall be plotted with corners at the following coordinates (CF-75, W-28), (CF-75, W-40), (CF-45, W-32.5), and (CF-45, W-41). If the point determined by the intersection of the computed CF and W does not fall within the above parallelogram, the grading of each size of aggregate used and the proportions selected shall be changed as necessary.

e. In addition, the individual percent retained on each sieve shall be plotted for the combined aggregate grading, on either rectangular or semi-log graph paper. The graph shall show a relative smooth transition between coarse and fine aggregate and shall have no major valleys or peaks in the area smaller than the No. 8 sieve. If this plot does not meet the above criteria, the grading of each size aggregate used and the proportions selected shall be changed as necessary.

2.2.1 Coarse Aggregate

Coarse aggregate shall have a satisfactory service record of at least 5 years successful service in three paving projects or, if a new source is used, shall meet the requirements when tested for resistance to freezing and thawing.

2.2.1.1 Material Composition

Coarse aggregate shall consist of crushed gravel. Crushed gravel shall contain not less than 75 percent of crushed particles by mass in each sieve size, as determined by COE CRD-C 171. Reclaimed concrete pavement or granular base produced from required removal operations shall not be used for aggregate.

2.2.1.2 Quality

Aggregates as delivered to the mixers shall consist of clean, hard, uncoated particles meeting the requirements of ASTM C 33 and other requirements specified herein.

2.2.1.3 Particle Shape Characteristics

Particles of the coarse aggregate shall be generally spherical or cubical in shape. The quantity of flat and elongated particles in any size group shall not exceed 20 percent by weight as determined by COE CRD-C 119. A flat particle is defined as one having a ratio of width to thickness greater than 3; an elongated particle is one having a ratio of length to width greater than 3.

2.2.1.4 Size and Grading

The nominal maximum size of the coarse aggregate shall be 1.5 inches and shall meet the size groups below. When the nominal maximum coarse size is greater than 1 inch, the aggregates shall be furnished in two size groups as follows:

Nominal Maximum Size Inches	Size Group
3/4	ASTM C 33 --No.67 (No. 4 to 3/4 inch)
1-1/2	ASTM C 33 --No. 4 (3/4 to 1-1/2 inch)

The grading of the coarse aggregate within the separated size groups shall conform to the requirements of ASTM C 33, Sizes 67 and 4 as delivered to the mixer.

2.2.1.5 Deleterious Materials - Airfield Pavements

The amount of deleterious material in each sieve size of coarse aggregate shall not exceed the limits shown in Table 5 below, determined in accordance with the test methods shown.

TABLE 5

LIMITS OF DELETERIOUS MATERIALS IN COARSE AGGREGATE
FOR AIRFIELD PAVEMENTS

	Percentage by Mass
Clay lumps and friable particles (ASTM C 142)	0.2
Shale (a) (ASTM C 295)	0.1
Material finer than 0.075 mm (No. 200 sieve) (b) (ASTM C 117)	0.5
Lightweight particles (c) (ASTM C 123)	0.2
Clay ironstone (d) (ASTM C 295)	0.1
Chert and cherty stone (less than 2.40 Mg/cubic meter density SSD (2.40 Sp. Gr.)) (e) (ASTM C 295)	0.1
Claystone, mudstone, and siltstone (f) (ASTM C 295)	0.1
Shaly and argillaceous limestone (g) (ASTM C 295)	0.2
Other soft particles COE CRD-C 130	1.0
Total of all deleterious substances exclusive of material finer than 0.075 mm (No. 200 sieve)	1.0

a. Shale is defined as a fine-grained, thinly laminated or fissile sedimentary rock. It is commonly composed of clay or silt or both. It has been indurated by compaction or by cementation, but not so much as to have become slate.

b. Limit for material finer than 0.075 mm (No. 200 sieve) will be increased to 1.5 percent for crushed aggregates if the fine material consists of crusher dust that is essentially free from clay or shale.

c. The separation medium shall have a density of 2.0 Mg/cubic meter (Sp. Gr. of 2.0). This limit does not apply to coarse aggregate manufactured from blast-furnace slag unless contamination is evident.

d. Clay ironstone is defined as an impure variety of iron carbonate, iron oxide, hydrous iron oxide, or combinations thereof, commonly mixed with clay, silt, or sand. It commonly occurs as dull, earthy particles, homogeneous concretionary masses, or

hard-shell particles with soft interiors. Other names commonly used for clay ironstone are "chocolate bars" and limonite concretions.

e. Chert is defined as a rock composed of quartz, chalcedony or opal, or any mixture of these forms of silica. It is variable in color. The texture is so fine that the individual mineral grains are too small to be distinguished by the unaided eye. Its hardness is such that it scratches glass but is not scratched by a knife blade. It may contain impurities such as clay, carbonates, iron oxides, and other minerals. Other names commonly applied to varieties of chert are: flint, jasper, agate, onyx, hornstone, porcellanite, novaculite, sard, carnelian, plasma, bloodstone, touchstone, chrysoprase, heliotrope, and petrified wood. Cherty stone is defined as any type of rock (generally limestone) that contains chert as lenses and nodules, or irregular masses partially or completely replacing the original stone.

f. Claystone, mudstone, or siltstone, is defined as a massive fine-grained sedimentary rock that consists predominantly of indurated clay or silt without laminations or fissility. It may be indurated either by compaction or by cementation.

g. Shaly limestone is defined as limestone in which shale occurs as one or more thin beds or laminae. These laminae may be regular or very irregular and may be spaced from a few inches down to minute fractions of an inch. Argillaceous limestone is defined as a limestone in which clay minerals occur disseminated in the stone in the amount of 10 to 50 percent by weight of the rock; when these make up from 50 to 90 percent, the rock is known as calcareous (or dolomitic) shale (or claystone, mudstone, or siltstone).

2.2.1.6 Testing Sequence, Deleterious Materials

The size of the sample shall be at least 200 pounds for the 3/4 to 1-1/2 inch size and 25 pounds for the No. 4 to 3/4 inch coarse aggregate and 10 pounds for the fine aggregate. The Contractor shall provide facilities for the ready procurement of representative test samples. Samples shall be taken and tested by and at the expense of the Contractor, using appropriate Corps of Engineers laboratory and ASTM test methods. Additional tests and analyses of aggregates at various stages in the processing and handling operations may be made by the Government at the discretion of the Contracting Officer. Such Government testing will not relieve the Contractor of any of its testing responsibilities. The testing procedure on each sample of coarse aggregate for compliance with limits on deleterious materials shall be as follows:

Step 1: Test approximately one-fifth of sample for material finer than the No. 200 sieve.

Step 2: Wash off material finer than No. 200 sieve from the remainder of the sample and recombine the remainder with material retained on the No. 200 sieve from Step 1.

Step 3: Test remaining full sample for clay lumps and friable particles and remove.

Step 4: Test remaining full sample for lightweight particles and remove, and then for chert and/or cherty stone with SSD density of less than 2.40 Mg/cubic meter (Sp. Gr. 2.40) and remove.

Step 5: Test remaining sample for clay-ironstone, shale, claystone, mudstone, siltstone, shaly and/or argillaceous limestone, and remove.

Step 6: Test approximately one-fifth of remaining full sample for other soft particles.

Determination of deleterious materials listed in Steps 4 and 5 shall be performed by an individual specifically trained in petrographic identification. The individual selected to perform the identification of these deleterious materials shall be subject to approval and, at least 10 days before any individual is proposed to commence this type of work, the Contractor shall submit a written resume of the individual's training and experience for approval by the Contracting Officer. The Contractor will not be entitled to any extension of time or additional payment due to any delays caused by the testing, evaluation, or personnel requirements.

2.2.1.7 Resistance to Freezing and Thawing

Coarse aggregate not having a satisfactory demonstrable service record shall have a durability factor of 50 or more when subjected to freezing and thawing in concrete in accordance with COE CRD-C 114.

2.2.1.8 Resistance to Abrasion

Coarse aggregate shall not show more than 40 percent loss when subjected to the Los Angeles abrasion test in accordance with ASTM C 131.

2.2.1.9 Alkali-Aggregate Reactivity

Fine and coarse aggregates to be used in all concrete shall be evaluated and tested by the Contractor for alkali-aggregate reactivity in accordance with ASTM C 1260. The Contractor is advised that many local aggregate sources have tested positive for alkali-aggregate reactivity in the past. Both the coarse aggregate size groups shall be tested if from different sources. Test results shall have a measured expansion equal to or less than 0.08 percent at 16 days. Should the test data indicate an expansion greater than 0.08 percent, the aggregate(s) shall be rejected, or additional testing, using a modified version of ASTM C 1260 shall be performed by the Contractor as described below. ASTM C 1260 shall be modified as follows to include one of the following options:

a. Utilize the Contractor's proposed low alkali portland cement and Class "F" fly ash in combination for the test proportioning. Class "F" fly ash shall contain less than 8 percent Calcium Oxide (CaO) and shall be used in the range of 25 percent to 35 percent of the total cementitious material by mass. The quantity shall be determined that will meet all the requirements of these specifications and that which will lower the expansion equal to or less than 0.08 percent at 16 days.

b. Utilize the Contractor's proposed low alkali portland cement and ground gransulated blast furnace (GGBF) slag in combination for the test proportioning. GGBF slag shall be used in the range of 40 percent to 50 percent of the total cementitious material by mass. The quantity shall be determined that will meet all the requirements of these specification and that which will lower the expansion equal to or less than 0.08 percent at 16 days.

If any of the above options does not lower the expansion equal to or less than 0.08 percent at 16 days, the aggregates(s) shall be rejected and the Contractor shall submit new aggregate

sources for retesting. The results of the testing shall be submitted to the Contracting Officer for evaluation and acceptance.

2.2.2 Fine Aggregate

Fine aggregate shall have a service record of at least 5 years satisfactory service in three paving projects or, if a new source is used, shall meet the requirements for resistance to freezing and thawing.

2.2.2.1 Composition

Fine aggregate shall consist of natural sand, manufactured sand, or a combination of the two, and shall be composed of clean, hard, durable particles. Irrespective of the source from which it is obtained, all fine aggregate shall be composed of clean, hard, durable particles meeting the requirements of ASTM C 33. Each type of fine aggregate shall be stockpiled and batched separately. Any degree of contamination will be cause for the rejection of the entire stockpile.

2.2.2.2 Particle Shape

Particles of the fine aggregate shall be generally spherical or cubical in shape.

2.2.2.3 Grading

Grading of the fine aggregate, as delivered to the mixer, shall conform to the requirements of ASTM C 33. In addition, the fine aggregate, as delivered to the mixer, shall have a fineness modulus of not less than 2.50 nor more than 3.00. The grading of the fine aggregate also shall be controlled so that the fineness moduli of at least nine of every set of ten consecutive samples of the fine aggregate, as delivered to the mixer, will not vary more than 0.15 from the average fineness moduli of all samples previously taken. The fineness modulus shall be determined by COE CRD-C 104.

2.2.2.4 Deleterious Material

The amount of deleterious material in the fine aggregate shall not exceed the following limits by mass:

Material	Percentage by Mass
Clay lumps and friable particles ASTM C 142	1.0
Material finer than 0.075 mm (No. 200 sieve) ASTM C 117	3.0
Lightweight particles ASTM C 123 using a medium with a density of 2.0 Mg/cubic meter (Sp. Gr. of 2.0))	0.5
Total of all above	3.0

2.2.2.5 Resistance to Freezing and Thawing

Fine aggregate not having a satisfactory demonstrable service record shall have a durability factor of 50 or more when subjected to freezing and thawing in concrete in accordance with COE CRD-C 114.

2.2.2.6 Alkali-Aggregate Reactivity

Fine aggregates shall be tested as required for coarse aggregates.

2.3 CHEMICAL ADMIXTURES

2.3.1 Air-Entraining Admixtures

The air-entraining admixture shall conform to ASTM C 260 and shall consistently entrain the air content in the specified ranges under field conditions. The air-entraining admixture shall be in a solution of suitable concentration for field use.

2.3.2 Accelerator

An accelerator shall be used only when specified in paragraph SPECIFIED CONCRETE STRENGTH AND OTHER PROPERTIES and shall not be used to reduce the amount of cementitious material used. Accelerator shall conform to ASTM C 494, Type C. Calcium chloride and admixtures containing calcium chloride shall not be used.

2.3.3 Retarder

A retarding admixture shall meet the requirements of ASTM C 494, Type B, except that the 6-month and 1-year compressive strength tests are waived. The use of the admixture is at the option of the Contractor, but shall not be used to reduce the amount of cementitious material.

2.3.4 Water-Reducer

A water-reducing admixture shall meet the requirements of ASTM C 494, Type A or D except that the 6-month and 1-year compressive strength tests are waived. The admixture may be added to the concrete mixture only when its use is approved or directed, and only when it has been used in mixture proportioning studies to arrive at approved mixture proportions.

2.4 CURING MATERIALS

2.4.1 Membrane Forming Curing Compound

Membrane forming curing compound shall be a white pigmented compound conforming to COE CRD-C 300.

2.4.2 Burlap

Burlap used for curing shall conform to AASHTO M 182, Class 3 or 4. Materials shall be new or shall be clean materials never used for anything other than curing concrete.

2.4.3 Impervious Sheet Materials

Impervious sheet materials shall conform to ASTM C 171, type optional, except polyethylene sheet shall not be used.

2.5 WATER

Water for mixing and curing shall be fresh, clean, potable, and free of injurious amounts of oil, acid, salt, or alkali, except that non-potable water may be used if it meets the requirements of COE CRD-C 400.

2.6 JOINT MATERIALS

2.6.1 Expansion Joint Material

Expansion joint filler shall be a preformed material conforming to ASTM D 1752. Expansion joint filler shall be 3/4 inch thick.

2.6.2 Slip Joint Material

Slip joint material shall be 1/4 inch thick expansion joint filler conforming to ASTM D 1752 .

2.7 REINFORCING

All reinforcement shall be free from loose, flaky rust, loose scale, oil, grease, mud, or other coatings that might reduce the bond with concrete. Removal of thin powdery rust and tight rust is not required. However, reinforcing steel which is rusted to the extent that it does not conform to the required dimensions or mechanical properties shall not be used.

2.7.1 Welded Wire Fabric

Welded steel wire fabric shall conform to ASTM A 185.

2.7.2 Deformed Wire Fabric

Welded deformed steel wire fabric shall conform to ASTM A 497.

2.8 DOWELS AND TIE BARS

2.8.1 Dowels

Dowels shall be single piece bars fabricated or cut to length at the shop or mill before delivery to the site. Dowels shall be free of loose, flaky rust and loose scale and shall be clean and straight. Dowels may be sheared to length provided that the deformation from true shape caused by shearing does not exceed 0.04 inch on the diameter of the dowel and does not extend more than 0.04 inch from the end of the dowel. Dowels shall be plain (non-deformed) steel bars conforming to ASTM A 615/A 615M, Grade 40 or 60; ASTM A 616/A 616M, Grade 50 or 60; or ASTM A 617/A 617M, Grade 40 or 60; or shall be steel pipe conforming to ASTM A 53, extra strong, as indicated. If split dowels are proposed for use, a complete description of the materials and installation procedures shall be submitted for approval at least 15 days before start of construction. Paint for dowels shall conform to MIL-DTL-24441/20A.

2.9 EPOXY RESIN

All epoxy-resin materials shall be two-component materials conforming to the requirements of ASTM C 881, Class as appropriate for each application temperature to be encountered, except that in addition, the materials shall meet the following requirements:

a. Material for use for embedding dowels and anchor bolts shall be Type IV, Grade 3.

b. Material for use as patching materials for complete filling of spalls, wide cracks, and other voids and for use in preparing epoxy resin mortar shall be Type III, Grade as approved.

c. Material for use for injecting cracks shall be Type IV, Grade 1.

d. Material for bonding freshly mixed portland cement concrete or mortar or freshly mixed epoxy resin concrete or mortar to hardened concrete shall be Type V, Grade as approved.

2.10 SPECIFIED CONCRETE STRENGTH AND OTHER PROPERTIES

2.10.1 Specified Flexural Strength

Specified flexural strength, R, for concrete is 650 psi at 28 days, as determined by tests made in accordance with ASTM C 78 of beams fabricated and cured in accordance with ASTM C 192/C 192M or as determined by equivalent flexural strength for acceptance as specified in paragraph, Flexural Strength. Maximum allowable water-cementitious material ratio is 0.45. The water-cementitious material ratio will be the equivalent water-cement ratio as determined by conversion from the weight ratio of water to cement plus pozzolan, silica fume, and ground granulated blast furnace slag by the mass equivalency method described in ACI 211.1. The concrete shall be air-entrained with a total air content of 6 plus or minus 1.5 percentage points, at the point of placement. Air content shall be determined in accordance with ASTM C 231. The maximum allowable slump of the concrete at the point of placement shall be 2 inches for pavement constructed with fixed forms. For slipformed pavement, at the start of the project, the Contractor shall select a maximum allowable slump which will produce in-place pavement meeting the specified tolerances for control of edge slump.

2.10.2 Concrete Temperature

The temperature of the concrete as delivered shall conform to the requirements of paragraphs, Paving in Hot Weather and Paving in Cold Weather. Temperature of concrete shall be determined in accordance with ASTM C 1064/C 1064M.

2.10.3 Concrete Strength for Final Acceptance

The strength of the concrete will be considered acceptable when the average equivalent 28-day Flexural strengths for each lot are above the'Specified Flexural Strength' as determined by correlation with 14-day compressive strength tests specified in paragraph MIXTURE PROPORTIONS BY CONTRACTOR for 28-day flexural Strength, and no individual set (2 cylinders per sublot) in the lot are 25 psi or more below the equivalent 'Specified Flexural Strength'. If any lot or sublot, respectively, fails to meet the above criteria, the lot or sublot shall be removed and replaced at no additional cost to the Government. This is in addition to

and does not replace the average strength required for day-to-day CQC operations as specified in paragraph Average Flexural Strength Required for Mixtures.

2.11 MIXTURE PROPORTIONS BY CONTRACTOR

2.11.1 Composition

Concrete shall be composed of cementitious material, water, fine and coarse aggregates, and admixtures. The cementitious material shall be portland cement, or only portland cement in combinations with pozzolan or ground granulated blast-furnace slag. Pozzolan, if used with non alkali-reactive aggregates, shall consist of not less than 15 percent of the cementitious material by mass and not more than 35 percent. If Class F fly ash or GGBF slag is required to mitigate potential alkali-aggregate reactivity, the percentage by mass determined from the modified ASTM C 1260 testing shall be used in the mixture proportioning studies. The total cementitious material content shall be at least 517 lb./cu. yd. Admixtures shall consist of air entraining admixture and may also include, as approved, water-reducing admixture. If water-reducer is used, it shall be used only at the dosage determined during mixture proportioning studies. High range water-reducing admixtures and admixtures to produce flowable concrete shall not be used.

2.11.2 Concrete Proportioning Studies, Pavement Concrete

Trial design batches, mixture proportioning studies, and testing requirements shall be the responsibility of the Contractor. Mixture proportioning studies shall be performed by a commercial laboratory, inspected by the Government, and approved in writing. The laboratory performing the mixture proportioning shall conform with ASTM C 1077. Strength requirements during mixture proportioning studies shall be based on flexural strength as determined by test specimens fabricated in accordance with ASTM C 192/C 192M and tested in accordance with ASTM C 78. Samples of all materials used in mixture proportioning studies shall be representative of those proposed for use on the project and shall be accompanied by the manufacturer's or producer's test reports indicating compliance with these specifications. Trial mixtures having proportions, slumps, and air content suitable for the work shall be based on methodology described in ACI 211.1, modified as necessary to accommodate flexural strength.

2.11.2.1 Water-Cement Ratio

At least three different water-cement ratios, which will produce a range of strength encompassing that required on the project, shall be used. The maximum allowable water-cement ratio required in paragraph Maximum Water-Cement Ratio will be the equivalent water-cement ratio as determined by conversion from the mass ratio of water to cement plus pozzolan, silica fume, and ground granulated blast furnace (GGBF) slag by the weight equivalency method as described in ACI 211.1. In the case where silica fume or GGBF slag is used, the mass of the silica fume and GGBF slag shall be included in the equations in ACI 211.1 for the term P, which is used to denote the mass of pozzolan. Laboratory trial mixtures shall be proportioned for maximum permitted slump and air content.

2.11.2.2 Trial Mixture Studies

Separate sets of trial mixture studies shall be made for each combination of cementitious materials and each combination of admixtures proposed for use. No combination of either

shall be used until proven by such studies, except that, if approved in writing and otherwise permitted by these specifications, an accelerator or a retarder may be used without separate trial mixture study. Separate trial mixture studies shall also be made for concrete for any placing method proposed which requires special properties. The temperature of concrete in each trial batch shall be reported. Each mixture shall be designed to promote easy and suitable concrete placement, consolidation and finishing, and to prevent segregation and excessive bleeding. Concrete proportioning studies shall be performed using the following procedures:

2.11.2.3 Mixture Proportioning for 28-day Flexural Strength

The following step by step procedure shall be followed:

a. Fabricate all beams and cylinders for each mixture from the same batch or blend of batches. Fabricate and cure all beams and cylinders in accordance with ASTM C 192/C 192M, using 6 x 6 inch beams and 6 x 12 inch cylinders.

b. Test beams in accordance with ASTM C 78, cylinders in accordance with ASTM C 39.

c. Fabricate and cure test beams from each mixture for 7, 14, and 28-day flexural tests; 6 beams to be tested per age.

d. Fabricate and cure test cylinders from each mixture for 7, 14, and 28-day compressive strength tests; 6 cylinders to be tested per age.

e. Using the average strength for each w/c at each age, plot all results from each of the three mixtures on separate graphs for w/c versus:

7-day flexural strength
14-day flexural strength
28-day flexural strength

7-day compressive strength
14-day compressive strength
28-day compressive strength

f. From these graphs select a w/c that will produce a mixture giving a 28-day flexural strength equal to the required strength determined in accordance with paragraph "Average Flexural Strength Required for Mixtures".

g. Using the above selected w/c, select from the graphs the expected 7, 14, and 28-day flexural strengths and the expected 7, 14, and 28-day compressive strengths for the mixture.

h. From the above expected strengths for the selected mixture determine the following Correlation Ratios:

(1) Ratio of the 14-day compressive strength of the selected mixture to the 28-day flexural strength of the mixture (for acceptance).

(2) Ratio of the 7-day compressive strength of the selected mixture to the 28-day flexural strength of the mixture (for CQC control).

i. If there is a change in materials, additional mixture design studies shall be made using the new materials and new Correlation Ratios shall be determined.

j. No concrete pavement shall be placed until the Contracting Officer has approved the Contractor's mixture proportions.

2.11.3 Contractor Quality Control for Average Flexural Strength

The Contractor's day to day production shall be Controlled (CQC) in accordance with the criteria herein, in the following subparagraphs, and in paragraph. 'Concrete Strength Testing for CQC'. This is entirely different from the acceptance requirements of paragraph 'Concrete Strength for Final Acceptance', and it is mandatory that both sets of requirements must be met. If at any time, the 'equivalent average 28-day flexural strength', for any lot, as determined by correlation with results of 7-day compressive test specimens, is 69 psi or more below the 'required equivalent average 28-day flexural strength', as specified below, the paving operation shall be stopped and the Contractor shall take necessary steps to improve the mixture proportioning, materials, or the batching and mixing to increase the strength. The paving operations shall not recommence until the Contracting Officer has approved the Contractor's Proposed changes in writing.

2.11.3.1 Average CQC Flexural Strength Required for Mixtures

In order to ensure meeting, the strength requirements specified in paragraph SPECIFIED CONCRETE STRENGTH AND OTHER PROPERTIES, during production, the mixture proportions selected during mixture proportioning studies and used during construction shall produce a required average CQC flexural strength exceeding the specified strength, R, by the amount indicated below. This required average CQC flexural strength, Ra, will be used only for CQC operations as specified in paragraph TESTING AND INSPECTION FOR CONTRACTOR QUALITY CONTROL and as specified in the previous paragraph. During production, the required Ra shall be adjusted (increased or decreased), as appropriate and as approved, based on the standard deviation of equivalent 28-day strengths being attained during paving.

a. From Previous Test Records: Where a concrete production facility has previous test records, a standard deviation shall be established in accordance with the applicable provisions of ACI 214.3R. Test records from which a standard deviation is calculated shall represent materials, quality control procedures, and conditions similar to those expected, shall represent concrete produced to meet a specified flexural strength or strengths within 150 psi of the 28-day flexural strength specified for the proposed work, and shall consist of at least 30 consecutive tests. A strength test shall be the average of the strengths of two specimens made from the same sample of concrete and tested at 90 days. Required average CQC flexural strength, Ra, used as the basis for selection of concrete proportions shall be the value from the equation that follows, using the standard deviation as determined above:

$$Ra = R + 1.34S$$

Where: S = standard deviation
R = specified flexural strength
Ra = required average flexural strength

Where a concrete production facility does not have test records meeting the requirements above but does have a record based on 15 to 29 consecutive tests, a standard deviation shall be established as the product of the calculated standard deviation and a modification factor from the following table:

NUMBER OF TESTS	MODIFICATION FACTOR FOR STANDARD DEVIATION
15	1.16
20	1.08
25	1.03
30 or more	1.00

b. Without Previous Test Records: When a concrete production facility does not have sufficient field strength test records for calculation of the standard deviation, the required average strength, Ra, shall be determined by adding 15 percent to the specified flexural strength, R.

3 EXECUTION

3.1 PREPARATION FOR PAVING

Before commencing paving, the following shall be performed. Surfaces to receive concrete shall be prepared as specified below. If used, forms shall be in place, cleaned, coated, and adequately supported. Any reinforcing steel needed shall be at the paving site. All transporting and transfer equipment shall be ready for use, clean, and free of hardened concrete and foreign material. Equipment for spreading, consolidating, screeding, finishing, and texturing concrete shall be at the paving site, clean and in proper working order. All equipment and material for curing and for protecting concrete from weather or mechanical damage shall be at the paving site, in proper working condition, and in sufficient amount for the entire placement. When hot, windy conditions during paving appear probable, equipment and material shall be at the paving site to provide windbreaks, shading, fogging, or other action to prevent plastic shrinkage cracking or other damaging drying of the concrete.

3.2 CONDITIONING OF UNDERLYING MATERIAL

3.2.1 General Procedures

Underlying material (base course) upon which concrete is to be placed shall be clean, damp, and free from debris, waste concrete or cement, frost, ice, and standing or running water. Prior to setting forms or placement of concrete, the underlying material shall be well drained and shall have been satisfactorily graded and uniformly compacted in accordance with the applicable Section of these specifications. The surface of the subgrade or base course shall be tested as to crown, elevation, and density in advance of setting forms or of concrete placement using slip-form techniques. High areas shall be trimmed to proper elevation. Low areas shall be filled and compacted to a condition similar to that of surrounding grade, or filled with concrete monolithically with the pavement. Where low areas are filled with concrete, the areas shall be marked, as approved, and cores for thickness determinations as required by

paragraph, Flexural Strength and Thickness shall not be drilled in those areas. Any underlying material disturbed by construction operations shall be reworked and recompacted to specified density immediately in front of the paver. If a slipform paver is permitted and is used, the same underlying material under the paving lane shall be continued beyond the edge of the lane a sufficient distance and shall be thoroughly compacted and true to grade to provide a suitable trackline for the slipform paver and firm support for the edge of the paving lane. Where an open-graded granular base is required under the concrete, the Contractor shall select paving equipment and procedures which will operate properly on the base course without causing displacement or other damage.

3.2.2 Traffic on Underlying Material

After the underlying material has been prepared for concrete placement, no equipment shall be permitted thereon. Subject to specific approval, crossing of the prepared subgrade or base course at specified intervals for construction purposes may be permitted, provided rutting or indentations do not occur; however, if traffic has been allowed to use the prepared subgrade or base course, the surface shall be reworked and reprepared to the satisfaction of the Contracting Officer before concrete is placed.

3.3 WEATHER LIMITATIONS

3.3.1 Placement and Protection During Inclement Weather

The Contractor shall not commence placing operations when heavy rain or other damaging weather conditions appear imminent. At all times when placing concrete, the Contractor shall maintain on-site sufficient waterproof cover and means to rapidly place it over all unhardened concrete or concrete that might be damaged by rain. Placement of concrete shall be suspended whenever rain or other damaging weather commences to damage the surface or texture of the placed unhardened concrete, washes cement out of the concrete, or changes the water content of the surface concrete. All unhardened concrete shall be immediately covered and protected from the rain or other damaging weather. Any pavement damaged by rain or other weather shall be completely removed and replaced at the Contractor's expense as specified in paragraph, Repair, Removal, Replacement of Slabs.

3.3.2 Paving in Hot Weather

When the ambient temperature during paving is expected to exceed 90 degrees F the concrete shall be properly placed and finished in accordance with procedures previously submitted and as specified herein. The concrete temperature at time of delivery to the forms shall not exceed the temperature shown in the table below when measured in accordance with ASTM C 1064/C 1064M. Cooling of the mixing water or aggregates or placing in the cooler part of the day may be required to obtain an adequate placing temperature. An approved retarder may be used to facilitate placing and finishing. Steel forms and reinforcing shall be cooled as approved prior to concrete placement when steel temperatures are greater than 120 degrees F. Transporting and placing equipment shall be cooled or protected if necessary to maintain proper concrete-placing temperature. Concrete shall be placed continuously and rapidly at a rate of not less than 100 feet of paving lane per hour. The finished surfaces of the newly laid pavement shall be kept damp by applying a fog spray (mist) with approved spraying equipment until the pavement is covered by the curing medium. If necessary, wind screens shall be provided to protect the concrete from an evaporation rate

in excess of 0.2 lb./square foot per hour, as determined by method shown in Figure 2.1.5 of ACI 305R.

Maximum Allowable Concrete Placing Temperature

Relative Humidity, Percent, During Time of Concrete Placement	Maximum Allowable Concrete Temperature in Degrees F
Greater than 60	90
40-60	85
Less than 40	80

3.3.3 Prevention of Plastic Shrinkage Cracking

During hot weather with low humidity, and particularly with appreciable wind, the Contractor shall develop and institute measures to prevent plastic shrinkage cracks from developing. Particular care shall be taken if plastic shrinkage cracking is potentially imminent and especially if it has developed during a previous placement. Periods of high potential for plastic shrinkage cracking can be anticipated by use of Fig. 2.1.5 of ACI 305R. In addition to the protective measures specified in the previous paragraph, the concrete placement shall be further protected by erecting shades and windbreaks and by applying fog sprays of water, sprinkling, ponding, or wet covering. When such water treatment is stopped, curing procedures shall be immediately commenced. Plastic shrinkage cracks that occur shall be filled by injection of epoxy resin as directed, after the concrete hardens. Plastic shrinkage cracks shall never be troweled over or filled with slurry.

3.3.4 Paving in Cold Weather

Special protection measures, as submitted and approved, and as specified herein, shall be used if freezing temperatures are anticipated before the expiration of the specified curing period. The ambient temperature of the air at the placing site and the temperature of surfaces to receive concrete shall be not less 40 degrees F. However, placement may begin when both the ambient temperature and the temperature of the underlying material are at least 35 debrees F and rising. When the ambient temperature is less than 50 degrees F the temperature of the concrete when placed shall be not less than 50 degrees F nor more than 75 degrees F. Heating of the mixing water or aggregates will be required to regulate the concrete placing temperature. Materials entering the mixer shall be free from ice, snow, or frozen lumps. Salt, chemicals or other materials shall not be incorporated in the concrete to prevent freezing. Upon written approval, chemical admixture conforming to ASTM C 494 Type C or E may be used provided it contains no calcium chloride. Calcium chloride shall not be used at any time. Covering and other means shall be provided for maintaining the concrete at a temperature of at least 50 degrees F for not less than 72 hours after placing, and at a temperature above freezing for the remainder of the curing period. Pavement damaged by freezing shall be completely removed and replaced at the Contractor's expense as specified in paragraph REPAIR, REMOVAL, REPLACEMENT OF SLABS.

3.4 CONCRETE PRODUCTION

Batching, mixing, and transporting equipment shall have a capacity sufficient to maintain a continuous, uniform forward movement of the paver of not less than 2.5 feet per minute. Concrete shall be deposited in front of the paver within 45 minutes from the time cement has been charged into the mixing drum, except that if the ambient temperature is above 90

degrees F the time shall be reduced to 30 minutes. No water shall be added to the concrete after it is batched except that, if truck mixers are permitted, water may be added at the paving site to adjust the slump as approved, provided the maximum allowable w/c is not exceeded. Such water shall be injected under pressure as described in subparagraph, Truck Mixers. Every load of concrete delivered to the paving site shall be accompanied by a batch ticket from the operator of the batching plant. Tickets shall be on approved forms and shall show at least the mass, or volume, of all ingredients in each batch delivered, the water meter and revolution meter reading on truck mixers and the time of day. Tickets shall be delivered to the placing foreman who shall keep them on file and deliver them to the Government weekly.

3.4.1 Batching and Mixing Concrete

The batching and mixing equipment and the operation thereof shall conform to the requirements of paragraph EQUIPMENT and as specified herein. All equipment shall be kept clean and in operable condition at all times. Scale pivots and bearings shall be kept clean and free of rust. Any equipment which fails to perform as specified shall immediately be removed from use until properly repaired and adjusted, or replaced.

3.4.2 Transporting and Transfer - Spreading Operations

The transporting and transfer equipment and the operation thereof shall conform to the requirements of paragraph EQUIPMENT and as specified herein. All equipment shall be kept clean and in operable condition at all times. Non-agitating equipment shall be used only on smooth roads and for haul time less than 15 minutes at all times during the work day. No transporting equipment shall be allowed to operate on the prepared and compacted underlying material in front of the paver-finisher. An approved transfer spreader may be used to transfer the concrete from hauling equipment outside the paving lane and to spread it evenly and strike it off to approximate grade in front of the paver-finisher. If a transfer spreader is not used, a travelling surge hopper shall be used to accept the concrete from the transporting equipment, store it as necessary, and feed it evenly across the paving lane at a depth which permits the paver to operate efficiently and at a rate that permits the paver to have a continuous forward movement. Concrete shall be deposited as close as possible to its final position in the paving lane. All equipment shall be operated to discharge and transfer concrete without segregation. In no case shall dumping of concrete in discrete piles be permitted. No transfer or spreading operation which requires the use of front-end loaders, dozers, or similar equipment to distribute the concrete will be permitted. All batching and mixing, transporting, transferring, paving, and finishing shall be properly coordinated and controlled such that the paver-finisher has a continuous forward movement at a reasonably uniform speed from beginning to end of each paving lane, except for inadvertent equipment breakdown. Failure to achieve this shall require the Contractor to halt operations, regroup, and modify operations to achieve this requirement.

3.5 PAVING

3.5.1 General Requirements

The paving and finishing equipment and the operation thereof shall conform to the requirements of paragraph EQUIPMENT and as specified herein. All equipment shall be kept clean and properly operable at all times. Pavement shall be constructed with paving and finishing equipment utilizing rigid fixed forms or by use of slipform paving equipment. Paving and finishing equipment and procedures shall be capable of constructing paving lanes of the

required width at a rate of at least 100 feet of paving lane per hour on a routine basis. Paving equipment and its operation shall be controlled, and coordinated with all other operations, such that the paver-finisher has a continuous forward movement, at a reasonably uniform speed, from beginning to end of each paving lane, except for inadvertent equipment breakdown. Workmen with foreign material on their footwear or construction equipment that might deposit foreign material shall not be permitted to walk or operate in the plastic concrete.

3.5.2 Consolidation

Concrete shall be consolidated with the specified type of lane-spanning, gang-mounted, mechanical, immersion type vibrating equipment mounted in front of the paver, supplemented, in rare instances as specified, by hand-operated vibrators. Gang-mounted vibrator spuds shall be spaced so as to thoroughly consolidate the entire paving lane, but not more than 30 inch spacing, and with the outside vibrators not more than 12 inches from the edge of the lane. The vibrators shall be inserted into the concrete to a depth that will provide the best full-depth consolidation but not closer to the underlying material than 2 inches. The vibrators or any tamping units in front of the paver shall be automatically controlled so that they shall be stopped immediately as forward motion ceases. Excessive vibration shall not be permitted. If the vibrators cause visible tracking in the paving lane, the paving operation shall be stopped and equipment and operations modified to prevent it. Concrete in small, odd-shaped slabs or in isolated locations inaccessible to the gang-mounted vibration equipment shall be vibrated with an approved hand-operated immersion vibrator. Vibrators shall not be used to transport or spread the concrete. Hand-operated vibrators shall not be operated in the concrete at one location for more than 20 seconds. For each paving train, at least one additional vibrator spud, or sufficient parts for rapid replacement and repair of vibrators shall be maintained at the paving site at all times. Any evidence of inadequate consolidation (honeycomb along the edges, large air pockets, or any other evidence) shall require the immediate stopping of the paving operation and approved adjustment of the equipment or procedures.

3.5.3 Operation

When the paver approaches a header at the end of a paving lane, a sufficient amount of concrete shall be maintained ahead of the paver to provide a roll of concrete which will spill over the header. The amount of extra concrete shall be sufficient to prevent any slurry that is formed and carried along ahead of the paver from being deposited adjacent to the header. The spud vibrators in front of the paver shall be brought as close to the header as possible before they are lifted. Additional consolidation shall be provided adjacent to the headers by hand-manipulated vibrators. When the paver is operated between or adjacent to previously constructed pavement (fill-in lanes), provisions shall be made to prevent damage to the previously constructed pavement. Transversely oscillating screeds and extrusion plates shall overlap the existing pavement the minimum possible, but in no case more than 8 inches. These screeds or extrusion plates shall be electronically controlled from the previously placed pavement so as to prevent them from applying pressure to the existing pavement and to prevent abrasion of the pavement surface. The overlapping area of existing pavement surface shall at all times be kept completely free of any loose or bonded foreign material as the paver-finisher operates across it. When the paver travels on existing pavement, approved provisions shall be made to prevent damage to the existing pavement. Pavers using transversely oscillating screeds shall not be used to form fill-in lanes that have widths less than a full width for which the paver was designed or adjusted.

3.5.4 Required Results

The paver-finisher, and its gang-mounted vibrators, together with its operating procedures shall be adjusted and operated and coordinated with the concrete mixture being used to produce a thoroughly consolidated slab throughout, true to line and grade within specified tolerances. The screed or the extrusion plate shall be properly adjusted to produce a pavement surface true to line and grade. Any necessary adjustment to compensate for surging behind the screed or for inadequate height of surface after paving shall be carefully made and checked frequently. The paver-finishing operation shall produce a surface finish free of irregularities, tears, voids of any kind, and any other discontinuities. It shall produce only a very minimum of paste at the surface; never more than 3/32-inch cover over the top layer of coarse aggregate. The paver-finisher shall make only one pass across the pavement; multiple passes will not be permitted. The equipment and its operation shall produce a finished surface requiring no hand finishing other than the use of cutting straightedges, except in very infrequent instances. If any equipment or operation fails to produce the above results, the paving shall be stopped, the equipment shall be replaced or properly adjusted, the operation shall be appropriately modified, or the mixture proportions modified, in order to produce the required results before recommencing paving. No water, other than true fog sprays (mist) as specified in paragraph, Prevention of Plastic Shrinkage Cracking, shall be applied to the concrete or the concrete surface during paving and finishing.

3.5.5 Fixed Form Paving

Paving equipment for fixed-form paving and the operation thereof shall conform to the requirements of paragraph EQUIPMENT, all requirements specified above under paragraph PAVING and as specified herein.

3.5.5.1 Forms for Fixed-Form Paving

a. Forms shall be steel, except that wood forms may be used for curves having a radius of 150 feet or less, and for fillets. Forms shall be equal in depth to the edge thickness of the slab as shown on the drawings. Forms shall be in one piece for the full depth required, except as permitted below. Under no conditions shall forms be adjusted by filling or excavating under the forms to an elevation other than the bottom of the pavement slab. Where the project requires several different slab thicknesses, forms may be built up with metal or wood to provide an increase in depth of not more than 25 percent. The required form depth may be obtained by securely bolting or welding to the bottom of the form a tubular metal section of the proper thickness or by securely bolting wood planks to the bottom of the form. The tubular metal section or wood planks shall completely cover the underside of the base of the form and shall extend beyond the edge of the base a sufficient distance to provide the necessary stability. The base width of the one-piece form, or built-up form, shall be not less than eight-tenths of the vertical height of the form, except that forms 8 inches or less in vertical height shall have a base width not less than the vertical height of the form. Forms shall not be built-up by adding to the top. The top surface of each form section shall not vary more than 1/16 inch in 12 feet from a true line. The face of the form shall not vary more than 3/16 inch in 12 feet from a true plane. Forms with battered top surfaces or distorted faces or bases shall be removed from the project. Where keyway forms are required, they shall be rigidly attached to the main form so no displacement can take place. Metal keyway forms shall be tack-welded to steel forms. Keyway forms shall be so aligned that there is

no variation over 1/4 inch either vertically or horizontally, when tested with a 12 foot template after forms are set, including tests across form joints.

b. Steel forms shall be furnished in sections not less than 10 feet in length, except that on curves having a radius of 150 fet or less, the length of the sections shall be 5 feet unless the sections are flexible or curved to the proper radius. Each 10-foot length of form shall be provided with at least three form braces and pin sockets so spaced that the form will be rigidly braced throughout its length. Lock joints between form sections shall be free from play or movement. Forms shall be free of warps, bends, or kinks.

c. Wood forms for curves and fillets shall be made of well-seasoned, surfaced plank or plywood, straight, and free from warp or bend. Wood forms shall be adequate in strength and rigidly braced.

d. The forms shall be set on firm material cut true to grade so that each form section when placed will be firmly in contact with the underlying layer for its entire length and base width. Underlying material shall be thoroughly compacted and trimmed to grade before forms are set in place. Setting forms on blocks or on built-up spots of underlying material will be not permitted under any condition. The form sections shall be staked into position and tightly locked together. The length of pins and quantity provided in each section shall be sufficient to hold the form at the correct line and grade. When tested with a straightedge, the top of the installed form shall conform to the requirements specified for the finished surface of the concrete, and the longitudinal axis of the upstanding leg shall not vary more than 1/4 inch from the straightedge. Conformity to the alignment and grade elevations shown on the drawings shall be checked and necessary corrections shall be made immediately prior to placing the concrete. Forms shall be set well in advance of concrete placement. The forms shall be cleaned and oiled each time before concrete is placed. No concrete shall be placed until setting of forms has been checked and approved by the CQC team.

3.5.5.2 Form Removal

Forms shall remain in place at least 12 hours after the concrete has been placed. When conditions are such that the early strength gain of the concrete is delayed, the forms shall be left in place for a longer time, as directed. Forms shall be removed by procedures that do not injure the concrete. Bars or heavy metal tools shall not be used directly against the concrete in removing the forms. Any concrete found to be defective after form removal shall be repaired promptly, using procedures specified hereinafter or as directed.

3.5.6 Slipform Paving

3.5.6.1 General

Paving equipment for slipform paving and the operation thereof shall conform to the requirement of paragraph EQUIPMENT, all requirements specified above in subparagraphs, General, Consolidation, Operation, and Required Results, and as specified herein. The slipform paver shall shape the concrete to the specified and indicated cross section, meeting all tolerances, in one pass. The slipform paver shall finish the surface and edges so that only a very minimum isolated amount of hand finishing is required. If the paving operation does

not meet the above requirements and the specified tolerances, the operation shall be immediately stopped, and the Contractor shall regroup and replace or modify any equipment as necessary, modify paving procedures or modify the concrete mix, in order to resolve the problem. The slipform paver shall be automatically electronically controlled from a taut wire guideline for horizontal alignment and on both sides from a taut wire guideline for vertical alignment, except that electronic control from a ski operating on a previously constructed adjoining lane shall be used where applicable for either or both sides. Automatic, electronic controls for vertical alignment shall always be used on both sides of the lane. Control from a slope-adjustment control or control operating from the underlying material shall never be used. If approved by the Contracting Officer after a preconstruction demonstration, automatic laser controls may be used in lieu of or to supplement the taut wire guidelines. Side forms on slipform pavers shall be properly adjusted so that the finished edge of the paving lane meets all specified tolerances. Dowels in longitudinal construction joints shall be installed as specified below. The installation of these dowels by dowel inserters attached to the paver or by any other means of inserting the dowels into the plastic concrete shall not be permitted.

3.5.6.2 Guideline for Slipform Paving

Guidelines shall be accurately and securely installed well in advance of concrete placement. Supports shall be provided at necessary intervals to eliminate all sag in the guideline when properly tightened. The guideline shall be high strength wire set with sufficient tension to remove all sag between supports. Supports shall be securely staked to the underlying material or other provisions made to ensure that the supports will not be displaced when the guideline is tightened or when the guideline or supports are accidentally touched by workmen or equipment during construction. The appliances for attaching the guideline to the supports shall be capable of easy adjustment in both the horizontal and vertical directions. When it is necessary to leave gaps in the guideline to permit equipment to use or cross underlying material, provisions shall be made for quickly and accurately replacing the guideline without any delay to the forward progress of the paver. Supports on either side of the gap shall be secured in such a manner as to avoid disturbing the remainder of the guideline when the portion across the gap is positioned and tightened. The guideline across the gap and adjacent to the gap for a distance of 200 feet shall be checked for horizontal and vertical alignment after the guideline across the gap is tightened. Vertical and horizontal positioning of the guideline shall be such that the finished pavement shall conform to the alignment and grade elevations shown on the drawings within the specified tolerances for grade and smoothness. The specified tolerances are intended to cover only the normal deviations in the finished pavement that may occur under good supervision and do not apply to setting of the guideline. The guideline shall be set true to line and grade.

3.5.6.3 Laser Controls

If the Contractor proposes to use any type of automatic laser controls, a detailed description of the system shall be submitted and a trial field demonstration shall be performed in the presence of the Contracting Officer at least one week prior to start of paving. Approval of the control system will be based on the results of the demonstration and on continuing satisfactory operation during paving.

3.5.7 Placing Reinforcing Steel

The type and amount of steel reinforcement shall be as shown on the drawings. For pavement thickness of 12 inches or more, the reinforcement steel shall be installed by the

strike-off method wherein a layer of concrete is deposited on the underlying material, consolidated, and struck to the indicated elevation of the steel reinforcement. The reinforcement shall be laid upon the pre-struck surface, and the remaining concrete shall then be placed and finished in the required manner. When placement of the second lift causes the steel to be displaced horizontally from its original position, provisions shall be made for increasing the thickness of the first lift and depressing the reinforcement into the unhardened concrete to the required elevation. The increase in thickness shall be only as necessary to permit correct horizontal alignment to be maintained. Any portions of the bottom layer of concrete that have been placed more than 30 minutes without being covered with the top layer shall be removed and replaced with newly mixed concrete without additional cost to the Government. For pavements less than 12 inches thick, the reinforcement shall be positioned on suitable chairs securely fastened to the subgrade prior to concrete placement. Concrete shall be vibrated after the steel has been placed. Regardless of placement procedure, the reinforcing steel shall be free from coatings which could impair bond between the steel and concrete, and laps in the reinforcement shall be as indicated. In lieu of the above, automatic reinforcement depressing attachments may be used to position the reinforcement, either bar mats or welded wire fabric, provided the entire operation is approved by the Contracting Officer. Regardless of the equipment or procedures used for installing reinforcement, the Contractor shall ensure that the entire depth of concrete is adequately consolidated.

3.5.8 Placing Dowels

The method used in installing and holding dowels in position shall ensure that the error in alignment of any dowel from its required alignment after the pavement has been completed will not be greater than 1/8 in. per ft. Except as otherwise specified below, location of dowels shall be within a horizontal tolerance of plus or minus 5/8 inch. The Contractor shall furnish an approved template for checking the alignment and position of the dowels. The portion of each dowel intended to move within the concrete or expansion cap shall be painted with one coat of the specified paint. When dry, the painted portion shall be wiped clean and coated with a thin, even film of lubricating oil before the concrete is placed. Pipe used as dowels shall be filled with a stiff sand-asphalt mixture or portland-cement mortar. Dowels in joints shall be omitted when the center of the dowel is located within a horizontal distance from an intersecting joint equal to or less than one-fourth of the slab thickness. Dowels shall be installed as specified in the following subparagraphs.

3.5.8.1 Contraction Joints

Dowels in longitudinal and transverse contraction joints within the paving lane shall be held securely in place, as indicated, by means of rigid metal frames or basket assemblies of an approved type. The assemblies shall consist of a framework of metal bars or wires arranged to provide rigid support for the dowels throughout the paving operation, with a minimum of four continuous bars or wires extending along the joint line. The dowels shall be welded to the assembly or held firmly by mechanical locking arrangements that will prevent them from rising, sliding out, or becoming distorted during paving operations. The basket assemblies shall be held securely in the proper location by means of suitable pins or anchors. At the Contractor's option, in lieu of the above, dowels in contraction joints shall be installed near the front of the paver by insertion into the plastic concrete using approved equipment and procedures. Approval will be based on the results of a preconstruction demonstration which the Contractor shall conduct, showing that the dowels are installed within specified tolerances.

3.5.8.2 Construction Joints-Fixed Form Paving

Installation of dowels shall be by the bonded-in-place method. Installation by removing and replacing in preformed holes will not be permitted. Dowels shall be prepared and placed across joints where indicated, correctly aligned, and securely held in the proper horizontal and vertical position during placing and finishing operations, by means of devices fastened to the forms. The spacing of dowels in construction joints shall be as indicated, except that, where the planned spacing cannot be maintained because of form length or interference with form braces, closer spacing with additional dowels shall be used.

3.5.8.3 Dowels Installed in Hardened Concrete

Dowels installed in hardened concrete, such as in longitudinal construction joints for slipform paving, in joints between new and existing pavement, and similar locations, shall be installed by bonding the dowels into holes drilled into the hardened concrete. The installation of dowels in longitudinal construction joints by dowel inserters attached to a slipform paver or by any other means of inserting the dowels into the plastic concrete shall not be permitted. However, when paving two lanes together with a longitudinal contraction joint between, any dowels required may be installed in this joint with an approved inserter. Holes approximately 1/8 inch greater in diameter than the dowels shall be drilled into the hardened concrete with rotary core drills to receive the dowels. In lieu of rotary drills, the contractor may use percussion drills, provided that spalling at the collar of the hole does not occur. Regardless of the type of drill used, the drill shall be held rigidly in exact alignment by means of a stable jig or framework, solidly supported; gang drills meeting this are acceptable. Any damage to the concrete face during drilling shall be repaired as directed; continuing damage shall require modification of the equipment and operation. Dowels shall be bonded in the drilled holes using epoxy resin. Epoxy resin shall be injected at the back of the hole before installing the dowel and extruded to the collar during insertion of the dowel so as to completely fill the void around the dowel. Application by buttering the dowel shall not be permitted. The dowels shall be held in alignment at the collar of the hole, after insertion and before the grout hardens, by means of a suitable metal or plastic collar fitted around the dowel. The vertical alignment of the dowels shall be checked by placing a straightedge on the surface of the pavement over the top of the dowel and measuring the vertical distance between the straightedge and the beginning and ending point of the exposed part of the dowel. The horizontal alignment shall be checked with a framing square. Dowels required to be installed in any joints between new and existing concrete shall be grouted in holes drilled in the existing concrete, all as specified above.

3.6 FINISHING

The finishing machine, or paver-finisher, shall meet all requirements specified in paragraph EQUIPMENT and herein. Finishing operations shall be a continuing part of placing operations starting immediately behind the strike-off of the paver and the machines shall be designed and operated to strike off, screed, and consolidate the concrete. Initial finishing shall be provided by the transverse screed or extrusion plate. The sequence of operations shall be transverse finishing, longitudinal machine floating if used, straightedge finishing, texturing, and then edging of joints. Finishing shall be by the machine method. The hand method shall be used only infrequently and only on isolated areas of odd slab widths or shapes and in the event of a breakdown of the mechanical finishing equipment. When approved, the hand finishing method may also be used for separate, isolated slabs during removal and replacement type repair operations. Supplemental hand finishing for machine

finished pavement shall be kept to an absolute minimum. Equipment to be used for supplemental hand finishing shall primarily be 10 to 12 feet cutting straightedges; only very sparing use of bull floats shall be allowed. Any machine finishing operation which requires appreciable hand finishing, other than a moderate amount of straightedge finishing, shall be immediately stopped and proper adjustments made or the equipment replaced. Every effort shall be made to prevent bringing excess paste to the surface and any operations which produce more than 3/32 inch of paste (mortar, water, laitance, etc.) over the top layer of coarse aggregate shall be halted immediately and the equipment, mixture, or procedures modified as necessary. Compensation shall be made for surging behind the screeds or extrusion plate and settlement during hardening and care shall be taken to ensure that paving and finishing machines are properly adjusted so that the finished surface of the concrete (not just the cutting edges of the screeds) will be at the required line and grade. Surface checks shall be made regularly and paving operations immediately halted and adjustments made whenever compensation is inadequate. Screed and float adjustments of the machines shall be checked at the start of each day's paving operations and more often if required. Machines that cause frequent delays due to mechanical failure shall be replaced. When machines ride the edge of a previously constructed slab, the edge shall be kept clean and provision shall be made to protect the surface of the slab. Clary screeds, "bridge deck" finishers, or other rotating pipe or tube type equipment will not be permitted. Finishing equipment and tools shall be maintained clean and in an approved condition. At no time shall water be added to the surface of the slab with the finishing equipment or tools, or in any other way, except for fog (mist) sprays specified to prevent plastic shrinkage cracking.

3.6.1 Longitudinal Floating

When the equipment contains a mechanical, longitudinal, oscillating float, the float shall be operated to smooth and finish the pavement immediately behind the transverse screed or extrusion plate. The float shall be operated maintaining contact with the surface at all times. Care shall be taken to prevent working paste to the surface in excess of the amount specified above.

3.6.2 Other Types of Finishing Equipment

Concrete finishing equipment of types other than those specified above may be used on a trial basis, when specifically approved, except that rotating pipe or tubes or bridge deck finishers will not be permitted. Approval will be given after demonstration on a test section prior to start of construction, and provided the Contracting Officer determines that the pavement produced is better than that produced by the specified equipment. The use of equipment that fails to produce finished concrete of the required quality, using concrete proportions and slump as specified, shall be discontinued, and the concrete shall be finished with specified equipment and in the manner specified above. Vibrating screeds or pans shall be used only for isolated slabs where hand finishing is permitted as specified, and only where specifically approved. Slipform paving equipment shall not be operated on fixed forms unless approved in writing prior to use.

3.6.3 Machine Finishing With Fixed Forms

The machine shall be designed to ride the forms and shall be operated to screed and consolidate the concrete. Machines that cause displacement of the forms shall be replaced. The machine shall make only one pass over each area of pavement. If the equipment and procedures do not produce a surface of uniform texture, true to grade, in one pass, the

operation shall be immediately stopped and the equipment, mixture, and procedures adjusted as necessary.

3.6.4 Machine Finishing With Slipform Pavers

The slipform paver shall be operated so that only a very minimum of additional finishing work is required to produce pavement surfaces and edges meeting the specified tolerances. Any equipment or procedure that fails to meet these specified requirements shall immediately be replaced or modified as necessary. A self-propelled nonrotating pipe float may be used if the Contractor desires while the concrete is still plastic, to remove minor irregularities and score marks. The pipe float shall be 6 to 10 inches in diameter and sufficiently long to span the full paving width when oriented at an angle of approximately 60 degrees with the center line. Only one pass of the pipe float shall be allowed. If there is sufficient concrete slurry or fluid paste on the surface that it runs over the edge of the pavement, the paving operation shall be immediately stopped and the equipment, mixture, or operation modified to prevent formation of such slurry. Any slurry which does run down the vertical edges shall be immediately removed by hand, using stiff brushes or scrapers. No slurry, concrete or concrete mortar shall be used to build up along the edges of the pavement to compensate for excessive edge slump, either while the concrete is plastic or after it hardens. Slabs having areas of edge slump in excess of the specified tolerances shall be removed and replaced in accordance with paragraph, REPAIR, REMOVAL, REPLACEMENT OF SLABS; repair operations on such areas will not be permitted.

3.6.5 Surface Correction and Testing

After all other finishing is completed but while the concrete is still plastic, minor irregularities and score marks in the pavement surface shall be eliminated by means of cutting straightedges. Such straightedges shall be 12 feet in length and shall be operated from the sides of the pavement and from bridges. A straightedge operated from the side of the pavement shall be equipped with a handle 3 feet longer than one-half the width of the pavement. The surface shall then be tested for trueness with a straightedge held in successive positions parallel and at right angles to the center line of the pavement, and the whole area covered as necessary to detect variations. The straightedge shall be advanced along the pavement in successive stages of not more than one-half the length of the straightedge. Depressions shall be immediately filled with freshly mixed concrete, struck off, consolidated, and refinished. Projections above the required elevation shall also be struck off and refinished. The straightedge testing and finishing shall continue until the entire surface of the concrete is free from observable departure from the straightedge and conforms to the surface requirements specified in paragraph ACCEPTABILITY OF WORK AND PAYMENT ADJUSTMENTS. Long-handled, flat bull floats shall be used very sparingly and only as necessary to correct minor, scattered surface defects. If frequent use of bull floats is necessary, the paving operation shall be stopped and the equipment, mixture or procedures adjusted to eliminate the surface defects. Finishing with hand floats and trowels shall be held to the absolute minimum necessary. Extreme care shall be taken to prevent overfinishing joints and edges. The surface finish of the pavement shall be produced essentially by the finishing machine and not by subsequent hand finishing operations. All hand finishing operations shall be subject to approval and shall be modified when directed. No water shall be added to the pavement surface during these operations.

3.6.6 Hand Finishing

Hand finishing operations shall be used only as specified above.

3.6.6.1 Equipment

In addition to approved mechanical internal vibrators for consolidating the concrete, a strike-off and tamping template and a longitudinal float shall be provided for hand finishing. The template shall be at least 1 foot longer than the width of pavement being finished, of an approved design, and sufficiently rigid to retain its shape, and shall be constructed of metal or other suitable material shod with metal. The longitudinal float shall be at least 10 feet long, of approved design, and rigid and substantially braced, and shall maintain a plane surface on the bottom . Grate tampers (jitterbugs) shall not be used.

3.6.6.2 Finishing and Floating

As soon as placed and vibrated, the concrete shall be struck off and screeded to the crown and cross section and to such elevation above grade that when consolidated and finished, the surface of the pavement will be at the required elevation. In addition to previously specified complete coverage with handheld immersion vibrators, the entire surface shall be tamped with the strike-off and tamping template, and the tamping operation continued until the required compaction and reduction of internal and surface voids are accomplished (grate tampers shall not be used). Immediately following the final tamping of the surface, the pavement shall be floated longitudinally from bridges resting on the side forms and spanning but not touching the concrete. If necessary, additional concrete shall be placed and screeded, and the float operated until a satisfactory surface has been produced. The floating operation shall be advanced not more than half the length of the float and then continued over the new and previously floated surfaces. Long-handled, flat bull floats shall be used very sparingly and only as necessary to correct minor, scattered surface defects. If frequent use of bull floats is necessary, the operation shall be stopped and adjusted to eliminate the surface defects. Finishing with hand floats and trowels shall be held to the absolute minimum necessary. Extreme care shall be taken to prevent overfinishing joints and edges. No water shall be added to the pavement during finishing operations.

3.6.7 Texturing

Before the surface sheen has disappeared and before the concrete hardens, the surface of the pavement shall be given a texture as described herein. After curing is complete, all textured surfaces shall be thoroughly power broomed to remove all debris.

3.6.7.1 Fabric Drag Surface Finish

Surface texture shall be applied by dragging the surface of the pavement, in the direction of the concrete placement, with an approved fabric drag. The drag shall be operated with the fabric moist, and the fabric shall be cleaned or changed as required to keep clean. The dragging shall be done so as to produce a uniform finished surface having a fine sandy texture without disfiguring marks.

3.6.8 Edging

After texturing has been completed, the edge of the slabs along the forms, along the edges of slipformed lanes, and at the joints shall be carefully finished with an edging tool to form a smooth rounded surface of 1/8 inch radius. Tool marks shall be eliminated, and the edges shall be smooth and true to line. No water shall be added to the surface during edging. Extreme care shall be taken to prevent overworking the concrete.

3.6.9 Outlets in Pavement

Recesses for the tie-down anchors, lighting fixtures, and other outlets in the pavement shall be constructed to conform to the details and dimensions shown. The concrete in these areas shall be carefully finished to provide a surface of the same texture as the surrounding area that will be within the requirements for plan grade and surface smoothness.

3.7 CURING

3.7.1 Protection of Concrete

Concrete shall be continuously protected against loss of moisture and rapid temperature changes for at least 7 days from the completion of finishing operations. Unhardened concrete shall be protected from rain and flowing water. All equipment needed for adequate curing and protection of the concrete shall be on hand and ready for use before actual concrete placement begins. Sufficient sheet material to protect unhardened concrete from rain shall be at the paver at all times. Protection shall be provided as necessary to prevent cracking of the pavement due to temperature changes during the curing period. If any selected method of curing does not afford the proper curing and protection against concrete cracking, the damaged pavement shall be removed and replaced, and another method of curing shall be employed as directed. Curing shall be accomplished by one of the following methods.

3.7.2 Membrane Curing

A uniform coating of white-pigmented, membrane-forming, curing compound shall be applied to the entire exposed surface of the concrete as soon as the free water has disappeared from the surface after finishing. If evaporation is high and no moisture is present on the surface even though bleeding has not stopped, fog sprays shall be used to keep the surface moist until setting of the cement occurs and bleeding is complete. Curing compound shall then be immediately applied. Along the formed edge faces, it shall be applied immediately after the forms are removed. Concrete shall not be allowed to dry before the application of the membrane. If any drying has occurred, the surface of the concrete shall be moistened with a fine spray of water, and the curing compound applied as soon as the free water disappears. The curing compound shall be applied to the finished surfaces by means of an approved automatic spraying machine. The spraying machine shall be self-propelled and shall span the newly paved lane. The machine shall have one or more spraying nozzles that can be controlled and operated to completely and uniformly cover the pavement surface with the required amount of curing compound. The curing compound in the drum used for the spraying operation shall be thoroughly and continuously agitated mechanically throughout the full depth of the drum during the application. Air agitation may be used only to supplement mechanical agitation. Spraying pressure shall be sufficient to produce a fine spray as necessary to cover the surface thoroughly and completely with a uniform film. Spray equipment shall be kept clean and properly maintained and the spray nozzle or nozzles shall

have adequate wind shields. The curing compound shall be applied with an overlapping coverage that will give a two-coat application at a coverage of 400 square feet per gallon, plus or minus 5.0 percent for each coat. A one-coat application may be applied provided a uniform application and coverage of 200 square feet per gallon, plus or minus 5.0 percent is obtained. The application of curing compound by hand-operated, mechanical powered pressure sprayers will be permitted only on odd widths or shapes of slabs where indicated and on concrete surfaces exposed by the removal of forms. When the application is made by hand-operated sprayers, the second coat shall be applied in a direction approximately at right angles to the direction of the first coat. The compound shall form a uniform, continuous, cohesive film that will not check, crack, or peel and that will be free from pinholes and other discontinuities. If pinholes, abrasions, or other discontinuities exist, an additional coat shall be applied to the affected areas within 30 minutes. Concrete surfaces that are subjected to heavy rainfall within 3 hours after the curing compound has been applied shall be resprayed by the method and at the coverage specified above. Areas where the curing compound is damaged by subsequent construction operations within the curing period shall be immediately resprayed. The surfaces adjacent to joint sawcuts shall be cleaned and resprayed with curing compound immediately after cutting. Approved standby facilities for curing concrete pavement shall be provided at an accessible location at the job site for use in the event of mechanical failure of the spraying equipment or other conditions that might prevent correct application of the membrane-curing compound at the proper time. Concrete surfaces to which membrane-curing compounds have been applied shall be adequately protected during the entire curing period from pedestrian and vehicular traffic, except as required for joint-sawing operations and surface tests, and from any other possible damage to the continuity of the membrane.

3.7.3 Moist Curing

Concrete to be moist-cured shall be maintained continuously wet for the entire curing period, or until curing compound is applied, commencing immediately after finishing. If forms are removed before the end of the curing period, curing shall be carried out as on unformed surfaces, using suitable materials. Surfaces shall be cured by ponding, by continuous sprinkling, by continuously saturated burlap or cotton mats, or by continuously saturated plastic coated burlap. Burlap and mats shall be clean and free from any contamination and shall be completely saturated before being placed on the concrete. The Contractor shall have an approved work system to ensure that moist curing is continuous 24 hours per day and that the entire surface is wet.

3.7.4 Removal of Curing Compound

After concrete in a work area has cured for at least 14 days, the membrane curing compound on that pavement shall be completely removed with high pressure water or other approved means. Removal method shall not damage underlying pavement.

3.8 JOINTS

3.8.1 General Requirements for Joints

Joints shall conform to the details indicated and shall be perpendicular to the finished grade of the pavement. All joints shall be straight and continuous from edge to edge or end to end of the pavement with no abrupt offset and no gradual deviation greater than 1/2 inch Before commencing construction, the Contractor shall submit for approval a control plan and

equipment to be used for ensuring that all joints are straight from edge to edge of the pavement within the above tolerances. Where any joint fails to meet these tolerances, the slabs adjacent to the joint shall be removed and replaced at no additional cost to the Government. No change from the jointing pattern shown on the drawings shall be made without written approval of the Contracting Officer. Sealing of joints shall be in accordance with Sections 02760A or 02762A as shown on the drawings.

3.8.2 Longitudinal Construction Joints

Longitudinal construction joints between paving lanes shall be located as indicated. Dowels shall be installed in the longitudinal construction joints, or the edges shall be thickened as indicated. Dowels shall be installed in conformance with paragraph, Placing Dowels and Tie Bars. After the end of the curing period, longitudinal construction joints shall be sawed to provide a groove at the top for sealant conforming to the details and dimensions indicated.

3.8.3 Transverse Construction Joints

Transverse construction joints shall be installed at the end of each day's placing operations and at any other points within a paving lane when concrete placement is interrupted for 30 minutes or longer. When concrete placement cannot be continued, the transverse construction joint shall be installed at a planned transverse joint, if possible. Transverse construction joints shall be constructed by utilizing headers and the very minimum amount of hand placement and finishing techniques. Pavement shall be constructed with the paver as close to the header as possible, and the paver shall be run out completely past the header. Transverse construction joints installed at a planned transverse joint shall be constructed as shown or, if not shown otherwise, shall be dowelled. Those not at a planned transverse joint shall be constructed with tie bars and shall not be sawed or sealed.

3.8.4 Expansion Joints

Expansion joints shall be formed where indicated, and about any structures and features that project through or into the pavement, using joint filler of the type, thickness, and width indicated, and shall be installed to form a complete, uniform separation between the structure and the pavement. The filler shall be attached to the original concrete placement with adhesive or other fasteners and shall extend the full slab depth. Adjacent sections of filler shall be fitted tightly together, and the filler shall extend across the full width of the paving lane or other complete distance in order to prevent entrance of concrete into the expansion space. Edges of the concrete at the joint face shall be finished with an edger with a radius of 1/8 inch. The joint filler strips shall be installed 3/4 inch below the pavement surface with a slightly tapered, dressed-and-oiled wood strip or other approved material temporarily secured to the top of the filler to form a recess to be filled with joint sealant. The wood strip shall be removed soon after the concrete has set and the reservoir temporarily filled with an approved material to protect the reservoir until the joint sealer is installed. Expansion joints shall be constructed with thickened edges for load transfer.

3.8.5 Slip Joints

Slip joints shall be installed where indicated using the specified materials. Preformed joint filler material shall be attached to the face of the original concrete placement with adhesive or other fasteners. Bituminous material shall be applied to cover the entire surface of the face of the original concrete placement to a depth of 1/4 inch plus or minus 1/16 inch. Only a

material which will remain in place on the vertical surface shall be used. In each case a 3/4 inch deep reservoir for joint sealant shall be constructed at the top of the joint. Edges of the joint face shall be finished with an edger with a radius of 1/8 inch

3.8.6 Contraction Joints

Transverse and longitudinal contraction joints shall be of the weakened-plane or dummy type and shall be constructed as indicated. Longitudinal contraction joints shall be constructed by sawing a groove in the hardened concrete with a power-driven saw in conformance with requirements for sawed joints, unless otherwise approved in writing. Transverse contraction joints shall be constructed in conformance with requirements for sawed joints.

3.8.6.1 Sawed Joints

Sawed contraction joints shall be constructed by sawing an initial groove in the concrete with a 1/8-inch blade to the indicated depth. During sawing of joints, and again 24 hours later, the CQC team shall inspect all exposed lane edges for development of cracks below the saw cut, and shall immediately report results to the Contracting Officer. If the Contracting Officer determines that there are more uncracked joints than desired, the Contractor will be directed to saw succeeding joints 25 percent deeper than originally indicated at no additional cost to the Government. After expiration of the curing period, the upper portion of the groove shall be widened by sawing to the width and depth indicated for the joint sealer. The time of initial sawing shall vary depending on existing and anticipated weather conditions and shall be such as to prevent uncontrolled cracking of the pavement. Sawing of the joints shall commence as soon as the concrete has hardened sufficiently to permit cutting the concrete without chipping, spalling, or tearing. The sawed faces of joints will be inspected for undercutting or washing of the concrete due to the early sawing, and sawing shall be delayed if undercutting is sufficiently deep to cause structural weakness or excessive roughness in the joint. The sawing operation shall be carried on as required during both day and night regardless of weather conditions. The joints shall be sawed at the required spacing consecutively in the sequence of the concrete placement. A chalk line or other suitable guide shall be used to mark the alignment of the joint. Before sawing a joint, the concrete shall be examined closely for cracks, and the joint shall not be sawed if a crack has occurred near the planned joint location. Sawing shall be discontinued when a crack develops ahead of the saw cut. Workmen and inspectors shall wear clean, rubber-soled footwear, and the number of persons walking on the pavement shall be limited to those actually performing the sawing operation. Immediately after the joint is sawed, the saw cut and adjacent concrete surface shall be thoroughly flushed with water until all waste from sawing is removed from the joint. The surface shall be resprayed with curing compound as soon as free water disappears. Necessary precautions shall be taken to insure that the concrete is properly cured at sawed joints, but that no curing compound enters the joints. The top of the joint opening and the joint groove at exposed edges shall be tightly sealed with cord, backer rod, or other approved material before the concrete in the region of the joint is resprayed with curing compound. The method used for sealing the joint groove shall prevent loss of moisture from the joint during the entire specified curing period and shall prevent infiltration of foreign material until removed immediately before sawing joint sealant reservoir. The sawing equipment shall be adequate in the number of units and the power to complete the sawing at the required rate. An ample supply of saw blades shall be available on the job before concrete placement is started and at all times during sawing. At least one standby sawing unit in good working order shall be available at the jobsite at all times during the sawing operation.

3.8.7 Thickened Edge Joints

Thickened edge joints shall be constructed as indicated on the drawings. Underlying material in the transition area shall be graded as shown and shall meet the requirements for smoothness and compaction specified for all other areas of the underlying material.

3.8.8 Special Joints

"Special joints" (undercut joints) shall be constructed adjacent to existing pavement as indicated. The concrete under the edge of the existing pavement and the concrete below the normal level of the bottom of the new pavement shall be placed as a separate operation in front of the paving train. The concrete shall be worked under the edge of the existing pavement to completely fill the void and shall be thoroughly consolidated by the use of hand-held vibrators. Timing shall be such that this concrete is still workable when the paving train goes across it. In no case shall this concrete be placed as part of the operation of the paving equipment.

3.8.9 Sealing Joints

Joints shall be sealed immediately following curing of the concrete or as soon thereafter as weather conditions permit. Joints shall be sealed as specified in Sections 02760 (R) FIELD MOLDED SEALANTS FOR SEALING JOINTS IN RIGID PAVEMENTS and 02762 (R) COMPRESSION JOINT SEALS FOR CONCRETE PAVEMENTS, in accordance with the plans.

3.9 REPAIR, REMOVAL, REPLACEMENT OF SLABS

3.9.1 General Criteria

New pavement slabs that are broken or contain cracks shall be removed and replaced or repaired, as specified hereinafter at no cost to the Government. Spalls along joints shall be repaired as specified. Where removal of partial slabs is permitted, as specified, removal and replacement shall be full depth, shall be full width of the paving lane, and the limit of removal shall be normal to the paving lane and not less than 10 feet from each original transverse joint (i.e., removal portion shall be at least 10 feet longitudinally, and portion to remain in place shall be at least longitudinally; thus, if original slab length is less than 20 feet, the entire slab shall be removed). The Contracting Officer will determine whether cracks extend full depth of the pavement and may require cores to be drilled on the crack to determine depth of cracking. Such cores shall be at least 6 inch diameter, shall be drilled by the Contractor and shall be filled by the Contractor with a well consolidated concrete mixture bonded to the walls of the hole with epoxy resin, using approved procedures. Drilling of cores and refilling holes shall be at no expense to the Government. All epoxy resin used in this work shall conform to paragraph EPOXY RESIN, Type and Grade as specified.

3.9.2 Slabs with Cracks Thru Interior Areas

Interior area is defined as that area more than 24 inchesfrom either adjacent original transverse joint. Slabs with any cracks that extend into the interior area, regardless of direction, shall be treated by one of the following procedures.

3.9.2.1 Cracks That Do Not Extend Full Depth of Slab

These cracks, and similar cracks within the areas 24 incheseach side of transverse joints, shall be cleaned and then pressure injected with epoxy resin, Type IV, Grade 1, using procedures as approved. The procedure shall not widen the crack during epoxy resin injection. All epoxy resin injection shall take place in the presence of a representative of the Contracting Officer.

3.9.2.2 Cracks That Extend Full Depth of Slab

Where there is any full depth crack at any place within the interior area, the full slab shall be removed. However, if the cracked area all lies within 10 feet of one original transverse joint, only a partial slab need be removed provided all criteria specified above for distance from each original transverse joint is met.

3.9.3 Cracks close to and Parallel to Transverse Joints

All cracks essentially parallel to original transverse joints, extending full depth of the slab, and lying wholly within 24 incheseither side of the joint shall be treated as specified hereinafter. Any crack extending more than 24 inches from the transverse joint shall be treated as specified above for Slabs With Cracks Through Interior Areas. Any cracks which do not extend full depth of the slab shall be treated as specified above in subparagraph, Cracks That Do Not Extend Full Depth Of Slab, and the original transverse joint constructed as originally designed.

3.9.3.1 Full Depth Cracks Present, Original Joint Not Opened

When the original transverse joint has not opened, the crack shall be routed and sealed, and the original transverse joint filled with epoxy resin. The crack shall be routed with an easily guided, wheel mounted, vertical shaft, powered rotary router designed so the routing spindle will caster as it moves along the crack, or with a small diameter saw designed for this use. The reservoir for joint sealant in the crack shall be formed by routing to a depth of 3/4 inch,plus or minus 1/16 inch, and to a width of 5/8 inch, plus or minus 1/8 inch. Any equipment or procedure which causes ravelling or spalling along the crack shall be modified or replaced to prevent such ravelling or spalling. The joint sealant shall be a liquid sealant as specified for rigid pavement joints. Installation of joint seal shall be as specified for sealing joints or as directed. The uncracked transverse joint shall be filled with epoxy resin. If the joint sealant reservoir has been sawed out, the reservoir and as much of the lower saw cut as possible shall be filled with epoxy resin, Type IV, Grade 2, thoroughly tooled into the void using approved procedures. If only the original narrow saw cut has been made, it shall be cleaned and pressure injected with epoxy resin, Type IV, Grade 1, using approved procedures. If filler material (joint insert) has been used to form a weakened plane in the transverse joint, it shall be completely sawed out and the saw cut pressure injected with epoxy resin, Type IV, Grade 1, using approved procedures. Where a parallel crack goes part way across the paving lane and then intersects and follows the original transverse joint which is cracked only for the remainder of the width, it shall be treated as follows: The area with the separate crack shall be treated as specified above for a parallel crack, and the cracked original joint shall be prepared and sealed as originally designed.

3.9.3.2 Full Depth Cracks, Original Joint Also Cracked

At a transverse joint, if there is any place in the lane width where a parallel crack and a cracked portion of the original joint overlap, a section of the slab containing the crack shall be removed and replaced for the full lane width and at least 10 feet long. If this partial slab removal places the limit of removal less than 10 feet from the next transverse joint, the entire slab shall be removed. If the parallel crack crosses the transverse joint line, a similar area shall be removed and replaced in both slabs.

3.9.4 Removal and Replacement of Full Slabs

Where it is necessary to remove full slabs, unless there are keys or dowels present, all edges of the slab shall be cut full depth with a concrete saw. All saw cuts shall be perpendicular to the slab surface. If keys, dowels, or tie bars are present along any edges, these edges shall be sawed full depth 6 inches from the edge if only keys are present, or just beyond the end of dowels or tie bars if they are present. These joints shall then be carefully sawed on the joint line to within 1 inch of the depth of the dowel or key. The main slab shall be further divided by sawing full depth, at appropriate locations, and each piece lifted out and removed. Suitable equipment shall be used to provide a truly vertical lift, and approved safe lifting devices used for attachment to the slabs. The narrow strips along keyed or doweled edges shall be carefully broken up and removed using light, hand-held jackhammers, 30 lb or less, or other approved similar equipment. Care shall be taken to prevent damage to the dowels, tie bars, or keys or to concrete to remain in place. The joint face below keys or dowels shall be suitably trimmed so that there is no abrupt offset in any direction greater than 1/2 inch and no gradual offset greater than 1 inch when tested in a horizontal direction with a straightedge. No mechanical impact breakers, other than the above hand-held equipment shall be used for any removal of slabs. If underbreak between 1-1/2 and 4 inches deep occurs at any point along any edge, the area shall be repaired as directed before replacing the removed slab. Procedures directed will be similar to those specified for surface spalls, modified as necessary. If underbreak over 4 inches deep occurs, the entire slab containing the underbreak shall be removed and replaced. Where there are no dowels, tie bars, or keys on an edge, or where they have been damaged, dowels of the size and spacing as specified for other joints in similar pavement shall be installed by epoxy grouting them into holes drilled into the existing concrete using procedures as specified in paragraph, Placing Dowels and Tie Bars. Original damaged dowels or tie bars shall be cut off flush with the joint face. Protruding portions of dowels shall be painted and lightly oiled. All four edges of the new slab shall thus contain dowels or original keys or original tie bars. Placement of concrete shall be as specified for original construction. Prior to placement of new concrete, the underlying material shall be recompacted and shaped as specified in the appropriate section of these specifications, and the surfaces of all four joint faces shall be cleaned of all loose material and contaminants and coated with a double application of membrane forming curing compound as bond breaker. Care shall be taken to prevent any curing compound from contacting dowels or tie bars. The resulting joints around the new slab shall be prepared and sealed as specified for original construction.

3.9.5 Removal and Replacement of Partial Slabs

Where the above criteria permits removal of partial slabs, removal and replacement operations shall be as specified for full slabs, except that the joint between the removed area and the partial slab to remain in place shall consist of a full depth saw cut across the full lane width and perpendicular to the centerline of the paving lane. Replacement operations shall

be the same as specified above, except that, at the joint between the removed area and the partial slab to remain, deformed tie bars shall be epoxy resin grouted into holes drilled into the slab to remain in place. Size and spacing of the tie bars shall be as specified for dowels. Drilling of holes and installation of tie bars shall be as specified for dowels in paragraph, Placing Dowels and Tie Bars, except that no portion of the tie bars shall be painted or oiled. No curing compound shall be used on this joint face and, immediately before placing new concrete, the joint surface of the partial slab remaining in place shall be coated with epoxy resin, Type V, Grade 2.

3.9.6 Repairing Spalls Along Joints

Where directed, spalls along joints of new slabs, along edges of adjacent existing concrete, and along parallel cracks shall be repaired by first making a vertical saw cut at least 1 inch outside the spalled area and to a depth of at least 2 inches. Saw cuts shall be straight lines forming rectangular areas. The concrete between the saw cut and the joint, or crack, shall be chipped out to remove all unsound concrete and at least a depth of 1/2 inch of visually sound concrete. The cavity thus formed shall be thoroughly cleaned with high pressure water jets supplemented with compressed air to remove all loose material. Immediately before filling the cavity, a prime coat shall be applied to the dry cleaned surface of all sides and bottom of the cavity, except any joint face. The prime coat shall be applied in a thin coating and scrubbed into the surface with a stiff-bristle brush. Prime coat for portland cement repairs shall be a neat cement grout and for epoxy resin repairs shall be epoxy resin, Type III, Grade 1. The cavity shall be filled with low slump portland cement concrete or mortar or with epoxy resin concrete or mortar. Portland cement concrete shall be used for larger spalls, those more than 1/3 cu. ft. in size after removal operations; portland cement mortar shall be used for spalls between 0.03 cu. ft. and 1/3 cu. ft.; and epoxy resin mortar or Type III, Grade 3 epoxy resin for those spalls less than 0.03 cu. ft.in size after removal operations. Portland cement concretes and mortars shall be very low slump mixtures, 1/2 inch slump or less, proportioned, mixed, placed, consolidated by tamping, and cured, all as directed. [If the materials and procedures are approved in writing, latex modified concrete mixtures may be used for repairing spalls less than 1/3 cu.ft. in size.] Epoxy resin mortars shall be made with Type III, Grade 1, epoxy resin, using proportions and mixing and placing procedures as recommended by the manufacturer and approved by the Contracting Officer. The epoxy resin materials shall be placed in the cavity in layers not over 2 inches thick. The time interval between placement of additional layers shall be such that the temperature of the epoxy resin material does not exceed 140 degrees F at any time during hardening. Mechanical vibrators and hand tampers shall be used to consolidate the concrete or mortar. Any repair material on the surrounding surfaces of the existing concrete shall be removed before it hardens. Where the spalled area abuts a joint, an insert or other bond-breaking medium shall be used to prevent bond at the joint face. A reservoir for the joint sealant shall be sawed to the dimensions required for other joints, or as required to be routed for cracks. The reservoir shall be thoroughly cleaned and then sealed with the sealer specified for the joints. If any spall penetrates half the depth of the slab or more, the entire slab, or 10 foot portion thereof, shall be removed and replaced as previously specified. In lieu of sawing, spalls not adjacent to joints, and popouts, both less than 6 inches in maximum dimension, may be prepared by drilling a core 2 inches in diameter greater than the size of the defect, centered over the defect, and 2 inches deep or 1/2 inch into sound concrete, whichever is greater. The core hole shall be repaired as specified above for other spalls.

3.10 EXISTING CONCRETE PAVEMENT REMOVAL AND REPAIR

Existing concrete pavement shall be removed as indicated and as specified in Section 02220 DEMOLITION, modified, and expanded as specified herein. Repairs shall be made as indicated and as specified herein. All operations shall be carefully controlled to prevent damage to the concrete pavement and to the underlying material to remain in place. All saw cuts shall be made perpendicular to the slab surface, and forming rectangular areas.

3.10.1 Removal of Existing Pavement Slab

When existing concrete pavement is to be removed and adjacent concrete is to be left in place, the joint between the removal area and adjoining pavement to stay in place , including dowels, tie bars or keys, shall first be cut full depth with a standard diamond-type concrete saw. Next, a full depth saw cut shall be made parallel to the joint at least 24 inches from the joint and at least 6 inches from the end of any dowels. This saw cut shall be made with a wheel saw as specified in paragraph SAWING EQUIPMENT. All pavement to be removed beyond this last saw cut shall be removed using equipment and procedures specified in Section 02220 (R) DEMOLITION and as approved. All pavement between this last saw cut and the joint line shall be removed by carefully pulling pieces and blocks away from the joint face with suitable equipment and then picking them up for removal. In lieu of this method, this strip of concrete may be carefully broken up and removed using hand-held jackhammers, 30 lb or less, or other approved light-duty equipment which will not cause stress to propagate across the joint saw cut and cause distress in the pavement which is to remain in place. In lieu of the above specified removal method, the slab may be sawcut full depth to divide it into several pieces and each piece lifted out and removed. Suitable equipment shall be used to provide a truly vertical lift, and safe lifting devices used for attachment to the slab. Dowels of the size and spacing indicated shall be installed as shown on the drawings by epoxy resin bonding them in holes drilled in the joint face as specified in paragraph, Placing Dowels and Tie Bars.

3.10.2 Edge Repair

The edge of existing concrete pavement against which new pavement abuts shall be protected from damage at all times. Areas which are damaged during construction shall be repaired at no cost to the Government; repair of previously existing damage areas will be considered a subsidiary part of concrete pavement construction.

3.10.2.1 Spall Repair

Spalls along joints and along cracks shall be repaired where indicated and where directed. Repair materials and procedures shall be as previously specified in subparagraph, Repairing Spalls Along Joints.

3.10.2.2 Underbreak Repair

All underbreak shall be repaired. First, all delaminated and loose material shall be carefully removed. Next, the underlying material shall be recompacted, without addition of any new material. Finally, the void shall be completely hand-filled with paving concrete mixture, thoroughly consolidated. Care shall be taken to produce an even joint face from top to bottom. Prior to placing concrete, the underlying material shall be thoroughly moistened.

After placement, the exposed surface shall be heavily coated with curing compound. All this shall be done at least 24 hours before placing the new paving concrete against the joint.

3.10.2.3 Underlying Material

The underlying material adjacent to the edge of and under the existing pavement which is to remain in place shall be protected from damage or disturbance during removal operations and until placement of new concrete, and shall be shaped as shown on the drawings or as directed. Sufficient underling material shall be kept in place outside the joint line to completely prevent disturbance of material under the pavement which is to remain in place. Any material under the portion of the concrete pavement to remain in place which is disturbed or loses its compaction shall be carefully removed and replaced with concrete as specified above under Underbreak Repair. The underlying material outside the joint line shall be thoroughly compacted and shall be moist when new concrete is placed.

3.11 PAVEMENT PROTECTION

The Contractor shall protect the pavement against all damage prior to final acceptance of the work by the Government. Aggregates rubble, or other similar construction materials shall not be piled on airfield pavements. Traffic shall be excluded from the new pavement by erecting and maintaining barricades and signs until the concrete is at least 14 days old, or for a longer period if so directed. As a construction expedient in paving intermediate lanes between newly paved pilot lanes, operation of the hauling equipment will be permitted on the new pavement after the pavement has been cured for 7 days and the joints have been sealed or otherwise protected. Also, the subgrade planer, concrete paving and finishing machines, and similar equipment may be permitted to ride upon the edges of previously constructed slabs when the concrete has attained a minimum flexural strength of 400 psi and approved means are furnished to prevent damage to the slab edge. All new and existing pavement carrying construction traffic or equipment shall be continuously kept completely clean, and spillage of concrete or other materials shall be cleaned up immediately upon occurrence. Special care shall be used where Contractor's traffic uses or crosses active airfield pavement. In these areas, if necessary in order to accomplish this, full-time workmen with hand brooms shall be used at anytime there is traffic. Other existing pavements used by the Contractor shall be power broomed at least daily when traffic operates. For fill-in lanes, equipment shall be used that will not damage or spall the edges or joints of the previously constructed pavement.

3.12 TESTING AND INSPECTION FOR CONTRACTOR QUALITY CONTROL

3.12.1 Testing and Inspection by Contractor

The Contractor shall perform the inspection and tests described below, and based upon the results of these inspections and tests, shall take the action required and submit reports as required. When, in the opinion of the Contracting Officer, the paving operation is out of control, concrete placement shall cease. The laboratory performing the tests shall be on-site and shall conform with ASTM C 1077. The individuals who sample and test concrete or the constituents of concrete as required in this specification shall have demonstrated a knowledge and ability to perform the necessary test procedures equivalent to the ACI minimum guidelines for certification of Concrete Field Testing Technicians, Grade I. The individuals who perform the inspection of concrete shall have demonstrated a knowledge and ability equivalent to the ACI minimum guidelines for certification of Concrete Construction Inspector, Level II. The Government will inspect the laboratory, equipment, and test

procedures prior to start of concreting operations and at least once per year thereafter for conformance with ASTM C 1077. This testing shall be performed by the Contractor regardless of any other testing performed by the Government, either for pay adjustment purposes or for any other reason.

3.12.2 Testing and Inspection Requirements

3.12.2.1 Fine Aggregate

a. Grading. At least once during each shift when the concrete plant is operating, there shall be one sieve analysis and fineness modulus determination in accordance with ASTM C 136 and COE CRD-C 104 for the fine aggregate or for each fine aggregate if it is batched in more than one size or classification. The location at which samples are taken may be selected by the Contractor as the most advantageous for control. However, the Contractor is responsible for delivering fine aggregate to the mixer within specification limits.

b. Corrective Action for Fine Aggregate Grading. When the amount passing on any sieve is outside the specification limits, the fine aggregate shall be immediately resampled and retested. If there is another failure on any sieve, the fact shall be immediately reported to the Contracting Officer, paving shall be stopped, and immediate steps taken to correct the grading.

3.12.2.2 Coarse Aggregate

a. Grading. At least once during each shift in which the concrete plant is operating, there shall be a sieve analysis in accordance with ASTM C 136 for each size of coarse aggregate. The location at which samples are taken may be selected by the Contractor as the most advantageous for production control. However, the Contractor shall be responsible for delivering the aggregate to the mixer within specification limits. A test record of samples of aggregate taken at the same locations shall show the results of the current test as well as the average results of the five most recent tests including the current test. The Contractor may adopt approved limits for control coarser than the specification limits for samples taken other than as delivered to the mixer to allow for degradation during handling.

b. Corrective Action for Grading. When the amount passing any sieve is outside the specification limits, the coarse aggregate shall be immediately resampled and retested. If the second sample fails on any sieve, that fact shall be reported to the Contracting Officer, and steps taken to correct the grading. Where two consecutive averages of 5 tests are outside specification limits, the operation shall be considered out of control and shall be reported to the Contracting Officer, paving shall be stopped, and immediate steps shall be taken to correct the grading.

3.12.2.3 Quality of Aggregates

Thirty days prior to the start of concrete placement, the Contractor shall perform all tests specified for aggregate quality, including deleterious materials. In addition, after the start of paving, the Contractor shall perform similar tests for aggregate quality at least once every month, and when the source of aggregate or aggregate quality changes. Testing interval may be increased to three months when the previous two tests indicate the aggregate meets all

quality requirements. Samples tested after the start of concrete placement shall be taken immediately prior to entering the concrete mixer.

3.12.2.4 Scales, Batching and Recording

a. Weighing Accuracy. The accuracy of the scales shall be checked by test weights prior to start of concrete operations and at least once every month for conformance with specified requirements. Such tests shall also be made as directed whenever there are variations in properties of the fresh concrete that could result from batching errors.

b. Batching and Recording Accuracy. Once a week the accuracy of each batching and recording device shall be checked during a weighing operation by noting and recording the required mass, recorded mass, and the actual mass batched. The Contractor shall test and ensure that the devices for dispensing admixtures are operating properly and accurately.

c. Corrective Action. When either the weighing accuracy or batching accuracy does not comply with specification requirements, the plant shall not be operated until necessary adjustments or repairs have been made. Discrepancies in recording accuracies shall be corrected immediately.

3.12.2.5 Batch-Plant Control

The measurement of all constituent materials including cementitious materials, each size of aggregate, water, and admixtures shall be continuously controlled. The aggregate masses and amount of added water shall be adjusted as necessary to compensate for free moisture in the aggregates. The amount of air-entraining agent shall be adjusted to control air content within specified limits. A report shall be prepared indicating type and source of cement used, type and source of pozzolan or slag used, amount and source of admixtures used, aggregate source, the required aggregate and water masses per cubic yard,amount of water as free moisture in each size of aggregate, and the batch aggregate and water masses per cubic yard for each class of concrete batched during each day's plant operation.

3.12.2.6 Concrete Mixture

a. Air Content Testing. Air content tests shall be made when test specimens are fabricated. In addition, at least two other tests for air content shall be made on randomly selected batches of each separate concrete mixture produced during each 8-hour period of paving. Additional tests shall be made when excessive variation in workability is reported by the placing foreman or Government inspector. Tests shall be made in accordance with ASTM C 231. Test results shall be plotted on control charts which are kept current and shall, at all times, be readily available to the Government and shall be submitted weekly. Copies of the current control charts shall be kept in the field by testing crews and results plotted as tests are made. When a single test result reaches either the upper or lower action limit, a second test shall immediately be made. The results of the two tests shall be averaged and this average used as the air content of the batch to plot on both the air content and the control chart for range, and for determining need for any remedial action. The result of each test, or average as noted in the previous sentence, shall be plotted on a separate control chart for each mixture on which an

average line is set at the midpoint of the specified air content range from paragraph SPECIFIED CONCRETE STRENGTH AND OTHER PROPERTIES. An upper warning limit and a lower warning limit line shall be set 1.0 percentage point above and below the average line, respectively. An upper action limit and a lower action limit line shall be set 1.5 percentage points above and below the average line, respectively. The range between each two consecutive tests shall be plotted on a secondary control chart for range where an upper warning limit is set at 2.0 percentage points and an upper action limit is set at 3.0 percentage points. Samples for air content shall be taken at the paving site. The Contractor shall deliver the concrete to the paving site at the stipulated air content. If the Contractor's materials or transportation methods cause air content loss between the mixer and the paving site, correlation samples shall be taken at the paving site as required by the Contracting Officer, and the air content at the mixer controlled as directed.

b. Air Content Corrective Action. Whenever points on the control chart for percent air reach either warning limit, an adjustment shall immediately be made in the amount of air-entraining admixture batched. As soon as practical after each adjustment, another test shall be made to verify the result of the adjustment. Whenever a point on the secondary control chart for range reaches the warning limit, the admixture dispenser shall be recalibrated to insure that it is operating accurately and with good reproducibility. Whenever a point on either control chart (single test or result of two tests made concurrently, as specified above) reaches an action limit line, the air content shall be considered out of control and the paving operation shall immediately be halted until the air content is under control. Additional air content tests shall be made when paving is restarted.

c. Slump Testing. Slump tests shall be made when test specimens are fabricated. In addition, at least four other slump tests shall be made on randomly selected batches in accordance with ASTM C 143 for each separate concrete mixture produced during each 8-hour or less period of concrete production each day. Also, additional tests shall be made when excessive variation in workability is reported by the placing foreman or Government inspector. Test results shall be plotted on control charts which shall at all times be readily available to the Government and shall be submitted weekly. Copies of the current control charts shall be kept in the field by testing crews and results plotted as tests are made. When a single slump test reaches or goes beyond the upper action limit, a second test shall immediately be made. The results of the two tests shall be averaged and this average used as the slump of the batch to plot on both the control chart for slump and the chart for range, and for determining need for any remedial action. An upper warning limit shall be set at 1/2 inch below the maximum allowable slump on separate control charts for slump used for each type of mixture as specified in paragraph, SPECIFIED CONCRETE STRENGTH AND OTHER PROPERTIES, and an upper action limit line shall be set at the maximum allowable slump, as specified in the same paragraph for fixed form paving or as selected by the Contractor at the start of the project for slipform paving. The range between each consecutive slump test for each type of mixture shall be plotted on a single control chart for range on which an upper action limit is set at 1-1/2 inches. Samples for slump shall be taken at the paving site. The Contractor is responsible for delivering the concrete to the paving site at the stipulated slump. If the Contractor's materials or transportation methods cause slump loss between the mixer and the paving site, correlation samples shall

be taken at the paving site as required by the Contracting Officer, and the slump at the mixer controlled as directed.

d. Slump Corrective Action. Whenever points on the control charts for slump reach the upper warning limit, an approved adjustment shall immediately be made in the batch masses of water and fine aggregate. The adjustments are to be made so that the total water content does not exceed that amount allowed by the maximum w/c specified, based on aggregates which are in a saturated surface dry condition. When a slump result (average of two tests made concurrently, as specified above) exceeds the upper action limit, no further concrete shall be delivered to the paving site until proper adjustments have been made. Immediately after each adjustment, another test shall be made to verify the correctness of the adjustment. Whenever two consecutive individual slump tests, made during a period when there was no adjustment of batch masses, produce a point on the control chart for range at or above the upper action limit, the paving operation shall immediately be halted, and the Contractor shall take approved steps to bring the slump under control. Additional slump tests shall be made as directed.

e. Temperature. The temperature of the concrete shall be measured when compressive strength specimens are fabricated. Measurement shall be in accordance with ASTM C 1064/C 1064M. The temperature shall be reported along with the compressive strength data.

3.12.2.7 Concrete Strength Testing for CQC

Contractor Quality Control operations for concrete strength shall consist of the following steps:

a. Take samples for strength tests at the paving site. Fabricate and cure test cylinders in accordance with ASTM C 31/C 31M; test them in accordance with ASTM C 39.

b. Fabricate and cure 2 test cylinders per sublot from the same batch or truckload and at the same time acceptance cylinders are fabricated and test them for compressive strength at 7-day age.

c. Average all 8 compressive tests per lot. Convert this average 7-day compressive strength per lot to equivalent 28-day flexural strength using the Correlation Ratio determined during mixture proportioning studies.

d. Compare the equivalent 28-day flexural strength from the conversion to the Average Flexural Strength Required for Mixtures from paragraph of same title.

e. If the equivalent average 28-day strength for the lot is below the Average Flexural Strength Required for Mixtures by 20 psi flexural strength or more, at any time, adjust the mixture to increase the strength, as approved.

f. If the equivalent average 28-day strength is above the Average Flexural Strength Required for Mixtures by 20 psi flexural strength or more for 2 consecutive days, the Contractor will be permitted to adjust the mixture to decrease the strength, as approved.

g. The Contractor's CQC testing agency shall maintain up-to-date control charts for strength, showing the 7-day CQC compressive strength, the 14-day compressive strength (from acceptance tests) and the 28-day equivalent flexural strength of each of these for each lot.

3.12.2.8 Inspection Before Placing

Underlying materials, construction joint faces, forms, reinforcing, dowels, and embedded items shall be inspected by the Contractor in sufficient time prior to each paving operation in order to certify to the Contracting Officer that they are ready to receive concrete. The results of each inspection shall be reported in writing.

3.12.2.9 Paving

a. Paving Inspection. The placing foreman shall supervise all placing and paving operations, shall determine that the correct quality of concrete is placed in each location as shown and that finishing is performed as specified; shall be responsible for measuring and recording concrete temperatures and ambient temperature hourly during placing operations, weather conditions, time of placement, volume of concrete placed, and method of paving and any problems encountered.

b. Placing and Paving Corrective Action. The paving foreman shall not permit batching and paving to begin until it has been verified that an adequate number of vibrators in working order and with competent operators are available. Paving shall not be continued if piles of concrete exist or if the concrete is inadequately consolidated or if surface finish is not satisfactory. If any batch of concrete fails to meet the temperature requirements, immediate steps shall be taken to improve temperature controls.

3.12.2.10 Vibrators

a. Vibrator Testing and Use. The frequency and amplitude of each vibrator shall be determined in accordance with COE CRD-C 521 prior to initial use and at least once a month when paving is in progress. Additional tests shall be made as directed when a vibrator does not appear to be adequately consolidating the concrete. The frequency shall be determined while the vibrator is operating in concrete with the tachometer being held against the upper end of the vibrator head while almost submerged and just before the vibrator is withdrawn from the concrete. The amplitude shall be determined with the head vibrating in air. Two measurements shall be taken, one near the tip and another near the upper end of the vibrator head, and these results averaged. The make, model, type, and size of the vibrator and frequency and amplitude results shall be reported in writing.

b. Vibrator Corrective Action. Any vibrator not meeting the requirements of subparagraphs, Paver-Finisher and Consolidation, shall be immediately removed from service and repaired or replaced.

3.12.2.11 Curing Inspection

a. Moist Curing Inspections. At least twice each shift, and not less than four times per day (never more than 7 hours apart) on both work and non-work days, an

inspection shall be made of all areas subject to moist curing. The surface moisture condition shall be noted and recorded.

b. Moist Curing Corrective Action. When any inspection finds an area of inadequate curing, immediate corrective action shall be taken, and the required curing period for the area shall be extended by 1 day.

c. Membrane Curing Inspection. No curing compound shall be applied until the Contractor has verified that the compound is properly mixed and ready for spraying. At the end of each day's operation, the quantity of compound used shall be determined by measurement of the container and the area of concrete surface covered; the Contractor shall then compute the rate of coverage in square feet per gallon and shall also note whether or not coverage is uniform. All this shall be reported daily.

d. Membrane Curing Corrective Action. When the coverage rate of the curing compound is less than that specified or when the coverage is not uniform, the entire surface shall be sprayed again.

e. Sheet Curing Inspection. At least once each shift and once per day on non-work days, an inspection shall be made of all areas being cured using impervious sheets. The condition of the covering and the tightness of the laps and tapes shall be noted and recorded.

f. Sheet Curing Corrective Action. When a daily inspection report lists any tears, holes, or laps or joints that are not completely closed, the tears and holes shall promptly be repaired or the sheets replaced, the joints closed, and the required curing period for those areas shall be extended by 1 day.

3.12.2.12 Cold-Weather Protection

At least once each shift and once per day on non-work days, an inspection shall be made of all areas subject to cold-weather protection. Any deficiencies shall be noted, corrected, and reported.

3.12.2.13 Mixer Uniformity

a. Stationary Mixers. Prior to the start of concrete placing and once every 4 months when concrete is being placed, or once for every 50,000 cubic yards of concrete placed, whichever results in the longest time interval, uniformity of concrete mixing shall be determined in accordance with COE CRD-C 55. The original test shall be a Regular Test. After the mixing operation has been tested and approved, subsequent tests shall be Abbreviated Tests.

b. Truck Mixers. Prior to the start of concrete placing and at least once every 4 months when concrete is being placed, uniformity of concrete mixing shall be determined in accordance with ASTM C 94/C 94M. The truck mixers shall be selected randomly for testing. When satisfactory performance is found in one truck mixer, the performance of mixers of substantially the same design and condition of the blades may be regarded as satisfactory.

c. Mixer Uniformity Corrective Action. When a mixer fails to meet mixer uniformity requirements, either the mixing time shall be increased, batching sequence changed, batch size reduced, or adjustments shall be made to the mixer until compliance is achieved. After adjustments have been made, another uniformity test shall be made.

3.12.2.14 Reports

All results of tests or inspections conducted shall be reported informally as they are completed and in writing daily. A weekly report shall be prepared for the updating of control charts covering the entire period from the start of the construction season through the current week. During periods of cold-weather protection, reports of pertinent temperatures shall be made daily. These requirements do not relieve the Contractor of the obligation to report certain failures immediately as required in preceding paragraphs. Such reports of failures and the action taken shall be confirmed in writing in the routine reports. The Contracting Officer has the right to examine all contractor quality control records.

END OF SECTION

This page intentionally blank

SECTION 02760 (R)

FIELD MOLDED SEALANTS FOR SEALING JOINTS IN RIGID PAVEMENTS

1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in this text by the basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 509	(1994) Elastomeric Cellular Preformed Gasket and Sealing Material
ASTM D 789	(1998) Determination of Relative Viscosity and Moisture Content of Polyamide (PA)
ASTM D 3405	(1997) Joint Sealants, Hot-Applied, for Concrete and Asphalt Pavements
ASTM D 3569	(1995) Joint Sealant, Hot-Applied, Elastomeric, Jet-Fuel-Resistant-Type for Portland Cement Concrete Pavements
ASTM D 5893	(1996) Cold Applied, Single Component Chemically Curing Silicon Joint Sealant for Portland Cement Concrete Pavement

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01300 SUBMITTAL PROCEDURES:

Product Data

Manufacturer's Recommendations; G.

Where installation procedures, or any part thereof, are required to be in accordance with the manufacturer's recommendations, printed copies of these recommendations, 14 days prior to use on the project. Installation of the material will not be allowed until the recommendations are received. Failure to furnish these recommendations can be cause for rejection of the material.

Construction Equipment List; G.

List of proposed equipment to be used in performance of construction work including descriptive data, 14 days prior to use on the project.

Samples

Materials; G.

Samples of the materials (sealant, primer if required, and backup material), in sufficient quantity for testing and approval 60 days prior to the beginning of work. No material will be allowed to be used until it has been approved.

1.3 EQUIPMENT

Machines, tools, and equipment used in the performance of the work required by this section shall be approved before the work is started and shall be maintained in satisfactory condition at all times.

1.3.1 Joint Cleaning Equipment

1.3.1.1 Tractor-Mounted Routing Tool

The routing tool used for removing old sealant from the joints shall be of such shape and dimensions and so mounted on the tractor that it will not damage the sides of the joints. The tool shall be designed so that it can be adjusted to remove the old material to varying depths as required. The use of V-shaped tools or rotary impact routing devices will not be permitted. Hand-operated spindle routing devices may be used to clean and enlarge random cracks.

1.3.1.2 Concrete Saw

A self-propelled power saw with water-cooled diamond or abrasive saw blades will be provided for cutting joints to the depths and widths specified or for refacing joints or cleaning sawed joints where sandblasting does not provide a clean joint.

1.3.1.3 Sandblasting Equipment

Sandblasting equipment shall include an air compressor, hose, and long-wearing venturi-type nozzle of proper size, shape and opening. The maximum nozzle opening should not exceed 1/4 inch. The air compressor shall be portable and shall be capable of furnishing not less than 150 cubic feet per minute and maintaining a line pressure of not less than 90 psi at the nozzle while in use. Compressor capability under job conditions must be demonstrated before approval. The compressor shall be equipped with traps that will maintain the compressed air free of oil and water. The nozzle shall have an adjustable guide that will hold the nozzle aligned with the joint approximately 1 inch above the pavement surface. The height, angle of inclination and the size of the nozzle shall be adjusted as necessary to secure satisfactory results.

1.3.1.4 Waterblasting Equipment

Waterblasting equipment shall include a trailer-mounted water tank, pumps, high-pressure hose, wand with safety release cutoff control, nozzle, and auxiliary water resupply equipment. The water tank and auxiliary resupply equipment shall be of sufficient capacity to permit continuous operations. The nozzle shall have an adjustable guide that will hold the nozzle aligned with the joint approximately 1 inch above the pavement surface. The height, angle of inclination and the size of the nozzle shall be adjustable as necessary to obtain satisfactory results. A pressure gauge mounted at the pump shall show at all times the pressure in pounds per square inch at which the equipment is operating.

1.3.1.5 Hand Tools

Hand tools may be used, when approved, for removing defective sealant from a crack and repairing or cleaning the crack faces.

1.3.2 Sealing Equipment

1.3.2.1 Cold-Applied, Single-Component Sealing Equipment

The equipment for installing ASTM D 5893 single component joint sealants shall consist of an extrusion pump, air compressor, following plate, hoses, and nozzle for transferring the sealant from the storage container into the joint opening. The dimension of the nozzle shall be such that the tip of the nozzle will extend into the joint to allow sealing from the bottom of the joint to the top. The initially approved equipment shall be maintained in good working condition, serviced in accordance with the supplier's instructions, and shall not be altered in any way without obtaining prior approval. Small hand-held air-powered equipment (i.e., caulking guns) may be used for small applications.

1.2 TRIAL JOINT SEALANT INSTALLATION

Prior to the cleaning and sealing of the joints for the entire project, a test section of at least 200 feet long shall be prepared using the specified materials and approved equipment, so as to demonstrate the proposed joint preparation and sealing of all types of joints in the project. Following the completion of the test section and before any other joint is sealed, the test section shall be inspected to determine that the materials and installation meet the requirements specified. If it is determined that the materials or installation do not meet the requirements, the materials shall be removed, and the joints shall be recleaned and resealed at no cost to the Government. When the test section meets the requirements, it may be incorporated into the permanent work and paid for at the contract unit price per linear foot for sealing items scheduled. All other joints shall be prepared and sealed in the manner approved for sealing the test section.

1.3 DELIVERY AND STORAGE

Materials delivered to the job site shall be inspected for defects, unloaded, and stored with a minimum of handling to avoid damage. Storage facilities shall be provided by the Contractor at the job site for maintaining materials at the temperatures and conditions recommended by the manufacturer.

1.4 ENVIRONMENTAL CONDITIONS

The ambient air temperature and the pavement temperature within the joint wall shall be a minimum of 50 degrees F and rising at the time of application of the materials. Sealant shall not be applied if moisture is observed in the joint.

2 PRODUCTS

2.1 SEALANTS

Materials for sealing cracks in the various paved areas indicated on the drawings shall be as follows:

Area	Sealing Material
As designated on the plans	ASTM D 5893 Dow Corning 890-SL, or approved equal.

2.2 PRIMERS

Primers, when their use is recommended by the manufacturer of the sealant, shall be as recommended by the manufacturer of the sealant.

2.3 BACKUP MATERIALS

The backup material shall be a compressible, nonshrinking, nonstaining, nonabsorbing material and shall be nonreactive with the joint sealant. The material shall have a melting point at least 5 degrees F greater than the pouring temperature of the sealant being used when tested in accordance with ASTM D 789. The material shall have a water absorption of not more than 5 percent of the sample weight when tested in accordance with ASTM C 509. The backup material shall be 25 plus or minus 5 percent larger in diameter than the nominal width of the crack.

2.4 BOND BREAKING TAPES

The bond breaking tape or separating material shall be a flexible, nonshrinkable, nonabsorbing, nonstaining, and nonreacting adhesive-backed tape. The material shall have a melting point at least 5 degrees F greater than the pouring temperature of the sealant being used when tested in accordance with ASTM D 789. The bond breaker tape shall be approximately 1/8 inch wider than the nominal width of the joint and shall not bond to the joint sealant.

3 EXECUTION

3.1 PREPARATION OF JOINTS

Immediately before the installation of the sealant, the joints shall be thoroughly cleaned to remove all laitance, curing compound, filler, protrusions of hardened concrete, and old sealant from the sides and upper edges of the joint space to be sealed.

3.1.1 Existing Sealant Removal

The in-place sealant shall be cut loose from both joint faces and to the depth shown on the drawings, using the tractor-mounted routing equipment concrete saw or waterblaster as specified in paragraph EQUIPMENT. Depth shall be sufficient to accommodate any separating or backup material that is required to maintain the depth of new sealant to be installed. Prior to further cleaning operations, all loose old sealant remaining in the joint opening shall be removed by blowing with compressed air. Hand tools may be required to remove sealant from random cracks. Chipping, spalling, or otherwise damaging the concrete will not be allowed.

3.1.2 Sawing

3.1.2.1 Refacing of Joints

Refacing of joints shall be accomplished using a concrete saw as specified in paragraph EQUIPMENT to remove all residual old sealant and a minimum of concrete from the joint face to provide exposure of newly cleaned concrete, and, if required, to enlarge the joint opening to the width and depth shown on the drawings. The blade shall be stiffened with a sufficient number of suitable dummy (used) blades or washers. Immediately following the sawing operation, the joint opening shall be thoroughly cleaned using a water jet to remove all saw cuttings and debris.

3.1.2.2 Refacing of Random Cracks

Sawing of the cracks shall be accomplished using a power-driven concrete saw as specified in paragraph EQUIPMENT. The saw blade shall be 6 inches or less in diameter to enable the saw to follow the trace of the crack. The blade shall be stiffened as necessary with suitable dummy (or used) blades or washers. Immediately following the sawing operation, the crack opening shall be thoroughly cleaned using a water jet to remove all saw cuttings and debris.

3.1.3 Sandblasting or Waterblasting

The newly exposed concrete joint faces and the pavement surfaces extending a minimum of 1/2 inch from the joint edges shall be sandblasted or waterblasted clean. A multiple-pass technique shall be used until the surfaces are free of dust, dirt, curing compound, filler, old sealant residue, or any foreign debris that might prevent the bonding of the sealant to the concrete. After final cleaning and immediately prior to sealing, the joints shall be blown out with compressed air and left completely free of debris and water.

3.1.4 Back-Up Material

When the joint opening is of a greater depth than indicated for the sealant depth, the lower portion of the joint opening shall be plugged or sealed off using a back-up material to prevent the entrance of the sealant below the specified depth. Care shall be taken to ensure that the backup material is placed at the specified depth and is not stretched or twisted during installation.

3.1.5 Bond Breaking Tape

Where inserts or filler materials contain bitumen, or the depth of the joint opening does not allow for the use of a backup material, a bond breaker separating tape will be inserted to prevent incompatibility with the filler materials and three-sided adhesion of the sealant. The tape shall be securely bonded to the bottom of the joint opening so it will not float up into the new sealant.

3.1.6 Rate of Progress of Joint Preparation

The stages of joint preparation which include sandblasting, air pressure cleaning and placing of the back-up material shall be limited to only that lineal footage that can be sealed during the same day.

3.2 PREPARATION OF SEALANT

3.2.1 Single-Component, Cold-Applied Sealants

The ASTM D 5893 sealant and containers shall be inspected prior to use. Any materials that contain water, hard caking of any separated constituents, nonreversible jell, or materials that are otherwise unsatisfactory shall be rejected. Settlement of constituents in a soft mass that can be readily and uniformly remixed in the field with simple tools will not be cause for rejection.

3.3 INSTALLATION OF SEALANT

3.3.1 Time of Application

Joints shall be sealed immediately following final cleaning of the joint walls and following the placement of the separating or backup material. Open joints that cannot be sealed under the conditions specified, or when rain interrupts sealing operations shall be recleaned and allowed to dry prior to installing the sealant.

3.3.2 Sealing Joints

Immediately preceding, but not more than 50 feet ahead of the joint sealing operations, a final cleaning with compressed air shall be performed. The joints shall be filled from the bottom up to 3/8 inch plus 1/8 inch or minus 0 inchesbelow the pavement surface. Excess or spilled sealant shall be removed from the pavement by approved methods and shall be discarded. The sealant shall be installed in such a manner as to prevent the formation of voids and entrapped air. In no case shall gravity methods or pouring pots be used to install the sealant material. Traffic shall not be permitted over newly sealed pavement until authorized by the Contracting Officer. When a primer is recommended by the manufacturer, it shall be applied evenly to the joint faces in accordance with the manufacturer's instructions. Joints shall be checked frequently to ensure that the newly installed sealant is cured to a tack-free condition within the time specified.

3.4 INSPECTION

3.4.1 Joint Cleaning

Joints shall be inspected during the cleaning process to correct improper equipment and cleaning techniques that damage the concrete pavement in any manner. Cleaned joints shall be approved prior to installation of the separating or back-up material and joint sealant.

3.4.2 Joint Sealant Application Equipment

The application equipment shall be inspected to ensure conformance to temperature requirements, proper proportioning and mixing (if two-component sealant) and proper installation. Evidences of bubbling, improper installation, failure to cure or set shall be cause to suspend operations until causes of the deficiencies are determined and corrected.

3.4.3 Joint Sealant

The joint sealant shall be inspected for proper rate of cure and set, bonding to the joint walls, cohesive separation within the sealant, reversion to liquid, entrapped air and voids. Sealants exhibiting any of these deficiencies at any time prior to the final acceptance of the project shall be removed from the joint, wasted, and replaced as specified herein at no additional cost to the Government.

3.5 CLEAN-UP

Upon completion of the project, all unused materials shall be removed from the site and the pavement shall be left in a clean condition.

END OF SECTION

This page intentionally blank

SECTION 02762 (R)

COMPRESSION JOINT SEALS FOR CONCRETE PAVEMENTS

1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in this text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 2628	(1991; R 1998) Preformed Polychloroprene Elastomeric Joint Seals for Concrete Pavements
ASTM D 2835	(1989; R 1998) Lubricant for Installation of Preformed Compression Seals in Concrete Pavements

U.S. ARMY CORPS OF ENGINEERS (USACE)

COE CRD-C 548	(1988) Jet-Fuel and Heat Resistant Preformed Polychloroprene Elastomeric Joint Seals for Rigid Pavements

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01300 SUBMITTAL PROCEDURES:

Product Data

Equipment; G

List of proposed equipment to be used in the performance of construction work, including descriptive data, 14 days prior to use on the project.

Manufacturer's Instructions; G

Where installation procedures are required in accordance with the manufacturer's recommendations, printed copies of manufacturers' instructions, 14 days prior to use on the project.

Certificates

Compression Seals; [G]
Lubricant/Adhesive; G

Certificate of Compliance.

1.3 EQUIPMENT

Machines, tools, and equipment used in the performance of the work required by this section shall be approved before the work is started and shall be maintained in satisfactory condition at all times.

1.3.1 Joint Cleaning Equipment

1.3.1.1 Concrete Saw

A self-propelled power saw with water-cooled diamond saw blades shall be provided for cutting joints to the depths and widths specified and for removing filler, existing old joint seal, or other material embedded in the joints or adhered to the joint faces.

1.3.1.2 Sandblasting Equipment

Sandblasting equipment shall include an air compressor, hose, and a long-wearing venturi-type nozzle of proper size, shape, and opening. The maximum nozzle opening should not exceed 1/4 inch. The air compressor shall be portable and shall be capable of furnishing not less than 150 cubic feet per minute and maintaining a line pressure of not less than 90 psi at the nozzle while in use. The compressor shall be equipped with traps that will maintain the compressed air free of oil and water. The nozzle shall have an adjustable guide that will hold the nozzle aligned with the joint about 1 inch above the pavement surface and will direct the blast to clean the joint walls. The height, angle of inclination, and the size of the nozzle shall be adjusted as necessary to ensure satisfactory results.

1.3.1.3 Waterblasting Equipment

Waterblasting equipment shall include a trailer-mounted water tank, pumps, high-pressure hose, a wand with safety release cutoff controls, nozzle, and auxiliary water resupply equipment. The water tank and auxiliary water resupply equipment shall be of sufficient capacity to permit continuous operations. The pumps, hoses, wand, and nozzle shall be of sufficient capacity to permit the cleaning of both walls of the joint and the pavement surface for a width of at least 1/2 inch on either side of the joint. A pressure gauge mounted at the pump shall show at all times the pressure in psi at which the equipment is operating.

1.3.2 Sealing Equipment

Equipment used to install the compression seal shall place the compression seal to the prescribed depths within the specified tolerances without cutting, nicking, twisting, or otherwise damaging the seal. The equipment shall be capable of placing the seal with not more than two percent longitudinal stretch or compression of the seal during installation. The machine shall be an automatic self-propelled joint seal application equipment and engine powered. The machine shall include a reservoir for the lubricant/adhesive, a device for conveying the lubricant/adhesive in the proper quantities to the sides of the compression seal or the sidewalls of the joints, a reel capable of holding one full spool of compression seal, and a power-driven apparatus for feeding the joint seal through a compression device and inserting the seal into the joint. The equipment shall also include a guide to maintain the proper course along the joint being sealed. The machine shall at all times be operated by an experienced operator.

1.4 TRIAL JOINT SEAL AND LUBRICANT/ADHESIVE INSTALLATION

Prior to the cleaning and sealing of the joints for the entire project, a test section at least 200 feet long shall be prepared at a designated location in the project pavement, using the specified materials and the approved equipment to demonstrate the proposed joint preparation and sealing of all types of joints in the project. Following the completion of the trial length and before any other joint is sealed, the trial joints will be inspected by the Government to determine that the materials and installation meet the requirements specified. If materials or installation do not meet requirements, the materials shall be removed, and the joints shall be recleaned and resealed at no cost to the Government. No other joints shall be sealed until the test installation has been approved. If the trial section is approved, it may be incorporated into the permanent work. Other joints shall be sealed in the manner approved for sealing the trial joint.

1.5 DELIVERY AND STORAGE

Materials delivered to the jobsite shall be inspected for defects, unloaded, and stored with a minimum of handling to avoid damage. Storage facilities shall protect materials from weather and shall maintain materials at temperatures recommended by the manufacturer.

1.6 ENVIRONMENTAL CONDITIONS

The ambient temperature and the pavement temperature within the joint wall shall be at least 35 degrees F and rising at the time of installation of the materials. Sealant installation will not be allowed if moisture or foreign material is observed in the joint.

2 PRODUCTS

2.1 COMPRESSION SEALS

Compression joint seal materials shall be a vulcanized elastomeric compound using polychloroprene as the only base polymer. The material and manufactured seal shall conform to ASTM D 2628 and COE CRD-C 548. The joint seal shall be a labyrinth type seal. The uncompressed depth of the face of the compression seal (that is to be bonded to the joint wall) shall be greater than the uncompressed width of the seal, except that for seals 1 inch or greater in width, the depth need be only 1 inch or greater. The actual width of the uncompressed seal for construction and contraction joints shall be 13/16 or 1 inch. The tolerance on the seal shall be plus 1/8 inch or minus 1/16 inch.

2.2 LUBRICANT/ADHESIVE

Lubricant/adhesive used for the compression elastomeric joint seal shall be a one-component compound conforming to ASTM D 2835.

3 EXECUTION

3.1 PREPARATION OF JOINTS

Immediately before installation of the compression joint seal, the joints shall be thoroughly cleaned to remove laitance, filler, existing sealer, foreign material and protrusions of hardened concrete from the sides and upper edges of the joint space to be sealed. Cleaning

shall be by sandblasting or waterblasting and shall extend along pavement surfaces at least 1/2 inch on either side of the joint. After final cleaning and immediately prior to sealing, the joints shall be blown out with compressed air and left completely free of debris and water. The Contractor shall demonstrate that the selected cleaning operation meets the cleanliness requirements. Any irregularity in the joint face which would prevent uniform contact between the joint seal and the joint face shall be corrected prior to the installation of the joint seal.

3.1.1 Sawing

Joints shall be cleaned and opened to the specified width and depth by sawing. Immediately following the sawing operation, the joint faces and opening shall be thoroughly cleaned using a water jet to remove saw cuttings or debris remaining on the faces or in the joint opening. Compression seal shall be installed within 3 calendar days of the time the joint cavity is sawed. Depth of the joint cavity shall be per manufacturer's instructions. The saw cut for the joint seal cavity shall be centered over the joint line. The nominal width of the sawed joint seal cavity shall be as follows; the actual width shall be within a tolerance of plus or minus 1/16 inch:

a. If a nominal 13/16-inch wide compression seal is furnished, the nominal width of the saw cut shall be 8/16 inches when the pavement temperature at the time of sawing is between +25 and +80 degrees F. If the pavement temperature at the time of sawing is above this range, the nominal width of the saw cut shall be decreased 1/16 inch. If the pavement temperature at the time of sawing is below this range, the nominal width of the saw cut shall be increased 1/16 inch.

b. If a nominal 1-inch wide compression seal is furnished, the nominal width of the saw cut shall be 9/16 inches when the pavement temperature at the time of sawing is between +25 and +140 degrees F. If the pavement temperature at the time of sawing is above this range, the nominal width of the saw cut shall be decreased 1/16 inch. If the pavement temperature at the time of sawing is below this range, the nominal width of the saw cut shall be increased 1/16 inch.

c. The pavement temperature shall be measured in the presence of the Contracting Officer. Measurement shall be made each day before commencing sawing and at any other time during the day when the temperature appears to be varying from the allowable sawing range.

3.1.2 Sandblast Cleaning

A multiple pass sandblasting technique shall be used until the surfaces are free of dust, dirt, curing compound, or any residue that might prevent ready insertion or uniform contact of the seal and bonding of the lubricant/adhesive to the concrete.

3.1.3 Waterblast Cleaning

A multiple pass waterblast technique shall be used until the surfaces are free of dust, dirt, curing compound, or any residue that might prevent ready insertion or uniform contact of the seal and bonding of the lubricant/adhesive to the concrete.

3.1.4 Rate of Progress

Sandblasting or waterblasting of joint faces shall be limited to the length of joint that can be sealed during the same workday.

3.2 INSTALLATION OF THE COMPRESSION SEAL

3.2.1 Time of Installation

Joints shall be sealed immediately within 3 calendar days of sawing the joint seal cavity and following concrete cure and the final cleaning of the joint walls. Open joints ready for sealing that cannot be sealed under the specified conditions shall be provided with an approved temporary seal to prevent infiltration of foreign material. When rain interrupts the sealing operations, the joints shall be washed, air pressure cleaned, and allowed to dry prior to installing the lubricant/adhesive and compression seal.

3.2.2 Sequence of Installation

Longitudinal joints shall be sealed first, followed by transverse joints. Seals in longitudinal joints shall be installed so that all transverse joint seals will be intact from edge to edge of the pavement. Intersections shall be made monolithic by use of joint seal adhesive and care in fitting the intersection parts together. Extender pieces of seal shall not be used at intersections. Any seal falling short at the intersection shall be removed and replaced with new seal at no additional cost to the Government. Seals that are required to change direction by more than 20 degrees, may require a poured sealant at the intersection. Poured sealant shall be per compression seal manufacturer's instructions.

3.3 SEALING OF JOINTS

The sides of the joint seal or the sides of the joint shall be covered with a coating of lubricant/adhesive and the seal installed as specified. Butt joints and seal intersections shall be coated with liberal applications of lubricant/ adhesive. Lubricant/adhesive spilled on the pavement shall be removed immediately to prevent setting on the pavement. The in-place joint seal shall be in an upright position and free from twisting, distortion, and cuts. Adjustments shall be made to the installation equipment and procedure, if the stretch exceeds 1 percent. Any seal exceeding 2 percent stretch shall be removed and replaced. The joint seal shall be placed at a uniform depth within the tolerances specified. In-place joint seal which fails to meet the specified requirements shall be removed and replaced with new joint seal at no cost to the Government. The compression joint seal shall be placed to a depth of 1/4 inch, plus or minus 1/8 inch, below the pavement surface except when the joint is beveled or has a radius at the surface, or unless otherwise directed. For beveled joints or joints with a radius at the surface, the compression joint seal shall be installed at a depth of 1/8 inch, plus or minus 1/8 inch, below the bottom of the edge of the bevel or radius. No part of the seal shall be allowed to project above the surface of the pavement or above the edge of the bevel or radius. The seal shall be installed in the longest practicable lengths in longitudinal joints and shall be cut at the joint intersections to provide continuous installation of the seal in the transverse joints. The lubricant/adhesive in the longitudinal joints shall be allowed to set for 1 hour prior to cutting at the joint intersections to reduce the possibility of shrinkage. For all transverse joints, the minimum length of the compression joint seal shall be the pavement width from edge to edge.

3.4 CLEAN-UP

Upon completion of the project, all unused materials shall be removed from the site, any lubricant/adhesive on the pavement surface shall be removed, and the pavement shall be left in clean condition.

3.5 QUALITY CONTROL PROVISIONS

3.5.1 Application Equipment

The application equipment shall be inspected to assure uniform application of lubricant/adhesive to the sides of the compression joint seal or the walls of the joint. If any equipment causes cutting, twisting, nicking, excessive stretching or compressing of the seal, or improper application of the lubricant/adhesive, the operation shall be suspended until causes of the deficiencies are determined and corrected.

3.5.2 Procedures

3.5.2.1 Quality Control Inspection

Quality control provisions shall be provided during the joint cleaning process to prevent or correct improper equipment and cleaning techniques that damage the concrete in any manner. Cleaned joints shall be approved by the Government prior to installation of the lubricant/adhesive and compression joint seal.

3.5.2.2 Conformance to Stretching and compression Limitations

Conformance to stretching and compression limitations shall be determined. The top surface of the compression seal shall be marked at 1 foot intervals in a manner clear and durable to enable length determinations of the seal. After installation, the distance between the marks shall be measured on the seal. If the stretching or compression exceeds 2 percent, the seal shall be removed and replaced with new joint at no additional cost to the Government. The seal shall be removed up to the last correct measurement. The seal shall be inspected a minimum of once per 400 feet of seal for compliance to the shrinkage or compression requirements. Measurements shall also be made at the same interval to determine conformance with depth and width of installation requirements. Compression seal that is not in conformance with specification requirements shall be removed and replaced with new joint seal at no additional cost to the Government.

3.5.2.3 Pavement Temperature

The pavement temperature shall be determined by placing a thermometer in the initial saw cut for the joint and the reading shall be recorded. The thermometer shall remain in the joint for an adequate time to provide a control reading.

3.5.3 Product

The joint sealing system (compression seal and lubricant/adhesive) shall be inspected for proper rate of cure and bonding to the concrete, cuts, twists, nicks and other deficiencies. Seals exhibiting any defects, at any time prior to final acceptance of the project, shall be removed from the joint, wasted, and replaced in a satisfactory manner.

END OF SECTION

SECTION 02763 (R)

PAVEMENT MARKINGS

1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO M 247	(1981; R 1996) Glass Beads Used in Traffic Paint

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 792	(1998) Density and Specific Gravity (Relative Density) of Plastics by Displacement
ASTM D 4280	(1996) Extended Life Type, Nonplowable, Prismatic, Raised, Retroreflective Pavement Markers
ASTM D 4505	(1996) Preformed Plastic Pavement Marking Tape for Extended Service Life
ASTM E 28	(1999) Softening Point of Resins by Ring and Ball Apparatus

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

FS TT-B-1325	(Rev C; Notice 1; Canc. Notice 2) Beads (Glass Spheres) Retro-Reflective (Metric)
FS TT-P-1952	(Rev D; Canc. Notice 1) Paint, Traffic and Airfield Marking, Waterborne (Metric)

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Product Data

Equipment; G

Lists of proposed equipment, including descriptive data, and notifications of proposed Contractor actions as specified in this section. List of removal equipment shall include descriptive data indicating area of coverage per pass, pressure adjustment range, tank and flow capacities, and safety precautions required for the equipment operation.

Composition Requirements; G

Manufacturer's current printed product description and Material Safety Data Sheets (MSDS) for each type paint/color proposed for use.

Qualifications; G

Document certifying that personnel are qualified for equipment operation and handling of chemicals.

Test Reports

Sampling and Testing; G

Certified copies of the test reports, prior to the use of the materials at the jobsite.

Certificates

Volatile Organic Compound (VOC); G

Certificate stating that the proposed pavement marking paint meets the VOC regulations of the local Air Pollution Control District having jurisdiction over the geographical area in which the project is located.

1.3 DELIVERY AND STORAGE

All materials shall be delivered and stored in sealed containers that plainly show the designated name, formula or specification number, batch number, color, date of manufacture, manufacturer's name, and directions, all of which shall be plainly legible at time of use.

1.4 EQUIPMENT

All machines, tools and equipment used in the performance of the work shall be approved and maintained in satisfactory operating condition. Equipment operating on roads and runways shall display low speed traffic markings and traffic warning lights.

1.4.1 Paint Application Equipment

The equipment to apply paint to pavements shall be a self-propelled or mobile-drawn pneumatic spraying machine with suitable arrangements of atomizing nozzles and controls to obtain the specified results. The machine shall have a speed during application not less than 5 mph, and shall be capable of applying the stripe widths indicated, at the paint coverage rate specified in paragraph APPLICATION, and of even uniform thickness with clear-cut edges. The equipment used to apply the paint binder to airfield pavements shall be a self-propelled or mobile-drawn pneumatic spraying machine with an arrangement of atomizing nozzles

capable of applying a line width at any one time in multiples of 6 inches, from 6 inches to 36 inches. The paint applicator shall have paint reservoirs or tanks of sufficient capacity and suitable gauges to apply paint in accordance with requirements specified. Tanks shall be equipped with suitable air-driven mechanical agitators. The spray mechanism shall be equipped with quick-action valves conveniently located, and shall include necessary pressure regulators and gauges in full view and reach of the operator. Paint strainers shall be installed in paint supply lines to ensure freedom from residue and foreign matter that may cause malfunction of the spray guns. The paint applicator shall be readily adaptable for attachment of an air-actuated dispenser for the reflective media approved for use. Pneumatic spray guns shall be provided for hand application of paint in areas where the mobile paint applicator cannot be used.

1.4.2 Reflective Media Dispenser

The dispenser for applying the reflective media shall be attached to the paint dispenser and shall operate automatically and simultaneously with the applicator through the same control mechanism. The dispenser shall be capable of adjustment and designed to provide uniform flow of reflective media over the full length and width of the stripe at the rate of coverage specified in paragraph APPLICATION, at all operating speeds of the applicator to which it is attached.

1.4.3 Surface Preparation Equipment

1.4.3.1 Sandblasting Equipment

Sandblasting equipment shall include an air compressor, hoses, and nozzles of proper size and capacity as required for cleaning surfaces to be painted. The compressor shall be capable of furnishing not less than 150 cfm of air at a pressure of not less than 90 psi at each nozzle used, and shall be equipped with traps that will maintain the compressed air free of oil and water.

1.4.3.2 Waterblast Equipment

The water pressure shall be specified at 2600 psi at 140 degrees F in order to adequately clean the surfaces to be marked.

1.4.4 Marking Removal Equipment

Equipment shall be mounted on rubber tires and shall be capable of removing markings from the pavement without damaging the pavement surface or joint sealant. Waterblasting equipment shall be capable of producing an adjustable, pressurized stream of water. Sandblasting equipment shall include an air compressor, hoses, and nozzles. The compressor shall be equipped with traps to maintain the air free of oil and water.

1.4.4.1 Shotblasting Equipment

Shotblasting equipment shall be capable of producing an adjustable depth of removal of marking and pavement. Each unit shall be self-cleaning and self-contained, shall be able to confine dust and debris from the operation, and shall be capable of recycling the abrasive for reuse.

1.4.4.2 Chemical Equipment

Chemical equipment shall be capable of application and removal of chemicals from the pavement surface, and shall leave only non-toxic biodegradeable residue.

1.4.5 Traffic Controls

Suitable warning signs shall be placed near the beginning of the worksite and well ahead of the worksite for alerting approaching traffic from both directions. Small markers shall be placed along newly painted lines or freshly placed raised markers to control traffic and prevent damage to newly painted surfaces or displacement of raised pavement markers. Painting equipment shall be marked with large warning signs indicating slow-moving painting equipment in operation.

1.5 HAND-OPERATED, PUSH-TYPE MACHINES

All machines, tools, and equipment used in performance of the work shall be approved and maintained in satisfactory operating condition. Hand-operated push-type machines of a type commonly used for application of paint to pavement surfaces will be acceptable for marking small streets and parking areas. Applicator machine shall be equipped with the necessary paint tanks and spraying nozzles, and shall be capable of applying paint uniformly at coverage specified. Sandblasting equipment shall be provided as required for cleaning surfaces to be painted. Hand-operated spray guns shall be provided for use in areas where push-type machines cannot be used.

1.6 MAINTENANCE OF TRAFFIC

1.6.1 Airfield

The performance of work in the controlled zones of airfields shall be coordinated with the Contracting Officer and with the Flight Operations Officer. Verbal communications shall be maintained with the control tower before and during work in the controlled zones of the airfield. The control tower shall be advised when the work is completed. A radio for this purpose shall be provided by the Contractor and approved by the Contracting Officer.

1.7 WEATHER LIMITATIONS FOR REMOVAL

Pavement surface shall be free of snow, ice, or slush. Surface temperature shall be at least 40 degrees F and rising at the beginning of operations, except those involving shot or sand blasting. Operation shall cease during thunderstorms. Operation shall cease during rainfall, except for waterblasting and removal of previously applied chemicals. Waterblasting shall cease where surface water accumulation alters the effectiveness of material removal.

2 PRODUCTS

2.1 PAINT

The paint shall be homogeneous, easily stirred to smooth consistency, and shall show no hard settlement or other objectionable characteristics during a storage period of 6 months. Paints for airfields, roads, and streets shall conform to FS TT-P-1952, color as indicated . Pavement marking paints shall comply with applicable state and local laws enacted to ensure

compliance with Federal Clean Air Standards. Paint materials shall conform to the restrictions of the local Air Pollution Control District.

2.2 REFLECTIVE MEDIA

Reflective media for airfields shall conform to FS TT-B-1325, Type I, Gradation A.

3 EXECUTION

3.1 SURFACE PREPARATION

Surfaces to be marked shall be thoroughly cleaned before application of the pavement marking material. Dust, dirt, and other granular surface deposits shall be removed by sweeping, blowing with compressed air, rinsing with water or a combination of these methods as required. Rubber deposits, surface laitance, existing paint markings, and other coatings adhering to the pavement shall be completely removed with scrapers, wire brushes, sandblasting, approved chemicals, or mechanical abrasion as directed. Areas of old pavement affected with oil or grease shall be scrubbed with several applications of trisodium phosphate solution or other approved detergent or degreaser, and rinsed thoroughly after each application. After cleaning, oil-soaked areas shall be sealed with cut shellac to prevent bleeding through the new paint. Pavement surfaces shall be allowed to dry, when water is used for cleaning, prior to striping or marking. Surfaces shall be recleaned, when work has been stopped due to rain.

3.1.1 Pretreatment for Early Painting

Where early painting is required on rigid pavements, a pretreatment with an aqueous solution containing 3 percent phosphoric acid and 2 percent zinc chloride shall be applied to prepared pavement areas prior to painting.

3.1.2 Cleaning Existing Pavement Markings

In general, markings shall not be placed over existing pavement marking patterns. Existing pavement markings, which are in good condition but interfere or conflict with the newly applied marking patterns, shall be removed. Deteriorated or obscured markings that are not misleading or confusing or interfere with the adhesion of the new marking material do not require removal. New preformed and thermoplastic pavement markings shall not be applied over existing preformed or thermoplastic markings. Whenever grinding, scraping, sandblasting or other operations are performed the work must be conducted in such a manner that the finished pavement surface is not damaged or left in a pattern that is misleading or confusing. When these operations are completed the pavement surface shall be blown off with compressed air to remove residue and debris resulting from the cleaning work.

3.1.3 Cleaning Concrete Curing Compounds

On new Portland cement concrete pavements, cleaning operations shall not begin until a minimum of 21 days after the placement of concrete. All new concrete pavements shall be cleaned by either sandblasting or water blasting. When water blasting is performed, thermoplastic and preformed markings shall be applied no sooner than 24 hours after the

blasting has been completed. The extent of the blasting work shall be to clean and prepare the concrete surface as follows:

a. There is no visible evidence of curing compound on the peaks of the textured concrete surface.

b. There are no heavy puddled deposits of curing compound in the valleys of the textured concrete surface.

c. All remaining curing compound is intact; all loose and flaking material is removed.

d. The peaks of the textured pavement surface are rounded in profile and free of sharp edges and irregularities.

e. The surface to be marked is dry.

3.2 APPLICATION

All pavement markings and patterns shall be placed as shown on the plans and shall include reflective media.

3.2.1 Paint

Paint shall be applied to clean, dry surfaces, and only when air and pavement temperatures are above 40 degrees F and less than 95 degrees F. Paint temperature shall be maintained within these same limits. Paint shall be applied pneumatically with approved equipment at rate of coverage specified. The Contractor shall provide guide lines and templates as necessary to control paint application. Special precautions shall be taken in marking numbers, letters, and symbols. Edges of markings shall be sharply outlined. All pavement markings shall be painted twice, as described in the project drawings. The first, “temporary” application of paint shall be made during each phase of construction. The “final” application of paint shall be made after all of the concrete and asphalt pavements in the project are at least 30 days old.

3.2.1.1 Rate of Application

a. Reflective Markings: Pigmented binder shall be applied evenly to the pavement area to be coated at a rate of 105 plus or minus 5 square feet per gallon. Glass spheres shall be applied uniformly to the wet paint on airfield pavement at a rate of 8 plus or minus 0.5 pounds of glass spheres per gallon of paint.

b. Nonreflective Markings: None included.

3.2.1.2 Drying

The maximum drying time requirements of the paint specifications will be strictly enforced to prevent undue softening of bitumen, and pickup, displacement, or discoloration by tires of traffic. If there is a delay in drying of the markings, painting operations shall be discontinued until cause of the slow drying is determined and corrected.

3.2.2 Reflective Media

Application of reflective media shall immediately follow application of pigmented binder. Drop-on application of glass spheres shall be accomplished to insure that reflective media is evenly distributed at the specified rate of coverage. Should there be malfunction of either paint applicator or reflective media dispenser, operations shall be discontinued immediately until deficiency is corrected.

3.3 MARKING REMOVAL

Pavement markings shall be removed in the areas shown on the drawings. Markings designated for removal include but are not limited to temporary markings for displaced thresholds and temporary aircraft arresting system markings. Removal of marking shall be as complete as possible without damage to the surface. The removal process shall not expose pavement aggregate. After the markings are removed, the cleaned pavement surfaces shall exhibit adequate texture for remarking as specified in paragraph SURFACE PREPARATION. Contractor shall demonstrate removal of pavement marking in an area designated by the Contracting Officer. The demonstration area will become the standard for the remainder of the work.

3.3.1 Equipment Operation

Equipment shall be controlled and operated to remove markings from the pavement surface, prevent dilution or removal of binder from underlying pavement, and prevent emission of blue smoke from asphalt or tar surfaces.

3.3.2 Cleanup and Waste Disposal

The worksite shall be kept clean of debris and waste from the removal operations. Cleanup shall immediately follow removal operations in areas subject to air traffic. Debris shall be disposed of at approved sites.

END OF SECTION

This page intentionally blank

SECTION 02900 (R)

LANDSCAPE WORK

1 PART 1 GENERAL

1.1 SUMMARY

This Section includes provisions for the following items:

a. Seeding of disturbed areas.
b. Soil sterilization.

1.2 REFERENCES

Drawings and general provisions of Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

ANSI: American National Standards Institute, 1430 Broadway, New york, NY 10018, (212) 354-3300

ANSi Z60.1: American Standard for Nursery Stock

1.3 SUBMITTALS

1.3.1 General

Submit the following in accordance with Conditions of Contract and Division 1 Specification Sections.

1.3.2 Plant and Material Certifications

a. Certificates of inspection as required by governmental authorities.

b. Manufacturer's or vendor's certified analysis for soil amendments and fertilizer materials.

c. Label data substantiating that materials comply with specified requirements.

1.3.3 Planting Schedule

Proposed planting schedule, indicating dates for each type of landscape work during normal seasons for such work in area of site. Correlate with specified maintenance periods to provide maintenance from date of substantial completion. Once accepted, revise dates only as approved in writing, after documentation of reasons for delays.

1.4 QUALITY ASSURANCE

a. Subcontract landscape and seeding work to a firm specializing in landscape work.

b. Source Quality Control: Source of all landscape plants and materials will be made available to WQA.

c. General: Ship landscape materials with certificates of inspection required by governing authorities. Comply with regulations applicable to landscape materials.

d. Do not make substitutions. If specified landscape material is not obtainable, submit proof of non-availability to Architect, together with proposal for use of equivalent material.

e. Analysis and Standards: Package standard products with manufacturer's certified analysis. For other materials, provide analysis by recognized laboratory made in accordance with methods established by the Association of Official Agriculture Chemists, wherever applicable.

1.5 DELIVERY, STORAGE AND HANDLING

Deliver packaged materials in containers showing weight, analysis, and name of manufacturer. Protect materials from deterioration during delivery, and while stored at site.

1.6 JOB CONDITIONS

1.6.1 Utilities

Determine location of underground utilities and perform work in a manner which will avoid possible damage. Hand excavate, as required. Maintain grade stakes set by others unti removal is mutually agreed upon by parties concerned.

1.6.2 Excavation

When conditions detrimental to plant growth are encountered, such as rubble fill, adverse drainage conditions, or obstructions, notify the Contracting Officer or his representative before planting.

1.7 SEQUENCING AND SCHEDULING

Proceed with, and complete landscape work as rapidly as portions of site become available, working within seasonal limitations for each kind of landscape work required.

a. Plant or install materials during normal planting seasons for each type of plant material required.

b. Correlate planting with specified maintenance periods to provide maintenance from date of substantial completion.

1.8 SPECIAL PROJECT WARRANTY

The Contractor shall warrant all seed areas for a period of one year.

2 PRODUCTS

2.1 GRASS MATERIALS

Provide fresh, clean, new-crop seed complying with tolerance for purity and germination established by Official Seed Analysts of North America. Provide seed mixture composed of

grass species, proportions and minimum precentages of purity, germination, and maximum percentage of weed seed, as specified. Grass seed will be perennial seed, no annual seed. Seed must be less than two years old. Seed shall be applied by hydroseeding during the month of October as approved by the Contracting Officer. The following seed mix shall be used:

Common Name	Botanical Name	Rate (lbs/acre)
Sandberg's Bluegrass	Poa sandbergii	7.0
Bottlebrush Squirreltail	Sitanion hystrix	4.0
Buffalograss	Buchloe dactyloides	5.0
Galleta Grass	Hillaria jamesii	6.0
Sheep Fescue	Festuca ovina	3.0

2.2 SOIL STERILANT

Provide soil sterilant for use in the areas identified in Paragraph 3.3. The sterilant shall be SSI Maxim Co. Weed Blast or approved equal and consist of the following ingredients:

Diuron	4%
Bromacil	4%
Inert Ingredients	92%

3 EXECUTION

3.1 ADVANCE PREPARATION AND CLEANUP

After grading of areas has completed and before applying seed, fertilizer and mulch mixture, areas to be seeded shall be raked or otherwise cleared of stones larger than 2 inches in any diameter, sticks, stumps and other debris which might interfere with sowing of seed, growth of grasses or subsequent maintenance of grass-covered areas. If any damage by erosion or other causes has occurred after the completion of grading and before beginning the application of seed, fertilizer and mulch mixture, the Contractor shall repair such damage. This may include filling gullies, smoothing irregularities and repairing other incidental damage.

An area to be seeded shall be considered a satisfactory seedbed without additional treatment if it has recently been thoroughly loosened and worked to a depth of not less than 5 inches as a result of grading operations and, if immediately prior to seeding, the top 3 inches of soil is loose, friable, reasonably free from large clods, rocks, large roots or other undesirable matter and if shaped to the required grade.

However, when the area to be seeded is sparsely sodded, weedy, barren and unworked, or packed and hard, any grass and weeds shall first be cut or otherwise satisfactorily disposed of and the soil then scarified or be worked into a satisfactory seedbed by discing or by use of cultipackers, rollers, drags, harrows or other appropriate means.

3.2 HYDROSEEDING

a. Mix specified seed, fertilizer, and pulverized mulch in water, using equipment specifically designed for hydroseed application. Continue mixing until uniformly blended into homogenous slurry suitable for hydraulic application.

b. Apply slurry uniformly to all areas to be seeded. Rate of application as required to obtain specified seed sowing rate.

3.3 SOIL STERILIZATION

Apply soil sterilant at the rate of 200 lbs per acre on soil adjacent to the runway. Limits of sterilization shall be 15 feet on either side of the runway along the full length, plus 5 acres at the overrun of each end of the runway. Sterilant shall be applied during the month of November, at a time approved by the Contracting Officer. The Contracting Officer may elect to direct the Contractor to provide the sterilant in bulk form for application by the Government.

3.4 CLEANUP AND PROTECTION

a. During landscape work, keep pavements clean and work area in an orderly condition.

b. Protect landscape work and materials from damage due to landscape operations, operations by other contractors and trades, and trespassers. Maintain protection during installation and maintenance periods. Treat, repair, or replace damaged landscape work as directed.

3.5 INSPECTION AND ACCEPTANCE

a. When landscape work is completed, including maintenance, the Contracting Officer will make an inspection to determine acceptability.

(1) Landscape work will be inspected for acceptance in portions as agreeable to the Government, provided each portion of work offered for inspection is complete, including maintenance.

b. When inspected landscape work does not comply with requirements, replace rejected work and continue specified maintenance until re-inspected by the Contracting Officer and found to be acceptable. Remove rejected plants and materials promptly from project site.

END OF SECTION

SECTION 02964 (R)

COLD MILLING OF BITUMINOUS PAVEMENTS

1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 136 (1996a) Sieve Analysis of Fine and Coarse Aggregates

1.2 EQUIPMENT, TOOLS, AND MACHINES

Equipment, tools, and machines used in the performance of the work shall be maintained in a satisfactory working condition.

1.2.1 Cold-Milling Machine

The cold-milling machine shall be a self-propelled machine equipped with a control system capable of automatically maintaining the specified cutting drum elevation. The control system shall be automatically actuated through a system of mechanical sensors or sensor-directed mechanisms or devices which will maintain the cutting drum at the proper elevation to obtain the required surface. Pavement milling machine shall be capable of establishing grade control; shall have means of controlling transverse slope; and shall have effective means of controlling dust produced during the pavement milling operation. The machine shall have the ability to remove the millings or cuttings from the pavement and load them into a truck. The milling machine shall not cause damage to any part of the pavement structure that is not to be removed.

1.2.2 Cleaning Equipment

Cleaning equipment shall be suitable for removing and cleaning loose material from the pavement surface.

1.2.3 Straightedge

The Contractor shall furnish and maintain at the site, in good condition, one 12 foot straightedge or other suitable device for each milling machine, for testing the finished surface. Straightedge shall be made available for Government use. Straightedges shall be constructed of aluminum or other lightweight metal, and shall have blades of box or box-girder cross section with flat bottom reinforced to insure rigidity and accuracy. Straightedges shall have handles to facilitate movement on the pavement without bending over.

1.3 WEATHER LIMITATIONS

Milling shall not be performed when there is accumulation of snow or ice on the pavement surface.

1.4 GRADE AND SURFACE-SMOOTHNESS REQUIREMENTS

1.4.1 Grade

The finished milled surfaces shall conform to the lines, grades, and cross sections indicated. The finished milled-pavement surfaces shall vary not more than 0.03 foot from the established plan grade line and elevation. Finished surfaces at a juncture with other pavements shall coincide with the finished surfaces of the abutting pavements. The deviations from the plan grade line and elevation will not be permitted in areas of pavements where closer conformance with planned grade and elevation is required for the proper functioning of appurtenant structures involved.

1.4.2 Surface Smoothness

Finished surfaces shall not deviate from the testing edge of a 12 foot straightedge more than 1/4 inch in the transverse or longitudinal direction.

2 PRODUCTS (NOT APPLICABLE)

3 EXECUTION

3.1 MILLING OPERATION

Sufficient passes shall be made so that the designated area is milled to the grades and cross sections indicated. The milling shall proceed with care and in depth increments that will not damage the pavement below the designated finished grade. Items damaged during milling, such as manholes, valve boxes, utility lines, pavement that is torn, cracked, gouged, broken, or undercut, shall be repaired or replaced as directed.

3.2 GRADE AND SURFACE-SMOOTHNESS TESTING

3.2.1 Grade-Conformance Tests

The finished milled surface of the pavement shall be tested for conformance with the plan-grade requirements by the Contractor by running lines of levels at intervals of 50 feet longitudinally and 50 feet transversely to determine the elevation of the completed pavement. The Contractor shall correct variations from the designated grade line and elevation in excess of the plan-grade requirements as directed. Skin patching for correcting low areas will not be permitted. The Contractor shall remove and replace the deficient low area. Sufficient material shall be removed to allow at least 1 inch of asphalt concrete to be placed. No additional payment shall be made for grade conformance corrections.

3.2.2 Surface-Smoothness Tests

After completion of the final milling, the finished milled surface will be tested by the Government with a straightedge. Other approved devices may be used, provided that when

satisfactorily and properly operated, such devices reveal all surface irregularities exceeding the tolerances specified. Surface irregularities that depart from the testing edge by more than 1/4 inch shall be corrected.

3.3 REMOVAL OF MILLED MATERIAL

Material that is removed shall be placed in the disposal area as specified or placed and spread on designated haul road.

END OF SECTION

This page intentionally blank

SECTION 02975 (R)

SEALING OF CRACKS IN BITUMINOUS PAVEMENTS

1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in this text by the basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 3405	(1997) Joint Sealants, Hot-Applied, for Concrete and Asphalt Pavements

1.2 UNIT PRICES

1.2.1 Measurement

The quantity of each sealing item and large crack repair to be paid for shall be determined by actual measurement of the number of linear feet of in-place material that has been approved.

1.2.2 Payment

Payment shall be made at the contract unit bid prices per linear foot for the sealing items and large crack repair scheduled. The unit bid prices shall include the cost of all labor, materials, and the use of all equipment and tools required to complete the work.

1.3 SYSTEM DESCRIPTION

Machines, tools, and equipment used in the performance of the work required by this section shall be approved before the work is started and shall be maintained in satisfactory condition at all times.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Product Data

Installation of Sealant; G

Manufacturer's instructions 14 days prior to the use of the material on the project. Installation of the material will not be allowed until the instructions are received.

Mix Design; G

Propose Job-mix Formula

Submit a formula for hot-asphalt plant mix for major highway or interstate highway level of materials quality, prepared within one year of submittal, for approval prior to preparing and placing the bituminous mixture. Job-mix formula for each mixture shall be in effect until modified in in writing by the Contractor and approved by the Contracting Officer. Provide a new job-mix formula for each source change.

Certificates

Joint Sealant; G

Certificate of Compliance.

1.5 TEST REQUIREMENTS

The crack sealant and backup material, when required, shall be tested for conformance with the referenced applicable material specification. The materials will be tested by the Government. The cost of the first test of samples will be borne by the Government. If the samples fail to meet specification requirements, the Contractor shall replace the materials represented by the sample and the new materials shall be tested at the Contractor's expense. Samples of materials shall be furnished, in sufficient quantity to be tested, upon request. Conformance with the requirements of the laboratory tests specified will not constitute final acceptance of the materials. Final acceptance will be based on the performance of the in-place materials.

1.6 EQUIPMENT

Machines, tools, and equipment used in the performance of the work required by this section shall be approved before the work is started and shall be maintained in satisfactory condition at all times.

1.6.1 Crack Cleaning Equipment

1.6.1.1 Routing Equipment

The routing equipment shall be a self-powered machine operating a power driven tool or bit specifically designed for routing bituminous pavements. The bit shall rotate about a vertical axis at sufficient speed to cut a smooth vertical-walled reservoir in the pavement surface and shall maintain accurate cutting without damaging the sides or top edges of the reservoir. The router shall be capable of following the trace of the crack without deviation. The use of rotary impact routing devices will be permitted if vertical-sided carbide tipped bits are used.

1.6.1.2 Pavement Saw

A self-propelled power saw with small diameter (6 inches or less) water-cooled diamond or abrasive saw blades shall be provided for cutting cracks to the depths and widths specified and for removing filler that is embedded in the cracks or adhered to the crack faces. The

diameter of the saw blade shall be small enough to allow the saw to closely follow the trace of the crack.

1.6.1.3 Sandblasting Equipment

Sandblasting equipment shall include an air compressor, hose, and long-wearing venturi-type nozzle of proper size, shape and opening. The maximum nozzle opening shall not exceed 1/4 inch. The air compressor shall be portable; and shall be capable of furnishing not less than 150 cfm and maintaining a line pressure of not less than 90 psi at the nozzle while in use. Compressor capability under job conditions shall be demonstrated before approval. The compressor shall be equipped with traps that will maintain the compressed air free of oil and water. The nozzle shall have an adjustable guide that will hold the nozzle aligned with the crack about 1 inch above the pavement surface. The height, angle of inclination and the size of the nozzle shall be adjusted as necessary to secure satisfactory results.

1.6.1.4 Waterblasting Equipment

Waterblasting equipment shall include a trailer-mounted water tank, pumps, high-pressure hose, wand with safety release cutoff control, nozzle, and auxiliary water resupply equipment. The water tank and auxiliary resupply equipment shall be of sufficient capacity to permit continuous operations. The hose, wand, and nozzle shall be capable of cleaning the crack faces and the pavement surface on both sides of the crack for a width of at least 1/2 inch. A pressure gauge mounted at the pump shall show at all times the pressure in pounds per square inch at which the equipment is operating.

1.6.1.5 Hand Tools

Hand tools may be used, when approved, for removing defective sealant from cracks and repairing or cleaning the crack faces.

1.6.2 Crack Sealing Equipment

The unit applicators used for heating and installing the hot-poured crack sealant materials shall be mobile and shall be equipped with a double-boiler, agitator-type kettle with an oil medium in the outer space for heat transfer; a direct-connected pressure-type extruding device with a nozzle shaped for inserting in the crack to be filled; positive temperature devices for controlling the temperature of the transfer oil and sealant; and a recording type thermometer for indicating the temperature of the sealant. The applicator unit design shall allow the sealant to circulate through the delivery hose and return to the inner kettle when not in use.

1.7 DELIVERY AND STORAGE

Materials delivered to the job site shall be inspected for defects, unloaded, and stored with a minimum of handling to avoid damage. Storage facilities shall be provided at the job site to protect materials from weather and to maintain them at the temperatures recommended by the manufacturer.

1.8 ENVIRONMENTAL CONDITIONS

The ambient air temperature and the pavement temperature within the joint wall shall be a minimum of 50 degrees F and rising at the time of application of the materials. Sealant shall not be applied if moisture is observed in the crack.

2 PRODUCTS

2.1 SEALANTS

All cracks repaired in the asphalt areas of the project shall be sealed with sealants conforming to ASTM D 3405.

2.2 BACKUP MATERIALS

Backup material shall be a compressible, nonshrinking, nonstaining, nonabsorptive material and shall be nonreactive with the crack sealant. The melting point of the backing material shall be at least 5 degrees F greater than the maximum pouring temperature of the sealant being used, when tested in accordance with ASTM D 789. The material shall have a water absorption of not more than 5 percent by weight when tested in accordance with ASTM C 509. The backup material shall be 25 percent (plus or minus 5 percent) larger in diameter than the nominal width of the crack.

3 EXECUTION

3.1 PREPARATION OF CRACKS

Immediately before the installation of the crack sealant, the cracks shall be thoroughly cleaned to remove oxidized pavement, loose aggregate and foreign debris. The preparation shall be as follows:

3.1.1 Cracks

3.1.1.1 Hairline Cracks

Cracks that are less than 1/4 inch will not be sealed.

3.1.1.2 Small Cracks

Cracks that are 1/4 to 3/4 inch wide shall be routed to a nominal width 1/8 inch greater than the existing nominal width and to a depth not less than 3/4 inch, sandblasted, waterblasted or wire brushed, and cleaned using compressed air. The estimated quantity of small cracks to be repaired in the project is 50,000 lineal feet.

3.1.1.3 Medium Cracks

Cracks that are 3/4 to 1-1/2 inches wide shall be sandblasted, ,waterblasted or wire brushed and cleaned using compressed air. The estimated quantity of medium cracks to be repaired in the project is 50,000 lineal feet.

3.1.1.4 Large Cracks

Cracks that are greater than 1-1/2 inches wide shall be repaired using pothole repair techniques instead of sealing. The estimated quantity of large cracks to be repaired in the project is 6,000 lineal feet.

3.1.2 Existing Sealant Removal

The in-place sealant shall be cut loose from both crack faces and to a depth shown on the drawings, using a concrete saw or hand tools as specified in paragraph EQUIPMENT. Depth shall be sufficient to accommodate any backup material that is required to maintain the depth of new sealant to be installed. Prior to further cleaning operations, all old loose sealant remaining in the crack opening shall be removed by blowing with compressed air.

3.1.3 Routing

Routing of the cracks shall be accomplished using a rotary router with a bit that is at least 1/8 inch wider than the nominal width of the crack to remove all residual old sealant (resealing), oxidized pavement and any loose aggregate in the crack wall.

3.1.4 Sawing

Sawing of the cracks shall be accomplished using a power-driving pavement saw as specified in paragraph EQUIPMENT. The blade shall be stiffened as necessary with suitable dummy (or used) blades or washers. Immediately following the sawing operation, the crack opening shall be cleaned using a water jet to remove all saw cuttings and debris.

Cracks wider than 1 1/2 inches shall be prepared by using a saw to cut away damaged pavement to provide vertical faces a minimum of two inches deep. Jackhammer and remove the defective material. After jackhammering, remove and discard the loose material.

3.1.5 Sandblasting or Waterblasting

The crack faces and the pavement surfaces extending a minimum of 1/2 inch from the crack edges shall be sandblasted clean. A multiple-pass technique shall be used until the surfaces are free of dust, dirt, old sealant residue, or foreign debris that might prevent the sealant material from bonding to the asphalt pavement. After final cleaning and immediately prior to sealing or filling, the cracks shall be blown out with compressed air and left completely free of debris and water. The Contractor shall ensure that sandblasting does not damage the pavement.

3.1.6 Backup Material

Backup material shall be used on all cracks that have a depth greater than 3/4 inch. The backup material shall be inserted into the lower portion of the crack as shown on the drawings. The Contractor shall ensure that the backup material is placed at the specified depth and is not stretched or twisted during installation.

3.1.7 Rate of Progress of Crack Preparation

The stages of crack preparation which include routing, sandblasting of the crack faces, air pressure cleaning and placing of the backup material shall be limited to only that linear footage that can be sealed during the same day.

3.2 PREPARATION OF SEALANT

Hot-poured sealants shall not be heated in excess of the safe heating temperature recommended by the manufacturer as shown on the sealant containers. Sealant that has been overheated or subjected to application temperatures for over 4 hours or that has remained in the applicator at the end of the day's operation shall be withdrawn and wasted.

3.3 INSTALLATION OF SEALANT

3.3.1 Time of Application

Cracks shall be sealed immediately following final cleaning of the crack walls and following the placement of the backup material (when required). Cracks that cannot be sealed under the conditions specified, or when rain interrupts sealing operations, shall be recleaned and allowed to dry prior to installing the sealant.

3.3.2 Sealing the Crack

Immediately preceding, but not more than 50 feet ahead of the crack sealing operations, a final cleaning with compressed air shall be performed. The cracks shall be filled from the bottom up to a minimum of 1/4 inch below the pavement surface and a maximum of 1/2 inch. Excess or spilled sealant shall be removed from the pavement by approved methods and shall be discarded. The sealant shall be installed in a manner which prevents the formation of voids and entrapped air. Several passes with the applicator wand may be necessary to obtain the specified sealant depth from the pavement surface. Gravity methods or pouring pots shall not be used to install the sealant material. Traffic shall not be permitted over newly sealed pavement until authorized by the Contracting Officer. Cracks shall be checked frequently to ensure that the newly installed sealant is cured to a tack-free condition within 3 hours.

3.3.3 Filling Large Cracks

The crack shall be clean, dry and free of dust to ensure that the tack coat will bond. The crack shall be tacked with material meeting the requirements of Section 02748 Bituminous Tack and Prime Coat at an application rate of 0.05 to 0.10 gallons per square yard. The crack shall be overfilled with hot-asphalt plant mix material to allow for compaction. A vibratory place compactor or steel-wheel roller shall be used to compact the mixture in the crack. After compaction the crack shall be level or no higher than 1/8 inch above the surrounding pavement.

3.3.4 Runway Centerline Pavement Repair

The runway centerline shall be milled to an overall width of ten feet and to a depth of six inches. The milled surface shall be clean, dry and free of dust to ensure that the tack coat will bond. The edges of the milled asphalt shall be tacked with material meeting the requirements

of Section 02748 Bituminous Tack and Prime Coat at an application rate of 0.05 to 0.10 gallons per square yard. The pavement repair shall be completed as specified in Section 02749 Hot Mix Asphalt (HMA) for Airfields. After compaction the repair shall be level or no higher than 1/8 inch above the surrounding pavement.

3.4 CRACK SEALANT INSTALLATION TEST SECTION

Prior to the cleaning and sealing of the cracks for the entire project, a test section at least 200 feet long shall be prepared using the specified materials and approved equipment, to demonstrate the proposed sealing of all cracks of the project. Following the completion of the test section and before any other crack is sealed, the test section will be inspected to determine that the materials and installation meet the requirements specified. If materials or installation do not meet requirements, the materials shall be removed and the cracks recleaned and resealed at no cost to the Government. When the test section meets the requirements, it may be incorporated into the permanent work and paid for at the contract unit price per linear foot for sealing items scheduled. All other cracks shall be sealed in the manner approved for sealing the test section.

3.5 CLEANUP

Upon completion of the project, unused materials shall be removed from the site and the pavement shall be left in a clean condition.

3.6 QUALITY CONTROL PROVISIONS

3.6.1 Crack Cleaning

Quality control provisions shall be provided during the crack cleaning process to correct improper equipment and cleaning techniques that damage the bituminous pavement in any manner. Cleaned cracks shall be approved prior to installation of the crack sealant.

3.6.2 Crack Seal Application Equipment

The application equipment shall be inspected to ensure conformance to temperature requirements and proper installation. Evidences of bubbling, improper installing, and failing to cure or set shall be cause to suspend operations until causes of the deficiencies are determined and corrected.

3.6.3 Crack Sealant

The crack sealant shall be inspected for proper cure and set rating, bonding to the bituminous pavement, cohesive separation within the sealant, reversion to liquid, and entrapped air and voids. Sealants exhibiting any of these deficiencies at any time prior to the final acceptance of the project shall be removed from the crack, wasted, and replaced as specified herein at no additional cost to the Government.

END OF SECTION

This page intentionally blank

SECTION 02981 (R)

GROOVING FOR AIRFIELD PAVEMENTS

1 GENERAL

1.1 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Product Data

Equipment; G

List of proposed equipment to be used in performance of construction work, including descriptive data.

1.2 GROOVING MACHINE

The grooving machine shall be a type equipped with diamond-saw cutting blades, and capable of making at least 60 inchesin width of multiple parallel grooves in one pass of the machine. Thickness of the cutting blades shall be capable of making the required width and depth of grooves in one pass of the machine. The cutting head shall not contain a mixture of new and worn blades or blades of unequal wear or diameter. The wheels on the grooving machine shall be of a design that will not scar or spall the pavement. The machine shall be provided with devices to control depth of groove and alignment within the specified tolerances.

1.3 WATER SUPPLY

Water for the grooving operation shall be provided by the Government and shall be transported from the source shown on the drawings to the job.

1.4 ENVIRONMENTAL REQUIREMENTS

Grooving operations will not be permitted when freezing conditions prevent the immediate removal of debris and/or drainage of water from the grooved area.

2 PRODUCTS (NOT APPLICABLE)

3 EXECUTION

3.1 PREPARATION

3.1.1 Existing Pavements (Not Applicable.)

3.1.2 New Pavements

New asphalt concrete pavements shall be allowed to cure for a minimum of 30 days before grooving, to allow the material to become stable enough to prevent closing of the grooves under normal use. New portland cement concrete pavements shall be allowed to cure for a minimum of 30 days before grooving.

3.2 GROOVING

3.2.1 Procedures

Grooves shall be cut in the asphalt and portland cement areas as indicated on the drawings. The dimensions and locations of grooves shall be as shown on the plans. The transverse alignment of the grooves shall not vary more than 3 inches plus or minus on a 75 foot length of grooving. The entire runway shall be grooved transversely beginning 70 feet from the runway centerline on one side of the runway and continuing to 70 feet past the centerline on the other side, with the exception of the areas identified below which shall not be grooved:

a. Asphalt Cement Pavement Areas: The area within 6 inches on either side of the runway centerline shall not be grooved.

b. Portland Cement Concrete Pavement Areas: The area within 6 inches of any longitudinal or transverse pavement area shall not be grooved.

c. Aircraft Arresting System Cable Areas: The pavement 10 feet on either side of the aircraft arresting system cable shall not be grooved.

3.2.2 Precautions

All reasonable precautions shall be taken to prevent damage to or roughening of the pavement between grooves. Spalling along or tearing or raveling of the groove edges shall not be allowed.

3.2.3 Clean-Up

Clean-up shall be continuous. Debris produced by the machine must be flushed to the edge of the runway or shall be picked up as it forms. The dust coating remaining shall be flushed to the edge of the runway if the resultant accumulation is not detrimental to the vegetation or storm drainage system. All flushing operations shall be accomplished in a manner to prevent erosion on the shoulders.

3.2.4 Repair of Damaged Pavement

Any damage that occurs to the pavement as a result of the grooving operations, which in the opinion of the Contracting Officer will be detrimental to aircraft tires, shall be repaired at the Contractor's expense to the satisfaction of the Contracting Officer.

END OF SECTION

SECTION 02999 (R)

INSTALLATION OF ULTRA-HIGH MOLECULAR-WEIGHT POLYETHYLENE PANELS UNDER AIRCRAFT ARRESTING SYSTEM CABLES

1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the test by basic designation only.

1.1.1 AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM):

The following ASTM standards form a part of this specification.

D 256	Test Methods for Impact Resistance of Plastics and Electrical Insulating Materials, Test Method A.
D 638	Test Method for Tensile Properties of Plastics
D 696	Test Method for Linear Thermal Expansion of Plastics
D 1505	Test Method for Density of Plastics by the Density-Gradient Technique
D 2240	Test Method for Rubber Property - Durometer Hardness
D 3028	Test Method for Kinetic Coefficient of Friction of Plastic Solids

1.1.2 Military Publications:

The following publication forms a part of this specification. Where a difference exists between these specifications and the referenced publication, these specifications shall govern. The publication is attached at the end of these specifications.

U.S. Air Force	AF ETL 95-3, Engineering Technical Letter 95-3: *Planning Guide for Installation of Ultra-High-Molecular-Weight (UHMW) Polyelthylene Panels Under Aircraft Arresting System Cables*

1.2 SUBMITTALS

Submit in accordance with Section 01330, SUBMITTAL PROCEDURES

1.2.1 Equipment Lists

Lists of proposed equipment to be used in performance of construction work, including descriptive data, and notifications of proposed Contractor actions as specified in this section.

1.2.2 Material Tests

Manufacturer's test reports or product data certifying that the proposed materials meet or exceed these specifications.

1.2.3 Work Plan

Submit a detailed description of each step in the installation of the panels, including proposed materials and tools and method of installation. Installation will follow exactly the procedures outlined in ETL 95-3, attached at the end of this section. Any proposed deviation must be approved by the Contracting Officer before it is attempted. No work shall begin on this portion of the project until the Work Plan is received and approved.

1.3 EQUIPMENT

All machines, tools and equipment used in the performance of the work shall be approved and maintained in satisfactory operating condition. A complete list of recommended tools and equipment is given at Attachment 3 of AF ETL 95-3.

2 PRODUCTS

2.1 POLYETHYLENE PANELS

2.1.1 Materials

The panels shall be fabricated from virgin UHMW polyethylene and will be black in color and stabilized against the effects of ultraviolet light. The UHMW polyethylene shall contain an anti-static additive.

2.1.2 Physical Requirements

UHMW polyethylene shall meet the physical requirements in Table 1

TABLE 1

Property	Test Method	Requirement
Density	ASTM D 1505	0.92-0.94 g/cm
Tensile elongation at break	ASTM D 638	400-500 %
Tensile yield strength	ASTM D 638	2,800-4,000 psi
Shore hardness "D"	ASTM D 2240	60-70
Coefficient of Friction	ASTM D 3028	0.2
Izod impact strength	ASTM D 256, Method A	>20 ft-lb/inch

* the test specimens shall have two (2) opposing 15-degree notches.

2.1.3 Panel Dimensions:

The UHMW polyethylene panel shall be 59.5 inches long by 24 inches wide by 1 1/2 inches. Tolerance on panel length and width will be +0/-1/8 inch. Panel thickness will not be greater than 1 1/2 inch or less than 1 7/16 inch.

2.1.4 Anchor Stud Hole Locations and Dimensions:

Each panel will have 6 anchor stud holes centered 4 inches from the edge of the panel. The anchor stud hole will be 1 inch for the through hole and 2 inches for the countersink hole. The countersink hole will be 7/8-inch deep with square shoulders for a flat washer to lay firmly against. Figure 1 in AF ETL 95-3 shows dimensions and drilling details. Tolerances on dimensions for locations and diameters of anchor holes shall be $\pm$ 1/16 inch.

2.1.5 Holes for Cable Tiedown Anchors:

Cable tiedown anchors shall be provided in the locations shown on the drawings. The cable tiedown anchor hole will be 4 inches in diameter and will be drilled completely through the panel. Cable tiedown anchor holes will be located as shown. The number of tiedown anchors required is 8 per installation.

2.2 JOINT SEALANT

2.2.1 Material

Joint sealant shall be self-leveling, ultra-low modulus, silicone rubber sealant designed to seal expansion joints, Dow Corning 890-SL, or approved equal that meets the requirements of Specification Section 02760A, FIELD MOLDED SEALANTS FOR SEALING JOINTS IN RIGID PAVEMENT.

2.2.2 Backup Material:

The backup material shall be a compressible, nonshrinking, nonstaining, nonabsorbinb material and shall be nonreactive with the joint sealant. The material shall have a melting point at least 5 degrees F greater than the pouring temperature of the sealant being used when tested in accordance with ASTM D 789. The material shall have a water absorption of not more than 5 percent of the sample weight when tested in accordance with ASTM C 509. The backup material shall be 25 plus or minus 5 percent larger in diameter than the nominal width of the joint.

2.2.3 Primer

Use a primer as recommended by the manufacturer of sealant materials. If the manufacturer recommends a primer for this application, a primer must be used.

2.3 CONCRETE

2.3.1 Materials

Ordinary Portland cement concrete shall be used in this portion of work. 28-day strength shall be as follows: 5,000 psi compression/650 psi flexural. A sample shall be taken from

each day's pour and tested for strength as described in Section 02753A, CONCRETE PAVEMENT FOR AIRFIELDS AND OTHER HEAVY-DUTY PAVEMENTS. The contractor has the option of testing concrete from this portion of the project with a standard compression test, in lieu of flexural testing.

2.3.2 Mix Design

Develop and submit for approval a mix design for concrete intended for use in this work. Guidelines for developing a mix are given in AF ETL 95-3, Paragraph 5.4.2. The following limits are placed on the mix:

Maximum Aggregate Size: 3/8 inch.

Water-to-Cement Ratio: 0.3:1, maximum

2.4 ADDITIONAL MATERIALS

Supply four additional UHMW polyethylene panels drilled for anchor studs only and four additional eyebolts. Additional materials shall be delivered at time of panel installation to a location on base to be identified by the Contracting Officer.

3 EXECUTION

3.1 PREPARE THE RECEIVING SLOT

3.1.1 Remove Concrete

3.1.1.1 Area Dimensions

Dimensions of removal shall be 140 feet, 1 inch long and 25 inches wide, to a depth of at least 2.5 inches.

3.1.1.2 Perimeter Cuts

Make perimeter cuts at least 3 inches deep and overlap at the corners at least 3 inches, to ensure corners are square. Cuts must be perfectly straight. Make at least two additional cuts in the interior of the removal area, to ease removal. Extend cuts perpendicular to the centerline as shown on drawings. Extension cuts shall be 1/4 inch wide and shall be tapered to allow water to drain from under panels. Do not make any cuts in the concrete until it has cured for at least seven days.

3.1.1.3 Concrete Removal

Remove concrete with a light chipping hammer or milling machine. Do not damage adjacent pavement. Any damage caused by the removal operation will be fixed at Contractor's expense. Remove concrete within limits to a depth of at least 2.5 inches or to sound concrete

3.1.2 Prepare Receiving Slot

3.1.2.1 Inspect Receiving Slot

With notched board as seen in AF ETL 95-3, check that concrete is removed to sufficient depth. Sound concrete with a steel rod to ensure soundness.

3.1.2.2 Clean Concrete Substrate

Completely clean the sidewalls and bottom of the receiving slot before placing concrete. Clean with sandblasting equipment or wire brushes, followed by compressed air.

3.1.3 Place Concrete Setting Bed

3.1.3.1 Place Concrete

Place concrete in receiving slot to approximate depth of setting bed. Place concrete in fairlead beam bed as shown on the plans. Mechanically vibrate or "jitterbug" the concrete to consolidate the mix.

3.1.3.2 Level Concrete

Level the concrete with screed as shown in AF ETL 95-3, Paragraph 5.4.2.3.

3.1.3.3 Extended Pavement Joints

Extend existing pavement joints through setting bed by sawcutting full depth through the setting bed after it has sufficiently cured. Alternatively, install expansion board at existing joints before pouring setting bed.

3.2 INSTALL UHMW PANELS

3.2.1 Place Panels and Check

3.2.1.1 Setting Bed

Allow setting bed to harden to the minimum psi that allows drilling without spalls.

3.2.1.2 Lay Out Panels

Lay panels in place, using 1/2-inch thick boards to ensure spacing between panels.

3.2.1.3 Check Panel Height

Check height of all panels relative to pavement surface. The panels shall be recessed 1/16 to 1/8 inch below the adjacent pavement. If any location is high, grind the underlying setting bed until the panel is properly recessed. If any location is low, install shims in accordance with AF ETL 95-3.

3.2.1.4 Preparation For Drilling

Secure panels with wood wedges to prevent movement during drilling for anchor studs.

3.2.2 Install Panel Anchor Studs and Tiedown Anchors

3.2.2.1 Drill Holes

Position alignment tool (Figure 4, AF ETL 95-3) over predrilled hole in panel. Drill 7/8-inch holes to proper depth, ensuring that hole is not too deep or too shallow. (See AF ETL 95-3 and bolt and epoxy manufacturer's recommendations).

3.2.2.2 Prepare Holes

Thoroughly clean holes with wire brush and compressed air. Use a fine tube to ensure all fines are removed from holes.

3.2.2.3 Installation of Panel Anchor Studs

Install panel anchor studs by inserting adhesive capsule into the hole and installing bolt per manufacturer's recommendations and AF ETL 95-3.

3.2.2.4 Installation of Cable Tiedown Anchors

Install Cable Tiedown Anchors at the locations shown on the drawings. Drill and epoxy these anchors by the same procedure used for panel anchors.

3.2.3 Final Installation

When adhesive has fully cured, remove cap nut from bolts and seal around stud with silicone joint sealant. Install flat washers, lock washers and nuts. Torque nuts to 60 ft-lbs. Grind off any portion of stud that protrudes above panel surface.

3.3 SEAL JOINTS

3.3.1 Preparation

Thoroughly clean spaces between panels and between panels and pavement. Remove all laitance, dust and other debris. Joints shall be cleaned in accordance with Section 02560a of these specifications. Ensure that the joint is completely dry before proceeding with sealing operation.

3.3.2 Backer Rod

Place backer rod as shown on project drawings to ensure sealant is recessed and has proper thickness.

3.3.3 Joint Sealant

Seal joints with poured silicone sealant. Place the sealant according to manufacturer's recommendations.

3.4 INSPECTION

Inspect the panels after they are installed, checking the items listed below. Any defective item will be repaired or replaced at the Contractor's expense.

3.4.1 Panel Inspection

Panel recess is a least 1/16 inch and not more than 1/8 inch in all locations. Check each panel at each end and the center.

3.4.2 Bolt Inspection

All bolts are adequately torqued and recessed below the panel height.

3.4.3 Joint Sealant Inspection

All joint sealants are fully bonded and recessed as specified.

DEPARTMENT OF THE AIR FORCE
HEADQUARTERS AIR FORCE CIVIL ENGINEER SUPPORT AGENCY

FROM: HQ AFCESA/CES
139 Barnes Drive
Tyndall AFB FL 32403-5319

SUBJECT: **Engineering Technical Letter (ETL) 95-3: Planning Guide for Installation of Ultra-High-Molecular-Weight (UHMW) Polyethylene Panels Under Aircraft Arresting System Cables (CONUS Installations)**

1. Purpose. This ETL provides a planning guide for installation of UHMW polyethylene panels under aircraft arresting system cables. It includes panel specifications, and installation and inspection guidelines.

2. Application. Requirements of this ETL are mandatory for new construction. Designers should also consider thickened slabs under UHMW panels for new construction. Installation of UHMW panels is the preferred method of repair for existing pavements. Other repair options may be justified based on economy or mission. Requirements of this ETL are mandatory for all UHMW panel installations within the Air Force.

NOTE: Use of "will" indicates a mandatory requirement. "May" or "should" indicates a nonmandatory action or condition.

2.1. Authority: AFPD 32-10, *Air Force Installations and Facilities.*

2.2. Effective Date: Immediately. Expires five years from date of issue.

NOTE: The following issue of this ETL will present measurements with metric equivalents.

3. Referenced Publications.

3.1. AFI 32-1043, *Management of Aircraft Arresting Systems.*

4. Definitions.

4.1. *EPH:* effective pendant height. The clearance between an aircraft arresting system cable and the projected surface (plane) of adjacent pavement [approximately 2 inches. Refer to AFI 32-1043, Paragraph 1.3.11 for procedures for measuring EPH.

5. Specific Requirements. Aircraft arresting system cables impact underlying pavement, eroding grooves in the pavement; the rubber disks supporting the cable sink

into the grooves, lowering the cable. When the EPH is below 1-1/2 inches, the aircraft tailhook may miss the cable. These areas must be repaired to maintain a uniform pavement surface and the proper EPH to ensure reliability of the arresting system.

5.1. Criteria for Repairs:

- Materials must (1) install easily; (2) not warp or erode.
- Method must be cost-effective.

5.2. Options for Repair.

5.2.1. Bonded Partial Depth Inlays. The Air Force has used numerous cementitious-, epoxy-, and polyurethane-based materials under arresting system cables. Performance varies from satisfactory to very poor, even with the same material. Most of these repairs have been costly and/or eroded quickly.

5.2.2. Preformed Panels. The Air Force has tested non-UHMW preformed panels with only limited success: panels warp and panel edges protrude above the adjacent runway pavement, causing the aircraft arresting hook to skip the cable. It is absolutely critical to keep panels flush, or preferably slightly recessed (1/16 to 1/8 inch) below the adjacent pavement surface. Thermal compatibility of the panel material, the anchoring system, and the adjacent pavement is extremely important.

5.2.3. UHMW Polyethylene Panels. UHMW panels have proven effective for several years at European air bases at Bremgarten, Lahr, Wildenrath, and Laarbruch. The Air Force has installed test panels at RAF Lakenheath (1992), Holloman AFB (1992), and Elmendorf AFB (1993), and full-runway-width panels at Incirlik AB (1994). UHMW panels show great promise as a successful method of pavement repair.

5.3. Guidelines for Panel Sizing and Preparation.

5.3.1. Panel Dimensions: Uncut panel stock is 48 inches wide by 10 feet long by 1-1/2 inches thick. Size panels to avoid material waste.

5.3.1.1. Length. Cut panels to allow joints between panels to line up with runway pavement joints. For runways with 20-foot or 25-foot longitudinal paving lane joint spacing, panels should be 4 feet, 11-1/2 inches long. (Two panels can be cut from the 10-foot-long stock with minimal waste.) Panels may be shorter, but must never exceed 5 feet.

NOTE: Recommended joint space between panels is 1/2 inch.

5.3.1.2. Width: To reduce panel warping and damage to joints from cable impact, panels should be a nominal 24 inches wide for all installations.

5.3.1.3. Thickness: Panel thickness should not be less than 1-7/16 inches nor more than 1-1/2 inches.

5.3.2. Panel Finishing. The panel supplier should predrill holes in panels (for anchor stud installation) IAW Figure 1.



Panel Dimensions and Anchor Hole Locations



Detail of Anchor Hole

NOTE: The MAJCOM aircraft arresting system engineer will specify the required number and spacing of tiedown anchors. If cable tiedown anchors will be used, the supplier should predrill panel centers with 4 inch diameter holes to allow anchor installation.

Figure 1. Cable Tiedown, Anchor Hole Locations and Detail.

5.4. Guidelines for Pavement Preparation and UHMW Panel Installation. The procedure to install UHMW panels under arresting system cables involves the following major steps:

- preparing the receiving slot.
- placing a cementitious setting bed.
- installing the UHMW panels.
- installing panel anchor studs.

- installing new cable tiedown anchors (if required).
- sealing the joints.

5.4.1. Preparing the Receiving Slot.

5.4.1.1. Remove Concrete.

5.4.1.1.1. Area Dimensions. Dimensions of the area of concrete removed depend upon the number of panels installed.

Example:

Given: Each panel is 59-1/2 inches long by 24 inches wide; the gap between panels is 1/2 inch.

For an inlay of 8 panels, 40 feet across the runway (20 feet on each side of the runway centerline), the saw cut area must be:

- 40 feet, 1/2 inches long
- 25 inches wide
- at least 2-1/2 inches deep.

An installation extending completely across an 150-foot wide runway requires 30 panels.

5.4.1.1.2. Perimeter Cuts. Perimeter saw cuts must be 3 inches deep and overlap at least 3 inches to ensure corners are perfectly square when pavement is removed. Remove all loose, unsound concrete within the area. Additional saw cuts inside the perimeter will make removing concrete easier (using chipping hammers), and result in a more uniform concrete profile.

5.4.1.2. Inspect Receiving Slot Following Concrete Removal. With a notched board (Figure 2), check the depth of the concrete within the recessed setting bed. Use a chipping hammer to remove any portions less than 2-1/2 inches from the surface of the adjacent pavement. Then check the concrete visually; sound it with a steel rod to identify any unsound portions; and remove all unsound concrete.



Figure 2. Notched Board for Checking Minimum Depth (2-1/2 Inches) of Concrete Within the Receiving Bed.

5.4.1.3. Remove Existing Tiedown Anchors. Cut existing aircraft arresting system cable tiedown anchors flush with the bottom of the concrete substrate before placing the setting bed.

5.4.1.4. Clean Concrete Substrate. Clean the saw-cut side walls and floor of the excavation before laying the setting bed. Sandblast or use wire brushes, followed by compressed air.

5.4.2. Placing a Setting Bed. Place a cementitious setting bed under the panels and allow the bed to cure before drilling and anchoring the panel anchor studs. Use ordinary Portland cement concrete, airfield strength (5,000 psi compression/650 psi flexural strength in 28 days) when several hours' cure time is available. As a suggested mix, use:

- a lean 7-bag mix with 3/8-inch maximum size aggregate
- water-to-cement ratio not to exceed 0.3:1
- platicizer admixture
- substitute fly ash for -50 sieve size sand as required

This will allow drilling within 18 to 24 hours. For short-cure-time applications, a prepackaged material such as Rapid Set Concrete Mix is satisfactory. Rapid Set Concrete Mix is packaged in 60-pound bags which will yield approximately 1/2 cubic foot of concrete when mixed with water (refer to Attachment 4 for ordering information). Placing a small test sample in a disposable pail the same depth as the setting bed may also serve as a helpful tool in determining adequate cure time for drilling operations.

5.4.2.1. Mixing Equipment Placement. Position two mechanical mortar or concrete mixers approximately 20 feet from the prepared inlay near the center of the runway. Transport mixed mortar in a wheelbarrow. Mortar mixers are preferred. Depending upon the type material used, drum mixers may not agitate material enough to produce the desired workability when the recommended amount of water is used.

5.4.2.2. Mixing and Placing Procedure for Rapid Set Concrete Mix:

- Place three to four quarts of water in the mixer. In hot climates, the setting time of the mix can be extended by using cold water. In cold climates, the setting time may be shortened by using hot water and heating the substrate.
- Add one bag of Rapid Set Concrete Mix and mix for two to three minutes.
- Place the material within ten minutes after mixing. If temperature is above freezing, wet the substrate first. If below freezing, do not wet the substrate.
- Finish the material from the center of the bed to the edges to achieve proper bonding along the side walls of the excavation.
- After initial set, when the surface becomes hard to the touch, fog or spray mist cure with water for one hour.

NOTE: This mix "wets" slowly. Do not add more water until the full mixing time is elapsed. Overwatering will weaken the final mix.

5.4.2.3. Leveling Setting Bed.

- Mechanically vibrate or jitterbug the concrete before screeding to consolidate the mass.
- Level the concrete to the proper depth in the setting bed using a notched screed board (Figure 3). Strike the screed periodically to ensure proper depth and uniform surface. The 1-9/16 inch depth of the screed board is based upon a panel thickness of 1-1/2 inches. Measure the actual panel thickness to establish the screed dimensions.
- Extend existing pavement joints through the setting bed by saw-cutting or using an expansion board. The saw cut should be a single blade-width and extend completely through the setting bed. Expansion board must be set the full depth of the setting bed.



Figure 3. Notched Screed Board.

5.4.3. Installing UHMW Panels. Install panels IAW the following:

- Allow setting bed to harden (approximately 4 hours, depending on the type bed used) to the minimum psi which allows drilling without spalls.
- Lay the panels in place.
- Grind the bedding material or panel edges as necessary so that the panel surface is slightly recessed (1/16 to 1/8 inch) below the adjacent pavement surface. Panel height is especially critical in center half of runway.
- Set spacing between panels using a 1/2-inch thick board.
- Secure all panels in place with wood wedges (minimum four sets per panel) to prevent panels' shifting during drilling of anchor stud holes.

5.4.4. Installing Panel Anchor Studs. Refer to Attachment 3 for a list of tools and equipment.

5.4.4.1. Drill Holes.

- Position locally fabricated alignment tool (Figure 4) over predrilled hole in panel.
- Drill 7/8 inch diameter holes in setting bed. Not all anchor studs are consistent in length as ordered, so check actual anchor stud lengths and drill to accommodate the longest stud. The hole depth is critical. If it is not deep enough, the stud will protrude above the panel surface and require

excessive grinding. If it is too deep, the adhesive capsule will be positioned below the stud and not provide adequate coverage.

- Thoroughly clean debris from drilled hole with round wire brush and compressed air. A 3/8- to 1/2-inch diameter tube attached to the compressed air line is necessary to remove all fines from the holes. Insert tubing to bottom of hole to ensure all particles are removed.



Figure 4. Alignment Tool.

NOTE: Use a drill-mounted depth gage rod or mark a position on the drill bit shaft the length of the stud plus the depth of the alignment tool to ensure proper hole depth when drilling.

5.4.4.2. Install Anchor Studs.

- Insert adhesive capsule into hole with rounded end facing hole bottom.
- Screw cap nut or other manufacturer provided adapter onto end of anchor bolt and attach unit to heavy-duty drill (or rotary impact hammer).
- Insert flat washer onto threaded stud just below adapter, or position the washer over the panel hole inside the countersink.
- Drive anchor stud to end of hole; continue rotating stud in hole for at least 3 seconds to mix adhesive.
- Allow adhesive to cure (approximately 1 hour or as recommended by the manufacturer) to the point where the cap nut can be removed without disturbing the stud position.
- Remove cap nut and flat washer; seal around stud with silicone sealant; reinsert flat washer; attach lock washer and nut to top of anchor stud.
- Allow adhesive to fully cure according to manufacturer's instructions.
- Torque nuts to 60 ft-lbs.
- Grind off portion of stud that protrudes above panel surface.

NOTE: To avoid work stoppage while adhesive cures, have at least 12 cap nuts available.

5.4.5. Installing New Cable Tiedown Anchors. The MAJCOM aircraft arresting system engineer will prescribe the number and spacing of cable tiedown anchors required.

Each cable tiedown anchor hole will be located in the center of the appropriate installed panel. Depending on the location of existing runway pavement joints in relation to the runway centerline and the longitudinal joint spacing, UHMW panels may be installed with a panel joint or panel center falling on the runway centerline. Figures 5 through 8 depict recommended cable anchor tiedown locations when installing standard 5-foot panels, Use 8-point tiedown configurations for F-16 aircraft operations. Use 4-point configurations for all other aircraft operations.

NOTE: This requirement does not apply where tiedown anchors are not used.



Figure 5. 8-Point Cable Tiedown Locations - Panel Joint on Runway Centerline.



Figure 6. 4-Point Cable Tiedown Locations - Panel Joint on Runway Centerline.



Figure 7. 8-Point Cable Tiedown Locations - Panel Center on Runway Centerline.



Figure 8. 4-Point Cable Tiedown Locations - Panel Center on Runway Centerline.

5.4.6. Sealing Joints. Apply joint sealant in spacing between and around panel edges, recessed 1/8-inch below the panel top surface. Joint sealants do not adhere well to UHMW panels and joints should be inspected frequently.

NOTE: Joints should be resealed just prior to onset of cold weather to prevent moisture accumulation and freezing below panels. Freezing below panels may result in panel failure, anchor failure, or excessive panel warping.

5.5. Guidelines for Inspection. Bases should establish formal procedures to ensure satisfactory performance of UHMW panels. UHMW panels should be inspected daily and monthly for effects of aircraft traffic and thermal movement (expansion/ contraction/warping) IAW the following.

5.5.1. Daily Inspection. Panel inspection should be added to the daily arresting system inspection by power production personnel. Visually check for panel buckling, warping, and surface variations.

5.5.2. Weekly Inspection. Check for panel buckling, warping, and surface variations by placing a steel straight edge on top of each panel parallel to the runway centerline at:

- each joint between panels;
- at least two locations within each panel; and
- any other location that appears raised or irregular.

The straight edge must be long enough to overlap the pavement on each side of the panel by a minimum of 12 inches. Immediately report raised edges or high spots exceeding 1/8-inch above the plane of the adjacent runway to the base pavements engineer and to the MAJCOM arresting systems engineer for further evaluation. Take color slides or photographs to document findings.

5.5.3. Monthly Inspection. The base pavements engineer should participate once each month in the daily inspections with the power production personnel. Record all panel conditions, including (but not limited to):

- erosion/EPH,
- distresses,

- warping/curling,
- soundness,
- delamination,
- anchor stud effectiveness,
- joint seal performance, and
- spalling.

NOTE: Anchor stud nuts may be over-torqued if done repeatedly. Consider using a thread locking or seizing compound such as Loc-Tite on nuts that continually loosen. Report any significant deterioration or problem to the MAJCOM immediately for further evaluation.

6. Point of Contact: Mr. Cliff Sander, HQ ACC CES/ESO, DSN 574-9337; CMSgt Richard Smith, HQ AFCESA/CESC, DSN 523-6429, commercial (904) 283-6429, or FAX 523-6219.

WILLIAM G. SCHAUZ, Colonel
Director of Technical Support

6 Atch
1. Distribution List
2. ETL Index
3. Typical Tools and Equipment
4. Material Cost and Source
5. Typical Schedule of Events
6. Technical Specifications for Ultra-High-Molecular-Weight (UHMW) Polyethylene Barrier Panels

DISTRIBUTION LIST

DEPARTMENT OF DEFENSE

Defense Commissary Service (1)
Director of Facilities
Bldg 8400
Lackland AFB TX 78236-5000

AAFES/ATTN: CFE (1)
PO Box 660320
Dallas TX 75266-0320

Defense Technical Information Center (1)
ATTN: DTIC-FDA
Alexandria VA 22034-6145

SPECIAL INTEREST ORGANIZATIONS

IHS (A.A. DeSimone) (1)
1990 M Street NW, Suite 400
Washington DC 20036

Construction Criteria Database (1)
National Institute of Bldg Sciences
1201 L Street NW, Suite 400
Washington DC 20005

ENGINEERING TECHNICAL LETTERS (ETL)

SECTION A - CURRENT ETLs

ETL Number	Title	Date Issued
83-1	Design of Control Systems for HVAC	16 Feb 83
	Change No. 1 to ETL 83-1, U.S. Air Force Standardized Heating, Ventilating & Air Conditioning (HVAC) Control Systems	22 Jul 87
83-3	Interior Wiring Systems, AFM 88-15, Para 7-3	2 Mar 83
83-4	EMCS Data Transmission Media (DTM) Considerations	3 Apr 83
83-7	Plumbing, AFM 88-8, Chapter 4	30 Aug 83
83-8	Use of Air-to-Air Unitary Heat Pumps	15 Sep 83
83-9	Insulation	14 Nov 83
84-7	MCP Energy Conservation Investment Program (ECIP)	13 Jun 84
84-10	Air Force Building Construction and the Use of Termiticides	1 Aug 84
86-2	Energy Management and Control Systems (EMCS)	5 Feb 86
86-4	Paints and Protective Coatings	12 May 86
86-5	Fuels Use Criteria for Air Force Construction	22 May 86
86-8	Aqueous Film Forming Foam Waste Discharge Retention and Disposal	4 Jun 86
86-9	Lodging Facility Design Guide	4 Jun 86
86-10	Antiterrorism Planning and Design Guidance	13 Jun 86
86-14	Solar Applications	15 Oct 86
86-16	Direct Digital Control Heating, Ventilation, and Air Conditioning Systems	9 Dec 86
87-1	Lead Ban Requirements of Drinking Water	15 Jan 87
87-2	Volatile Organic Compounds	4 Mar 87
87-9	Prewiring	21 Oct 87
88-2	Photovoltaic Applications	21 Jan 88
88-3	Design Standards for Critical Facilities	15 Jun 88
88-4	Reliability & Maintainability (R&M) Design Checklist	24 Jun 88
88-6	Heat Distribution Systems Outside of Buildings	1 Aug 88
88-9	Radon Reduction in New Facility Construction	7 Oct 88
88-10	Prewired Workstations Guide Specification	29 Dec 88
89-2	Standard Guidelines for Submission of Facility Operating and Maintenance Manuals	23 May 89
89-4	Systems Furniture Guide Specification	6 Jul 89
89-6	Power Conditioning and Continuation Interfacing Equipment (PCCIE) in the Military Construction Program (MCP)	7 Sep 89
89-7	Design of Air Force Courtrooms	29 Sep 89

ENGINEERING TECHNICAL LETTERS (ETL)

SECTION A - CURRENT ETLs

ETL Number	Title	Date Issued
90-1	Built-Up Roof (BUR) Repair/Replacement Guide Specification	23 Jan 90
90-2	General Policy for Prewired Workstations and Systems Furniture	26 Jan 90
90-3	TEMPEST Protection for Facilities Change 1 Ref: HQ USAF/LEEDE Ltr dated 20 April 90, Same Subject	23 Mar 90
90-5	Fuel and Lube Oil Bulk Storage Capacity for Emergency Generators	26 Jul 90
90-6	Electrical System Grounding, Static Grounding and Lightning Protection	3 Oct 90
90-7	Air Force Interior Design Policy	12 Oct 90
90-8	Guide Specifications for Ethylene Propylene Diene Monomer (EPDM) Roofing	17 Oct 90
90-9	Fire Protection Engineering Criteria for Aircraft Maintenance, Servicing, and Storage Facilities	2 Nov 90
90-10	Commissioning of Heating, Ventilating, and Air Conditioning (HVAC) Systems Guide Specification	17 Oct 90
91-1	Fire Protection Engineering Criteria Testing Halon Fire Suppression Systems	2 Jan 91
91-2	High Altitude Electromagnetic Pulse (HEMP) Hardening in Facilities	4 Mar 91
91-4	Site Selection Criteria for Fire Protection Training Areas	14 Jun 91
91-6	Cathodic Protection	3 Jul 91
91-7	Chlorofluorocarbon (CFC) Limitation in \Heating, Ventilating and Air-Conditioning (HVAC) Systems	21 Aug 91
93-1	Construction Signs	11 Mar 93
93-2	Dormitory Criteria for Humid Areas	13 Jul 93
93-3	Inventory, Screening, Prioritization, and Evaluation of Existing Buildings for Seismic Risk	18 Aug 93
93-4	Fire Protection Engineering Criteria - Automatic Sprinkler Systems in Military Family Housing (MFH)	11 Aug 93

ENGINEERING TECHNICAL LETTERS (ETL)

SECTION A - CURRENT ETLs

ETL Number	Title	Date Issued
93-5	Fire Protection Engineering Criteria - Electronic Equipment Installations	22 Dec 93
94-1	Standard Airfield Pavement Marking Schemes	5 Apr 94
94-2	Utility Meters in New and Renovated Facilities	10 Jun 94
94-3	Air Force Carpet Standard	10 Jun 94
94-4	Energy Usage Criteria for Facilities in the Military Construction Program	19 Aug 94
94-5	Fire Protection Engineering Criteria and Technical Guidance - Emergency Lighting and Marking of Exits	8 Nov 94
94-6	Fire Protection Engineering Criteria and Technical Guidance - Removal of Halogenated Agent Fire Suppression Systems	5 Dec 94
94-7	Affirmative Procurement Requirements for Construction and Other Civil Engineering Specifications	14 Dec 94
94-8	Design in Metric	14 Dec 94
94-9	Silicone Joint Sealants for Pavements	14 Dec 94
95-1	Halon 1301 Management Planning Guidance	12 May 95
95-2	Preparation of Requirements and Management Plan (RAMP) Packages for Military Construction (MILCON) Program Projects	26 Oct 95
95-3	Planning Guide for Installation of Ultra-High-Molecular-Weight (UHMW) Polyethylene Panels Under Aircraft Arresting System Cables (CONUS Installations)	26 Oct 95

ENGINEERING TECHNICAL LETTERS (ETL)

SECTION B - OBSOLETE ETLs

ETL Number	Date	Status
82-1	10 Nov 82	Superseded by ETLs 83-10, 86-1, 87-4
82-2	10 Nov 82	Superseded by AFEPPM 88-10
82-3	10 Nov 82	Superseded by ETLs 83-5, 84-2
82-4	10 Nov 82	Superseded by ETL 84-7
82-5	10 Nov 82	Superseded by ETLs 84-1, 86-13, 86-14
82-6	30 Dec 82	Cancelled
82-7	30 Nov 82	Cancelled
83-2	16 Feb 83	Superseded by ETL 84-3
83-5	5 May 83	Superseded by ETL 84-2
83-6	24 May 83	Cancelled
83-10	28 Nov 83	Superseded by ETL 86-1
84-1	18 Jan 84	Superseded by ETL 86-14
84-2	27 Mar 84	Superseded by ETL 94-4
84-3	21 Mar 84	Cancelled
84-4	10 Apr 84	Superseded by ETLs 86-7, 86-15, 87-5
84-5	7 May 84	Superseded by ETLs 84-8, 86-11, 86-18, 88-6
84-6	Not Issued	Cancelled/Not Used
84-8	19 Jun 84	Superseded by ETL 86-11
84-9	5 Jul 84	Superseded by ETL 88-7
88-5	2 Aug 88	Superseded by ETL 91-6
86-1	3 Feb 86	Superseded by ETL 87-7
86-3	21 Feb 86	Superseded by ETL 86-4
86-6	3 Jun 86	Superseded by ETLs 86-11, 86-18, 88-6
86-7	3 Jun 86	Superseded by ETL 86-15
86-11	3 Jul 86	Superseded by ETL 88-6
86-12	3 Jul 86	Superseded by ETL 90-2
86-13	18 Aug 86	Superseded by ETL 86-14
86-15	13 Nov 86	Superseded by ETL 87-5
86-17	17 Dec 86	Superseded by ETL 89-6
86-18	18 Dec 86	Superseded by ETL 88-6
87-3	12 Mar 87	Superseded by ETLs 87-6, ETL 88-5
87-4	13 Mar 87	Superseded by ETL 94-4
87-5	13 July 87	Superseded by ETL 94-2
87-6	21 Aug 87	Superseded by ETL 88-5
87-7	14 Oct 87	Superseded by ETL 89-1
87-8	19 Oct 87	Superseded by ETL 90-1
88-1	5 Jan 88	Superseded by ETL 89-2
88-5	2 Aug 88	Superseded by ETL 91-6
88-7	24 Aug 88	Superseded by ETLs 90-3, 91-2
88-8	4 Oct 88	Superseded by ETL 91-7

ENGINEERING TECHNICAL LETTERS (ETL)

SECTION B - OBSOLETE ETLs

ETL Number	Date	Status
89-1	6 Feb 89	Superseded by ETL 90-4
89-3	9 Jun 89	Superseded by ETL 93-5
89-5		Issued as ETL 90-7
90-4	24 May 90	Cancelled
91-8	24 Sep 91	Cancelled
91-3	14 Jun 91	Superseded by MIL HDBK 1008B, Jan 94
91-5	18 Jun 91	Superseded by ETL 94-5

CONSTRUCTION TECHNICAL LETTERS (CTL)

SECTION C - CURRENT CTLs

CTL Number	Title	Date Issued
88-2	DD Form 1354 Checklist	6 Jan 88
88-7	Constructibility Review Checklist	1 Nov 88
89-1	Thirty-Percent Design Submittal	10 Apr 89
89-2	MAJCOM Construction Management	30 May 89
89-3	Warranty and Guarantee Program	22 Sep 89
90-1	Management of the MILCON Planning and Execution Process	6 Mar 90
90-2	Definitions for Design Milestones	13 Mar 90
91-5	Fire Protection Engineering Criteria - Emergency Lighting and Marking of Exits	18 Jun 91

SECTION D - OBSOLETE CTLs

CTL Number	Status
87-1	Superseded by CTL 88-3
88-1	Superseded by CTL 90-1
88-3	Superseded by ETL
88-4	Replaced by Electronic Data File and Documentation in PDC/WIMS
88-5	Superseded by CTL 90-2
88-6	Issuance Cancelled

TYPICAL TOOLS AND EQUIPMENT

Quantity	Unit	Description
1	each	Concrete saw, self propelled
1	each	Hand-held portable saw
2	each	Saw blades
1	each	Water distributor
50	LF	Expansion board, asphalt impregnated, 4" x 1/2"
3	each	Mortar mixer, 4 cubic feet (2 for use, 1 spare)
1	each	Sand blast unit for air compressor
3	each	Jackhammer, 90 lb, with chisel and spade bits
1	each	Heavy-duty disc-type electric grinder
2	each	1.25 gal containers for mixing water
3	each	Electric generators (1 per drill)
3	tons	Pea gravel (clean, washed gravel, 3/8-inch)
150	bags	Rapid Set Concrete Mix Repair Material
4	buckets	5 gal size, for measuring aggregate
1	board	Notched screed, 2" x 4" x 40"
1	board	Notched depth gauge, 2" x 4" x 40"
30	panels	UHMW polyethylene, 24 inches wide, 59-1/2 inches long, 1-1/2 inches thick, predrilled with six 1-inch diameter anchor holes and 2-inch diameter countersinks
192	each	Anchor studs, 3/4-inch diameter, 9-5/8 inches long, fully threaded, with nuts, flat washers and vinyl ester resin vials. (6 per panel plus spares)
12(min)	each	Cap nuts, 3/4-inch, 10 UNC
2	each	Magnesium floats
1	pair	Vice grips for cap nut removal
1	each	Screwdriver to help with cap nut removal
1	each	Concrete vibrator, small size
2	each	Steel trowels
4	each	Shovels, square point
1	each	Electric drill, 13-millimeter (1/2-inch) drive

1	each	Torque wrench to apply 81 N•m (60 ft-lb) torque
1	each	Tymco Airfield sweeper
1	each	Air compressor
1	each	Front end loader
2	each	Dump trucks
2	each	Wheelbarrow, 4 cubic foot
2	each	Knives
1	each	Pickup truck
2	each	Hammer
2	each	Steel chisel, hand-held
1	each	Joint seal kettle with SS-S-1401 joint seal. NOTE: Silicone joint seal is also recommended and preferred. A recommended silicone joint seal is Dow Corning 890SL in 29-ounce tubes (96 tubes required) and a caulking gun for 29-ounce caulk tubes.
3	each	Electric impact drill (Hilti HE72 or equal) with 7/8-inch diameter by 21-inch long masonry bits.
1	each	Goose neck wrecking bar, 4 feet long, minimum
1	each	Pick for debris breakout and removal
2	each	Wire brushes for slot cleaning
1	each	Roll of heavy cloth or plastic tape for marking drill bits for depth of drilling
2	each	Alignment tools for drilling holes vertically
As req'd		Wood wedges to secure panels in position, at least eight tapered wood wedges per panel
As req'd		Safety equipment including, but not limited to, dust masks, goggles, ear protectors, work gloves, and safety shoes *Ensure an eye wash is available.
As req'd		Wood spacers, 1/2-inch thick by 4 inches) by approximately 3 inches, used to maintain spacing between panels during panel installation
As req'd		String line, spray paint, straight edge board, and a 100-foot tape to measure and mark for saw cuts

MATERIAL COST & SOURCE

NOTE: Costs do not include shipping. Suggestion of vendors is provided to assist in locating sources and does not constitute an endorsement of products from these companies.

Quantity	Item	Suggested Source	Approximate cost
30 each	UHMW polyethylene panels, predrilled with six countersunk anchor holes	Roechling Engineered Plastics PO Box 2729 Gastonia, NC 28053 Phone: (704) 922-7814 or Ultra Poly 2926 South Steele Tacoma, WA 98409 Phone: (800) 872-8469	$10,000
192 each	Anchor studs, 3/4-inch diameter, 9-5/8 inches long, full-threaded (Hilti PN 686691) with vinyl ester bonding vials (Hilti PN 668129), nuts, and flat washers (Hilti HVA Adhesive Anchor System with HEA 3/4-inch capsule and HAS 3/4-inch rod)	Hilti Fastening Systems PO Box 21148 Tulsa, OK 74121 Phone: (800) 879-8000 or Williams Form Engineering Corporation 1448 College Grand Rapids, MI 49507 Phone: (616) 452-3107	$1,000
4 each	Drive sockets	Hilti Fastening Systems	$36
4 each	Drive socket shafts	Hilti Fastening Systems	$160
4 each	Masonry drill bits, 7/8-inch diameter, 21-inches long	Hilti Fastening Systems	$360

25 each	Cap nuts, 3/4-inch diameter, 10 UNC (P/N 91875A036)	McMaster-Carr PO Box 440, New Brunswick, NJ 08903-0440 Phone: (908) 329-3200	$80
150 bags	Rapid Set Concrete Mix	Rapid Set Products Midwestern Regional Off ice 1211 South 6th Street St. Charles, IL 60174 Phone: (312) 773-4949 or (800) 929-3030	$2,550
96 tubes	Silicone joint seal (Dow Corning 890-SL)	The Fred R. Hiller Company 2696 Peachtree Square Road Atlanta, GA 30360 Phone: (404) 451-4661	$1,800

TYPICAL SCHEDULE OF EVENTS
(For Installation of 8 Panels)

Date	Times	Event Description
24 Jun	1800-2200	Perimeter saw cutting, Runway 33. Crew size 2 men. Saw cuts 3 inches deep.
25 Jun	1500-1745	Excavation starts on Runway 33 inlay. Crew size 9 men. Concrete removed using three go-pound jackhammers and one cold milling cutter drum on a "Bobcat 843" skid-steer loader. Debris loaded into a dump truck using a front end loader. Large rubble removed by hand and shovel; small debris removed using the suction wand of the "Tymco" airfield sweeper.
25 Jun	1745-1915	Excavation is complete. Slot cleaned with high pressure air. Substrate sounded and delaminated (unsound, hollow) material removed. Approximate final slot size: 100 feet long by 25 inches wide by 3 inches deep. Notched depth gauge board used to check depth in the center 40-foot area where panels are to be installed.
25 Jun	1915-2000	Final slot inspection. Loose hollow-sounding areas removed with jackhammer and pick. (Hand-held hammer and steel chisel may also be used.) Slot side walls cleaned with wire brushes. Slot cleaned and dried with high pressure air.
25 Jun	2000-2230	Mixing and placing of the setting bed begins. Both concrete mixers used. Ten-person crew is used. No bonding agent used or needed. Notched board used to keep the setting bed at the correct level below the surrounding pavement surface.
25 Jun	2030-2242	Curing compound applied periodically as-the setting bed is placed.
25 Jun	2242-2300	Cleanup accomplished and runway cleared. Approximately 90 bags of mortar placed.
26 Jun	0855-1030	Joints and cracks saw-cut through the mortar patches, both flush and recessed patch areas. Hand-held portable saw used for recessed setting bed cracks/joints and self-propelled pavement saw used for flush patches.
26 Jun	1015-1045	Panel placement begins. Panels positioned and tightly wedged into place using wood spacers and wood shims (wedges). Panels as ordered for the job have predrilled bolt holes.
26 Jun	1050-1130	Drilling bolt holes begins. Three heavy-duty electric impact drills (two Hilti HE72, one Milwaukee) used and work well. Three

		minutes drilling time per hole required. Portable drill alignment tool used to keep drill bit positioned vertically to start hole. Drill bits marked with tape to control hole depth. Long slender tube inserted completely to bottom of bolt holes delivers compressed air to thoroughly clean holes. Recommended wire brushing of holes is not accomplished.
26 Jun	1130-1345	Panel anchor studs set in position using electric drill with adapter attachment. Anchor studs anchored into pavement with adhesive capsule inserted before inserting anchor stud in hole. Installation of anchors is delayed during first hour while new adapter is fabricated locally for anchor installation. After first adapter is tried and proven, two more adapters are fabricated. Anchor stud installation then progresses rapidly with most anchor studs installed in last hour. Applying oil on ends of studs aids adapter removal after stud installation.
26 Jun	1340-1400	Shims removed. Site cleaned with compressed air to remove all particles before sealing around panels with joint sealant.
26 Jun	1710-1730	Studs torqued to 60 foot-pounds with torque wrenches. All studs torqued adequately, but several stud ends protrude above panel surface.
26 Jun	1810-1820	High studs ground down flush with surface using a heavy-duty disc-type electric grinder.
26 Jun	1720-1820	Sealant applied to joints around panels using kettle with hot applied single component non-jet fuel resistant sealant (SS-S-1401). Job complete.
26 Jun	1820-1830	Final inspection and job site cleanup completed.

TECHNICAL SPECIFICATION FOR ULTRA-HIGH-MOLECULAR-WEIGHT (UHMW) POLYETHYLENE BARRIER PANELS

A1. Scope. This specification covers ultra-high-molecular-weight (UHMW) polyethylene panels to be installed under barrier cables.

A2. Referenced Documents. ASTM Standards:

D 256, *Test Methods for Impact Resistance of Plastics and Electrical Insulating Materials,* Test Method A.

D 638, *Test Method for Tensile Properties of Plastics*

D 696, *Test Method for Linear Thermal Expansion of Plastics*

D 1505, *Test Method for Density of Plastics by the Density-Gradient Technique*

D 3028, *Test Method for Kinetic Coefficient of Friction of Plastic Solids*

D 2240, *Test Method for Rubber Property - Durometer Hardness*

A3. Panel Dimensions and Anchor Stud Locations.

A3.1. Panel Dimensions. The UHMW polyethylene panel will be 59-1/2 by 24 by 1-1/2 inches. Tolerance on panel length and width will be +0/-1/8 inch. Panel thickness will not be greater than 1-1/2 inch or less than 1-7/16 inch.

A3.2. Anchor Stud Hole Locations and Dimensions. Each panel will have 6 anchor stud holes centered 4 inches from the edge of the panel. The anchor stud hole will be 1 inch for the through hole and 2 inches for the countersink hole. The countersink hole will be 7/8-inch deep with square shoulders for a flat washer to lay firmly against. Figure 1 shows dimensions and drilling details. Tolerances on dimensions for locations and diameters of anchor holes shall be ±1/16-inch.

A3.3. Holes for Cable Tiedown Anchors. The agency ordering panels will specify if cable tiedown anchor holes are required and will specify the number of panels which will be furnished with cable tiedown anchor holes. The cable tiedown anchor hole will be 4 inches in diameter and will be drilled completely through the panel. Cable tiedown anchor holes will be located in the center of the panel. The location of the cable tiedown anchor hole is shown in Figure 1. The number of tiedown anchors required should be provided by the MAJCOM aircraft arresting system engineer.

A4. Material.

A4.1. The panels will be fabricated from virgin UHMW polyethylene and will be black in color and be UV-stabilized. An antistatic additive will be added to the UHMW polyethylene.

A4.2. The UHMW polyethylene will meet the physical requirements of Table 1.

Table A1. Physical Requirement of UHMW Polyethylene.

Property	Test Method	Requirement
Density	ASTM D 1505	0.92 - 0.94 g/cm
Tensile elongation at break	ASTM D 638	400 - 500%
Tensile yield strength	ASTM D 638	2,800 - 4,000 psi
Shore hardness "D"	ASTM	60 - 70
Coefficient of Friction	ASTM D 3028	0.2
Izod impact strength	ASTM D 256, Method A*	>20 ft-lb/inch

*The test specimens shall have two (2) opposing 15-degree notches.

End of Section

THE FOLLOWING TECHNICAL SPECIFICATIONS APPLY TO
REPAIR AIRCRAFT PARKING APRON ONLY:

Section No.	Section Title
	DIVISION 16 - ELECTRICAL
	Repair Aircraft Parking Apron
16300 A	Electrical Work, Underground

This page was intentionally left blank for duplex printing.

SECTION 16300 (A)

ELECTRICAL WORK, UNDERGROUND

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI C80.1	(1995) Rigid Steel Conduit - Zinc Coated

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C2	(1997) National Electrical Safety Code

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA TC 6	(1990) PVC and ABS Plastic Utilities Duct for Underground Installation

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(1999) National Electrical Code

UNDERWRITERS LABORATORIES (UL)

UL 6	(1997) Rigid Metal Conduit
UL 651	(1995; Rev thru Oct 1998) Schedule 40 and 80 Rigid PVC Conduit
UL 1684	(1996) Reinforced Thermosetting Resin Conduit (RTRC) and Fittings

1.2 GENERAL REQUIREMENTS

1.2.1 Terminology

Terminology used in this specification is as defined in IEEE Std 100.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

Shop Drawings

Conduit System;

Detail drawings consisting of equipment drawings, illustrations, schedules, instructions, diagrams manufacturers standard installation drawings and other information necessary to define the installation and enable the Government to check conformity with the requirements of the contract drawings. If departures from the contract drawings are deemed necessary by the Contractor, complete details of such departures shall be included with the detail drawings. Approved departures shall be made at no additional cost to the Government.

Detail drawings shall show how components are assembled, function together and how they will be installed on the project. Data and drawings for component parts of an item or system shall be coordinated and submitted as a unit. Data and drawings shall be coordinated and included in a single submission. Multiple submissions for the same equipment or system are not acceptable except where prior approval has been obtained from the Contracting Officer. In such cases, a list of data to be submitted later shall be included with the first submission.

As-Built Drawings;

The as-built drawings shall be a record of the construction as installed. The drawings shall include the information shown on the contract drawings as well as deviations, modifications, and changes from the contract drawings, however minor. The as-built drawings shall be a full sized set of prints marked to reflect deviations, modifications, and changes. The as-built drawings shall be complete and show the location, size, dimensions, part identification, and other information. Additional sheets may be added. The as-built drawings shall be jointly inspected for accuracy and completeness by the Contractor's quality control representative and by the Contracting Officer prior to the submission of each monthly pay estimate. Upon completion of the work, the Contractor shall provide three full sized sets of the marked prints to the Contracting Officer for approval. If upon review, the as-built drawings are found to contain errors and/or omissions, they will be returned to the Contractor for correction. The Contractor shall correct and return the as-built drawings to the Contracting Officer for approval within 10 calendar days from the time the drawings are returned to the Contractor.

Product Data

Material and Equipment;

A complete itemized listing of equipment and materials proposed for incorporation into the work. Each entry shall include an item number, the quantity of items proposed, and the name of the manufacturer of each such item.

Certificates

Material and Equipment;

Where materials or equipment are specified to conform to the standards of the Underwriters Laboratories (UL) or to be constructed or tested, or both, in accordance with the standards of the American National Standards Institute (ANSI), the Institute of Electrical and Electronics Engineers (IEEE), or the National Electrical Manufacturers Association (NEMA), the Contractor shall submit proof that the items provided conform to such requirements. The label of, or listing by, UL will be acceptable as evidence that the items conform. Either a certification or a published catalog specification data statement, to the effect that the item is in accordance with the referenced ANSI or IEEE standard, will be acceptable as evidence that the item conforms. A similar certification or published catalog specification data statement to the effect that the item is in accordance with the referenced NEMA standard, by a company listed as a member company of NEMA, will be acceptable as evidence that the item conforms. In lieu of such certification or published data, the Contractor may submit a certificate from a recognized testing agency equipped and competent to perform such services, stating that the items have been tested and that they conform to the requirements listed, including methods of testing of the specified agencies. Compliance with above-named requirements does not relieve the Contractor from compliance with any other requirements of the specifications.

1.4 DELIVERY, STORAGE, AND HANDLING

Devices and equipment shall be visually inspected by the Contractor when received and prior to acceptance from conveyance. Stored items shall be protected from the environment in accordance with the manufacturer's published instructions. Damaged items shall be replaced.

PART 2 PRODUCTS

2.1 STANDARD PRODUCT

Material and equipment shall be the standard product of a manufacturer regularly engaged in the manufacture of the product and shall essentially duplicate items that have been in satisfactory use for at least 2 years prior to bid opening. Items of the same classification shall be identical including equipment, assemblies, parts, and components.

2.2 CONDUIT AND DUCTS

Ducts shall be single, round-bore type, with wall thickness and fittings suitable for the application.

2.2.1 Metallic Conduit

Rigid galvanized steel conduit shall comply with UL 6 and ANSI C80.1.

2.2.2 Nonmetallic Ducts

2.2.2.1 Concrete Encased Ducts

UL 651 Schedule 40 or NEMA TC 6 Type EB.

2.2.3 Conduit Sealing Compound

Compounds for sealing ducts and conduit shall have a putty-like consistency workable with the hands at temperatures as low as 2 degrees C (35 degrees F), shall neither slump at a temperature of 150 degrees C (300 degrees F), nor harden materially when exposed to the air. Compounds shall adhere to clean surfaces of fiber or plastic ducts; metallic conduits or conduit coatings; concrete, masonry, or lead; any cable sheaths, jackets, covers, or insulation materials; and the common metals. Compounds shall form a seal without dissolving, noticeably changing characteristics, or removing any of the ingredients. Compounds shall have no injurious effect upon the hands of workmen or upon materials.

2.3 CONCRETE AND REINFORCEMENT

Concrete work shall conform to the requirements of Section 02753 CONCRETE PAVEMENT FOR AIRFIELDS AND OTHER HEAVY-DUTY PAVEMENTS. Concrete reinforcing shall be as specified on the drawings.

PART 3 EXECUTION

3.1 GENERAL INSTALLATION REQUIREMENTS

Equipment shall be installed in accordance with the manufacturer's published instructions. Except as covered herein, excavation, trenching, and backfilling shall conform to the requirements of Section 02316 EXCAVATION, TRENCHING, AND BACKFILLING FOR UTILITIES SYSTEMS.

3.1.1 Conformance to Codes

The installation shall comply with the requirements and recommendations of NFPA 70 and IEEE C2 as applicable.

3.1.2 Verification of Dimensions

The Contractor shall become familiar with details of the work, shall verify dimensions in the field, and shall advise the Contracting Officer of any discrepancy before performing any work.

3.2 DUCT LINES

3.2.1 Requirements

Numbers and sizes of ducts shall be as indicated. Duct lines shall be laid with a minimum slope of 100 mm per 30 m. (4 inches per 100 feet). Depending on the contour of the finished grade, the high point may be at each end of the duct bank or at the mid-point of the ramp. The minimum manufactured bend radius shall be 450 mm (18 inches) for ducts of less than 80 mm (3 inch) diameter, and 900 mm (36 inches) for ducts 80 mm (3 inches) or greater in diameter. Otherwise, long sweep bends having a minimum radius of 7.6 m (25 feet) shall be used for a change of direction of more than 5 degrees, either horizontally or vertically. Both curved and straight sections may be used to form long sweep bends, but the maximum curve used shall be 30 degrees and manufactured bends shall be used.

3.2.2 Treatment

Ducts shall be kept clean of concrete, dirt, or foreign substances during construction. Field cuts requiring tapers shall be made with proper tools and match factory tapers. A coupling recommended by the duct manufacturer shall be used whenever an existing duct is connected to a duct of different material or shape. Ducts shall be stored to avoid warping and deterioration with ends sufficiently plugged to prevent entry of any water or solid substances. Ducts shall be thoroughly cleaned before being laid. Plastic ducts shall be stored on a flat surface and protected from the direct rays of the sun.

3.2.3 Concrete Encasement

Ducts requiring concrete encasements shall comply with NFPA 70, except that electrical duct bank configurations for ducts 150 mm (6 inches) in diameter shall be determined by calculation and as shown on the drawings. The separation between adjacent electric power and communication ducts shall conform to IEEE C2. Duct line encasements shall be monolithic construction. Where a connection is made to a previously poured encasement, the new encasement shall be well bonded or doweled to the existing encasement. The Contractor shall submit proposed bonding method for approval in accordance with the detail drawing portion of paragraph SUBMITTALS. At railroad and airfield crossings, duct lines shall be encased with concrete and reinforced as indicated to withstand specified surface loadings. Tops of concrete encasements shall be not less than 1.5 m (5 feet) below tops of rails or airfield paving unless otherwise indicated. Where ducts are jacked under existing pavement, rigid steel conduit will be installed because of its strength. To protect the corrosion-resistant conduit coating, pre-drilling or installing conduit inside a larger iron pipe sleeve (jack-and-sleeve) is required. For crossings of existing railroads and airfield pavements greater than 15 m (50 feet) in length, the pre-drilling method or the jack-and-sleeve method will be used. Separators or spacing blocks shall be made of steel, concrete, plastic, or a combination of these materials placed not farther apart than 1.2 m (4 feet) on centers. Ducts shall be securely anchored to prevent movement during the placement of concrete and joints shall be staggered at least 150 mm (6 inches) vertically.

3.2.4 Installation of Couplings

Joints in each type of duct shall be made up in accordance with the manufacturer's recommendations for the particular type of duct and coupling selected and as approved.

3.2.4.1 Plastic Duct

Duct joints shall be made by brushing a plastic solvent cement on insides of plastic coupling fittings and on outsides of duct ends. Each duct and fitting shall then be slipped together with a quick 1/4-turn twist to set the joint tightly.

3.2.5 Duct Line Markers

Duct line markers shall be provided at both ends of the duct line because the terminations shall be completely below-grade. In addition to markers, a 0.127 mm (5 mil) brightly colored plastic tape, not less than 75 mm (3 inches) in width and suitably inscribed at not more than 3 m (10 feet) on centers with a continuous metallic backing and a corrosion-resistant 0.0254 mm (1 mil) metallic foil core to permit easy location of the duct line, shall be placed approximately 300 mm (12 inches) below finished grade levels of such lines.

3.3 ACCEPTANCE

Final acceptance of the facility will not be given until the Contractor has successfully completed all tests and after all defects in installation, material or operation have been corrected.

END OF SECTION

THE FOLLOWING TECHNICAL SPECIFICATIONS APPLY TO
REPAIR RUNWAY ONLY:

Section No.	Section Title
	Repair Runway
16302 R	Underground Transmission and Distribution
16522 R	Airfield Lighting
16900 R	Installation of Runway Ice Detection System Upgrade

This page was intentionally left blank for duplex printing.

SECTION 16302 (R)

UNDERGROUND TRANSMISSION AND DISTRIBUTION

1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI C2	(1997) National Electrical Safety Code

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 260	(1995) Air-Entraining Admixtures for Concrete
ASTM F 512	(1995) Smooth-Wall Poly (Vinyl Chloride) (PVC) Conduit and Fittings for Underground Installation

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA RN 1	(1989) Polyvinyl-Chloride (PVC) Externally Coated Galvanized Rigid Steel Conduit and Intermediate Metal Conduit
NEMA TC 2	(1990) Electrical Plastic Tubing (EPT) and Conduit (EPC-40 and EPC-80)
NEMA TC 3	(1990) PVC Fittings for Use with Rigid PVC Conduit and Tubing
NEMA TC 6	(1990) PVC and ABS Plastic Utilities Duct for Underground Installation
NEMA TC 8	(1990) Extra-Strength PVC Plastic Utilities Duct for Underground Installation
NEMA TC 9	(1990) Fittings for ABS and PVC Plastic Utilities Duct for Underground Installation

INTERNATIONAL ELECTRICAL TESTING ASSOCIATION (NETA)

NETA ATS	(1991) Electrical Power Distribution Equipment and Systems

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(1999) National Electrical Code
NFPA 70B	(1998) Electrical Equipment Maintenance

UNDERWRITERS LABORATORIES (UL)

UL 467	(1993; Bul. 1994, R 1996) Grounding and Bonding Equipment
UL 514B	(1997; R 1998) Fittings for Cable and Conduit
UL 651	(1995; R 1998) Schedule 40 and 80 Rigid PVC Conduit

1.2 DEFINITIONS

a. In the text of this section, the words conduit and duct are used interchangeably and have the same meaning.

b. In the text of this section, "medium voltage cable splices," and "medium voltage cable joints" are used interchangeably and have the same meaning.

1.3 SUBMITTALS

Submit the following in accordance with Section 01330,"Submittal Procedures."

Shop Drawings

Proposed precast sectional underground duct bank; G

2 PRODUCTS

2.1 MATERIALS AND EQUIPMENT

2.1.1 Conduit

2.1.1.1 Plastic Utilities Duct for Concrete Encasement

Type EB-35

2.1.2 Fittings

2.1.2.1 PVC Conduit Fittings

NEMA TC 3

2.1.2.2 PVC Duct Fittings

NEMA TC 9.

2.1.3 Tape

2.1.3.1 Buried Warning and Identification Tape

Provide detectable aluminum foil plastic-backed tape or detectable magnetic plastic tape manufactured specifically for warning and identification of buried cable and conduit. Tape shall be detectable by an electronic detection instrument. Provide tape in rolls, 2 inches minimum width, color coded for the utility involved with warning and identification imprinted in bold black letters continuously and repeatedly over entire tape length. Warning and identification shall be CAUTION BURIED ELECTRIC CABLE BELOW or similar. Use permanent code and letter coloring unaffected by moisture and other substances contained in trench backfill material.

2.1.4 Pull Rope

Shall be plastic having a minimum tensile strength of 200 pounds. Leave a minimum of 24 inches of slack at each end of the pull wires.

3 EXECUTION

3.1 INSTALLATION

NFPA 70 and ANSI C2

3.1.1 Concrete

Concrete work for electrical requirements shall be 3000 psi minimum ultimate 28-day compressive strength with one inch minimum aggregate.

3.1.2 Underground Duct with Concrete Encasement

Construct underground duct lines of individual conduits encased in concrete. Except where rigid galvanized steel conduit is indicated or specified, the conduit shall be PVC Type EB-35. Do not mix different kinds of conduit in any one duct bank. Ducts shall not be smaller than 5 inches in diameter unless otherwise indicated. Concrete encasement surrounding the bank shall be rectangular in cross-section and shall provide at least 3 inches of concrete cover for ducts. Separate conduits by a minimum concrete thickness of 2 inches, except separate light and power conduits from control, signal, and telephone conduits by a minimum concrete thickness of 3 inches. Provide color, type and depth of warning tape as specified in paragraphs "BURIED WARNING AND IDENTIFICATION TAPE."

3.1.2.1 Depth of Encasement

Top of the concrete encasement shall not be less than 18 inchesbelow grade except that under roads and pavement concrete be a minimum of 48 inches below grade.

3.1.2.2 Slope of Encasement

Duct banks shall have a continuous slope downward toward underground structures and away from buildings with a minimum pitch of 3 inches in 100 feet. Except at conduit risers, accomplish changes in direction of runs exceeding a total of 10 degrees, either vertical or

horizontal, by long sweep bends having a minimum radius of curvature of 25 feet; sweep bends may be made up of one or more curved or straight sections or combinations thereof. Manufactured bends shall have a minimum radius of 18 inches for use with conduits of less than 3 inches in diameter and a minimum radius of 36 inches for ducts of 3 inches in diameter and larger. Excavate trenches along straight lines from structure to structure before ducts are laid or structure constructed so the elevation can be adjusted, if necessary, to avoid unseen obstruction.

3.1.2.3 Conduits

Terminate conduits in end-bells where duct lines enter underground structures. Stagger conduit joints by rows and layers to strengthen the duct bank. Provide plastic duct spacers that interlock vertically and horizontally. Spacer assembly shall consist of base spacers, intermediate spacers, and top spacers to provide a completely enclosed and locked-in duct bank. Install spacers per manufacture's instructions, but provide a minimum of two spacer assemblies per 10 feet of duct bank. Before pouring concrete, anchor duct bank assemblies to prevent the assemblies from floating during concrete pouring. Anchoring shall be done by driving reinforcing rods adjacent to every other duct spacer assembly and attaching the rod to the spacer assembly.

3.1.2.4 Test Mandrel

As each section of a duct line is completed from structure to structure, draw a flexible testing mandrel approximately 12 inches long with a diameter less than the diameter of the conduit through each conduit. After which, draw a stiff bristle brush through the conduit, until conduit is clear of particles of earth, sand, and gravel; then immediately install end plugs.

3.1.2.5 Conduit Plugs and Pull Rope

New conduit indicated as being unused or empty shall be provided with plugs on each end. Plugs shall contain a weephole or screen to allow water drainage. Provide a plastic pull rope having 3 feet of slack at each end of unused or empty conduits.

3.1.2.6 Partially Completed Duct Banks

During construction wherever a construction joint is necessary in a duct bank, prevent debris such as mud, and, and dirt from entering ducts by providing suitable conduit plugs. Fit concrete envelope of a partially completed duct bank with reinforcing steel extending a minimum of 2 feet back into the envelope and a minimum of 2 feet beyond the end of the envelope. Provide one No. 4 bar in each corner, 3 inches from the edge of the envelope. Secure corner bars with two No. 3 ties, spaced approximately one footapart. Restrain reinforcing assembly from moving during concrete pouring.

3.1.2.7 Optional Precast Sectional Underground Duct Bank

The Contractor may choose to substitute concrete, precast, sectional, underground duct bank, with PVC conduits, for the cast-in-place underground conduit with concrete encasement. Key and tie together precast sections in a manner to provide the strength and integrity of a cast-in-place structure. Keep conduits in alignment from section to section to provide a smooth surface for pulling cables. Lock precast sections together so that the maximum gap after settlement does not exceed 1/4 inch. Fill gaps between concrete

sections with flexible plastic grouting material to prevent entry of water and foreign material. Install rebar in precast sections in accordance with the requirements of cast-in-place duct banks. Key the precast duct bank into manholes, with a cast-in-place section, of 3 feet minimum, joining the last section to each manhole. The alignment vertically and horizontally of any two adjacent sections shall not vary more than 1/4 inch when measured from end of conduit to end of conduit. Concrete strength shall be the same as for cast-in-place units. Precast duct banks without the PVC conduits will not be permitted.

3.1.3 Buried Warning and Identification Tape

Bury tape with the printed side up at a depth of 12 inches below the top surface of earth or the top surface of the subgrade under pavements.

3.1.4 Special Conditions

During the construction of duct banks and underground structures located in streets, the streets shall remain open to traffic. Plan and execute the work to meet this condition. At locations where duct banks cross railroad tracks and the work requires closing of the tracks, secure permission from the Contracting Officer for each track closure.

3.1.5 Earthwork for Utilities

Section 02316A, "Excavation, Trenching, and Backfilling for Utilities Systems."

3.1.6 Reconditioning of Surfaces

3.1.6.1 Unpaved Surfaces

Restore to their original elevation and condition unpaved surfaces disturbed during installation of duct. Preserve sod and topsoil removed during excavation and reinstall after backfilling is completed. Replace sod that is damaged by sod of quality equal to that removed. When the surface is disturbed in a newly seeded area, re-seed the restored surface with the same quantity and formula of seed as that used in the original seeding.

3.1.6.2 Paving Repairs

Where trenches, pits, or other excavations are made in existing roadways and other areas of pavement where surface treatment of any kind exists. make repairs as specified in Section 02749 “Hot Mix Asphalt (HMA) for Airfields” and Section 02753A, "Concrete Pavement for Airfields and Other Heavy Duty Pavements."

3.2 FIELD QUALITY CONTROL

As an exception to requirements that may be stated elsewhere in the contract, notify the Contracting Officer 5 working days prior to each test. Furnish labor, equipment. and incidentals required for testing, except that the Government will provide electric power required for the tests. Correct defects in the work provided by the Contractor and repeat tests until the work is in compliance with contract requirements.

3.2.1 Performance of Acceptance Checks and Tests

Perform in accordance with the manufacturer's recommendations, NFPA 70B, NETA ATS, and referenced ANSI standards. Include the following visual and mechanical inspections and electrical tests, performed in accordance with NETA ATS.

END OF SECTION

SECTION 16522 (R)

AIRFIELD LIGHTING

1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM B209	(2000) Aluminum and Aluminum-Alloy Sheet and Plate
ASTM C603	(1990; R 1997) Extrusion Rate and Application Life of Elastomeric Sealants
ASTM C639	(1995) Rheological (Flow) Properties of Elastomeric Sealants
ASTM C661	(1998) Indentation Hardness of Elastomeric-Type Sealants by Means of a Durometer
ASTM C679	(1987; R 1997) Tack-Free Time of Elastomeric Sealants
ASTM C719	(1993; R 1998) Adhesion and Cohesion of Elastomeric Joint Sealants Under Cyclic Movement (Hockman Cycle)
ASTM C792	(1993; Rev 1998) Effects of Heat Aging on Weight Loss, Cracking, and Chalking of Elastomeric Sealants
ASTM C793	(1991; R 1997) Effects of Accelerated Weathering on Elastomeric Joint Sealants
ASTM D412	(1998; Rev. A) Vulcanized Rubber and Thermoplastic Elastomers - Tension
ASTM D709	(2000) Laminated Thermosetting Materials
ASTM D1248	(2000) Polyethylene Plastics Extrusion Materials for Wire and Cabling
ASTM D1535	(1997) Specifying Color by the Munsell System

U.S. FEDERAL AVIATION ADMINISTRATION (FAA)

FAA AC-150/5345-7	(1981; Rev. D) L-824 Underground Electrical Cable for Airport Lighting Circuits

FAA AC-150/5345-26	(2000; Rev. C) L-823 Plug and Receptacle, Cable Connectors
FAA AC-150/5345-42	(1989; Rev. C) Airport Light Bases, Transformer Houses, Junction Boxes and Accessories
FAA AC-150/5345-46	(1998; Rev. B) Runway and Taxiway Light Fixtures
FAA AC-150/5345-47	(1987; Rev. A) Isolation Transformers for Airport Lighting Systems
FAA AC-150/5370-10	(1989; Rev. A; through change 12) Specifying Construction of Airports
FAA E-982	(1988; 1991 Rev. H) PAR-56 Lampholder
FAA E-1315	(1967; 1971 Rev A) Light Base and Transformer Housing
FAA E-2690	(1978) Isolation Transformer (1500 Watt) for High Intensity Approach Lighting Systems
FAA E-2702	(1979) Low Impact Resistant Structures

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C2	(1997) National Electrical Safety Code

U.S. DEPARTMENT OF DEFENSE (DOD)

MIL-L-5904	(1978; Rev. D; 1981 Am. 1) Light, Runway Marker, Elevated, Type C-1
MIL-T-27535	(1999; Rev. A) Transformer, Power, Isolation, Series Circuit, Airport Lighting
MIL-STD-108	(1966; 1990 Rev. E) Definitions of and Basic Requirements for Enclosures for Electric and Electronic Equipment
MIL-STD-461	(1999; Rev. E) Control of Electromagnetic Interference Characteristics of Subsytems and Equipment
MS 17814	(1972; Rev C) Coupling, Frangible, Aviation Ground Lights

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA TC 2	(1998) Electrical Polyvinyl Chloride (PVC) Tubing and Conduit

NEMA TC 3	(1999) PVC Fittings for Use with Rigid PVC Conduit and Tubing
NEMA TC 6	(1999) PVC Plastic Utilities Ducts for Underground Installations
NEMA WC 3	(1992; 1994 Rev. 1) Rubber-Insulated Wire and Cable for the Transmission and Distribution of Electrical Energy
NEMA WC 7	(1993; 1996 Rev 3) Cross-Linked-Thermosetting-Polyethylene-Insulated Wire and Cable for the Transmission and Distribution of Electrical Energy
NEMA WC 8	(1993; 1996 Rev 3) Ethylene-Propylene-Rubber-Insulated Wire and Cable for the Transmission and Distribution of Electrical Energy

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(1999) National Electrical Code
NFPA 70B	(1998) Electrical Equipment Maintenance (National Fire Codes, Vol 9)

THE SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC SP 1	(1982) Solvent Cleaning (Steel Sturctures Painting Manual, Ch2 - Surface Preparation Specs)

UNDERWRITERS LABORATORIES (UL)

UL 44	(1999) Thermoset-Insulated Wires and Cables Fifteenth Edition
UL 83	(1998; 2000) Thermoplastic-Insulated Wires and Cables Twelfth Edition
UL 510	(1994; R 1998) Polyvinyl Chloride, Polyethylene, and Rubber Insulating Tape Seventh Edition

1.2 SUBMITTALS

Submit the following in accordance with Section 01330, "Submittal Procedures."

Shop Drawings

Each type of airfield lighting fixture installation

Product Data

Control cable

Series airfield lighting cable

Isolating transformers

Each type of runway and taxiway lighting fixture

Each type of light bases

Frangible couplings

FAA Type P-606 sealant

FAA Type L-823 connectors

Test Reports

Counterpoise system test

Certificates

Installer Qualifications; G

Construction Outage Plan; G

1.3 QUALITY ASSURANCE

1.3.1 Qualifications

Do not install materials which are not approved as "Approved Airport Equipment" by FAA unless specifically approved by the electrical design engineer. Inspect wire and cable for date of manufacture. Do not use wire and cable manufactured more than one year before delivery to job site.

1.3.2 Regulatory Requirements

Provide materials and equipment listed by FAA, UL, ETL or approved by Factory Mutual Engineering and Research (FM), when such equipment is listed or approved. Do not use askarel, tetrachlorethylene and insulating liquids containing polychlorinated biphenyls (PCBs) in equipment. Provide submersible type equipment installed below grade in vaults, manholes, and handholes. Materials must be certified and listed as "Approved Airport Lighting Equipment" downloadable from: http://www.faa.gov/arp/pdf/534553ad.pdf.

1.3.3 Installer Qualifications

The aviation lighting equipment contractor and installation electricians must be experienced in installing, testing and maintaining aviation lighting systems of a similar complexity. The contractor must provide a list of government projects and 3 years of experience in

constructing similar projects. Include written certification that systems have performed satisfactorily for not less than 18 months.

1.3.4 Construction Outage Plan

The contractor must provide a construction outage plan and schedule for installing new and retrofitting the existing lighting system to ensure that aviation lighting circuits are fully operational between dusk and dawn during each day of the construction contract. The plan must be submitted to and approved by the Contracting Officer and the Airfield Manager prior to starting construction.

1.4 EXISTING AIRFIELD LIGHTING SYSTEMS

Existing airfield lighting systems shall remain in operating condition and interruptions shall be held to a minimum. Where interruptions are necessary, they shall be scheduled as approved in writing by the Contracting Officer. Prior to the scheduled time for each interruption, all necessary materials and a sufficient labor force shall be assembled to permit completing the work within the scheduled time interval. Under no circumstances shall any of the existing airfield lighting circuits be left inoperative without making provisions for suitable temporary connections in the affected area or areas. All airfield lighting circuits covered under this Contract shall be replaced in such a manner that they will be operational at dusk each day. The Contractor shall submit to the Contracting Officer a plan for outages and maintaining lighting and lighting control.

2 PRODUCTS

2.1 ELECTRICAL TAPE

UL 510, plastic insulating tape.

2.2 CONDUIT, CONDUIT FITTINGS, AND BOXES

2.3 FRANGIBLE COUPLINGS AND ADAPTERS

MS 17814. Provide upper section of frangible coupling with one of the following:

a. Unthreaded for slip-fitter connections.

b. 2 13/32 inch: 16N-1A modified thread for nut and compression ring to secure 2 inch EMT.

c. 2 inch: 11 1/2-N.P.T. (tapered) with 7/32-inch nominal wall thickness to accept rigid conduit coupling.

3 WIRE AND CABLE

Do not provide or install wire and cable manufactured more than one year before delivery to the job site. Conductors shall be copper.

3.1.1 Conductor Sizes

Conform to American Wire Gage (AWG).

3.1.2 Power Cables for Use in Airfield Lighting

Rated 5 kV, 133 percent insulation level, with shield and jacket conforming to NEMA WC 7 for crosslinked polyethylene.

3.1.3 Wire and Cable for Airfield Lighting Systems

3.1.3.1 Airfield Lighting Cable

FAA AC-150/5345-7, Type L-824, for crosslinked polyethylene Type C 5000-volt cable. Series airfield lighting cable shall be unshielded.

3.1.3.2 Cable for Pavement Slot Installation

UL 83, Type THWN.

3.1.3.3 Counterpoise Wire

No. 4 AWG bare stranded copper, annealed or soft drawn. ASTM specifiations B3 and B8.

3.1.4 Cable Tags

Provide cable tags for each cable or wire at duct entrances entering or leaving of manholes, handholes, and at each terminal within the lighting vault. Provide stainless steel, bronze, lead strap, or copper strip tags approximately 1/16 inch thick or hard plastic 1/8 inch thick suitable for immersion in salt water and impervious to petroleum products. Provide sufficient length for imprinting the legend on one line using raised letters not less than 1/4 inch in size. Permanently mark or stamp with the identification as directed. Two-color laminated plastic is acceptable. Provide dark colored plastic tags with markings of light color to provide contrast so that identification can be easily read. Provide fastening material of a type that will not deteriorate when exposed to water with a high saline content and petroleum products.

3.2 LIGHT BASES

FAA AC-150/5345-42 Type L-867. Provide steel bases, Class 1, Size as indicated as required to accommodate the fixture or device installed thereon if diameter is not shown.

3.2.1 Accessories

Provide base plates, cover plates, and adapter plates to accommodate various sizes of fixtures. Bolts shall be stainless steel.

3.3 SEALING FIXTURES AND WIRES IN DRILLED HOLES OR SAW KERFS

FAA AC-150/5370-10, Type P-606.

3.3.1 Sealant Type

FAA Type P-606 sealant for use in asphaltic concrete (AC) or Portland cement concrete (PCC) pavement compatible with AC pavement and having a minimum elongation of 50 percent. Formulations of Type P-606 which are compatible with PCC pavement only are prohibited.

3.3.2 Single Component Cold-Applied Silicone

Silicone sealant shall be self-leveling, non-acid curing, meet the requirements of ASTM D 5893 and shall be Dow Corning 890-SL, or approved equal.

3.4 LAMPS AND FILTERS

Provide lamps of size and type indicated, or required by fixture manufacturer for each lighting fixture required under this contract. Provide filters as indicated and conforming to the specification for the light concerned or to the standard referenced.

3.5 RUNWAY AND TAXIWAY LIGHTING SYSTEMS

Include runway edge lights, temporary runway threshold lights, and the associated equipment and interconnecting wiring to provide complete systems as indicated and specified herein.

3.5.1 Runway Edge Lights

FAA AC-150/5345-46, Type L-862 for elevated mounting; Provide filters as indicated conforming to requirements of fixture specifications.

3.6 CONNECTORS

FAA AC-150/5345-26, FAA Type L-823 connectors for use with FAA Type L-824 airfield lighting cable.

3.7 EXECUTION

3.8 ELECTRICAL REQUIREMENTS

Electrical installation shall conform to IEEE C2, NFPA 70, NFPA 70Bnd requirements specified herein.

3.9 CONCRETE

Unless otherwise specified, provide 3000 psi concrete for below grade and 4000 psi concrete for above grade use with one inch maximum aggregate.

3.10 EARTHWORK

Provide excavation and backfilling as specified in Section 2300A, "EARTHWORK."

3.11 CABLE MARKERS

Provide cable markers or tags for each cable at duct entrances entering or leaving manholes or handholes and at each termination within the lighting vault. Tag cables in each manhole or handhole with not less than two tags per cable, one near each duct entrance hole. Immediately after cable installation, permanently attach tags to cables and wires so that they cannot be accidentally detached.

3.12 FRANGIBLE REQUIREMENTS

Install frangible supports, couplings, and adapters as indicated and specified. Install with the type conduit indicated.

3.13 ELEVATED AIRFIELD LIGHTS

Frangibly mount normally not exceeding 14 inches in height unless higher mounting is permitted in snow accumulation areas. Frangibly mount equipment exceeding 14 inches in height as indicated.

3.14 WIRES, FIXTURES, AND ENCLOSURES IN SAW KERFS OR DRILLED HOLES

Sealant is specified in paragraph entitled "Sealing Fixtures and Wires in Drilled Holes or Saw Kerfs."

3.14.1 Saw Kerfs and Splice Chambers

Cut saw kerfs and splice chambers in pavements where indicated. Provide saw cuts in straight lines and with vertical sides. Provide width and depth of saw cuts adequate for the required number of wires as indicated. Saw kerfs shall have the vertical edges chamfered at intersections. Where a saw kerf crosses a construction joint, increase the depth sufficiently to allow for slack wire under the joint.

3.14.2 Sandblasting

Sandblast saw kerfs, grooves, and holes to remove foreign or loose material. Accomplish sandblasting by using approved equipment maintained in good working order at all times. Provide sand used for blasting of the proper size and quality as necessary to perform the work. Provide nozzles used for sandblasting of the proper size in relation to the groove or holes to be cleaned. Replace nozzles enlarged by wear as necessary. Sandblast at an air pressure of not less than 90 psi.

3.14.3 Cleaning

Immediately prior to installation of wire or light fixtures, flush saw kerfs and holes with a high velocity water jet or steam, and clean and dry with a high velocity air jet to remove dirt and foreign material.

3.14.4 Installation of Circuit Wires in Pavement

Place the wires in saw kerfs and anchor at bottom by means of rubber or plastic wedges or noncorrosive metal clips placed every 2 or 3 feet or as often as necessary to hold the wire

down. Where wires cross existing joints, encase wires in a 12 inch length of flexible tubing of polyethylene material conforming to ASTM D1248, Type II or Type III, to break the bond between the wires and the sealing material. Provide tubing centered on the joint and of sufficient size to accommodate the wires to allow for movement of the wires as the joint opens and closes. Wrap ends of tubing with tape to prevent entrance of sealing materials. Pack the adjacent joint area temporarily with roving material, such as hemp, jute, cotton or flax, to prevent sealing material from flowing into the open joint. Carefully mix and apply sealing materials in accordance with the manufacturer's instructions and at the recommended temperature. Remove surplus or spilled material.

3.15 SPLICES FOR AIRFIELD LIGHTING CABLE

3.15.1 Connectors

Use kit type connectors to splice 5 kV single-conductor series lighting cables. During installation and prior to covering with earth, keep mating surfaces of connectors covered until connected and clean when plugged together. At joints where connectors come together, install heat shrinkable tubing with waterproof sealant. Joint shall prevent entrapment of air which might subsequently loosen the joint.

3.15.2 Splicing Fixtures to the Wires in Pavement Saw Kerfs

Make splices with preinsulated watertight connector sleeves crimped with a tool that requires a complete crimp before tool can be removed.

3.16 GROUNDING SYSTEMS

3.16.1 Counterpoise Installation

Lay counterpoise wire for entire length of circuits supplying airfield lighting. Provide wire in one piece, except where distance exceeds the length usually supplied, and install on top of the envelope of concrete-encased duct and approximately 6 inches above direct burial cables and duct lines. Where trenches or duct lines intersect, electrically interconnect counterpoise wires by exothermic welding.

3.16.2 Fixture Grounding

Ground each fixture or group of adjacent fixtures to the counterpoise system. Connect fixtures, steel light bases or grounding bushings on steel conduits to the counterpoise system by a No. 6 AWG bare-stranded copper wire. Semiflush (pancake) fixtures for direct mounting in pavement may not be grounded. Connect copper wire to the counterpoise by exothermic weld.

3.17 ISOLATION TRANSFORMERS

Make connections of transformer primary leads to primary cables with connectors conforming to FAA AC-150/5345-26. Make connection to transformer secondary with connectors conforming to FAA AC-150/5345-26and plug directly into a mating connector on the transformer secondary leads. During installation, keep mating surfaces of connectors covered until connected and clean when plugged together. At joint where connectors come together,

install heat shrinkable tubing with waterproof sealantJoint shall prevent entrapment of air which might subsequently loosen the joint.

3.18 FIELD QUALITY CONTROL

Give the Contracting Officer 5working days notice prior to eachtest. Correct deficiencies found and repeat tests.

3.18.1 Operating Test

After installation has been completed, conduct an operating test. Demonstrate equipment to operate in accordance with the requirements of this section. Conduct tests oneday and onenight for the Contracting Officer.

3.18.2 Distribution Conductors, 600-Volt Class

Test to verify that no short circuits or accidental grounds exist.Make tests using an instrument which applies a voltage of approximately 500 volts providing a direct reading in resistance.

3.18.3 Counterpoise System Test and Inspection

Make a visual inspection of continuity of counterpoise system at accessible locations. Test continuity of counterpoise system to the vault grounding system in manhole closest to the vault.

3.18.4 Progress Testing for Series Airfield Lighting Circuits

Conduct a megger test on each section of circuit or progressive combinations of sections as they are installed. Check each section or progressive combination of sections with a megohmmeter providing a voltage of approximately 1000 volts to provide a direct reading in resistance, and document results. Locate any faults indicated by these tests and eliminate before proceeding with the circuit installation.

3.18.5 Electrical Acceptance Tests

Perform acceptance tests for series and multiple airfield lighting circuits only on complete lighting circuits. Subject each series and multiple lighting circuit to a high voltage insulation resistance test.

3.18.5.1 Low Voltage Continuity Tests

Test each series circuit for electrical continuity. Locate faults indicated by this test and eliminate before proceeding with the high voltage insulation resistance test.

3.18.5.2 High Voltage Insulation Resistance Test

Subject each series lighting circuit to a high voltage insulation resistance test by measurement of the insulation leakage current.Provide a suitable high voltage test instrument which has a steady, filtered direct current output voltage and limited current. High voltage tester shall include an accurate voltmeter and microammeter for reading voltage applied to

the circuit and resultant insulation leakage current. Do not apply voltages in excess of test values specified below.

a. Test Procedure: Disconnect both leads from regulator output terminals and support so that air gaps of several inches exist between bare conductors and ground. Clean and dry cable sheaths, for a distance of one foot from ends of cables and exposed insulation at ends of cables. Connect ends of both conductors of the circuit together and to high-voltage terminals of test equipment, and apply test voltage specified in the following tabulation between conductors and ground for a period of 5 minutes.

	Test Voltage, dc	
Series Lighting Circuits	First Test on New Circuits	Test on Existing Circuits
High intensity series lighting circuits (5000-volt leads, 500- and 200-watt transformers)	9000	5000
Medium intensity series lighting circuits (5000-volt leads, 30/45-watt transformers)	6000	3000
600-volt circuits	1800	600

When additions are made to existing circuits, test only new sections in accordance with "First Test on New Circuits" in table above.

b. Leakage Current: Measure and record insulation leakage current in microamperes for each circuit for each minute application of test voltage. Do not exceed the value of the insulation leakage current calculated on the basis of the following leakage current allowances for cable and connected equipment for each circuit:

(1) 3 microamperes for each 1000 feet of cable.

(2) 2 microamperes for each 200-watt and each 500-watt 5000-volt series transformer.

(3) 2 microamperes for each 30/45-watt 5000-volt series transformer.

Note: The above values include allowances for the normal number of connectors and splices.

If measured value of insulation leakage current exceeds calculated value, sectionalize the circuit and repeat specified test for each section. Locate defective

components and repair or replace until repeated tests indicate an acceptable value of leakage current for the entire circuit.

3.18.5.3 Operating Test

Upon completion of tests, show by demonstration in service that circuits, control equipment, and lights covered by the contract are in good operating condition. Operate each switch in the control tower lighting panels so that each switch position is engaged at least twice. During this process, observe lights and associated equipment to determine that each switch controls properly corresponding circuit. Provide telephone or radio communication between the operator and the observers. Repeat tests from the alternate control station, from the remote control points, and again from the local control switches on the regulators. Test each lighting circuit by operating the lamps at maximum brightness for not less than 30 minutes. Visually examine at the beginning and at the end of this test to ensure that the correct number of lights are burning at full brightness. Conduct one-day and one-night operating test for the Contracting Officer.

END OF SECTION

This new Section replaces the old Section 16900 (R) in it's entirety (R0001)

SECTION 16900

INSTALLATION OF RUNWAY ICE DETECTION SYSTEM UPGRADE

PART 1 GENERAL

1.1 DESCRIPTION

The Contractor shall furnish and install an upgrade to the existing Runway Ice Detection System (RIDS) that is specifically designed for monitoring and displaying pavement surface conditions, pavement temperature, freeze point temperature, chemical percentage, subsurface temperature, and atmospheric temperatures and conditions from multiple locations as shown in the contract documents. The existing system was provided by Surface Systems, Inc. (SSI, 1162 Lilburn Park Road, St. Louis, MO 63146. The system upgrade provided shall be or compatible with the existing system. Pavement surface conditions shall include dry, wet, frost, chemical wet, and snow/ice warning. Atmospheric condition options shall include air temperature, relative humidity, precipitation, dew point, visibility and wind/speed direction. The system shall include all hardware, software, and licenses to operate as follows:

- Pavement surface sensors shall measure pavement surface temperature, chemical concentration, and pavement surface condition inputs and communicate the signals to the Remote Processing Unit (RPU).
- Atmospheric sensors shall measure their respective weather parameters and communicate the signals from each to the RPU.
- Each RPU shall process the output from the sensor(s) and/or atmospherics, store the data temporarily, and send the data to a Network Server (NS) by VHF radio communications media. Data exchanges shall utilize SSBP protocol.
- The NS shall store the data in a standard SQL Server database for access via web browser over the existing Air Force Base computer network.
- Users shall view the sensor data in a browser-based runway map data display format from any IBM compatible Pentium-class personal computer running Windows 95, Windows 98 or Windows NT operating system, and on the existing Air Force Base computer network.

1.2 SUBMITTALS

Submit the following in accordance with Section 01330, SUBMITTAL PROCEDURES:

1.2.1 Equipment Lists

Lists of proposed equipment to be used in performance of construction work, including descriptive data, and notifications of proposed Contractor actions as specified in this section.

1.2.2 Work Plan

Submit a detailed description of each step in the installation of the system, including proposed materials, tools and method of installation. No work shall begin on this portion of the project until the Work Plan has been received and approved by the Contracting Officer. Installation

will follow the procedures outlined in the approved Work Plan. The Contracting Officer must approve any proposed deviation to the Work Plan in advance.

1.2.3 Documentation and Manuals

The Contractor shall provide 5 sets of training manuals, which detail the configuration and operation of the system, no later than 30 days after commissioning and acceptance of the system. The Contractor shall also submit warranty documentation no later than 30 days after contract award.

PART 2 PRODUCTS

2.1 RUNWAY ICE DETECTION SYSTEM

2.1.1 Surface Sensors

The Contractor shall provide and install 7 (seven) new surface sensors in the runway pavement surface as shown in the plans. The Contractor shall also be responsible for splicing the 7 new sensor cables to the existing runs of Type V direct burial cable in existing cans at the edge of the runway. If any of the existing runs of Type V cable are damaged or are not electrically intact, the Contractor shall notify the Contracting Officer immediately. The surface sensors as supplied by the Contractor shall be furnished with a limited lifetime warranty from the equipment vendor, covering parts only. Each sensor shall be a single solid-state electronic device, constructed of materials that have thermal characteristics similar to common pavement. The top of the sensor shall approximate the runway pavement color and texture. It shall be installed with epoxy sealer so the top is flush with the surrounding runway surface. The sensor shall be thermally passive, providing stable operation over a temperature range from -30°C to 50°C (-22°F to 122°F). The sensor and cable shall withstand a temperature range of -37°C to 80°C (-35°F to 175°F) without sustaining damage. Weather conditions, airplane traffic, or ice control chemicals shall not degrade its performance. Each sensor shall be supplied with 91 m (300') of attached molded cable that is waterproofed and sealed as an integral part of the assembly and shall be capable of operating at extended cable lengths, up to 762 m (2500 ft) from the RPU. Each sensor shall electronically sample the following pavement conditions:

- Surface temperature at the sensor head.
- Dry pavement condition.
- Wet pavement condition above 0°C (32°F).
- Wet but not frozen pavement condition at or below 0°C (32°F).
- Snowy or icy pavement condition at or below 0°C (32°F).
- In addition, the pavement sensors shall supply data for determining the following pavement surface conditions when sufficient moisture is present:
- Freezing point temperature of the moisture/ice-control-chemical solution present on the surface of the pavement sensor for commonly used ice-control-chemicals.
- Depth of the moisture/ice-control-chemical-solution present on the surface of the pavement sensor up to a depth of 12 mm (0.5 inches).
- Percentage of ice particles present in the moisture/ice-control-chemical solution resident on the surface of the pavement sensor.

2.1.2 Subsurface Temperature Probe

The Contractor shall provide and install 1 (one) new subsurface temperature probe in the new runway pavement surface as shown in the plans. The Contractor shall also be responsible for splicing the new probe cable to the existing run of Type V direct burial cable in one of the existing cans at the edge of the runway. If the existing run of Type V cable is damaged or is not electrically intact, the Contractor shall notify the Contracting Officer immediately. The subsurface probe as supplied by the Contractor shall be furnished with a limited lifetime warranty from the equipment vendor, covering parts only. The Subsurface Temperature Probe shall be a single solid-state electronic device that measures the temperature below the runway pavement surface near the interface between the sub-grade and the soil below. The probe shall be installed under the runway near a surface sensor as shown on the plans. The temperature-sensing element of the probe shall operate over the temperature range from -30°C to 50°C (-22°F to 122°F). The probe shall be supplied with 91 m (300 ft) of attached cable, which is waterproofed and sealed as an integral part of the assembly and shall be capable of operating at extended cable lengths, up to 762 m (2500 feet) from the RPU.

2.1.3 Air Temperature/Relative Humidity Sensor

The Contractor shall provide and install 1 (one) new air temperature/relative humidity sensor at one of the RPU locations. The Contracting Officer shall identify which RPU location. The sensor shall have an air temperature-sensing element, which operates over the temperature range of -30°C to 50°C (-22°F to 122°F), with a survival operating range of -37°C to 80°C (-35°F to 176°F). The relative humidity sensing element shall be of the “human hair” type and have a measuring range of 10 to 100% RH. The operating temperature range is -30°C to 50°C (-22°F to 122°F). System dew point temperature shall be calculated from the air temperature and relative humidity. The sensor shall be mounted on the existing RPU structure approximately 2 meters (6 feet) above ground level in a solar/wind-radiation shield. The combined sensor shall operate to specifications at cable lengths up to 46 m (150 ft) from the RPU.

2.1.4 Wind Speed/Direction Sensor

The Contractor shall provide and install 1 (one) new wind speed/direction sensor at one of the RPU locations. The Contracting Officer shall identify which RPU location. The sensor shall have an operating range of 0 to 161 km per hr (0 to 100 mph). The sensor survival operation limit shall be 264 km per hr (180 mph) with an operating azimuth of 360° mechanical and 355° electrical. The temperature operating range shall be -40°C to 60°C (-40°F to 140°F) with a survival operating range to 85°C (185°F). The sensor shall operate to specifications at cable lengths up to 46 m (150 ft) from the RPU. It shall be installed approximately 2 meters (6 feet) above ground level on the existing RPU structure.

2.1.5 Digital Precipitation Classifying Sensor

The Contractor shall provide and install 1 (one) new digital precipitation-classifying sensor at one of the RPU locations. The Contracting Officer shall identify which RPU location. This sensor shall function as a precipitation classifier and a precipitation rate meter by sensing the difference between rain, snow, and drizzle; as well as measure actual precipitation rates and water equivalent. Precipitation rate error shall be less than 10% for the full-expected range of 2.5 to 500 mm per hr (0.1 to 20 in per hr), with less than a 5% error within the more normal range of 10 to 100 mm per hr (0.4 to 4.0 in per hr). The sensor housing should be all weather and ice-proof with heated optics to prevent ice, dew or frost buildup. Normal operating

temperature range should be from -50°C to 50°C (-58°F to 122°F). The sensor shall be installed approximately 2 meters (6 feet) above ground level at one of the RPU locations as shown on the plans. The sensor shall operate to specifications at cable lengths up to 46 m (150 ft) from the RPU.

2.1.6 Remote Processing Units (RPUs)

2.1.6.1 Hardware

The Contractor shall provide and install 2 (two) sets of upgraded RPU back planes with associated electronics, as shown at each of the locations on the plans. The existing RPU structures and all existing RPU equipment not identified for replacement or upgrade in this specification shall be retained and reused. The Contractor shall also provide and install a new RPU radio, modem, antenna, and cabling at each of the RPUs. The new back planes shall be installed inside the two existing NEMA 4 lockable aluminum enclosures, which are already mounted on freestanding FAA approved mounting structures at locations shown on the plans. The RPU shall gather data from all connected sensors and remote pavement sensors, and process, store and transmit this data to the Network Server (NS). Each new RPU shall be capable of collecting data from the following sensors:

- 1 to 8 Surface Sensors that are “hardwired”
- 1 to 8 Surface Sensors that are communicating remotely
- 1 to 8 Subsurface Sensors that are “hardwired”
- 1 to 8 Subsurface Sensors that are communicating remotely
- 1 Air Temperature/Relative Humidity Sensor
- 1 Wind Speed/Direction sensor
- 1 Present Weather Sensor
- 1 NTSC black and white, or color, video camera input

The RPUs as shown on the plans shall operate in a range of 100-130 VAC at 50-60 Hz and shall use not more than approximately 50 Watts of continuous power (excluding options). The primary power shall be installed and fused at 15A with voltage protection.

The RPU design shall maximize the use of solid-state components and modular circuit cards for ease of maintenance. All circuitry of the RPU, the voltage inputs, the sensor inputs, and the communications ports shall be designed and tested to provide transient and surge protection. The RPU shall provide stable operation over a temperature range of -30°C to 70°C (-40°F to 160°F) and 0-90% RH non-condensing.

2.1.6.2 Software

Both RPUs shall be provided with a software algorithm for use with the freeze point surface sensors to detect the chemical concentration of Potassium Acetate runway anti-icing chemical. The RPU shall incorporate “watch-dog” circuitry and monitor its own operation and reset itself if the RPU software enters an indeterminate state. The RPU shall have the capability to be reset by a “user administrator” from the NS. The RPU shall be capable of remote alignment, reconfiguration, and accepting downloads of updated software from the NS over the same communication link used to collect data from the RPU.

2.1.6.3 RPU to Network Server Data Communications

The RPU shall communicate with the NS via one CCITT V.24/EIA RS-232C communication interface port on the RPU coupled to a modem and VHF radio. The NS shall poll each RPU

at a time interval specified by the agency to transfer and refresh its data. Mountain Home Air Force Base already has an FCC radio license for 2 of the RPU locations, both on the same military frequency. The Contractor shall provide and install all new radios, modems, cables and antennas for the entire system.

2.1.7 Network Server (NS)

The NS shall be a Windows NT Operating System Server, which shall collect sensor data from all RPUs in the system, then process and store the information in a Microsoft™ SQL Server Relational Database Management System. The Network Server shall be an IBM-compatible Pentium-class Server having sufficient processing power and capacity to meet the following operational requirements:

- Collect all sensor data from a maximum of RPUs in the Base system
- Permit up to 10 Base users to access the RWIS data simultaneously
- Store historical data from the sensors for one (1) winter season.

The NS shall serve the sensor data to users via a permanent network connection to the existing Air Force Base LAN. The RWIS Server application shall be 32-bit and employ Microsoft SQL Server Relational database to store RWIS data and allow multiple, simultaneous access to the database for updates from the RPUs together with simultaneous user interface access. The NS and associated peripheral equipment shall operate from 100-128 VAC and shall be operated in an environmentally controlled and secured area.

2.1.8 Network Web Page Data Displays

The vendor shall provide a Server-based Internet Web Page Data Display (IWPDD). The IWPDD shall reside on the Network Server and provide access to RWIS data via the existing Air Force Base LAN using a widely available "Internet Browser" (Internet Explorer or equal). IWPDD shall employ the Networking and Database capability of the Network Server with Microsoft's Internet Information Server (IIS), Active Server Pages (ASP), and Hyper Text Transfer Protocol (HTTP). IWPDD shall provide access to timely data from the Network Server over a network or dial-up connection using the computer facilities that, in most cases, are already present on the user's Windows-based PC or laptop. IWPDD shall only require a Standard Browser (MS Internet Explorer or Netscape), a network or dial-up connection, and TCP/IP or PPP on the user's PC. All software, configuration, and administration shall be handled through the Network Server.

Access and display of current and historical RWIS sensor data, and forecast data resident on the Network Server from the Weather and Site Forecasting Service, shall be available through the IWPDD in a text based format. IWPDD shall display any RPU site video images that are resident in the Network Server. The IWPDD shall be capable of displaying NTCIP-ESS data. The various display pages are described in the following sections.

2.1.9.1 Summary Page

This page shall display a one-line summary of current data for each RPU in the system. This data includes (depending on RPU sensor configuration):

- RPU Name
- Representative Surface Sensor Name
- Data Collection Time for the RPU
- Surface Status for the RPU's representative surface sensor

- Surface Temperature, if available, for the RPU's representative surface sensor
- Subsurface Temperature, if available, for the RPU's representative subsurface probe
- Air Temperature
- Relative Humidity
- Dew point Temperature
- Precipitation Type
- Precipitation Intensity
- Precipitation Rate
- Visibility Distance
- Wind Gust Speed
- Average Wind Direction

The Summary Page shall use color to indicate the Surface Status and Precipitation Type. If left unattended, the Summary Page shall refresh every 6 minutes. The Summary Page shall link to the Surface Summary Page and each RPU's Status Page. The title of each data field shall also be a link, which will display the Glossary definition for the field. There may be other links on this page depending on the availability of data such as maps, forecasts, cameras, etc.

2.1.9.2 Surface Summary Page

The Surface Summary Page shall display current data for each surface sensor in the system grouped by RPU. This data includes (depending on the model of surface sensor):

- Surface Sensor Name and number
- Surface Status
- Surface Temperature
- Subsurface Temperature, if available, for the surface sensor
- Freeze Point Temperature
- Chemical Factor
- Chemical Percent
- Solution Depth
- Ice Percent

In addition, the following RPU data items should be displayed for each group of surface sensors (depending on RPU sensor configuration):

- RPU Name
- Data Collection Time for the RPU
- Air Temperature
- Dew point Temperature
- Average Wind Speed
- Average Wind Direction
- Precipitation Type

The Surface Summary Page shall use color to indicate the Surface Status for each surface sensor. If left unattended, the Surface Summary Page must refresh every 6 minutes. The Surface Summary Page shall link to the Summary Page, each RPU's Status Page, and each sensor's history page. The title of each data field shall also be a link, which shall display the Glossary definition for the field. There may be other links on this page depending on the availability of data such as maps, etc.

2.1.9.3 RPU Status Page

The RPU Status Page should display all current data for a single RPU. This data includes (depending on RPU sensor configuration):

- RPU Name
- Data Collection Time
- Air Temperature
- Relative Humidity
- Dew point Temperature
- Average Wind Speed
- Wind Gust Speed
- Minimum Wind Direction
- Average Wind Direction
- Maximum Wind Direction
- Visibility Distance
- Precipitation Type
- Precipitation Intensity
- Precipitation Accumulation
- Precipitation Rate
- Water Level
- Surface Sensor Name
- Surface Status for each surface sensor
- Surface Temperature for each surface sensor
- Subsurface Temperature, if available, for the surface sensor
- Freeze Point Temperature
- Chemical Factor
- Chemical Percent
- Solution Depth
- Ice Percent

The RPU Status page shall use color to indicate Surface Status and Precipitation Type. If left unattended, the RPU Status Page shall refresh every 6 minutes. This RPU Status Page shall link to the Summary Page and the History Page for the representative sensor. The title of each data field shall also be a link, which will display the Glossary definition for the field. There may be other links on this page depending on the availability of data such as maps, forecasts, cameras, etc.

2.1.9.4 History Page

The History Page shall display 8 hours of temperature, wind, and precipitation history data for a single RPU ordered most recent to least recent. The History Page shall include (depending on RPU sensor configuration):

- RPU Name
- History Time Period
- Data Collection Time for each history data snapshot
- Surface Temperature for the RPU's representative surface sensor
- Subsurface Temperature, if available, for the RPU's representative surface sensor
- Air Temperature
- Relative Humidity
- Dew point Temperature
- Average Wind Speed
- Wind Gust Speed

- Average Wind Direction
- Precipitation Type
- Precipitation Intensity

The History Page shall use color to indicate the Precipitation Type. The History Page shall link to the Summary Page, the Surface Summary Page, the RPU Status Page, and the History Graph page. The History Page shall include links to access the previous or next 8 hours of history data. Using these links, the user shall be able to navigate back through any history data available for an RPU. The title of each data field shall also be a link, which will display the Glossary definition for the field. The data currently displayed on the History page shall be linked to the data displayed on the Precipitation/Surface History Page.

2.1.9.5 Surface History Page

The Surface History Page shall display 8 hours of surface status, surface temperature, and precipitation history data for a single RPU ordered most-recent to least-recent. The Precipitation/Surface History Page shall include (depending on RPU sensor configuration and surface sensor model):

- RPU Name
- History Time Period
- Data Collection Time for each history data snapshot
- Surface Status for the RPU's representative surface sensor
- Surface Temperature for the RPU's representative surface sensor
- Subsurface Temperature, if available, for the RPU's representative surface sensor
- Freeze Point Temperature for the RPU's representative surface sensor
- Chemical Factor for the RPU's representative surface sensor
- Chemical Percent for the RPU's representative surface sensor
- Solution Depth for the RPU's representative surface sensor
- Ice Percent for the RPU's representative surface sensor
- Precipitation Type
- Precipitation Intensity
- Precipitation Accumulation
- Precipitation Rate

The Surface History Page shall use color to indicate the Surface Status and Precipitation. The Surface History Page shall link to the Summary Page, the RPU Status Page, the History page, and the History Graph page. The Surface History Page shall include links to access the previous or next 8 hours of history data. Using these links, the user shall be able to navigate back through any history data available for an RPU. The title of each data field shall also be a link, which will display the Glossary definition for the field.

2.1.9.6 History Graph Page

The History Graph should present a line graph representation of historical temperature data for a single RPU. The data displayed on the graph includes:

- Surface Temperature for each sensor
- Freeze Temperature for each sensor
- Air Temperature
- Dew point Temperature

The History Graph shall include an Options section at the bottom that will allow the user to customize the display of data as needed. Each customization option shall be available as described below:

Chart Scale: The End Date and the Time Period shall determine the chart scale. The date and time shall be entered in *dd mon yyyy hh:mm* format. The date shall be the end of the range of history data to be viewed. When the graph is initially displayed, the current date and time shall be displayed in this field. The Time Period selected shall determine how many hours of data previous to the End Date are displayed in the graph.

Chart Selections: The Chart Selections shall determine the lines that are displayed on the graph. There shall be 4 types of lines that can be displayed. They are:

- Air Temp – If selected, the Air temperature history line shall be displayed (default).
- Dew Temp – If selected, the Dew point temperature history line shall be displayed.
- Surface Temp – If selected, a surface temperature history line shall be displayed for each sensor that is selected (default).
- Freeze Temp – If selected, a freeze temperature history line shall be displayed for each sensor that selected.

The name and number of each sensor for the current RPU is displayed along with a checkbox. Select the sensor or sensors you want displayed on the graph. When the graph is initially displayed, the representative sensor is selected as the default.

Legends: This checkbox shall allow the user to determine whether the Precipitation Type & Intensity legend and the Surface Status legend are displayed. The box shall be checked by default. The legends shall be removed by unchecking the box.

2.1.9.7 Glossary Page

In addition to the RIDS data pages, a Glossary display page shall be included which defines each of the data items displayed and other important terms. Every Web page shall provide links to the Glossary Page to provide convenient access to on-line help.

2.1.9.8 Runway Map Page

The server shall provide all users with a runway map display page for displaying system data graphically. The runway map shall have both RPU sites as well as all the sensors associated with the RPUs. Clicking on an RPU site noted on the map shall display the current atmospheric data for the RPU. Clicking on a sensor site shall display current data for the sensor. Sensors shall be color-coded based on its surface status. The runway map shall display each RPU associated with a data tag. Only one data item shall be displayed on a tag at any time. The same data item shall be displayed for each RPU on the map. By default, the air temperature shall be displayed. The default data item to be displayed on all maps during the current browser session shall be configured on the Map Options page.

2.2 EQUIPMENT SUMMARY

All RIDS equipment furnished on this project shall be state of the art and in current manufacture at the time of purchase. The instruments and data processing equipment to be supplied are summarized in the following table. This summary may not include all tools or materials necessary to complete the work.

Quantity	Description
2	RPU-Upgrade-SP Size Enclosures, 30x24x12
2	RPU Software & Licenses - (KAc) Algorithm for Potassium Acetate (KAc)
1	SCAN for Windows (or Equal) Server, ALR 7210 Pentium III 933MHz, 512K Cache, 256MB RAM, 2-9GB Mirrored Ultra2 SCSI HDD's, 1.44MB FDD, CD ROM, 2MB PCI Video, 12/20GB Tape Back-Up, Keyboard, Mouse, APC UPS, 33.6K External Modem, 10/100 10 Base-T NIC, SSI products supported on this platform: SCAN for Windows, SCAN Sentry, SCAN Web
1	17" SVGA Color Monitor
1	SCAN for Windows Server (or equal) Setup and Configuration.
1	SCAN for Windows Server (or equal) Data Collection Software & Media
1	Microsoft NT Server 4.0 License Pack W/Media
1	Microsoft SQL Server x.x License Pack (current version)
1	Acceleport - Serial 2 Port Expansion Board for Server
1	Thies (or equal) Relative Humidity/Air Temperature Sensor
1	RM Young (or equal) Wind Speed/Direction Sensor
1	SCTI Optical DIGITAL (or equal) Precipitation Classifying Sensor
1	Cable 50ft ORG 175 to ESP-RPU
1	OWI/Wivis/ORG (or equal) Support Arm
2	FP2000 Sensor 300' Grey #3 Replacement Kit (or equal) Includes 300' Type IIA cable, 1-20 oz. Encapsulating Epoxy, 1-6 oz. Topcoat Epoxy #3 Concrete, 1 Steel Stick
5	FP2000 Sensor 300' Black #9 Replacement Kit (or equal) Includes 300' Type IIA cable, 1-20 oz. Encapsulating Epoxy, 1-6 oz. Topcoat Epoxy #9 Asphalt, 1 Steel Stick
1	Subsurface Temperature Probe w/300' D Kit Includes 300' Type IIA cable, 1-20 oz. Encapsulating Epoxy

1 Splice Tool Kit
crimper, swagging tool

7 Splice Kit

2 USR 56K Server Modem

1 Motorola CDM750 VHF 1-25 watt Radio Server Kit (or equal)
Paccomm EWM 24M w/cable (or equal)
Cable: Motorola CDM750 to Paccomm EWM2400 (or equal)
Motorola VHF 1-25 watt CDM750 radio (or equal)
Mini UHF Male to SO259 Connector (or equal)
Adapter, #4400 Amphenol (or equal)
Power Supply, Astron 110 Volt, 7 Amps (or equal)
Power interrupter Adapter
DTR controlled Power interrupter (Kerchuncker) (or equal)
1 HUSTLER G7-150-1, 148-154 MHz, VHF (or equal)
1 COAX CABLE 100'

2 Motorola CDM-750 VHF 1-25 watt radio RPU Kit (or equal)
Adapter, #4400 Amphenol (or equal)
S-Connector, Bulkhead (or equal)
S-Adapter, Angle/Jack-Plug, Amphenol (or equal)
S-Mini UHF Male to UHF Female Adapter
Power Supply, Astron 110 Volt, 7 Amps (or equal)
Cable: Motorola CDM-750 to Paccomm EWM2400 (or equal)
Coax cable 5'
Paccomm Wireless Modem EWM 24M w/cable (or equal)
Motorola 1-25 watt VHF CDM-750 radio (or equal)
2 ANTENNA 148-154Mhz (ASP-816)-(Airport)
2 COAX CABLE 12'

1 SCAN Web Software (Current Version) (or equal)

This includes the software and Non-Redistribution License for a Single User (Agency)'s SCAN Web Server. Provided with one site map.

1 Chart Works OEM License (or equal)
1 Scan Web Version 3.0 (or equal)

1 Single RPU Site Custom Link Map (SCAN Web STD)

(Site depiction drawing linking to data page included in software)

1 Commissioning by Field Service Engineer - Systems

1 Pre Commissioning Checklist

1	Airport System Installation Manual
1	Sensor/Sub Probe Installation Manual
1	Sensor Splice Manual
1	System User Training, 4 Hour Session, On Site

PART 3 EXECUTION

3.1 INSTALLATION

All equipment required to upgrade the RIDS shall be installed by a licensed electrician and in strict accordance with the manufacturer's or vendor's recommendations and the approved work plan. The Contractor is responsible for a complete installation, including system components, tools and miscellaneous requirements.

3.1.1 Existing Components Retained

Junction boxes along the runway that are part of the existing RIDS shall be retained. The junction boxes shall be used to connect new sensor cables to existing remote processing unit cabling. The cables connecting the sensor cables to the remote processing units shall also be reused. Except where specifically identified in this specifications, all structures and equipment associated with existing RPUs shall be retained and incorporated into the upgraded system.

3.1.2 Pavement Cuts

The Contractor shall coordinate with the Contracting Officer prior to making cuts in the pavement for installation of sensors and probes. Cuts must be perfectly straight. Do not make any cuts in the pavement until it has cured for at least seven days.

3.1.3 Server

The Contractor shall coordinate with the Contracting Officer for location and installation of the server.

3.1.4 Repair of Existing Cable

The Contractor shall splice existing cut Type V Cable at the location identified in the plans. This cable shall be spliced with an approved direct-bury splice kit to restore this run of cable to operational condition.

3.2 SYSTEM COMMISSIONING

After the Contractor has completed installation of the equipment, the equipment vendor shall perform all final system checks, sensor alignments, software setup, and software configuration to provide a fully operational RIDS.

3.3 EQUIPMENT WARRANTY

After contract acceptance, the equipment vendor shall provide limited, on-site, warranty coverage on all equipment for a 12-month period from the RIDS commissioning date. A copy of the vendor's warranty documentation shall be submitted to the Contracting Officer after contract award. Additionally, the vendor for the in-pavement sensors will provide a limited lifetime warranty.

3.4 SYSTEM USER TRAINING

The equipment vendor shall provide an on-line computer based training tutorial with the RIDS, which provides training on the operation web browser accessed user software. The equipment vendor shall also provide 4 hours of on-site system user training to Air Force Base personnel at a mutually agreeable time at the base. Training shall cover basic operation of the system and how to use the system information in agency operations. The vendor shall provide 5 sets of training manuals, which detail the configuration and operation of the system.

END OF SECTION

This page intentionally blank